



City of Colleyville City Council Worksession Agenda

City Hall
100 Main Street
Colleyville, Texas 76034
817.503.1000
www.colleyville.com

Thursday, March 8, 2018
5:00 p.m.

Executive Conference Room
Third Floor - City Hall

1. CALL TO ORDER

2. PRESENTATION AND DISCUSSION

2a Review of proposed amendments to the Land Development Code

3. ADJOURNMENT

I hereby certify this agenda was posted on City Hall bulletin boards Friday, March 2, 2018 by 5:00 p.m.

Christine Loven, TRMC
City Secretary

A quorum of any Colleyville board, commission, or committee may be present at this meeting.

Any matter on this agenda may, at the discretion of the governing body, be opened for public comment and discussion.

If you plan to attend this public meeting and have a disability that requires special accommodations, please advise the City Secretary at least 48 hours in advance at 817.503.1133, and reasonable accommodations will be made to assist you.



City of Colleyville Colleyville City Council Worksession Agenda Briefing

City Hall
100 Main Street
Colleyville, Texas 76034
www.colleyville.com

Agenda Number 2a	Agenda Date 03/08/2018	Number
Type Presentation and Discussion		
Department Community Development		

Title

Review of proposed amendments to the Land Development Code

Strategic Plan

1.4 Communicate thoroughly and strategically

Explanation

Staff will present the progress of the internal reviews and recommendations for amendments to the Land Development Code (LDC). Staff has included the proposed LDC priority amendments list for reference.

The discussion will finalize the outstanding elements for Chapter 1: General Provisions and Chapter 3: Land Use and also include Chapter 4: Landscaping and Buffering and Chapter 6: Commercial Design Standards for review and discussion.

Attachments

1. Proposed LDC Priority Amendments List - CC 03.08.2018
2. Ch. 01 General Provisions - Redline v2 (03.02.18)
3. Ch. 03 Land Use - Redline v2 (03.02.18)
4. Ch. 04 Landscaping and Buffering - Redline v1 (03.02.18)
5. Ch. 06 Commercial Design Standards - Redline v1 (03.02.18)
6. Topics For Further Review - Ch. 1 & Ch. 3
7. Notification Example 1 - 1312 John McCain Rd
8. Notification Example 2 - 2313 Hall Johnson Rd
9. Notification Example 3 - 5713 Colleyville Blvd
10. Notification Example 4 - 8060 Precinct Line Rd
11. Perimeter Subdivision Fence Examples

Proposed LDC Priority Amendments

Update (March 2018): At the January 23, 2018 Council worksession meeting, staff presented the proposed amendments for Chapter 1: General Provisions and Chapter 3: Land Use to the City Council. The majority of the suggested amendments were accepted while several other amendments were noted by the City Council. Additionally, there were outstanding items that Council asked staff to review and present again to the City Council. Updated red-line versions for both of these chapters are included for review.

The follow-up discussion for Chapter 1 and Chapter 3 include the following topics:

Chapter 1

- Powers given to the ZBA by the authority of the City Council
- Increase in distance for adjacent property notice (increase from 200')

Chapter 3

- Pool/pond fencing requirements
- Open space requirement in PUD districts
- Building score/large commercial buildings (to be included as part of Ch. 6)
- Inclusion of standards for Perimeter Subdivision Fences
- Exemption of total number of accessory buildings for larger lots (>80,000 SF)
- Residential carport regulations
- Allowance for minor reduction in parking to be approved by staff

In addition to the follow-up discussion for Chapter 1 and Chapter 3, staff has included a red-line version of Chapter 4: Landscaping and Buffering and Chapter 6: Commercial Design Standards.

Update (January 2018): Staff presented a list of amendments to the Land Development Code (LDC) at the August 1st Council Worksession meeting. At that meeting, the Council confirmed that the list was complete and the priority ranking satisfactory.

Subsequently, the Council participated in a visioning workshop. As a result of the workshop, the Council asked that the list be presented again to discuss the prioritization of the amendments and the best method for completing the entirety of the task at hand. This was to be discussed at a worksession meeting in December. However, the meeting was cancelled and rescheduled to January 23, 2018.

In anticipation of the worksession, city staff has initiated a full review of LDC. A red-line version of Chapter 1: General Provisions and Chapter 3: Land Use are included with the intent to initiate discussion. A selected list of amendments includes:

- Increase in distance for adjacent property notice (increase to 300' from 200')
- Requirement for Concept Plan & Preliminary Drainage Study for all zoning change requests (including non-PUD)
- Requirement for properties with the R-10 zoning designation to comply with R-15 zoning standards
- Removal of 'density bonus' from the PUD zoning overlay
- Complete review of the Schedule of Permitted Principal Uses chart
- Inclusion of standards for Perimeter Subdivision Fences
- Change in maximum square footage allowance for accessory buildings (percentage of lot calculation)

- Revision to accessory dwelling (previously servant quarters) size limitations
- Allowance for minor reduction in parking to be approved by staff

A few sections that require additional review from staff include the following:

- Review of Non-Conforming Uses, Lots and Buildings section
- Open space & street frontage design regulations for PUD zoning
- Revision to ratio of alcohol to food receipts (increase to 60/40?)
- Design criteria and regulations for commercial buildings
- Residential carport regulations

Explanation: The attached list identifies the subject, chapter, estimated staff preparation time, estimated overall completion time, and indication on the need for outside help. Staff has attempted to identify and prioritize these amendments based on input and direction from the City Council over the past several months.

The list has primarily been arranged in ranking from high priority to lesser priority with a few less complicated amendments incorporated strategically in order to accomplish the list in a timely manner. Many of the top priorities were taken from the recently amended comprehensive plan, *Destination Colleyville*. The other amendments were either provided by the City Council or identified by staff for review.

The proposed timeline is very aggressive and will be a best case scenario. Staff will endeavor to follow this schedule as best as possible with the understanding that priorities can change and projects may shift depending on preferences, available resources, and outside influences.

Proposed LDC Priority Amendments

Proposed LDC Amendment	Staff Prep*	Total Time (Final action)	Outside Participation	Source
Revise the LDC to require an accompanying conceptual plan and ability to condition approval of straight zoning requests (non-PUD) to ensure new developments are built in substantial compliance to the approved conceptual plan. (Chapter 3)	1 – 2 months Oct – WS (worksession)	3 – 4 months Nov – P&Z Dec – CC	Yes – need help verifying legality and proper procedure	City Council/ Comp Plan
Evaluate annexation process for areas in the City's ETJ, if any.	2 – 3 months Nov – WS	4 – 5 months Dec – P&Z Jan – CC	None	City Council
Revise setback regulations for fencing on corner lots. (Chapter 3) – Possible reduction in the setback required on the 'street' side yard.	1 – 2 months Nov - WS	3 – 4 months Dec – P&Z Jan – CC	None	Staff
Revise PUD-R development standards to establish rural frontage (character) standards along key roadways. (Chapter 3)	2 – 3 months Dec – WS	4 – 5 months Jan – P&Z Feb – CC	Yes	Comp Plan
Revise PUD-R standards to require appropriate transitions and quality open space. (Chapter 3) – More specifically, establish design and performance criteria for open space to maximize value creation, tree preservation, preservation of rural frontage along key roadways, etc.	4 – 6 months Dec - WS	6 – 8 months Jan – P&Z Feb – CC	Yes	Comp Plan
Replace Chapter 5: Tree Preservation chapter of the LDC.	3 – 4 months Jan - WS	5 – 6 months Feb – P&Z Mar – CC	None	Staff
Revise regulations for accessory buildings regarding definition, size, setbacks, and more. (Chapter 3)	2 – 3 months Feb - WS	4 – 5 months Mar – P&Z Apr – CC	None	Staff
Revise regulations for Servants Quarters regarding maximum size allowed. (Chapter 3) – Allow for larger size through SUP approval process	1 – 2 months Feb – WS	3 – 4 months Mar – P&Z Apr – CC	None	Staff
Clean up and revisions to Chapter 7: Signage	4 – 6 months Mar – WS	6 – 8 months Apr – P&Z May – CC	Very little, if any	Staff
Review Chapter 4: Landscaping and Buffering as it relates to buffers between residential and non-residential uses, and amend as appropriate.	1 – 2 months Apr – WS	3 – 4 months May – P&Z June – CC	None	Staff
Create an integrated regulatory tool (through a Corridor Zoning/Overlay District or similar tool) to achieve a mix of commercial uses, appropriate transitions and buffers, and desired character that is tailored to the 4 different sections of the Boulevard as described in the vision.	4 – 6 months May – WS	6 – 8 months June – P&Z July – CC	Yes – would be 1 st overlay district for Colleyville	Comp Plan
Create public realm and streetscape standards to complement private realm standards.	2 – 3 months June – WS	4 – 5 months July – P&Z Aug – CC	None	Comp Plan
Streamline all commercial design standards into one section of the LDC. (Chapter 6) – Building and site design	3 – 4 months July – WS	5 – 6 months Aug – P&Z Sep – CC	None	Comp Plan
Ensure environmental concerns are included in the LDC to limit development that may significantly harm the environment.	???	???	Yes	Comp Plan

*Lead time to prepare for initial presentation to City Council worksession

Chapter 1

General Provisions

Rev. 05/04/2010

Section 1.1 Title

This document shall be known and may be cited as the Land Development Code of the City of Colleyville, Texas.

Section 1.2 Applicability

The provisions of this Land Development Code shall apply to all lots, parcels of land, rights-of-way, buildings and structures located within the Corporate Limits of the City of Colleyville.

Section 1.3 Authorization for Adoption of This Land Development Code

The regulations contained in the various chapters of this Land Development Code have been adopted upon approval of an ordinance, after public hearing, by the City Council of the City of Colleyville in accordance with the authority described within each chapter and the following:

1. *Chapter 51 – General Powers of Municipalities of the Texas Local Government Code*, which authorizes a municipality to adopt ordinances, rules, or police regulations that are for the good government, peace, or the trade and commerce of the municipality; and.
2. *The Home Rule Charter of the City of Colleyville*, which authorizes the City Council to exercise all powers granted to municipalities by the Constitution or the laws of the State of Texas.

Section 1.4 Purpose of the Land Development Code

The purpose of this Land Development Code is to promote the health, safety, and general welfare of the community and to:

1. combine zoning, subdivision and other regulations into a single document that can be used for development of property and public facilities in Colleyville, Texas;
2. establish reasonable standards of design and procedures for subdivisions in order to further the orderly layout and use of land, and to ensure proper legal descriptions of subdivided land;
3. provide that the cost of improvements which primarily benefit the tract of land being developed be borne by the owners or developers of the tract and that the cost of improvements which primarily benefit the entire community be borne by the community as a whole; and
4. avoid overlapping, conflicting or inconsistent regulations found in land use control systems consisting of separate zoning, subdivision, and other ordinances.

Section 1.5 Purpose of This Chapter

The purpose of this Chapter is to:

1. establish rules, regulations and procedures for the administration of this Land Development Code and to establish the process for amending this Code;

2. establish regulations which describe the process for considering waivers, variances and appeals regarding this Land Development Code; and
3. establish specific boards and commissions responsible for considering requests for a waiver or variance from a regulation or to hear an appeal of a decision of an Administrative Official authorized to enforce and administer this Land Development Code.

Section 1.6 Administration and Enforcement

The provisions of the Land Development Code shall be administered, interpreted and enforced by the City Manager, his designee, or by the administrator designated within this Code.

Section 1.7 Fees

The schedule of fees and charges associated with application filing, processing, plan review, or any other fee required by provisions of this Land Development Code, shall be established by the City Council. Furthermore, until all applicable fees, charges and expenses have been paid in full, no action shall be taken on any application or appeal authorized by this Land Development Code. Fees required by this Land Development Code shall not be refundable, except where a specific provision provides for refunding.

Section 1.8 Compliance Required

All land, buildings, structures or appurtenances thereon located within the City which are hereafter occupied, used, erected, altered or converted shall be used, placed and erected in conformance with the regulations prescribed herein. In their interpretation and application, the provisions of these regulations shall be construed to be the minimum requirements for the promotion of the public health, safety, convenience, comfort, morals and general welfare. Land used in meeting the requirements of this Land Development Code with respect to a particular use or building shall not be used to meet the requirements for any other use or building. No approval, authorization to proceed, or issuance of any certificate or permit shall be construed as an approval of a violation of the provisions of this document or of other ordinances of the City of Colleyville. Certificates presuming to give authority to violate or cancel the provisions of this document or of other ordinances of the jurisdiction shall be void.

Section 1.9 Certificate of Occupancy Required

Certificate of Occupancy requirements shall be in accordance with the currently adopted Building Code(s) in effect at such time.

~~1.9.A CERTIFICATE REQUIRED PRIOR TO OCCUPANCY~~

~~No building, or portion thereof, or parcel of land shall be occupied or used until a certificate of occupancy has been issued by the City. Furthermore, no non-residential building, or portion thereof, or parcel of land shall change in use or occupancy until a certificate of occupancy has been issued by the City. A current certificate of occupancy is required on all land, buildings, or portions thereof except non-habitable accessory buildings. Failure to comply with this provision may result in the issuance of a citation and/or constitute basis for denial of or disconnection from City utilities or to require a franchised utility company to do likewise.~~

~~1.9.B CONNECTION TO UTILITIES~~

~~No connection to the City utility systems shall be allowed unless and until a certificate of occupancy has~~

Commented [EW1]: The International Building Code (IBC) and International Residential Code (IRC) contain provisions for CO's and this language is contradictory or otherwise in conflict

been issued by the City Inspector. However, temporary connection of utilities for a specified duration may be authorized by the City Inspector for the purpose of clean up, construction or other such purposes.

1.9.C RECORDS

The Building Inspection Office shall maintain a record of all buildings or parcels of land for which a Certificate of Occupancy has been issued.

1.9.D CERTIFICATE OF OCCUPANCY APPLICATION

Application for a certificate of occupancy shall be made to the Building Inspection Office. No application for a certificate of occupancy shall be approved which does not, at a minimum, contain the following information: business name, business address, business phone number, type of proposed use, business owner, business owner's address, business owner's phone number and emergency phone number, applicant's driver's license number, applicant's date of birth, and applicant's signature.

1.9.E DISPLAY AND STATUS OF CERTIFICATE OF OCCUPANCY

1. All non-residential occupancies shall display a certificate of occupancy on the site and in a conspicuous place.
2. The holder of a certificate of occupancy for a non-residential occupancy is required to notify the Building Inspection Office of any change of address, name changes, or other pertinent information listed on the certificate of occupancy application.

Section 1.10 Project Under Construction at Time of Code Adoption

DELETE THIS SECTION

Nothing herein contained shall require any change in the plans, construction or designated use of a building actually under construction within the city on the effective date of this document and which entire building shall be completed within one (1) year from the effective date of the document or which building shall be maintained under continuous construction even though not completed within one (1) year. Nothing herein contained shall require any change in plan, construction or designated use of a building for which a building permit has been heretofore issued while such permit is valid and provided the building shall have been started within 180 days of the date of issuance of the permit and which entire building shall be maintained under continuous construction even though not completed within one (1) year.

Commented [EW2]: Time limitations are already addressed in the currently adopted building codes

Section 1.11 Compliance Required for Building Permits & Utility Services

DELETE THIS SECTION

No building or structure may be erected, constructed or installed on any lot, tract or parcel of land and public utilities shall not be extended or connected to a building or structure unless the lot, tract or parcel of land is in compliance with the provisions and requirements of this Land Development Code and all applicable Building Permits and authorizations to proceed are first obtained.

Commented [EW3]: Language is stating the obvious and utility connections are addressed by current codes and/or policies

Section 1.12 Waivers and Appeals - Generally

Any person seeking approval of a development as required by this Land Development Code may request a waiver of or a variance from a requirement contained in this Code, or appeal a decision of an Administrative Official by submitting a request using the procedures described in this Chapter. Due to the unique arrangement and statutory organization of this Land Development Code, provisions for waivers, variances and appeals of administrative decisions vary from chapter to chapter. The following table shows the approval authority for waiver, variance and appeal requests for the specific chapters of this Land Development Code.

Approval Authority for Waiver, Variance and Appeal Requests					
Chapter Title	City Council	P & Z Commission	ZBA	Sign Board	Staff
Chapter 2 – Definitions	N/A	N/A	See Section 1.16	N/A	N/A
Chapter 3 – Land Use	N/A	N/A	See Section 1.16	N/A	N/A
Chapter 4 – Landscaping & Buffering	N/A	N/A	N/A See Section 1.16	N/A	See Section 4.6 N/A
Chapter 5 – Tree Preservation	N/A	See Section 1.14	N/A	N/A	N/A
Chapter 6 – Building Design	N/A	See Section 1.14	N/A	N/A	N/A
Chapter 7 – Sign Regulations	N/A	N/A	N/A	See Section 1.15	N/A
Chapter 8 – Platting Procedures (except perimeter streets)	See Section 1.13	See Section 1.14 & 7.2	N/A	N/A	N/A
Perimeter streets	See Section 1.13	N/A	N/A	N/A	N/A
Chapter 9 – Subdivision Design & Required Facilities	See Section 1.13	N/A	N/A	N/A	N/A
Chapter 10 – Private Streets & Entrance Gates	See Section 1.13	N/A	N/A	N/A	N/A
Chapter 11 – Park Land Dedication	See Section 1.13	N/A	N/A	N/A	N/A
Chapter 12 – Erosion Control	See Section 1.13	N/A	N/A	N/A	N/A
Chapter 13 – Impact Fees	See Section 1.13	N/A	N/A	N/A	N/A
Chapter 14 – Engineering Design	See Section 1.13	N/A	N/A	N/A	N/A
Chapter 15 – Public Works Construction Details	See Section 1.13	N/A	N/A	N/A	N/A

Note to table above: N/A – Not Authorized

Section 1.13 Waivers and Appeals – City Council

Where specifically provided for in this Land Development Code, the City Council shall have the authority to consider requests for a waiver or to hear and decide an appeal from an administrative decision on a regulation. The City Council may approve, disapprove or modify such a request provided that such approval or modification will not be detrimental to the public safety, health, or welfare or injurious to other property. The applicant shall provide information to support a claim that there are extraordinary hardships or practical difficulties which may result from strict compliance with the regulation or that the public interest may be better served by an alternative proposal.

Commented [BB4]: Ordinance Amendment in 2017; needs to be updated by staff

Section 1.14 Waivers and Appeals – Planning and Zoning Commission

Where specifically provided for in this Land Development Code, the Planning and Zoning Commission shall have the authority to consider a waiver or to hear and decide an appeal from an administrative decision on a regulation. The Planning and Zoning Commission may approve, disapprove or modify such a request provided that such approval or modification will not be detrimental to the public safety, health, or welfare or

injurious to other property. The applicant shall provide information to support a claim that there are extraordinary hardships or practical difficulties which may result from strict compliance with the regulation or that the public interest may be better served by an alternative proposal.

Section 1.15 Waivers and Appeals – Sign Board of Appeals

Note: Section 1.15 replaced in its entirety. (Ord. O-03-1414 / 09-02-2003)

- A. Creation of Sign Board of Appeals – There is hereby created a Sign Board of Appeals consisting of five (5) members and two (2) alternate members, each to be appointed by the Council for a two year term, or until a successor is appointed. Three members of the Board and one (1) alternate member shall be selected in even numbered years and two members and one (1) alternate member in odd numbered years. In the event of a vacancy, the Council shall appoint a member to serve for the unexpired term. Alternate Board members shall serve in the absence of regular members. The Sign Board of Appeals shall consist of the same members and officers as the Zoning Board of Adjustment.
- B. Authority of the Sign Board of Appeals – The Sign Board of Appeals shall have the authority to hear and decide on requests for a variance from the requirements contained in *Chapter 7 – Sign Regulations* of this Land Development Code. The Sign Board of Appeals shall also have the authority to hear and decide an appeal of an administrative decision on a regulation contained in *Chapter 7 – Sign Regulations* of this Land Development Code. The authority established under this paragraph shall be applicable to a definition contained in *Chapter 2 – Definitions* of this Land Development Code required for the administration and enforcement of the provisions of *Chapter 7 – Sign Regulations*.
- C. Quorum and Organization — ~~Four~~ Four members of the Sign Board of Appeals shall constitute a quorum. In the event of the absence of the Chairman and Vice-Chairman, the four members constituting the quorum shall elect for that meeting a member to preside as Acting Chairman and to assume all duties of the Chairman.
- D. Meetings, Hearings and Rules of Procedures – The Board shall adopt rules of procedure for the conduct of its meetings. Meetings shall be held at the call of the Chairman or at such times as the Board may determine. All meetings and hearings shall be open to the public and shall be conducted in accordance with the procedure set forth in these regulations and the rules of procedure adopted by the Sign Board of Appeals. Such rules of procedure may be amended by the Sign Board of Appeals membership. The minutes of the meetings shall be recorded, showing the vote of each member upon the question, and shall be made a matter of public record. The concurring vote of four members of the Board shall be necessary to render a decision on any matter before the Board. The Sign Board of Appeals shall meet monthly, provided there has been an appeal or request for variance filed with the ~~Building~~ Administrative Official on or before the last date to receive applications prior to the scheduled meeting date. The Building Official shall publish a calendar establishing such final application dates.
- E. Variance – A person may request a variance from a requirement contained in *Chapter 7 – Sign Regulations* by filing said request with the ~~building official~~ Administrative Official. A request for a variance shall be accompanied by a non-refundable filing fee. The filing fee shall be established by separate ordinance by the City Council. A request for variance shall be referred for consideration to the Sign Board of Appeals. In considering a request for a variance, the Sign Board of Appeals shall consider, among other things, the degree of variance, the reason for the variance requested, the location of the variance request, the duration of the requested variance, the effect on public safety, the protection of neighborhood property, the degree of hardship or injustice involved, and the effects of the variance on the general plan of regulation of signs within the City.
- F. Fees – No action shall be taken on any application submitted to the Sign Board of Appeals until all applicable fees have been paid in full. No refund of any application fee shall be made after the request has been advertised and scheduled for consideration by the Board.
- G. Public Hearing and Written Notification – No action to approve or deny any application shall be taken until the Board has held a public hearing and received comment, and only after written notice of the public hearing of the date, time and place where the variance request is to be considered has been sent to the

Commented [EW5]: Provision should not list a specific position

Commented [EW6]: Provision should not list a specific position

owners of real property lying within ~~two~~ three hundred (~~200~~300) feet of the property where the application is being considered. Such notice shall be given to each property owner as listed on the last approved tax roll not less than fifteen (15) days before the date set for hearing by depositing letters properly addressed and postage paid in the United States Post Office.

Commented [BB7]: Increased for more notification coverage

- H. Appeal to City Council – The decision by the Sign Board of Appeals shall be final, unless the applicant submits a written notice of appeal within ten (10) days from the date of the action by the Board. The enforcement official shall re-notify all property owners lying within ~~two~~ three hundred (~~200~~300) feet of the area being considered and place the applicant's appeal request on the next available agenda for consideration by the City Council.

Commented [BB8]: Increased for more notification coverage

Section 1.16 Variances & Appeals – Zoning Board of Adjustment

The Zoning Board of Adjustment shall have the authority to consider requests for a variance of a zoning regulation or to hear an appeal from an administrative decision on a regulation in *Chapter 3 – Land Use Regulations*; and Chapter 4 – Landscaping and Buffering; ~~and Chapter 6 – Building Design (except for requests regarding tree mitigation requests which are considered by the Planning and Zoning Commission)~~. The Zoning Board of Adjustment shall additionally have the authority to consider requests for an interpretation of any regulation or definition contained in this Land Development Code. The rules and procedures contained in this section shall be applicable to such request.

Commented [BB9]: Authority for Chapter 6 is the P&Z Commission

1.16-A. A ZONING BOARD OF ADJUSTMENT ESTABLISHED

A Zoning Board of Adjustment is hereby established, which shall consist of five (5) members and two (2) alternates, each to be appointed for a two (2) year alternate term by the City Council. All vacancies occurring on the Zoning Board of Adjustment shall be filled by appointment by the City Council. Each year after a new term begins members shall elect a Chairman and Vice-Chairman, a new term beginning at the first meeting in October. Members of the Zoning Board of Adjustment may be removed from office by the City Council for cause upon written charges and after a public hearing. Vacancies shall be filled by resolution of the City Council for the unexpired term of the member affected. The City Council shall appoint two (2) alternate Board members to serve in the absence of regular members.

1.16-B. B PROCEEDINGS

The Zoning Board of Adjustment shall adopt rules necessary to the conduct of its affairs and in keeping with the provisions of this ordinance. Meetings shall be held at the call of the Chairman or Vice-Chairman and at such other times as the Board may determine. The Chairman, or in his absence the Acting Chairman, may administer oaths and compel the attendance of witnesses. All meetings shall be open to the public.

Said Board shall keep minutes of its proceedings, showing the vote of each member upon each question, or if absent or failing to vote indicating such fact, and shall keep records of its examinations and other official actions, all of which shall be made a matter of public record and be immediately filed in the office of the City and maintained by the person acting as City Secretary.

1.16-C. C HEARINGS; APPEALS; NOTICE

Appeals to the Zoning Board of Adjustment concerning interpretation or administration of a regulation may be taken by any person aggrieved or by any officer, agency, department or commission of the governing body of the City affected by any decision of the Administrative Official. Such appeals shall be taken within a reasonable time, not to exceed fifteen (15) days or such lesser period as may be provided by the rules of the Board, by filing with the Administrative Official on behalf of the Zoning Board of Adjustment a notice of appeal specifying the grounds thereof. The Administrative Official shall forthwith transmit to the Board all papers constituting the record upon which the action appealed from was taken.

The Board shall fix a reasonable time for the hearing of an appeal, give public notice thereof as well as written notice to the parties in interest, and decide the same within a reasonable time. At the hearing, any party may appear in person or by an agent or attorney.

1.16.D STAY OF PROCEEDINGS

An appeal stays all proceedings in furtherance of the action appealed from, unless the Administrative Official from whom the appeal is taken certifies to the Zoning Board of Adjustment after the notice of appeal is filed with him that, by reason of facts stated in the certificate, a stay would, in his opinion, cause imminent peril to life and property. In such case, proceedings shall not be stayed other than by a court of record on application, on notice to the Administrative Official from whom the appeal is taken and on due cause shown.

1.16.E JURISDICTION OF ZBA

When in its judgment the public convenience and welfare will be substantially served, the Board of Adjustment may issue appropriate orders to the Administrative Official to guard against future error; and to promulgate appropriate procedure in addition to that under which the Administrative Official already operates. When the appropriate use of the neighboring property will not be substantially or permanently injured, the Board of Adjustment may in specific cases, after public notice and public hearing, (subject to appropriate conditions and safeguards and in accordance with Section 211.009, Local Government Code, V.T.C.A.), authorize the following variances and special exceptions to the regulations herein established and take action relative to the continuance or discontinuance of a nonconforming use. Thus, the Board has jurisdiction to:

1. Hear and decide appeals where it is alleged there is error on any order, requirement, decision or determination made by the Administrative Official in the enforcement of this code.
2. Interpret the intent of the Zoning District Map where uncertainty exists because the physical features, on the ground vary from those on the Zoning District Map and none of the rules set forth in *Chapter 3 – Land Use, Section 3.5.C - "Rules For Interpretation of District Boundaries"* apply.
3. Approve the use of a lot or lots in a residential district contiguous to (even if separated by a street or alley) an apartment, office, retail, commercial or industrial district for off-street parking of passenger vehicles subject to such standards and safeguards as are appropriate for the protection of adjacent residential uses.
4. Initiate on its motion or cause presented by interested property owners an action to bring about the discontinuance of a nonconforming use in accordance with the following:
 - a. Require the discontinuance of a nonconforming use under any plan whereby full value of the structure can be amortized within a definite period of time, taking into consideration the general character of the neighborhood and the necessity for all property to conform to the regulations of this ordinance.
5. Permit the change of occupancy of a nonconforming use to another nonconforming use in accordance with the provisions of *Chapter 3 – Land Use* of this Land Development Code.
6. Permit the enlargement of a nonconforming use in accordance with the provisions of *Chapter 3 Land Use* of this Land Development Code.
7. Permit the reconstruction of a nonconforming structure or building on the lot or tract occupied by such building, provided such reconstruction does not, in the judgment of the Board, prevent the return of such property to a conforming use or increase the nonconformity of a nonconforming structure and provided that such actions conform to the non-conforming provisions of *Chapter 3 – Land Use* of this Land Development Code.

8. Require the vacation and demolition of a nonconforming structure, which is deemed to be obsolete, dilapidated or substandard.
9. Vary the provisions and conditions required for the development of off-street parking facilities when such variations are found to be in the interest of the area and necessary to secure reasonable parking use of a specific parcel of land.
10. Permit such variance of the front yard, side yard, rear yard, lot width, lot depth, coverage, minimum sidewalk or setback standards, off-street parking or off-street loading or visibility obstruction regulations where the literal enforcement of the provisions of this ordinance would result in an unnecessary hardship, and where such variance is necessary to permit a specific parcel of land which differs from other parcels of land in the same district by being of such restricted area, shape or slope that it cannot be developed in a manner commensurate with the development permitted upon other parcels of land in the same district. A modification of the standards established by this ordinance shall not be granted to relieve a self-created or personal hardship, nor for financial reason only, nor shall such modification be granted to permit any person a privilege in developing a parcel of land not permitted by this ordinance to other parcels of land in the district.
11. Permit such variances of fence heights when in the opinion of the Board such fence will not adversely affect neighboring property.

1.16.F SPECIAL EXCEPTIONS; CONDITIONS GOVERNING APPLICATIONS; PROCEDURES

A special exception shall not be granted by the Board of Adjustment unless and until:

1. A written application for a special exception is submitted indicating the section of this ordinance under which the special exception is sought and stating the grounds on which it is required.
2. Notice shall be given at least fifteen (15) days in advance of public hearing. The owner of the property for which special exception is sought or his agent shall be notified by certified mail. Notice of such hearings shall be posted at the City Hall; and one time in the official publication of the City, stating the time, place and nature of such hearing, at least fifteen (15) days prior to the public hearing. All property owners within two ~~three~~ hundred (290300) feet of the property shall be notified by mail not less than fifteen (15) days prior to the date of the public hearing.
3. The public hearing shall be held. Any party may appear in person, or by an agent or attorney.
4. The Zoning Board of Adjustment shall make a finding that it is empowered to grant the special exception, and that the granting of the special exception will not adversely affect the public interest.
5. In granting a special exception, the Zoning Board of Adjustment may also prescribe a time limit for which the special exception may continue. Failure to comply with this requirement stipulated by the Board shall void the special exception permit issued.
6. Violation of any reasonable provisions, conditions and safeguards that are made a part of the terms under which the special exception permit granted shall be deemed in violation of this ordinance and punishable under the penalty section of this Land Development Code.

1.16.G VARIANCES; CONDITIONS GOVERNING APPLICATIONS; PROCEDURES

The Zoning Board of Adjustment may authorize upon appeal in specific cases such variance from the terms of this ordinance as will not be contrary to the public interest where, owing to special conditions, a literal enforcement of the provisions of this ordinance would result in unnecessary hardship. A variance from the terms of this ordinance shall not be granted by the Zoning Board of Adjustment unless and until:

1. A written application for a variance is submitted demonstrating:

Commented [BB10]: Increased for more notification coverage

- a. That special conditions and circumstances exist which are peculiar to the land, structure, or building involved and which are not applicable to other lands, structures, or buildings in the same district;
 - b. That literal interpretation of the provisions of this ordinance would deprive the applicant of rights commonly enjoyed by other properties in the same district under the terms of this ordinance;
 - c. That the special conditions and circumstances do not result from the actions of the applicant;
 - d. That granting the variance requested will not confer on the applicant any special privilege that is denied by this ordinance to other lands, structures, or buildings in the same district;
 - e. No nonconforming use of neighboring lands, structures, or buildings in the same district, and no permitted or nonconforming use of lands, structures, or buildings in other districts shall be considered grounds for the issuance of a variance.
2. Notice shall be given at least fifteen (15) days in advance of public hearing. The owner of the property for which requested variance is sought or his agent shall be notified by certified mail. Notice of such hearings shall be posted at the City Hall; and one time in the official publication of the City, stating the time, place and nature of such hearing, at least fifteen (15) days prior to the public hearing. All property owners within ~~two~~ three hundred (~~200~~300) feet of the property shall be notified by mail not less than fifteen (15) days prior to the date of the public hearing.
 3. The public hearing shall be held. Any party may appear in person, or by an agent or by attorney.
 4. The Zoning Board of Adjustment shall make findings that the applicant has met the requirements of paragraph 1 above.
 5. The Board shall further make a finding that the reasons set forth in the application justify the granting of the variance, and that the variance is the minimum variance that will make possible the reasonable use of the land, building, or structure.
 6. The Zoning Board of Adjustment shall further make a finding that the granting of the variance will be in harmony with the general purpose and intent of this ordinance, and will not be injurious to the neighborhood, or otherwise detrimental to the public welfare.

In granting any variance, the Zoning Board of Adjustment may prescribe appropriate conditions and safeguards in conformity with this ordinance. Violation of such conditions and safeguards, when made a part of the terms under which the variance is granted, shall be deemed a violation of this ordinance and punishable under the penalty section of this Land Development Code.

Under no circumstances shall the Board grant a variance to allow a use not otherwise permissible under this section in the district involved, or any use expressly or by implication prohibited by the terms of this ordinance in said district.

1.16.H DECISION OF ZONING BOARD OF ADJUSTMENT

The concurring vote of four members of the Board shall be necessary to reverse any order, requirement, decision, or determination of the Administrative Official, or to decide in favor of the applicant on any matter upon which it is required to pass under this Land Development Code, or to effect any variation in the application of this ordinance.

1.16.I APPEAL PROCEDURES - ZBA

1. Any person or persons, or any board, taxpayer, department, commission or agency of the City aggrieved by any decision of the Zoning Board of Adjustment may seek review by a court of record of such decision, and under the time limit specified in Section 211.011, Local Government

Commented [BB11]: Increased for more notification coverage

Code, V.T.C.A. If no appeal has been taken from the Zoning Board of Adjustment ruling within the time limit specified under the above mentioned Article, the Board's ruling shall be final.

2. It is the intent of this ordinance that all questions of interpretation and enforcement shall be first presented to the Administrative Official, and that such questions shall be presented to the Zoning Board of Adjustment only on appeal from the decision of the Administrative Official, and that recourse from the decisions of the Zoning Board of Adjustment shall be to the courts as provided by law.
3. It is further the intent of this ordinance that the duties of the City Council in connection with this section shall not include hearing and deciding questions of interpretation and enforcement that may arise. Under this ordinance the City Council shall have only the duties of considering and adopting or rejecting proposed amendments, or the repeal of this ordinance, as provided by law.
4. Conditions: The Board or City Council, as may apply, is empowered to impose upon any variance or special exception any condition reasonably necessary to protect the public interest and community welfare.

Section 1.17 Reserved

Section 1.18 Amending the Land Development Code

The regulations and restrictions imposed by this Land Development Code and the districts and boundaries created by the Official Zoning Map may be amended from time to time using the procedures provided in this section.

1.18.A AMENDING A SUBDIVISION PLAT REGULATION

A subdivision plat regulation as contained in Chapters 8, 9, 10, 11, 12, 14 & 15 of this Land Development Code, may be amended upon adoption of an ordinance approved by the City Council after public hearing. Notice of said public hearing to be given in a newspaper having general circulation in the city not less than ten ~~fifteen~~ (1015) days prior to the hearing. The City Council may request the recommendation of the Planning and Zoning Commission on any proposed amendment to a plat regulation. Said amendment shall be additionally subject to the standard rules, regulations and procedural requirements established in Chapter 212 – Local Government Code and Article VI – Charter of the City of Colleyville.

Commented [BB12]: Current practice is 15 days

1.18.B AMENDING A ZONING REGULATION OR THE OFFICIAL ZONING MAP

The City Council may from time to time amend, supplement, change, modify or repeal the regulations and restrictions imposed in Chapter 1 – General Provisions; Chapter 2 – Definitions; or Chapter 3 – Land Use, of this Land Development Code, and the districts and boundaries described on the Official Zoning Map, using the procedures described in this section. Such amendment shall additionally be subject to the rules and procedures in Chapter 211 – Local Government Code, and Article VI of the Charter of the City of Colleyville.

1. Zoning Regulation Amendments – Any person or corporation may petition the City Council for a change or amendment to the provisions of these regulations; or the Planning and Zoning Commission or City Council may, on its own motion, initiate study and proposal for changes or amendments to a zoning regulation in the public interest.
2. Zoning District Boundary Changes – Any person or corporation having a proprietary interest in a parcel of land may request a change in zoning on such property; or the Planning and Zoning Commission or City Council may, on its own motion, initiate proceedings to consider a change in zoning on a parcel of land. All requests for a change in zoning shall be submitted, together with the required fee, to the Administrative Official, which officer shall cause notices to be sent and the

request placed on the Planning and Zoning Commission agenda. Only one application for a zoning change will be considered at any one time on a parcel of land. No additional rezoning application on a parcel of land will be considered until final action of any pending application has been completed, subject to the time limits imposed elsewhere in these regulations.

3. **Fees** – Until all applicable fees, charges, expenses and delinquent city, county, and school taxes have been paid in full, no action shall be taken on any zoning application. No refund of any application fee shall be made after the request has been scheduled for consideration by the Commission.
4. **Commission Public Hearing and Written Notification** - Before making report of an application for a planned development, special use permit, or proposed amendment to a zoning regulation or zoning district boundary, the Planning and Zoning Commission shall hold a public hearing and receive comment in accordance with the following:
 - a. No less than ~~ten~~ fifteen ~~(10)~~ (15) days notice of the time, place and nature of the public hearing shall be published in publication having general circulation in the city of Colleyville.
 - b. When a proposed change affects a specific tract of land, written notice of the public hearing shall be sent to all owners of real property lying within ~~two hundred~~ three hundred ~~(200)~~ (300) feet of the area being considered. Such notice to be given to each property owner as listed on the last approved tax roll not less than ~~ten~~ fifteen ~~(10)~~ (15) days before the day set for hearing by depositing letters properly addressed and postage paid in the United States Post Office. The applicant will be sent notice by certified mail. The land area within 200 feet of the proposed Special Use Permit shall be used to calculate whether a protest against the request would require a super-majority vote of the City Council to approve the Special Use Permit.
 - i. **Alcohol and Package Store SUP Requests** – When a rezoning application includes a provision for a Special Use Permit for the sale of alcoholic beverages or a package store, the written notification of the public hearing stated in the preceding paragraph shall be sent to all owners of real property lying within five hundred (500) feet of the area being considered. The land area within 200 feet of the proposed Special Use Permit shall be used to calculate whether a protest against the request would require a super-majority vote of the City Council to approve the Special Use Permit. (Ord. O-03-1399 / 04-15-2003).
5. **Sign Posting** - The Administrative Official is directed to cause a sign to be placed upon the property clearly visible to passersby, which states that the property is the subject of a rezoning application (or words of like intent). The sign shall be posted at least ten (10) days prior to the hearing and shall remain posted until the hearing. Failure to perform this particular notice provision shall, however, in no way prevent the Planning and Zoning Commission from hearing the application and disposing of the issues involved on the hearing date.
6. **Report of Commission** – After a public hearing, the Planning and Zoning Commission shall vote on the proposal and report its recommendation to the City Council. The proposal, as recommended by the Commission, shall be placed on the next available City Council agenda, provided proper notice has been given.
 - a. **Amended Proposals:** The Planning and Zoning Commission may consider a request from the applicant to amend the proposal without additional notification of adjacent property owners, provided that the amended request is determined by the Commission as being more restrictive than the initial request and the boundary or content of the amended request is not expanded.
 - b. **Notice of Appeal:** Denial of the proposal by the Planning and Zoning Commission shall be final, unless the applicant submits a written notice of appeal within ten (10) days from the date of the action by the Commission. The Administrative Official shall re-notify all property owners lying within two hundred (200) feet of the area being considered and place the

Commented [BB13]: Current practice is 15 days; same as ZBA notice

Commented [BB14]: Increased for more notification coverage

Commented [BB15]: Current practice is 15 days; same as ZBA notice

Commented [BB16]: Similar practice as outlined for Alcohol & Package Store SUP Requests in the paragraph below.

applicant's rezoning request on the next available agenda for consideration by the City Council.

- c. Failure to Act Provision: Failure by the Commission to act on an amendment within sixty (60) days of the first date of public hearing shall be considered a recommendation for denial of the amendment.
7. City Council Public Hearing and Newspaper Notice - A zoning regulation or a zoning district boundary may be amended by the City Council upon adoption of an ordinance, but no amendment shall be made without public hearing before the City Council. No less than fifteen (15) days notice of the time, place and nature of such hearing shall be published in publication having general circulation in the City of Colleyville. No amendment to a regulation or to a district boundary shall be considered by the City Council until a report of the proposed amendment has been made by the Planning and Zoning Commission. Unless denied by the Planning and Zoning Commission, every rezoning request receiving final approval of the Commission shall be forwarded to the City Council for consideration, unless the applicant has requested the proposal be withdrawn. The City Council may refer any amended rezoning request back to the Planning and Zoning Commission for further study and recommendation.
8. Special City Council Voting Requirements - No change of which the Planning and Zoning Commission has recommended denial or in case of a protest against such change, signed by the owners of twenty (20) percent or more of either the area of lots or land included in such proposed change, or lots or land immediately adjoining same and extending two hundred (200) feet therefrom, filed with the City Secretary, shall be passed except by a favorable vote of three-fourths (3/4) of all members of the City Council. In computing the percentage of land area, the area of streets and alleys shall be included in the computation.
9. Withdrawal - Any proposal or application that is withdrawn by the applicant before a vote is considered by the City Council shall not be subject to the time limit for submittal of a new application.
10. Time Limit for Re-submittal - No one shall request a zoning change on the same parcel of property more often than once every twelve (12) months. However, a request for a change of zoning of a parcel of property to a different zoning classification than that previously requested may be filed as frequently as desired.
11. Submittal Requirements for Zoning District Change - Every petition for a zoning district change shall be accompanied by supporting documents of the area petitioned for a zone change. In general the petitioners shall submit a drawing and supporting documents as follows:
- a. ~~Scale - No smaller than 1/4" = 100'~~
 - b. ~~Zoning and use of adjacent property~~
 - c. ~~Vicinity Map - showing location of the land within the community~~
 - d. ~~Physical features - The location of existing streets, water courses, railroads, etc., on and adjacent to the subject property~~
 - e. ~~100-year flood plain limits within the subject property~~
 - f. ~~Legal description (metes and bounds) of the total site area proposed for rezoning, development, or special use permit to be included on the Zoning Exhibit and submitted on a separate letter or legal size single page.~~

Concept Plan - The Concept Plan, which may be conceptual and general in nature, but in sufficient detail appropriate for the type of development being proposed and shall at a minimum include the following items, where applicable:

Commented [BB17]: New regulation for Concept Plan & Preliminary Drainage Study requirement

- a. Proposed layout, indicating the approximate size and dimensions of all residential lots
 - b. Proposed land uses and building locations
 - c. Landscaping, lighting, fencing and screening of common areas
 - d. General locations of existing tree clusters
 - e. Location and construction type of perimeter fencing
 - f. Design of ingress and egress with description of any special pavement treatments
 - g. Location and description of subdivision signs and landscaping at entrance areas
 - h. Street names on all proposed streets
 - i. Drainage Analysis – The applicant shall submit a Preliminary Drainage Analysis to determine the need for drainage facilities. The Preliminary Drainage Analysis shall be prepared in accordance with drainage analysis requirements contained in Chapter 14 – Engineering Design Standards of the Land Development Code.
 - j. For properties with significant slope, cross section exhibits shall be required showing the impact of the proposed development with adjacent properties.
- Exception: A change of zoning application may be submitted and approved without a Concept Plan if the scale of the request does not justify preparation of the plan.
- g. Preliminary drainage study.

Commented [BB18]: Added per Council direction

12. **Special Application Requirements** - Site Plan and Supporting Documents Required - Every petition for a zoning district change to R-D, R-MF, MH, C-PO, CN, C-C and M-L and all Special Use Permit requests shall additionally be accompanied by a site plan and supporting documents of the area petitioned for a zone change. The purpose of the site plan is to illustrate the logical arrangement of the elements on the land and to show relationships of elements to each other.

The petitioner is encouraged to meet with the appropriate city staff member in an informal work session to ascertain the exact extent of plans and documents required, if any, prior to the City initiating the advertisement for public hearing on the petition. The Administrative Official may waive the site plan requirement altogether when appropriate.

Commented [BB19]: In rare situations a site plan may not be warranted based on the limited scale of the zoning request

The general type and extent of site plans and supporting documents which may be required of the petitioner include, but are not necessarily limited to:

- a. Site Plan, meeting all of the requirements of ~~a "Preliminary Plat"~~ Section 3.31.D Site Plan Approval Required as described in the City's ~~subdivision regulations~~ Land Use chapter, except that topographic and drainage map information provisions may be waived by the reviewing body when the inclusion of such data would not materially contribute to the necessary evaluation of the project petition. Additional site plan drawing information which the reviewing body may require include:
 1. Existing and proposed zoning district classifications and boundaries;
 2. General outline of extensive tree cover areas;
 3. Drainage ways and 100-year flood plain limits;
 4. Proposed treatment for screening the perimeter of the land embraced by the petition, including screening of internal separations of land use where required;
 5. Proposed internal non-vehicular circulation linkages, such as: pedestrian paths and hike trails; bike trails; and equestrian bridle paths, where applicable, including their interrelationships with vehicular circulation systems and proposed handling of points of conflict;
 6. A graphic illustration showing the location of proposed buildings, driveways and all physical elements and a tabular summary schedule indicating:

- a) The gross acreage and percent of each type of zoning category proposed;
 - b) The gross acreage and percent of each type of land use proposed, with streets and open space categories listed separately, and residential uses further stratified as to type, i.e., single family, two-family, multifamily, townhouse, etc., including the total gross project acreage;
 - c) The gross residential density of each type of residential land use proposed, expressed in dwelling units per acre; and based on net residential land use plus one-half of any abutting street, only;
 - d) The quantitative number of dwelling units proposed for each residential dwelling type, i.e., single family, two-family, etc.;
 - e) Proposed maximum lot coverage by building types (i.e., one-family, multifamily, commercial, office, industrial, etc.) expressed in terms of percent or floor area ratio of the lot or site.
- b. Architectural Drawings, such as elevations, concept sketches or renderings depicting building types and other significant proposed improvements including the treatment and use of open spaces, etc., where the submission of such drawings would more clearly portray the nature and character of the applicant's land use and development proposals.
- c. Written Documents, in narrative form on 8-1/2" X 11" sheets, including:
- 1. Statement(s) on planning objectives to be achieved in the land use/development proposal, including a narrative description of the character of the proposed development and rationale behind the assumptions and choices made by the applicant, including use and ownership of open spaces, etc.
 - 2. Legal description of the total site area proposed for rezoning, development or special use permit.
 - 3. A development schedule, if any, indicating the approximate date(s) when construction of the proposed development, and subsequent stages or phases can be expected to begin and be completed, to the best of the applicant's knowledge and belief.
 - 4. A statement as to the present and proposed ownership of the site or parcels thereof embraced by the application.
 - 5. Statement(s) as to how and when the applicant proposes to provide water and sewer to the development.
 - 6. Signature(s) and title(s) of the applicant(s) and preparer(s) of the written documents certifying the information presented in all of the plans and supporting documents reflect a reasonably accurate portrayal of the general nature, character and feasibility of the applicant's proposals. All signatures will be dated.
13. **Traffic Impact Analysis** - When a proposed development is projected to generate more than 1000 vehicle trips per day, a traffic impact analysis shall be required with the rezoning request. The traffic impact analysis shall be prepared in accordance with the requirements of the Director of Public Services. The purpose of the traffic impact analysis is to determine the need for traffic mitigation measures which may include, but are not limited to, dedication of additional right-of-way, construction of turning lanes, or construction of traffic control facilities.

1.18.C RESERVED

1.18.D AMENDING ALL OTHER REGULATIONS

A regulation contained in any of the other Chapters of this Land Development Code that have not been previously mentioned may be amended upon adoption of an ordinance approved by the City Council after public hearing. Notice of said public hearing to be given in a newspaper having general circulation in the city not less than ~~ten~~ fifteen (1015) days prior to the hearing. The City Council may request the recommendation of the Planning and Zoning Commission on any proposed amendment. Amendments shall be additionally subject to the standard rules, regulations and procedural requirements established in Chapter 51 – Local Government Code and Article VI of the Charter of the City of Colleyville.

Commented [BB20]: Current practice is 15 days

Section 1.19 Violations and Penalties

Any person, firm or corporation violating any of the provisions of this Land Development Code shall be guilty of a misdemeanor and upon conviction thereof shall be fined in a sum not to exceed two thousand dollars (\$2,000.00), unless a lesser fine is provided for in the section of the Code so violated. Each and every day such violation continues shall constitute a separate offense and shall be punishable as such.

The owner or tenant of any building, structure, premises, or part thereof, and any architect, builder, contractor, engineer, planner, agent, or other person who commits, participates in, assists in, or maintains such violation may each be found guilty of a separate offense and suffer the penalties herein provided.

Section 1.20 Relationship to Other Laws and Restrictions

It is not intended by this Land Development Code to interfere with or abrogate or annul any other resolution or rule, regulation or permit, previously adopted or issued or which shall be adopted or issued, not in conflict with any of the provisions contained herein; nor is it intended by this Land Development Code to interfere with or abrogate or annul any easements, covenants or other agreements between parties; provided, however, that where this Land Development Code imposes a greater restriction upon land, buildings, or structures than is imposed by other ordinances, covenants, restrictions or agreements, then the provisions of this Code shall govern. If other ordinances are more strict than this Code, then the more strict provisions shall prevail.

Section 1.21 Repeal of Conflicting Ordinances

All ordinances or parts of ordinances in conflict herewith are repealed to the extent of the conflict only.

Section 1.22 Severability Clause

It is hereby declared to be the intention of the City Council of the City of Colleyville, that the sections, paragraphs, sentences, clauses and phrases of this Code are severable, and if any phrase, clause, sentence, paragraph, or section of this Code shall be declared unconstitutional, such unconstitutionality or invalidity shall not affect any of the remaining phrases, clauses, sentences, paragraphs or sections of this Code since the same would have been enacted by the City Council without the incorporation in this Code of any such unconstitutional or invalid phrase, clause, sentence, paragraph or section.

Section 1.23 Amendments to This Chapter

Reserved for listing of amendments to this Chapter.

Ord. Number	Date	Subject
O-03-1399	04/15/2003	500 foot notification for alcohol SUP requests
O-03-1414	09/02/2003	Sign Board of Appeals authority
O-10-1750	05-04-2010	Addition of Package Store SUP Requirements

Chapter 3 Land Use

Rev. 04/15/2014

Section 3.1 – Purpose of This Chapter

The zoning regulations and districts herein established have been made in accordance with a comprehensive plan for the purpose of promoting health, safety, morals and general welfare of the City of Colleyville. They have been designed to lessen congestion in the streets; to secure safety from fire, panic and other dangers; to provide adequate light and air; to prevent the overcrowding of land; to avoid undue concentration of population; to facilitate the adequate provision of transportation, water, sewage, schools, parks and other public facilities. The zoning districts have been created with reasonable consideration, among other things, of the character of the district and its peculiar suitability for the particular uses and with a view of conserving the value of buildings and encouraging the most appropriate use of land throughout the community.

Section 3.2 – Authorization for Adoption of This Chapter

The regulations contained in this Chapter have been adopted under the authority of *Chapter 211 – Municipal Zoning Authority of the Texas Local Government Code*, which authorizes a municipality to divide a municipality into districts and, within each district, regulate the erection, construction, reconstruction, alteration, repair, or use of buildings, other structures, or land. This Chapter is also adopted under the authority of the *Home Rule Charter of the City of Colleyville*, which authorizes the City Council to exercise all powers granted to municipalities by the Constitution or the laws of the State of Texas.

Section 3.3 – Variances and Appeals

Any person seeking approval of a development as required by this Land Development Code may request a variance from a requirement contained in this Chapter, or appeal a decision of an Administrative Official by submitting a request using the procedures described in *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.4 – Definitions

Definitions applicable to this Chapter may be found in *Chapter 2 - Definitions* of this Land Development Code.

Section 3.5 – Establishment of Districts

- A. Official Zoning Map – The City is hereby divided into zones, or districts, as shown on the Official Zoning Map which, together with all explanatory matter thereon, is hereby adopted by reference and declared to be a part of this Chapter. The Official Zoning Map shall be identified by the signature of the Mayor, attested by the City Secretary, and bearing the seal of the City under the following words: "This is to certify that this is the Official Zoning Map referred to in Ordinance No. 0-77-248 of the City of Colleyville, Texas," together with the date of adoption of this Chapter.
1. The Official Zoning Map shall be made current from time to time to reflect the changes and amendments, if any, that are approved by the City Council. Any such notations to bring said map current shall include, but not be limited to, the following: Ordinance number of zoning change, date of minutes of passage of said ordinance, boundary of zoning change, zoning classification declared by changing ordinance, and the initial of the City Secretary amending the map. Any unauthorized change of whatever kind to the Official Zoning Map by any person shall be and the same is prohibited.

Commented [BB1]: Need to clarify

2. The Official Zoning Map is not intended to control the procedural prerequisites applicable and the ordinances should be looked to as the authoritative source for all zoning. The Official Zoning Map shall be located and displayed in the Colleyville City Hall.
- B. Replacement of Official Zoning Map – In the event that the Official Zoning Map becomes damaged, destroyed, lost, or difficult to interpret because of the nature or number of changes and additions, the City Council may by resolution adopt a new Official Zoning Map which shall supersede the prior Official Zoning Map. The new Official Zoning Map may correct drafting or other errors or omissions in the prior Official Zoning Map and bring the Official Zoning Map up-to-date to reflect any and all amendments or changes in the same.
- C. Rules for Interpretation of District Boundaries – Where uncertainty exists as to the boundaries of districts as shown on the Official Zoning Map, the following rules shall apply:
 1. Boundaries indicated as approximately following the centerlines of streets, highways, or alleys shall be construed to follow such centerlines.
 2. Boundaries indicated as approximately following platted lot lines shall be construed as following such lot lines.
 3. Boundaries indicated as approximately following City Limits shall be construed as following City Limits.
 4. Boundaries indicated as following railroad lines shall be construed to be midway between the main tracks.
 5. Boundaries indicated as following shore lines shall be construed to follow such shore lines, and in the event of change in the shore line shall be construed as moving with the actual shore line; boundaries indicated as approximately following the centerlines of streams, drainage courses, creeks, canals, lakes, or other bodies of water shall be construed to follow such centerlines.
 6. Boundaries indicated as parallel to, or extensions of, features indicated in paragraphs 1 through 5 above shall be so construed. Distances not specifically indicated on the Official Zoning Map shall be determined by the scale of the map.
 7. Where physical or cultural features existing on the ground are at variance with those shown on the Official Zoning Map or in other circumstances not covered by paragraphs 1 through 6 above, the Zoning Board of Adjustment shall interpret the district boundaries.
 8. Where a district boundary line divides a lot which was in single ownership at the time of passage of the original zoning ordinance, the Zoning Board of Adjustment may permit, as a special exception, the extension of the regulations for either portion of the lot not to exceed fifty (50') feet beyond the district line into the remaining portion of the lot to either side of said district line.

Section 3.6 – Application of District Regulations; Classification of New and Unlisted Uses; and Platting of Property Not Properly Zoned

- A. Application – The regulations set by this Chapter within each district shall be minimum regulations and shall apply uniformly to each class or kind of structure or land and particularly except as hereinafter provided:
 1. No building, structure, or land shall hereafter be used or occupied, and no building or structure or part thereof shall hereafter be erected, constructed, re-constructed, moved, or structurally altered unless in conformity with all of the regulations herein specified for the district in which it is located.
 2. No building or other structure shall hereafter be erected or altered:

- a. to exceed the height;
 - b. to accommodate or house a greater number of families;
 - c. to occupy a greater percentage of lot area;
 - d. to have narrower or smaller rear yards, front yards, side yards, or other open spaces than herein required; or in any other manner contrary to the provisions of this Chapter.
 3. No part of a yard, other open space, or off-street parking or loading space required about or in connection with any building for the purpose of complying with this Chapter shall be included as part of a yard, open space, or off-street parking or loading space similarly required for any other building except as specified in the "Off-Street Parking Requirements." of this Chapter.
 4. No yard or lot existing at the time of passage of this Chapter shall be reduced in dimension or area below the minimum requirements set forth herein. Yards or lots created after the effective date of the original zoning ordinance shall meet at least the minimum requirements established by this Chapter.
 5. In every dwelling unit the density of occupancy shall not exceed 1.5 persons per room.
 6. All territory which hereafter is annexed to the City shall automatically be considered to be in the AG - Agricultural District, unless otherwise classified by the City Council after public hearing and upon recommendation from the Planning and Zoning Commission.
- B. Classification of New and Unlisted Uses – It is recognized that new types of land may develop and forms of land use not anticipated herein may seek to locate in the City. In order to provide for such changes and contingencies, a determination as to the appropriate classification of any new or unlisted form of land and use shall be made as follows:
1. The Administrative Official shall refer the question concerning any new or unlisted use to the Planning and Zoning Commission requesting an interpretation as to the proper zoning classification into which such use should be placed. The use interpretation question shall be determined as to the nature of the use and whether it involves dwelling activity, sales, processing, type of product, storage and the amount and nature thereof, (i.e., enclosed or open storage), anticipated employment, transportation requirements, the general degree of noise, odor, fumes, dust, toxic material and vibration likely to be generated, if any, and the general requirements for public utilities such as water and sanitary sewer.
 2. The Planning and Zoning Commission shall consider the nature and described performance of the proposed use and its compatibility with the uses permitted in the various zoning districts, and determine the zoning district or districts within which such use should be permitted.
 3. The Planning and Zoning Commission shall transmit its findings and recommendations to the City Council as to the classification proposed for any new or unlisted use. The City Council shall approve the recommendation of the Planning and Zoning Commission, or make such other determination concerning the classification of such use as appropriate, based upon its findings of fact, and amend this Chapter to reflect said findings and decisions.
- C. Platting of Property not Properly Zoned – No plat of any residential or non-residential subdivision within the City, or that which is being annexed to the City, shall be approved unless and until the area covered by the proposed plat is or shall be zoned to the proper zoning classification by the City Council, upon recommendation from the Planning and Zoning Commission. A public hearing by the Planning and Zoning Commission on a proposed annexation, zoning classification, and plat approval, or any combination thereof, may be held simultaneously.

Section 3.7 – Non-conforming Uses, Lots and Buildings

- A. Intent – Within the districts established by this Chapter, or amendments that may later be adopted, there exist lots and uses of land, buildings and structures, uses of land and buildings in combination, and characteristics of use which were lawful before the original zoning ordinance was passed or amended, but which would be prohibited, regulated, or restricted under the terms of this Chapter or future amendment. It is the intent of this Chapter to permit these non-conformities to continue until they are

Commented [BB2]: Needs further review

removed, but not to encourage their survival. It is further the intent of this Chapter that such non-conformities shall not be enlarged upon, expanded or extended, nor be used as ground for adding other buildings and structures or uses prohibited elsewhere in the same district.

Non-conforming uses are declared by this Chapter to be incompatible with permitted uses in the districts involved. A non-conforming use of a building or structure, a non-conforming use of land, or a non-conforming use of buildings and land in combination shall not be extended or enlarged after passage of this Chapter by attachment on a building or premises or by the addition of other uses of a nature which would be prohibited generally in the district involved.

To avoid undue hardship, nothing in this Chapter shall be deemed to require a change in the plans, construction, or designated use of any building on which actual construction was lawfully begun prior to the effective date of adoption or amendment of this Chapter and upon which actual building construction has been carried on diligently. Actual construction is hereby defined to include the placing of construction materials in permanent position and fastened in a permanent manner. Where excavation or demolition or removal of an existing building has been substantially begun preparatory to rebuilding, such excavation or demolition or removal shall be deemed to be actual construction, provided that work shall be carried on diligently.

- B. Non-conforming Lots of Record – In any zoning district in which single-family dwellings or commercial buildings are permitted, a single-family dwelling or commercial building and customary accessory buildings may be erected on any single lot of record at the effective date of adoption or amendment of this Chapter, notwithstanding limitations imposed by other provisions of this Chapter. Such lot must be in separate ownership and not of continuous frontage with other lots in the same ownership. This provision shall apply even though such lot fails to meet the requirements for area or width, or both, that are generally applicable in the district, provided that yard dimensions and requirements other than those applying to area or width, or both, of the lot shall conform to the regulations for the district in which such lot is located. Variance of yard requirements shall be obtained only through action of the Zoning Board of Adjustment.
- C. Non-conforming Uses of Land (or Land with Minor Building Only) – Where at the time of passage of this Chapter lawful use of land exists which would not be permitted by the regulations imposed by this Chapter, and where such use involves no individual structure with a replacement cost exceeding one thousand dollars (\$1,000), the use may be continued so long as it remains otherwise lawful, provided:
1. No such nonconforming use shall be enlarged or increased, nor extended to occupy a greater area of land than was occupied at the effective date of adoption or amendment of the original zoning ordinance;
 2. No such nonconforming use shall be moved in whole or in part to any portion of the same lot or parcel other than that occupied by such use at the effective date of adoption or amendment of the original zoning ordinance;
 3. If any such nonconforming use of land ceases for any reason for a period of more than ninety (90) consecutive days, any subsequent use of such land shall conform to the regulations specified by this Chapter for the district in which such land is located;
 4. No additional building not conforming to the requirements of this Chapter shall be erected in connection with such nonconforming use of land.
- D. Non-conforming Buildings – Where a lawful building exists at the effective date of adoption or amendment of this Chapter that could not be built under the terms of this Chapter by reason of restrictions on area, lot coverage, height, yards, its location on the lot, or other requirements concerning the building, such building may be continued so long as it remains otherwise lawful, subject to the following provisions:
1. No such non-conforming building may be enlarged or altered in a way which increases its nonconformity, but any building or portion thereof may be altered to decrease its nonconformity or to comply with City building codes.

2. Should such non-conforming building or non-conforming portion of a building be destroyed by any means to an extent of more than fifty (50) percent of its replacement cost at time of destruction; it shall not be reconstructed except in conformity with the provisions of this Chapter, or when approved by the Zoning Board of Adjustment, after public hearing thereon, when the Board's findings, having due regard for the property rights of persons affected, were considered in the light of public welfare and the character of the area surrounding the nonconforming building and the conservation and protection of property.
 3. Should such building be moved for any reason any distance whatever, it shall thereafter conform to the regulations of the district in which it is located after it is moved.
- E. Non-conforming Uses of Buildings or of Buildings and Premises in Combination – If lawful use involving individual buildings with a replacement cost of one thousand dollars (\$1,000.00) or more, or of buildings and premises in combination, exist at the effective date of adoption or amendment of this Chapter that would not be allowed in a particular district under the terms of this Chapter, the lawful use may be continued so long as it remains otherwise lawful, subject to the following provisions:
1. No existing building devoted to a use not permitted by this Chapter in the district in which it is located shall be enlarged, extended, constructed, reconstructed, moved, or structurally altered except in changing the use of the building to a use permitted in the district in which it is located, or to comply with City building codes.
 2. Any non-conforming use may be extended throughout any parts of a building which were manifestly arranged or designed for such use at the time of adoption or amendment of this Chapter, but no such use shall be extended to occupy any land outside such building.
 3. If no structural alterations are made, except as required by the City's building codes, any non-conforming use of a building, or building and premises, may, as a special exception, be changed to another non-conforming use provided that the Zoning Board of Adjustment, either by general rule or by making findings in the specific case, shall find that the proposed use is equally appropriate or more appropriate to the district than the existing non-conforming use. In permitting such change, the Zoning Board of Adjustment may require appropriate conditions and safeguards in accord with the provisions of this Chapter.
 4. Any building, or building and land in combination, in or on which a non-conforming use is superseded by a permitted use, shall thereafter conform to the regulations for the district, and the non-conforming use may not thereafter be resumed.
 5. When a non-conforming use of a building, or building and premises in combination, is discontinued or abandoned for six (6) consecutive months or for eighteen (18) months during any three-year period (except when government action impedes access to the premises), the building, or building and premises in combination, shall not thereafter be used except in conformity with the regulations of the district in which it is located.
 6. Where non-conforming use status applies to a building and premises in combination, removal or destruction of the building shall eliminate the non-conforming status and any new construction shall be in accordance with the zoning regulations applicable to the district. Destruction for the purpose of this subsection is defined as damage to an extent of more than fifty (50) percent of the replacement cost at time of destruction. (O-00-1261 / 12/19/00)
- F. Repairs and Maintenance – On any non-conforming building or portion of a building containing a non-conforming use, work may be done in any period of twelve (12) consecutive months on ordinary repairs, or on repair or replacement of non-bearing walls, fixtures, wiring, or plumbing, to an extent not exceeding ten (10) percent of the current replacement cost of the non-conforming building or non-conforming portion of the building as the case may be, provided that the cubic content existing when it became non-conforming shall not be increased.

If a non-conforming building or portion of a building containing a non-conforming use becomes physically

unsafe or unlawful due to lack of repairs and maintenance, and is declared by any duly authorized City official to be unsafe or unlawful by reason of physical condition, it shall not thereafter be restored, repaired, or rebuilt except in conformity with the regulations of the district in which it is located.

Nothing in this Chapter shall be deemed to prevent the strengthening or restoring to a safe condition of any building or part thereof declared to be unsafe by any official charged with protecting the public safety, upon order of such official.

G. Changing Non-conforming Uses

1. Any non-conforming use may be changed to a conforming use and once such change is made, the use shall not thereafter be changed back to a non-conforming use.
2. The Zoning Board of Adjustment may grant a change of use from one non-conforming use to another non-conforming use provided such change is to a use permitted in a zoning district where the original non-conforming use would be permitted or such change is to a use permitted in a more restrictive classification. However, such change of use and occupancy shall not tend to prolong the life of a non-conforming use. Upon review of the facts in accordance with the procedures for the Zoning Board of Adjustment, contained in *Chapter 1 – General Provisions* of this Land Development Code, the Zoning Board of Adjustment may establish a specific period of time for the return of the occupancy to a conforming use.
3. The Zoning Board of Adjustment may approve the remodeling or enlargement of a non-conforming use when such an enlargement would not tend to prolong the life of the non-conforming use. Upon review of the facts, the Zoning Board of Adjustment may establish a specific period of time for the return of the occupancy to a conforming use in accordance with the procedures of the Zoning Board of Adjustment contained in *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.8 AG – Agricultural District

- A. Agricultural District – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this Section, are the regulations of the AG - Agricultural District.
- B. Purpose and Intent – The purpose of the AG - Agricultural District is to provide for compatible land, building and structure uses primarily oriented to agricultural farming and ranching, and extremely low density residential purposes. The district's locational characteristics are usually confined to the outer fringe of developed urbanized areas and/or along, unprotected flood-prone areas. The district also serves as: 1) a transitional land use element pending future, more intensive urbanization; 2) open space for the protection and enhancement of scenic areas, vistas, and recreational uses, and 3) where unusual or problematic soils, topographic conditions, or sensitive ecological features are present that would normally not be conducive or appropriate to more intensive forms and patterns of urbanization

The primary intent of this district is a land use designated to aid in the protection of certain lands suitable for producing and supplying food and related agricultural farm and ranch products from more intense urbanization until such time as warranted by demand and supportive community facilities and services.

- C. Use Regulations – Land, buildings and structures may be used only for the purposes allowed in this Chapter.
- D. Permitted Principal Uses – The permitted principal uses allowed in this district as are designated in *Section 3.24.C - Schedule of Permitted Principal Uses*.
- E. Permitted Accessory Uses – Subject to the provisions of *Section 3.28 - Supplementary District Regulations*, accessory buildings, structures and uses customarily incidental to the "Permitted Principal Uses" are allowed, including but not limited to the following:
1. Buildings, structures and uses accessory to permitted farming and ranching operations;
 2. Private residential garages, carports and related storage buildings and greenhouses accessory to

permitted residential uses.

3. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All "at-grade" swimming pools with a depth greater than twenty-four (24") inches and "above-grade" swimming pools having a water depth twenty-four (24") inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than (4') feet nor more than eight (8') feet in height, and of such material and design to discourage unauthorized entry to the facility. Such pool(s) may be located in a required side or rear yard, but not within a required front yard not forward of the primary dwelling, and shall not be located closer than five (5') feet to any side or rear property line.~~
4. ~~Servants quarters for domestic servants employed on the premises or family members~~ Accessory dwellings provided the gross habitable square feet of floor area shall not exceed six hundred (600) square feet complies with regulations found in Section 3.27 of this chapter. Such quarters may be housed within the principal residential dwelling, above a residential garage, or be part of an accessory building on the same premises, and shall comply with minimum standards for light, health, safety, and occupancy in conformance with other applicable City codes and ordinances.
5. Lanais, gazebos, garden and patio shelters, and children's play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
6. Non-commercial radio and television receiving antennae and non-commercial radio transmitting antennae limited in height to sixty (60) feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
7. Required off-street parking and loading spaces.
8. Home occupation uses as defined in *Chapter 2 – Definitions* of this Land Development Code.
9. Parking and storage of private boats(s), camper trailer(s), or other recreational vehicle(s), in conformance with the regulations for "Parking, Storage or Use of Major Recreational Equipment and Vehicles."
10. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code and other applicable City codes and ordinances.
11. Supplemental single-family dwelling for a farm employee and family when located on the same premises as the principal agricultural use, provided:
 - a. Such dwelling shall be used exclusively for the housing of a single-family employed full time on the premises in the conduct of operation or management of the principal agricultural use;
 - b. Such dwelling is under the same ownership as that of the agricultural use and is on the same land as the owner's principal place of residency;
 - c. The land area devoted to such dwelling conforms with the minimum requirements established in *Section 3.24 - Schedule of District Regulations* for single-family dwellings in an "RE" District, as if it were on a separate recorded lot; and
 - d. The total land area under common ownership comprising the agriculture use and related owner's and employee's residence is not less than twenty (20) acres.

~~F. Special Exception Uses – In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the "Zoning Board of Adjustment"~~

Commented [EW3]: Recommendation that the pool not extend past the front of the house

Commented [EW4]: Pool barrier requirements are codified in the adopted building codes

Commented [BB5]: New standards for Accessory Dwellings

Commented [BB6]: Deleted per Council direction

~~may, after public hearing thereon, authorize and grant the issuance of a "Special Exception" for such special exception uses as allowed in Section 3.24 - "Schedule of Permitted Principal Uses." The issuance of such "exception" by the "Board" shall be contingent upon reasonable and appropriate conditions and safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use, or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

GE. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions for ~~—~~ "Classification of New and Unlisted Uses."

HG. Density, Area, Yard, Height, and Lot Coverage Requirement – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes, (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of *Section 3.24 - Schedule of District Regulations* and other applicable provisions of *Section 3.28 - Supplementary District Regulations*.

H. Off Street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform ~~with~~to the "Off-Street Parking Requirements" and "Off-Street Loading Requirements" contained elsewhere in this Land Development Code.

J. Land Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the official zoning map affecting this district shall be accompanied by a land plan and supporting document therefor, in conformance with the provisions of *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.9 RE – Single Family "Estate" Residential District

A. **RE-Single Family Estate Residential District** – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this section, are the regulations of the RE - Single-Family Residential Estate District.

B. **Purpose and Intent** – The purpose and intent of the RE - Single-Family Estate Residential District is to provide for compatible land, building, and structural uses primarily oriented to low density residential estate purposes, select agricultural uses, open space uses, and selected community facility uses. The locational characteristic of this district is generally confined to the outer fringe of the more intensely urbanized and developed areas and/or along unprotected flood prone areas. The district further serves as a transitional element between limited residential development and intense agricultural activities and of higher density urbanized areas of the city. Low density detached single-family residential dwellings and estate development, along with the aforescribed uses, comprise the principal elements of the district.

C. **Use Regulations** – Land, buildings and structures may be used only for the purposes allowed in this Section.

D. **Permitted Principal Uses** – The permitted principal uses allowed in this district are as designated in *Section 3.24 - Schedule of Permitted Principal Uses*.

E. **Permitted Accessory Uses** – Subject to the provisions of *Section 3.28 - Supplementary District Regulations*, accessory buildings, structures, and uses customarily incidental to the "Permitted Principal Uses" are allowed, including but not limited to the following:

1. Buildings, structures, and uses accessory to permitted farming and ranching operations;
2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All "at grade" swimming pools with a water depth greater than twenty-four (24") inches and "above grade" swimming pools having a~~

~~water depth twenty-four (24") inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than four (4') feet nor more than eight (8') feet in height, and of such material and design to discourage unauthorized entry to the facility. Such pool(s) may be located in a required side or rear yard, but not within a required front yard forward of the primary dwelling on the lot, and shall not be located closer than five (5') feet to any side or rear property line.~~

Commented [EW7]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW8]: Recommend that the pool does not extend past the front of the dwelling

3. Private residential garages, carports, and related storage buildings and greenhouses accessory to permitted residential uses.
4. ~~Servants quarters for domestic servants employed on the premises or family members. Accessory dwellings provided the gross habitable square feet of floor area shall not exceed six hundred (600) square feet complies with regulations found in Section 3.27 of this chapter. Servants quarters for domestic servants employed on the premises or family members provided the gross habitable square feet of floor area shall not exceed six hundred (600) square feet.~~ Such quarters may be housed within the principal residential dwelling, above a residential garage, or be part of an accessory building on the same premises, and shall comply with minimum standards for light, health, safety, and occupancy in conformance with other applicable City codes and ordinances.
5. Lanais, gazebos, garden and patio shelters, and children's play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
6. Non-commercial radio and television receiving antennae and non-commercial radio transmitting antennae limited in height to sixty (60) feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
7. Required off-street parking and loading spaces.
8. Home occupation uses as defined in *Chapter 2 – Definitions* of this Land Development Code
9. Parking and storage of private boat(s), camper trailer(s) or other recreational vehicle(s), in conformance with the regulations for "Parking, Storage or Use of Major Recreational Equipment and Vehicles."
10. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code.
11. Private domestic greenhouses.
12. Private stables for the keeping of grazing animals, provided:
 - a. Significant ground accumulations of manure shall be collected and properly disposed of so as not to create offensive odors, fly breeding, or in any way become a health hazard or nuisance to humans or animals;
 - b. Fences for pens, corrals or similar enclosures shall be of sufficient height and strength to properly retain the grazing animal(s) on the premises; and
 - c. The minimum space area of the lot upon which such grazing animal(s) may be kept, including pens, corrals, and stables, shall not be less than 15,000 square feet per each grazing animal over five hundred (500) pounds and not less than five thousand (5,000) square feet for any other grazing animal.

Commented [BB9]: New standards for Accessory Dwellings

~~F. **Special Exception Uses** — In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the "Zoning Board of Adjustment" may, after public hearing thereon, authorize and grant the issuance of a "Special Exception" for such special exception uses as allowed in Section 3.24 – Schedule of Permitted Principal Uses. The issuance of such "exception" by the "Board" shall be contingent upon reasonable and appropriate conditions and~~

~~safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

GF. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions for the “Classification of New and Unlisted Uses.”

HG. Density, Area, Yard, Height, and Lot Coverage Requirements – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of *Section 3.24 - Schedule of District Regulations* and other applicable provisions of *Section 3.28 - Supplementary District Regulations*.

H. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform ~~with~~to the provisions of the “Off-Street Parking Requirements,” and the “Off-Street Loading Requirements.”

J. Land Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the Official Zoning Map affecting this district shall be accompanied by a land plan and supporting document therefore, in conformance with the provisions of *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.10 ~~R-40~~ **Single Family Residential District**

A. **~~R-40~~ Single Family Residential District** – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this section, are the regulations of the ~~R-40~~ **Single Family Residential District**.

B. **Purpose and Intent** – The purpose and intent of the ~~R-40~~ **Single Family Residential District** is to provide for compatible land, building and structure uses primarily oriented to low density residential purposes, open space uses, and select community facility uses. The locational characteristics of this district are not confined to any specific or general area; however, they are most appropriate on the outer fringe of the more intensively urbanized parts of the community, and/or along protected flood prone areas. Land uses in this district are normally connected to an approved public or private sewage collection and treatment system, rather than individual septic tanks and subsurface drainage fields. Low density detached single family residential dwellings and development, along with the aforescribed uses, comprise the principal elements of the district.

C. **Use Regulation** – Land, buildings and structures may be used only for the purposes allowed in this Section.

D. **Permitted Principal Uses** – The permitted principal uses allowed in this district are as designated in *Section 3.24 - Schedule of Permitted Principal Uses*.

E. **Permitted Accessory Uses** – Subject to the provisions of *Section 3.28 - Supplementary District Regulations*, accessory buildings, structures, and uses customarily incidental to the “Permitted Principal Uses” are allowed, including but not limited to the following:

1. Private residential garages, carports and related storage buildings and greenhouses accessory to permitted residential uses.
2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. All “at grade” swimming pools with a water depth greater than twenty-four (24”) inches and “above grade” swimming pools having a water depth twenty-four (24”) inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than four (4’) feet nor more than six (6’) feet in height, and of

~~such material and design to discourage unauthorized entry to the facility. Such pool(s) may be located in a required side or rear yard, but not within a required front yard -but not forward of the primary dwelling on the lot,- and shall not be located closer than five (5') feet to any side' or rear property line.~~

Commented [EW10]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW11]: Recommend that the pool cannot extend beyond the front of the existing dwelling

3. Lanais, gazebos, garden and patio shelters, and children's play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
4. Noncommercial radio and television receiving antennae and noncommercial radio transmitting antennae limited in height to sixty (60') feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
5. Required off-street parking and loading spaces.
6. Home occupation uses as defined in *Chapter 2 – Definitions* of this Land Development Code.
7. Parking and storage of private boat(s), camper trailer(s), or other recreational vehicle(s), in conformance with the regulations for the "Parking, Storage or Use of Major Recreational Equipment and Vehicles."
8. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code
9. Private domestic greenhouses.
10. Private stables for the keeping of grazing animals, provided:
 - a. Significant ground accumulations of manure shall be collected and properly disposed of so as not to create offensive odors, fly breeding, or in any way become a health hazard or nuisance to humans or animals;
 - b. Fences for pens, corrals or similar enclosures shall be of sufficient height and strength to properly retain the grazing animal(s) on the premises; and
 - c. The minimum space area of the lot upon which such grazing animal(s) may be kept, including pens, corrals, and stables, shall not be less than 15,000 square feet per each grazing animal over five hundred (500) pounds and not less than five thousand (5,000) square feet for any other grazing animal.

~~F. Special Exception Uses – In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the "Zoning Board of Adjustment" may, after public hearing thereon, authorize and grant the issuance of a "Special Exception" for such special exception uses as allowed in Section 3.24 - "Schedule of Permitted Principal Uses." The issuance of such "exception" by the "Board" shall be contingent upon reasonable and appropriate conditions and safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

~~G.F. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions of the regulation for the "Classification of New and Unlisted Uses."~~

~~H.G. Density; Area; Yard; Height; and Lot Coverage Requirements – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of Section 3.24 - *Schedule of District Regulations* and other applicable provisions of Section 3.28 - *Supplementary District Regulations*.~~

H. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform ~~with~~to the provisions for "Off-Street Parking Requirements," and "Off-Street Loading Requirements."

J. Land Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the Official Zoning Map affecting this district shall be accompanied by a land plan and supporting document therefore, in conformance with the provisions of *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.11 ~~R-30~~ Single Family Residential District

A. **~~R-30~~ Single Family Residential District** – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this Section, are the regulations of the ~~R-30~~ Single-Family Residential District.

B. **Purpose and Intent** – The purpose and intent of the ~~R-30~~ Single-Family Residential District is to provide for compatible land, building, and structural uses primarily oriented to low density residential purposes, open space uses, and selected community facility uses. The locational characteristics of this district are generally found in the inner urbanized developed areas of the City. Land uses in this district are normally connected to an approved public or private sewage collection and treatment system, rather than individual septic tanks and subsurface drainage fields. Moderately low density detached single-family residential dwellings and development, along with the aforescribed uses, comprise the principal elements of the district.

C. **Use Regulation** – Land, buildings and structures may be used only for the purposes allowed in this Section.

D. **Permitted Principal Uses** – The permitted principal uses allowed in this district are as designated in *Section 3.24 - Schedule of Permitted Principal Uses*.

E. **Permitted Accessory Uses** – Subject to the provisions of *Section 3.28 - Supplementary District Regulations*, accessory buildings, structures, and uses customarily incidental to the "Permitted Principal Uses" are allowed, including but not limited to the following:

1. Private residential garages, carports and related storage buildings and greenhouses accessory to permitted residential uses.
2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All "at-grade" swimming pools with a water depth greater than (24") inches and "above grade" swimming pools having a water depth (24") inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than (4') feet nor more than (8') feet in height, and of such material and design to discourage unauthorized entry to the facility. Such pool(s) may be located in a required side or rear yard, but not within a required front yard forward of the primary dwelling on the lot,~~ and shall not be located closer than (5') feet to any side or rear property line.
3. Lanais, gazebos, garden and patio shelters, and children's play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
4. Noncommercial radio and television receiving antennae and noncommercial radio transmitting antennae limited in height to sixty (60') feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
5. Required off-street parking and loading spaces.

Commented [EW12]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW13]: Recommend that the pool cannot extend beyond the front of the existing dwelling on the lot

6. Home occupation uses as defined in *Chapter 2 – Definitions* of this Land Development Code.
7. Parking and storage of private boats(s), camper trailer(s), or other recreational vehicle(s), in conformance with the regulations for the "Parking, Storage or Use of Major Recreational Equipment and Vehicles."
8. Signs, in conformance with these regulations and other applicable City codes and ordinances.
9. Private domestic greenhouses.

~~F. Special Exception Uses – In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the "Zoning Board of Adjustment" may, after public hearing thereon, authorize and grant the issuance of a "Special Exception" for such as allowed in Section 2.24 – "Schedule of Permitted Principal Uses." The issuance of such "special exception uses" by the "Board" shall be contingent upon reasonable and appropriate conditions and safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use, or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

~~GE. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions for the "Classification of New and Unlisted Uses."~~

~~HG. Density, Area, Yard, Height, and Lot Coverage Requirement – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes, (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of Section 3.24 - "Schedule of District Regulations" and other applicable provisions of Section 3.28 - "Supplementary District Regulations."~~

~~JH. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform with the provisions of the "Off-Street Parking Requirements" and "Off-Street Loading Requirements."~~

~~JL. Land Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the "Official Zoning Map" affecting this district shall be accompanied by a land plan and supporting document therefore, in conformance with the provisions of Chapter 1 – ~~General~~ General Provisions of this Land Development Code regarding "Petition for Zoning District Change: Land Plan and Supporting Documents Required."~~

Section 3.12 ~~R-20~~ Single Family Residential District

- A. R-20 – Single Family Residential District – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this Section, are the regulations of the ~~R-20~~ Single-Family Residential District.
- B. Purpose and Intent – The purpose and intent of the ~~R-20~~ Single-Family Residential District is to provide for compatible land, building, and structural uses primarily oriented to medium-low density residential purposes, open space uses, and selected community facility uses. The locational characteristics of this district are generally found in the inner urbanized developed areas of the city, adjacent to shopping facilities. Land uses in this district are normally connected to an approved public or private sewage collection and treatment system, rather than individual septic tanks and sub-surface drainage fields. Moderately low density detached single-family residential dwellings as exist in the inner area of the city comprise the principal elements of the district. It is further the intent to use this district and its regulations to accommodate and recognize the existence of small lot conventional single-family development, which presently exists in the city.

- C. Use Regulations – Land, buildings and structures may be used only for the purposes allowed in this Section.
- D. Permitted Principal Uses – The permitted principal uses allowed in this district are as designated in *Section 3.24 - Schedule of Permitted Principal Uses*.
- E. Permitted Accessory Uses – Subject to the provisions of *Section 3.28 - Supplementary District Regulations*, accessory buildings, structures, and uses customarily incidental to the “permitted principal uses” are allowed, including but not limited to the following:
1. Private residential garages, carports and related storage buildings and greenhouses accessory to permitted residential uses.
 2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All “at-grade” swimming pools with a water depth greater than twenty-four (24”) inches and “above-grade” swimming pools having a water depth twenty-four (24”) inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than four (4’) feet nor more than eight (8’) feet in height, and of such material and design to discourage unauthorized entry to the facility. Such pool(s) may be located in a required side or rear yard, but not within a required front yard forward of the primary dwelling on the lot, and shall not be located closer than five (5’) feet to any side or rear property line.~~
 3. Lanais, gazebos, garden and patio shelters, and children’s play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
 4. Noncommercial radio and television receiving antennae and noncommercial radio transmitting antennae limited in height to sixty (60) feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses.
 5. Required off-street parking and loading spaces.
 6. Home occupation uses as defined in *Chapter 2 – Definitions* of this Land Development Code.
 7. Parking and storage of private boat(s), camper trailer(s), or other recreational vehicle(s), in conformance with the regulations for “Parking, Storage or Use of Major Recreational Equipment and Vehicles.”
 8. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code.
 9. Private domestic greenhouses.

~~F. Special Exception Uses – In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the “Zoning Board of Adjustment” may, after public hearing thereon, authorize and grant the issuance of a “Special Exception” for such special exception uses as allowed in *Section 3.24 – “Schedule of Permitted Principal Uses.”* The issuance of such “exception” by the “Board” shall be contingent upon reasonable and appropriate conditions and safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

F. R-10 Single-Family Residential District Historic Designation: All lots within the City of Colleyville with the R-10 designation shall conform to the standards of the R-20 zoning district.

Commented [EW14]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW15]: Recommend that the pool cannot extend beyond the front of the existing dwelling on the lot

Commented [BB16]: This will address the existing R-10 properties

- G. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions for the “Classification of New and Unlisted Uses.”
- H. Density, Area, Yard, Height, and Lot Coverage Requirements – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of *Section 3.24 - “Schedule of District Regulations”* and other applicable provisions of *Section 3.28 - “Supplementary District Regulations.”*
- I. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform ~~with~~ the provisions for “Off-Street Parking Requirements,” and “Off-Street Loading Requirements.”
- J. Land Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the Official Zoning Map affecting this district shall be accompanied by a land plan and supporting document therefore, in conformance with the provisions contained in *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.13 ~~R-15~~ – Single Family Residential District

- A. R-15 – Single Family Residential District – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this Section, are the regulations of the ~~R-15~~ – Single-Family Residential District.
- B. Purpose and Intent – The purpose and intent of the ~~R-15~~ – Single-Family Residential District is to provide for compatible land, building, and structural uses primarily oriented to medium-low density residential purposes, open space uses, and selected community facility uses. The locational characteristics of this district are generally found in the inner urbanized developed core of the city and/or adjacent to shopping facilities. Land uses in this district are normally connected to an approved public or private sewage collection and treatment system, rather than individual septic tanks and sub-surface drainage fields. Medium low density detached single-family residential buildings as exist in the inner core area of the city on typically small lots, along with the aforescribed uses, comprise the principal elements of the district. It is further the intent to use this district and its regulations to accommodate and recognize the existence of small lot conventional single-family development, which presently exists in the city, but not to create new-zoned areas for such conventional small lots.
- C. Use Regulations – Land, buildings and structures may be used only for the purposes allowed in this Section.
- D. Permitted Principal Uses – The permitted principal uses allowed in this district are as designated in *Section 3.24 - Schedule of Permitted Principal Uses*.
- E. Permitted Accessory Uses – Subject to the provisions of *Section 2.28 - Supplementary District Regulations*, accessory buildings, structures, and uses customarily incidental to the “permitted principal uses” are allowed, including but not limited to the following:
 - 1. Private residential garages, carports and related storage buildings and greenhouses accessory to permitted residential uses.
 - 2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All “at-grade” swimming pools with a water depth greater than twenty-four (24”) inches and “above grade” swimming pools having a water depth twenty-four (24”) inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than four (4) feet nor more than eight (8) feet in height, and of~~

~~such material and design to discourage unauthorized entry to the facility.~~ Such pool (s) may be located in a required side or rear yard, but not within a required front yard forward of the primary dwelling on the lot, and shall not be located closer than five (5') feet to any side or rear property line.

Commented [EW17]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW18]: Recommend that the pool cannot extend beyond the front of the existing dwelling on the lot

3. Lanais, gazebos, garden and patio shelters, and children's play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
4. Noncommercial radio and television receiving antennae and noncommercial radio transmitting antennae limited in height to sixty (60') feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
5. Required off-street parking and loading spaces.
6. Home occupation uses, as defined in *Chapter 2 – Definitions* of this Land Development Code.
7. Parking and storage of private boat(s), camper trailer(s), or other recreational vehicle(s), in conformance with the regulations for the "Parking, Storage or Use of Major Recreational Equipment and Vehicles."
8. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code.
9. Private domestic greenhouses.

~~F. R-10 Single-Family Residential District Historic Designation: All lots within the City of Colleyville with the R-10 designation shall conform to the standards of the R-15 zoning district.~~

Commented [BB19]: This will address the existing R-10 properties. {At the worksession this was moved to the R-20 district}

~~G. Special-Exception Uses – In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the "Zoning Board of Adjustment" may, after public hearing thereon, authorize and grant the issuance of a "Special-Exception" for such special-exception uses as allowed in Section 3.24 – "Schedule of Permitted Principal Uses." The issuance of such "exception" by the "Board" shall be contingent upon reasonable and appropriate conditions and safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

- G. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the regulations for the "Classification of New and Unlisted Uses."
- H. Density; Area; Yard; Height; and Lot Coverage Requirements – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of *Section 3.24 "Schedule of District Regulations"* and other applicable provisions of *Section 3.28 - "Supplementary District Regulations."*
- I. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform with the provisions for "Off-Street Parking Requirements," and "Off-Street Loading Requirements."
- J. Land Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the Official Zoning Map affecting this district shall be accompanied by a land plan and supporting document therefore, in conformance with the provisions of *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.14 RD – Two-Family Residential District

- A. ~~RD — Two-Family Residential District~~ – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this Section, are the regulations of the ~~RD — Two-Family Residential District~~.
- B. Purpose and Intent – The purpose and intent of the ~~RD — Two-Family Residential District~~ is to provide for compatible land, building, and structure uses primarily oriented to medium-low density two-family residential purposes, open space usage, and selected community facility uses. The locational characteristics of this district are generally, but not always, found in the inner urbanized developed core of the city around shopping centers and neighborhood service facilities, plus as a transitional element between low density, single family districts and higher density multiple family districts. Land uses in this district are normally connected to an approved public or private sewage collection and treatment system, rather than individual septic tanks and sub-surface drainage fields. Dwellings containing two-family dwelling units, plus the aforescribed uses, comprise the principal elements of the district. ~~The intent of this district is not to allow single-family detached dwellings.~~
- C. Use Regulations – Land, buildings and structures may be used only for the purposes allowed in this Section.
- D. Permitted Principal Uses – The permitted principal uses allowed in this district are as designated in *Section 3.24 - Schedule of Permitted Principal Uses*.
- E. Permitted Accessory Uses – Subject to the provisions of *Section 3.28 - Supplementary District Regulations*, accessory buildings, structures, and uses customarily incidental to the “permitted principal uses” are allowed, including but not limited to the following:
1. Private residential garages, carports and related storage buildings and greenhouses accessory to permitted residential uses.
 2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All “at-grade” swimming pools with a water depth greater than twenty-four (24”) inches and “above-grade” swimming pools having a water depth twenty-four (24”) inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than four (4’) feet nor more than eight (8’) feet in height, and of such material and design to discourage unauthorized entry to the facility. Such pool (s) may be located in a required side or rear yard, but not within a required front yard.~~ forward of the primary dwelling on the lot. and shall not be located closer than five (5’) feet to any side or rear property line.
 3. Lanais, gazebos, garden and patio shelters, and children’s play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
 4. Noncommercial radio and television receiving antennae and noncommercial radio transmitting antennae limited in height to sixty (60’) feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
 5. Required off-street parking and loading spaces.
 6. Home occupation uses, as defined in *Chapter 2 – Definitions* of this Land Development Code.
 7. Parking and storage of private boat(s), camper trailer(s), or other recreational vehicle(s), in conformance with the requirements for “Parking, Storage or Use of Major Recreational Equipment and Vehicles.”
 8. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code.
 9. Private domestic greenhouses.

Commented [BB20]: The vast majority of properties zoned RD are developed with single-family residences

Commented [EW21]:

Commented [EW22R21]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW23]: Recommend that the pool cannot extend beyond the front of the existing dwelling on the lot

~~F. Special Exception Uses – In order to allow for certain uses which, because of the unique or unusual character thereof, can not be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the “Zoning Board of Adjustment” may, after public hearing thereon, authorize and grant the issuance of a “Special Exception” for such special exception uses as allowed in Section 2.24 – “Schedule of Permitted Principal Uses.” The issuance of such “exception” by the “Board” shall be contingent upon reasonable and appropriate conditions and safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

F. Single-Family Residential Uses – When a property with RD zoning is developed with a single-family residential use, the property shall conform to the standards of the R-20 Single Family Residential zoning district.

Commented [BB24]: Added per Council direction to address single-family residential development

G. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions for the “Classification of New and Unlisted Uses.”

H. Density, Area, Yard, Height, and Lot Coverage Requirements – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of Section 3.24 - “Schedule of District Regulations” and other applicable provisions of Section 3.28 - “Supplementary District Regulations.”

I. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform with the provisions for the “Off-Street Parking Requirements,” and “Off-Street Loading Requirements.”

J. Land Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the Official Zoning Map affecting this district shall be accompanied by a land plan and supporting document therefore, in conformance with the provisions of Chapter 1 – General Provisions of this Land Development Code.

Section 3.15 RMF – ~~Multi-family~~ Family Residential District

A. RMF – ~~Multi-family~~ Family Residential District – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this Section, are the regulations of the RMF – ~~Multi-family~~ Family Residential District.

B. Purpose and Intent – The purpose and intent of the RMF – ~~Multi-family~~ Family Residential District is to provide for compatible land, building, and structure uses primarily oriented to medium density multi-family residential purposes, open space uses, select community facility uses, and under special conditions, single-family uses. The locational characteristics of this district are generally, but not always, found in the inner urbanized developed core of the city around shopping centers and neighborhood service facilities, near employment centers, at the intersections of major and secondary thoroughfare streets, and as a transitional element between lower density and more intense nonresidential land uses. Land uses in this district are normally connected to an approved public or private sewage collection and treatment system, rather than individual septic tanks and sub-surface drainage fields. Garden apartment buildings and condominiums, and low-density townhouses, plus the aforescribed uses, comprise the principal elements of the district.

C. Use Regulations – Land, buildings and structures may be used only for the purposes allowed in this Section.

D. Permitted Principal Uses – The permitted principal uses allowed in this district are as designated in Section 3.24 - Schedule of Permitted Principal Uses.

E. Permitted Accessory Uses – Subject to the provisions of Section 3.28 - Supplementary District

Regulations, accessory buildings, structures, and uses customarily incidental to the "permitted principal uses" are allowed, including but not limited to the following:

1. Private residential garages, carports and related storage buildings and greenhouses accessory to permitted residential uses.
2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All "at-grade" swimming pools with a water depth greater than twenty-four (24") inches and "above-grade" swimming pools having a water depth twenty-four (24") inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than four (4') feet nor more than eight (8') feet in height, and of such material and design to discourage unauthorized entry to the facility. Such pool-(s) may be located in a required side or rear yard, but not within a required front yard forward of the primary dwelling on the lot,~~ and shall not be located closer than five (5') feet to any side or rear property line.
3. Lanais, gazebos, garden and patio shelters, and children's play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
4. Noncommercial radio and television receiving antennae and noncommercial radio transmitting antennae limited in height to (60) feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
5. Required off-street parking and loading spaces.
6. Parking and storage of private boat(s), camper trailer(s), or other recreational vehicle(s), in conformance with the regulations for "Parking, Storage or Use of Major Recreational Equipment and Vehicles."
7. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code.
8. Private domestic greenhouses.
9. Outdoor storage areas or storage buildings for boats, trailers, and other recreational equipment, automobiles, or household effects - for the exclusive use of the site occupants, provided these accessory uses are screened in general conformity with the requirements for "Fences, Free Standing Walls, and Screening Materials."
10. An office area not containing more than (2) percent of the gross floor area of the main building in a multifamily development used exclusively for administration purposes for said development only.
11. Coin-operated vending machines in a principal or accessory building for newspapers, candy, tobacco, soft drinks, ice and similar services for use by the site occupants and guests of permitted uses in this district.
12. Social and recreation buildings for use by the site occupants and guests of permitted uses in this district.
13. Group dining quarters within a principal building.

Commented [EW25]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW26]: Recommend that the pool cannot extend beyond the front of the existing dwelling on the lot

~~F. **Special Exception Uses** — In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the "Zoning Board of Adjustment" may, after public hearing thereon, authorize and grant the issuance of a "Special Exception" for such special exception uses as allowed in Section 3.24 – "Schedule of Permitted Principal Uses." The issuance of such "exception" by the "Board" shall be contingent upon reasonable and appropriate conditions and~~

~~safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

F. Single-Family Residential Uses – When a property with MF zoning is developed with a single-family residential use, the property shall conform with the standards of the R-20 Single Family Residential zoning district.

Commented [BB27]: Added per Council direction to address single-family residential development

G. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions for the - "Classification of New and Unlisted Uses."

H. Density, Area, Yard, Height, and Lot Coverage Requirements – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of Section 3.24 - "Schedule of District Regulations" and other applicable provisions of Section 3.28 - "Supplementary District Regulations."

I. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform with the provisions of the "Off-Street Parking Requirements," and "and" "Off-Street Loading Requirements."

J. Site Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the Official Zoning Map affecting this district, or for a "Special Use Permit" to be issued in this district, shall be accompanied by a site plan and supporting document therefore, unless otherwise waived by the City Planning and Zoning Commission or Zoning Board of Adjustment, in conformance with the provisions of Chapter 1 – General Provisions of this Land Development Code.

K. Open Space Required – Unless waived by the Planning and Zoning Commission, the RMF ~~Multi-family~~ Family Residential District shall conform to the Open Space Requirements as set forth in the provision for "Open Space Requirements," "Maximum Residential Density Permitted; and Density Increase Bonuses," and "Guarantee of Common Open Space."

L. Planned Single-Family Use in RMF Zoning Districts by Special Use Permit

Commented [BB28]: Not needed; single-family residential development to be allowed by right

~~1. Purpose and Intent – the purpose and intent of the grant of a special use permit for single family use in a R-MF Zoning District is to provide for the use in said zoning district of land, buildings and structures, for an appropriate combination of residential uses, accessory uses and special uses and to accommodate uses of land in multifamily zoning districts for single family purposes when said use is pursuant to a plan designed to encourage the most appropriate and aesthetic uses of land having due regard for the special arrangement of buildings, land uses, open spaces, circulation transportation patterns and consideration of special site and topographical features, which are controlled and the actual development becomes incorporated into the grant of the special use permit.~~

~~2. Allowable Uses – land, buildings or structures within an area zoned R-MF on which a special use has been granted may be used for any appropriate combination of principal uses, accessory uses, and special uses as permitted in residential zoning districts. However, the Planning and Zoning Commission and the City Council reserve the right to prohibit and exclude certain uses within any planned district, when, in their opinion, the inclusion of certain uses would or could cause or create an adverse impact within or to an adjacent development, or be an otherwise inappropriate use within the development or detrimental to persons or property within the adjacent districts thereto.~~

~~3. Permitted Uses – the land, buildings and structures within an RMF Zoning District upon which a special use permit has been granted may be used in any single purpose or mixed type of residential dwellings, including but not limited to the attached single family dwelling on conventional subdivision type lots, attached dwellings such as duplexes and townhouses, "cluster housing", patio homes, atrium homes, zero-lot line homes, (with a maximum of one side wall of the dwelling in common with a side property line). Additionally, accessory uses customary and incidental and secondary to any allowed foregoing use are allowed in the district.~~

- ~~4. Prohibited Uses – uses not expressly permitted in residential zoning districts of this Chapter are expressly prohibited in any R-MF District with special use permit unless otherwise authorized and approved by the City Planning and Zoning Commission and the City Council.~~
- ~~5. Minimum Lot Size Requirements; Minimum Yard Requirements; Maximum Building Heights; and Maximum Lot Coverage – the maximum height, lot width, lot depth, floor area ratio and lot area, and the minimum off street parking and loading requirements for a special use permit in RMF Zoning District shall comply with or be more restrictive than the standard established in RMF Zoning Districts. The Planning and Zoning Commission and City Council may alter such requirements when in their opinion the proposed development densities and land use arrangements shown on the site plan would result in the more innovative siting of buildings and facilities which would improve the usefulness of yard areas and the relationship to traffic circulation, admittance of light and air to buildings, fire protection and useable open space.~~
- ~~6. Off-Street Parking and Loading Requirements – off street parking and loading requirements pertaining to uses allowed in this district shall conform with the provisions of the “Off-Street Parking Requirements,” and “Off-Street Loading Requirements.”~~
- ~~7. Site Plan and Supporting Documents Required – any application for a change in zoning district boundaries on the “official zoning map” to establish a special use permit in an RMF Zoning District shall be accompanied by a site plan and supporting documents therefore, in conformance with the provisions of Chapter 1 – General Provisions of this Land Development Code.~~
- ~~8. Nature of Amending Ordinance Approving a Special Use Permit in RMF Zoning Districts – in approving any request for a special use permit in RMF Zoning Districts, the City Council shall, on the recommendation of the Planning and Zoning Commission, incorporate in the amending ordinance reference to the approved site plan, supporting documents and other conditions or restrictions imposed on the project by the commission including those of Council, and said information, conditions and restrictions shall constitute controls and limitations upon the development and use of the property. The approval and adoption of the amending ordinance by the Council shall result in the appropriate change to the “Official Zoning Map.” However, the zoning change does not constitute recording of a “final plat”, nor authorize the issuance of building permits and “certificates of occupancy,” until such time as a “final plat,” and supporting legal and construction documents have been prepared and submitted for City Council approval on all or part of the proposed development, in conformance with the requirements and procedures of the City Subdivision Regulation Ordinance and the requested zoning change.~~
- ~~9. Requirements for “Final Plat,” Submission Following Grant of Special Use Permit – within a maximum of six (6) consecutive months, following the approval of the special use permit in the RMF Zoning District by the City Council, the applicant shall file with the City Planning and Zoning Commission a “final plat” and necessary supporting documents of all or a part of the site in conformance with the City’s Subdivision Regulations Ordinance. In its discretion and for good cause, the Planning Commission may extend for six (6) months the period of filing for the “final plat,” upon written request by the applicant. Should the applicant fail to submit a “final plat” within the six-month period following the City Council approval of the Special Use Permit, or by the termination date of the filing of the extension granted by the Planning and Zoning Commission, the Commission may initiate proceedings to amend the official zoning map by removing all or part of the Special Use Permit in the RMF Zoning District from the official zoning map. The City Council may uphold the Commission’s recommendation and proceed to advertise and hold public hearings thereon, or may elect to continue the special use permit in the R-MF Zoning District.~~
- ~~10. Compliance with Development Schedule – an application for a planned unit development district shall be accompanied by a development schedule indicating the appropriate date on which construction is expected to begin and the rate of anticipated development to completion. The development schedule, if adopted and approved by the City Council, shall become a part of the development plan and shall be adhered to by the owner, developer and his successors in interest. The development schedule shall be reviewed annually by the City Manager or his designee and he shall report to the Planning and Zoning Commission the actual development accomplished as compared with the~~

~~development schedule. The Planning and Zoning Commission may, if in its opinion the owner or owners of property are failing or have failed to meet the approved schedule, initiate proceedings to amend the official Zoning Map by removing all or part of the special use permit in the RMF Zoning District from the official zoning map. Upon the recommendation of the Planning and Zoning Commission and for good cause shown by the owner and developer, the City Council may also extend the development schedule or adopt such new development schedule as may be indicated by the facts and conditions of the case.~~

Section 3.16 MH – Mobile Home Residential District

- A. MH – Mobile Home Residential District – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this Section, are the regulations of the MH – Mobile Home Residential District.
- B. Purpose and Intent – The purpose and intent of the MH – Mobile Home Residential District is to provide for the orderly, safe, and healthful development of mobile home parks and mobile home subdivisions. Since mobile homes are recognized as a special form of housing, the intent of this district is to provide appropriate standards as to compatible land uses, density, minimum mobile home park or subdivision size, and other relevant requirements pertaining to the design, construction, alterations, and extensions of mobile home parks and mobile home subdivisions. Land uses in this district are normally connected to an approved public or private sewage collection and treatment system, rather than individual septic tanks and sub-surface drainage fields.
- C. Use Regulation – Every mobile home park or mobile home subdivision hereafter constructed, enlarged, altered, extended, or created shall comply with all regulations set forth under this Section.
- D. Permitted Principal Uses – The permitted principal uses allowed in this district are as designated in *Section 3.24 - Schedule of Permitted Principal Uses*.
- E. Permitted Accessory Uses – Subject to the provisions of *Section 3.28 - Supplementary District Regulations*, accessory buildings, structures, and uses customarily incidental to the "permitted principal uses" are allowed, including but not limited to the following:
1. Private residential garages, carports and related storage buildings and greenhouses accessory to permitted residential uses.
 2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All "at-grade" swimming pools with a water depth greater than twenty-four (24") inches and "above-grade" swimming pools having a water depth twenty-four (24") inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than four (4') feet nor more than eight (8') feet in height, and of such material and design to discourage unauthorized entry to the facility. Such pool (s) may be located in a required side or rear yard, but not within a required front yard~~ **forward of the primary dwelling on the lot**, and shall not be located closer than five (5') feet to any side or rear property line.
 3. Lanais, gazebos, garden and patio shelters, and children's play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
 4. Non-commercial radio and television receiving antennae and non-commercial radio transmitting antennae limited in height to sixty (60') feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
 5. Required off-street parking and loading spaces.
 6. Home occupation uses, as defined by *Chapter 2 – Definitions* of this Land Development Code.

Commented [EW29]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW30]: Recommend that the pool cannot extend beyond the front of the existing dwelling on the lot

7. Parking and storage of private boat(s), camper trailer(s), or other recreational vehicle(s), in conformance with the requirements for the "Parking, Storage or Use of Major Recreational Equipment and Vehicles."
8. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code.
9. Private domestic greenhouses.
10. Pool cabanas, laundry buildings, restroom/shower buildings, park office building, and other similar uses accessory to a Mobile Home Park or Mobile Home Subdivision.

~~F. Special Exception Uses – In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the "Zoning Board of Adjustment" may, after public hearing thereon, authorize and grant the issuance of a "Special Exception" for such special exception uses as allowed in Section 3.24 – "Schedule of Permitted Principal Uses." The issuance of such "exception" by the "Board" shall be contingent upon reasonable and appropriate conditions and safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

~~GE. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions for the "Classification of New and Unlisted Uses."~~

~~HG. Density, Area, Yard, Height, and Lot Coverage Requirements – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of Section 3.24 – "Schedule of District Regulations" and other applicable provisions of Section 3.28 – "Supplementary District Regulations."~~

~~IH. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform with the provisions for the "Off-Street Parking Requirements" and "Off-Street Loading Requirements."~~

~~J. Site Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the Official Zoning Map affecting this district, or for a "Special Use Permit" to be issued in this district, shall be accompanied by a site plan and supporting document therefor, unless otherwise waived by the Planning and Zoning Commission or Zoning Board of Adjustment, in conformance with the provisions of Chapter 1 – General Provisions of this Land Development Code.~~

Section 3.17 CPO - Professional Office Commercial District

A. Purpose – This district is designed to be compatible adjacent to or near residential areas and so as to provide office services needed by homeowners on a usual basis. The lot size maximum is small to encourage small-scale developments, and hours of operation do not permit businesses to be open at night.

B. Permitted Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

C. Special Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

D. Site Requirements

Minimum lot size: — 7, 200 s.f.	Minimum setbacks:	Max. Building height in stories: — 2 st.
Maximum lot size: 1 acre	front: 40 ft.	Max. building height in feet: — 35 ft.
Minimum lot width at front setback line: -100 ft.	side abutting residential: 25 ft.	Max. building height adj. to residential district: see Sec. 24
Minimum lot depth: 120 ft.	side abutting non-residential: 15 ft.	
Maximum lot coverage: 40%	rear abutting residential: 25 ft.	
	rear abutting non-residential: 10 ft.	

E. Supplementary Requirements

General:	Landscaping Plans:	Off-Street Parking:
- outdoor storage is not permitted	- required as per Chapter 4	- as required by Sec. 3.29
- uses adjacent to single family uses must be screened as per Sec. 3.26	Commercial Bldg. Design Stds.	Site Plans:
- may be operated in daytime only	- each site must have a minimum of 25 points as per Chapter 56	- plans must be submitted in accordance with Sec. 3.31

Section 3.18 CN - Neighborhood Commercial District

A. Purpose – This district is designed to be compatible adjacent to or near residential areas and to provide goods needed by homeowners on a usual basis. The lot size maximum is small to encourage small-scale developments, and hours of operation do not permit businesses to be open at night.

B. Permitted Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

C. Special Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

D. Site Requirements

General Requirements:	PRIMARY USE & STRUCTURE:	Accessory Use & Structure:
Minimum lot size: 10,000 s.f.	Minimum setbacks:	Permitted per Sec. 3.24 & 3.2827
Maximum lot size: 1 acre	front: 40 ft.	
Minimum lot width at front setback line: 100 ft.	side abutting residential: 25 ft.	
Minimum lot depth: 120 ft.	side abutting non-residential: 15 ft.	
Maximum lot coverage: 40%	rear abutting residential: 25 ft.	
	rear abutting non-residential: 10 ft.	
	Max. Building height in stories: 2 st.	
	Max. building height in feet: 35 ft.	
	Max. building height adj. To residential district: see Sec. 24	

E. Supplementary Requirements

General:	Landscaping Plans:	Off-Street Parking:
- outdoor storage is not permitted	- required per Chapter 4	- as required by Sec. 3.29
- uses adjacent to single family uses must be screened as per Sec. 24	Commercial Bldg. Design Stds.	Site Plans:
- may be operated in daytime only	- each site must have a minimum of 25 points per Chapter 65	- plans must be submitted in accordance with Sec. 3.31

Section 3.19 CC1 - Village Retail District

A. **Purpose** – This district is oriented to general commercial retail goods and services as well as some office, entertainment and community facility uses. While the district is designed to encourage “clustering” stores, the site requirements allow for a smaller scale than a shopping center type development. It is likely that Village Retail centers will be built without a major anchor store and be located near but not at major street intersections.

B. **Permitted Uses**

1. See Table 3.24.B - Schedule of Permitted Principle Uses

C. **Special Uses**

1. See Table 3.24.B - Schedule of Permitted Principle Uses

D. **Site Requirements**

General Requirements:	PRIMARY USE & STRUCTURE:	Accessory Use & Structure:
Minimum lot size: 15,000 s.f.	Minimum setbacks:	Permitted per Sec. 3.24 & 3.2827
Maximum lot size: 5 acres	front: 40 ft.	
Minimum lot width at front setback line: 150 ft.	side abutting residential: 25 ft.	
Minimum lot depth: 120 ft.	side abutting non-residential: 15 ft.	
Maximum lot coverage: 50%	rear abutting residential: 25 ft.	
	rear abutting non-residential: 10 ft.	
	Max. Building height in stories: 2 st.	
	Max. building height in feet: 35 ft.	
	Max. building height adj. To residential district: see Sec. 3.24 (A&B)	

E. **Supplementary Requirements**

General:	Landscaping Plans:	Off-Street Parking:
- outdoor storage is not permitted	- required as per Chapter 4	- as required by Sec. 3.29
- uses adjacent to single family uses must be screened as per Sec. 24	Commercial Bldg. Design Stds.	Site Plans:
- may be operated 24 hours/day	- each site must have a minimum of 30 points as defined by Chapter 56	- plans must be submitted in accordance with Sec. 3.31

Section 3.20 CC2 - Shopping Center District

A. **Purpose** – This district is oriented to general commercial goods and services as well as office, entertainment and community facility uses. By nature, shopping center tracts are large-scale usually accommodating a large anchor store and several smaller stores. These tracts are generally located at major street intersections.

B. **Permitted Uses**

1. See Table 3.24.B - Schedule of Permitted Principle Uses

C. **Special Uses**

1. See Table 3.24.B - Schedule of Permitted Principle Uses

D. Site Requirements

General Requirements:		<u>PRIMARY USE & STRUCTURE</u>	<u>Accessory Use & Structure</u>
Minimum lot size:	20,000 s.f.	Minimum setbacks:	Permitted per Sec. 3.24 & 3.2827
Maximum lot size:	none	front: 40 ft.*	
Minimum lot width at front setback line:	150 ft.	*see Sec. 23 (D) for special "urban Village" front yard setback.	
Minimum lot depth	120 ft.	side abutting residential: 25 ft.	
Maximum lot coverage	60%	side abutting non-residential: 15 ft.	
		rear abutting residential: 25 ft.	
		rear abutting non-residential: 10 ft.	
		Max. Building height in stories: 2 st.	
		Max. building height in feet: 35 ft.	
		Max. building height in PUD: 4 st.	
		Max. building height adj. To residential district: see Sec. 3.24 (A&B)	

E. Supplementary Requirements

General: - outdoor storage is not permitted - uses adjacent to single family uses must be screened as per Sec. 3.24 - may be operated 24 hours/day	Landscaping Plans: - required as per Chapter 4 Commercial Bldg. Design Std. - each site must have a minimum of 25 points as defined by Chapter 56	Off-Street Parking: - as required by Sec. 3.29 Site Plans: - plans must be submitted in accordance with Sec. 3.31
--	--	--

Section 3.21 CC3 - Highway Commercial District

A. Purpose – This district would permit uses that do not fit within the retail or manufacturing categories. Service and retail uses associated with outdoor storage, noise, especially auto repair and service and others would be permitted. The minimum lot size is less than the Shopping Center District to allow for more flexibility of uses. It is anticipated that most of these districts would not be located near residential districts.

B. Permitted Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

C. Special Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

D. Site Requirements

General Requirements:		<u>PRIMARY USE & STRUCTURE:</u>	<u>Accessory Use & Structure:</u>
Minimum lot size:	10,000 s.f.	Minimum setbacks:	Permitted as per Sec. 3.24 & 3.2827
Maximum lot size:	none	front: 40 ft.	
Minimum lot width at front setback line:	150 ft.	side abutting residential: 25 ft.	
Minimum lot depth	120 ft.	side abutting non-residential: 15 ft.	
Maximum lot coverage	70%	rear abutting residential: 25 ft.	
		rear abutting non-residential: 10 ft.	
		Max. Building height in stories: 2 st.	
		Max. building height in feet: 35 ft.	
		Max. building height adj. to residential district: see Sec. 3.24 (A&B)	

E. Supplementary Requirements

General: - outdoor storage is permitted - uses adjacent to single family uses must be screened as per Sec. 3.24 - may be operated 24 hours/day.	Landscaping Plans: - required as per Chapter 4 Commercial Bldg. Design Stds: - each site must have a minimum of 20 points as defined by Chapter 56	Off-Street Parking: - as required by Sec. 3.29 Site Plans: - plans must be submitted in accordance with Sec. 3.31
---	---	--

Section 3.22 ML - Light Manufacturing District

A. Purpose – This district would permit uses that involve the fabrication of products or have outdoor storage, noise, odors or other objectionable aspects that would not be compatible in retail or service areas. This district is limited to those uses that are not retail in nature or in some cases those that need outdoor space.

B. Permitted Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

C. Special Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

D. Site Requirements

General Requirements: Minimum lot size: 10,000 s.f. Maximum lot size: none Minimum lot width at front Setback line: 100 ft. Minimum lot depth 120 ft. Maximum lot coverage 60%	PRIMARY USE & STRUCTURE: Minimum setbacks: front: 40 ft. side abutting residential: 25 ft. side abutting non-residential: 15 ft. rear abutting residential: 25 ft. rear abutting non-residential 10 ft. Max. Building height in stories: 2 st. Max. building height in feet: 35 ft. Max. building height adj. To residential district: see Sec. 3.24 (A&B)	Accessory Use & Structure: Permitted per Sec. 3.24 & 3.2927
---	--	---

E. Supplementary Requirements

General: - outdoor storage is permitted - uses adjacent to single family uses Must be screened as per Sec. 3.24 - may be operated 24 hours/day.	Landscaping Plans: - required as per Chapter 4 Commercial Bldg. Design Stds: - each site must have a minimum of 30 points as defined by Chapter 56	Off-Street Parking: - as required by Sec. 3.29 Site Plans: - plans must be submitted in accordance with Sec. 3.31
--	---	--

Section 3.23 PUD – Planned Unit Developments

(Ord. O-05-1529 / 06/21/05)

A. Purpose - The purpose of a Planned Unit Development (PUD) is to provide for greater flexibility and discretion in the approval of residential, non-residential and mixed use developments by encouraging creative, efficient and aesthetically desirable residential and commercial projects that are superior to what could be accomplished in other zoning districts through the use of increased open spaces, greenbelts, or by providing enhanced amenities or features within the development that will be of special benefit to the property owners or to the community.

B. Ordinance Required and Effect on Official Zoning Map – Every Planned Unit Development approved

under the provisions of this section shall be considered an amendment to the Land Development Code and Official Zoning Map of the City of Colleyville, Texas. In approving any request for a Planned Unit Development district, the City Council shall, upon recommendation of the Planning and Zoning Commission, incorporate in the approving ordinance reference the approved site plan, supporting documents and include other conditions or restrictions imposed on the project by the Commission, including those of the Council. The approval and adoption of the amending ordinance by the City Council shall result in the appropriate change to the "Official Zoning Map."

- C. General Development Standards – The standards and requirements set forth in the Land Development Code shall be applicable to every Planned Unit Development, except where a new or different standard or requirement has been set forth in the ordinance establishing the PUD district. Such standards or requirements may be in addition to or in lieu of a development standard contained in the Land Development Code. The ordinance creating the Planned Unit Development may establish these requirements specifically in the ordinance or by reference to another zoning district.
- D. Classification of Planned Unit Developments – The approving ordinance establishing a Planned Unit Development shall include one of the following classifications, which shall also be shown on the Official Zoning Map using the applicable letter symbol.

Planned Unit Development Classifications		
PUD Classification	Planned Unit Development- Residential	Planned Unit Development - Commercial
Map Symbol	PUD-R	PUD-C
Classifications Defined	Planned developments containing primarily residential dwelling units, which may be grouped into clusters and may have a higher density than a conventional single family project of the same acreage, shall be classified as Planned Unit Development – Residential. A PUD-R may also contain a portion of non-residential uses.	Planned developments containing primarily non-residential uses, such as commercial, office, professional services, retail, institutional and industrial uses, or combinations thereof, shall be classified as Planned Unit Development – Commercial. A PUD-C may also contain a portion of residential uses.

- E. Permitted Uses – The uses permitted in a Planned Unit Development shall be enumerated in the approving ordinance with land use descriptions consistent with the Table of Permitted Uses, contained elsewhere in this Land Development Code. A Planned Unit Development may allow a combination of land uses, a specific use, or a class of generic uses, such as single family residential, office, retail, commercial or educational facilities, or a reference to another zoning district.
- F. Prohibited Uses – Uses not expressly permitted in the ordinance approving the Planned Unit Development shall be prohibited.
- G. Maximum Residential Density – The maximum residential density permitted in a PUD-R district, or in a PUD-C district where residential uses are proposed, shall not exceed 1.8 dwelling units per gross net acre. For the purpose of this regulation, the density calculation shall include all residential areas of the project and one-half of any abutting street situated adjacent to the project. This calculation shall exclude all proposed non-residential acreage and street rights-of-way from the gross-net acreage.

~~H. Density Bonus – A proposal for a PUD-R or a PUD-C containing a residential density exceeding 1.8 dwelling units per acre may be considered where the amount of open space area provided exceeds the minimum open space requirement or where additional amenities are provided within the open space area. A PUD proposal which contains a density exceeding 1.8 dwelling units per acre shall only be acceptable in an area consistent with sound land use planning, such as a transitional area situated between a non-residential area and less dense residential developments, or near a major street intersection, or for smaller parcels with unique topographical features that make less dense development economically difficult.~~

Commented [BB31]: No density bonus desired

- I. ~~Minimum Residential Lot Size – Notwithstanding Paragraph C above regarding maximum density, the minimum lot size in a PUD-R district shall be 13,000 square feet, with an average lot size of 16,000 square feet. No lot shall have less than 100 feet of width at the building line. The minimum lot size in a Planned Unit Development district shall be stated in the approving ordinance.~~
- J. **Open Space Requirements** – All requests for approval of a Planned Unit Development shall include provisions for open space areas in conformance with the following:
1. **Residential Areas** – For all residential uses, common open space land, comprising not less than twenty percent (20%) of the gross residential project area, shall be provided for the primary use of the occupants of the residential units.
 2. **Non-Residential Areas** – For all non-residential uses, open space land, comprising not less than twenty percent (20%) of the non-residential area, shall be provided. Said open space area may be the same area as the landscaped area required elsewhere in this Land Development Code.
 3. **Definition of Common Open Space.** For the purpose of this section, common open space is defined as follows:
 - a. Common Open Space may include:
 - i. land area of the development used for aesthetic, leisure and recreational purposes, that is accessible to and permanently reserved for the common use and enjoyment of the occupants of the development,
 - ii. golf courses, parks, and public open space areas adjacent to the development, which are readily accessible,
 - iii. low-impact passive uses include conservation of open land in its natural state (for example, woodland, fallow field, or meadow), neighborhood squares, common areas, picnic areas, community gardens, walking trails, bikeways, other kinds of pathways, and similar low-impact passive recreational uses, or
 - iv. active recreation uses including recreational playing fields, playgrounds, tennis courts, neighborhood pools, and clubhouse structures.
 - b. Common Open Space shall not include:
 - i. land areas reserved for the exclusive use and benefit of an individual owner or tenant,
 - ii. public or private street right-of-way, parkways, alleys, driveways, parking or loading areas,
 - iii. religious institutions or private school sites, or
 - iv. street medians or islands.
2. **Open Space Design Requirements.**
- a. An application for a Planned Unit Development that includes a common open space area shall include a written description or a plan of amenities, such as landscaped areas, trees and shrubs, sidewalks and trails, benches, pavilions, and play areas, to be included in the open space areas.
 - b. The maximum amount of common open space used for storm water detention or retention purposes shall not exceed twenty-five (25%) of the common open space area. If the open space area contains a retention pond, the pond shall include at least one (1) aeration device, such as a fountain, waterfall or underwater device.
 - c. Common open space areas adjacent to street rights-of-way shall be a minimum depth of twenty-five (25) feet and shall be landscaped to include the retention or planting of one (1) three (3") inch caliper tree per each fifty (50) feet of street frontage, which may be clustered or distributed within the open space area.
3. **Guarantee of Common Open Space.** In order to guarantee the preservation and maintenance of the common open space, one of the following methods shall be required:
- a. **Public Open Space** – Common open space may be conveyed to the City or other public agency,

Commented [BB32]: The PUD ordinance will determine minimum lot standards for area dimension (size, width & depth)

Commented [BB33]: Should the 20% standard be a recommendation? Should Council be able to reduce this standard as part of the PUD approval?

provided the public agency accepts the conveyance and agrees to maintain the common open space and any buildings, structures or other improvements.

- b. Private Open Space – Common open space may be conveyed to a homeowner's association or property owner's association, provided the declaration of covenants and restrictions that govern the association include, but is not limited to, the following:
 - i. the establishment of the association is made before any lot in the development is sold or any building occupied,
 - ii. membership in the association is mandatory for each building or property owner and any successive owner and give the association the power to compel contributions from residents of the development to cover their proportionate shares of the costs associated with the maintenance and upkeep of the common open space areas,
 - iii. ownership and maintenance of the common open space is guaranteed by a restrictive covenant, which is permanent, running with the land for the benefit of the occupants of the development and state that the association is totally responsible for the maintenance of the common open space and any improvements,
 - iv. submittal of a draft copy of the proposed covenants at the time of preliminary platting, which will ensure the guarantees stated in this section and provides for restricting the use of common spaces for the designated purposes, and
 - v. the plat contains a note stating that the common open space shall be maintained by the home owners association

K. Special Submittal and Exhibit Requirements – To facilitate the review and public hearing process, all applications for a Planned Unit Development shall include the following documents and exhibits:

- 1. *Application* – These forms are furnished by the Administrative Official.
- 2. *Application Fee* – No application shall be processed or scheduled for public hearing until the application fee has been paid.
- 3. *Statement of Planning Objectives* – The developer shall provide a written statement of planning objectives which describes the nature and character of the proposed development, any proposed development standards, and the rationale behind the assumptions and choices made by the applicant, including use and ownership of any open spaces, etc.
- 4. *Legal Description* – A written metes and bounds description of the total site area proposed for the Planned Unit Development.
- 5. *Development Schedule* – A development schedule indicating the target dates for the start and completion of the project, including any key dates of phasing of the project. The development schedule, if adopted and approved by the City Council, shall be incorporated into the approving ordinance, which shall be adhered to by the owner, developer and his successors in interest.

If upon review by the Administrative Official, the owner or owners of property fail to meet the approved schedule, the Planning and Zoning Commission or City Council may initiate proceedings under Chapter 1 – General Provisions of this Land Development Code regarding "Amendments, Frequency of Petition and Site Plan Requirements: Zoning and Special Use Permits," to amend the Planned Development District by removing all or part of the Planned Development District from the Official Zoning Map and placing the area involved in another appropriate zoning district. Upon the recommendation of the Planning and Zoning Commission and for good cause shown by the owner and developer, the City Council may also extend the development schedule or adopt such new development schedule as may be indicated by the facts and conditions of the case.

- 6. *Site Plan* – The Site Plan, which may be conceptual and general in nature, but in sufficient detail appropriate for the type of development being proposed and shall at a minimum include the following items, where applicable:
 - a. Proposed layout, indicating the approximate size and dimensions of all residential and non-residential lots
 - b. Proposed land uses and building locations
 - c. General elevation drawings of all non-residential structures indicating building height
 - d. Landscaping, lighting, fencing and screening of common areas
 - e. General locations of existing tree clusters
 - f. Location and construction type of perimeter fencing

- h. Design of ingress and egress with description of any special pavement treatments
- i. Calculations and location of off-street parking and loading facilities
- j. Location and type of all commercial signage and lighting, including pole heights, for parking lots and common areas
- k. Location and description of subdivision signs and landscaping at entrance areas
- l. Street names on all proposed streets

Exception: A Planned Unit Development application may be submitted and approved without a Site Plan, if the approving ordinance contains sufficient written detail to establish all site criteria.

- 7. *Drainage Analysis* – The applicant shall submit a Preliminary Drainage Analysis to determine the need for drainage facilities. The Preliminary Drainage Analysis shall be prepared in accordance with drainage analysis requirements contained in *Chapter 14 – Engineering Design Standards* of the Land Development Code.

- L. Optional Preliminary Plat Submittal – To expedite a development proposal, a developer may submit a separate application for a Preliminary Plat, which meets all of the requirements specified in Chapter 8 of this Land Development Code for a Preliminary Plat submittal, and which may be processed and reviewed concurrently with a PUD application, provided that no Preliminary Plat application shall be approved prior to the approval of the PUD application. The developer shall request a waiver of the 30 day time limit for Preliminary Plat approval where such applications run concurrently with a PUD application.

M. Approval Process

- a. *Application* – An application for a Planned Unit Development shall be submitted and processed using the same requirements used for submittal of a rezoning request, which shall be reviewed and considered in accordance with the procedures specified in Chapter One of this Land Development Code.
- b. *Conditions Related to Approval* – In establishing a Planned Unit Development, each application shall be evaluated by the Planning and Zoning Commission and City Council as to its probable effect on the adjacent property and the community. The Planned Unit Development may be approved or denied as the findings indicate appropriate. The Planning and Zoning Commission may recommend and the City Council may approve safeguards or conditions of approval to reduce the effect on adjacent or surrounding properties, which may include any or all of the following site conditions:

- | | |
|-------------------------------------|---|
| i. Accessory buildings | xi. Lot sizes and dimensions |
| ii. Building and structure heights | xii. Outside storage and display |
| iii. Drainage | xiii. Pedestrian circulation |
| iv. Exterior construction materials | xiv. Public street access |
| v. Exterior lighting | xv. Refuse and waste storage |
| vi. Fire protection measures | xvi. Screening or buffer areas |
| vii. Hours of operation | xvii. Signs |
| viii. Land uses | xviii. Vehicle traffic, circulation, and parking lots |
| ix. Landscaping and open space | xix. Other conditions deemed appropriate |
| x. Lot coverage, density & setbacks | xx. Project phasing and development schedule |

- c. *Modification of a PUD requirement* – The Planning and Zoning Commission may recommend and the City Council may approve a proposal for a Planned Unit Development that includes a provision which modifies any requirement contained in these Planned Unit Development regulations.
- d. *Amending a Planned Unit Development* – Changes to a Planned Unit Development or to its approved Site Plan shall be processed in the same manner as the original request. However, the administrator of this Code may approve minor modifications in an approved Concept Plan, provided the modifications:
 - i. Do not alter the basic physical relationship of the property to adjacent property;
 - ii. Do not change the permitted land uses;
 - iii. Do not increase the maximum density, floor area, height; or,
 - iv. Do not reduce the minimum yards or setbacks.

- N. Effect of this Section on Existing Planned Unit Developments – Previously approved PUD amending

ordinances to the City's preceding zoning ordinance and Land Development Code, including accompanying plans and supporting documents, shall remain in full force and effect with respect to this Chapter and shall not be made to comply with the provisions of this Chapter. Where a prior ordinance fails to provide specific information regarding minimum lot sizes, lot width, lot depth, set backs, building heights and maximum lot coverage, the requirements contained in Section 3.24.G shall prevail.

Section 3.24 Schedule of Permitted Uses

- A. General Requirement and Symbols Used – Land and buildings may be used in accordance with Table 3.24.C, *Schedule of Permitted Principal Uses* and the additional requirements of this section. The following symbols are used in Table 3.24.C, *Schedule of Permitted Principal Uses*:
1. *Permitted Uses* – A "P" in a cell indicates that the use is allowed by right as the principal use in the applicable zoning district in accordance with Table 3.24.C, *Schedule of Permitted Principal Uses*.
 2. *Specific Uses* – An "S" in a cell indicates that the use may be allowed with the approval by the City Council of a Special Use Permit following the applicable review and approval procedures.
 3. *Prohibited Uses* – An empty cell indicates that the land use is prohibited in the applicable zoning district, unless otherwise allowed with the approval by the City Council of an ordinance establishing a Planned Unit Development District, or authorized by a Special Use Permit, or in conformance with the provisions contained in Section 3.6.B-*Classification of New and Unlisted Uses*.

Table 3.24.B- - Schedule of Permitted Principal Uses

Table 3.24.B- - Schedule of Permitted Principal Uses																		
Land Use Classification	Residential District									Non-Residential Districts						Special Land Use Standards or Section Ref.	Parking Group	
	AG	RE	R40	R30	R20	R15	RD	RMF	MH	CPO	CN	CC1	CC2	CC3	ML			
A. RESIDENTIAL ACCOMODATION USES																		
Single Family Detached Dwelling	P	P	P	P	P	P	P	S	S	P							8	3
Duplex – Attached Dwelling							P	S									8	2
Townhome – Attached Dwellings								P									8	4
Multi-family – Attached Dwellings								P									8	4
HUD Code Manufactured Housing									P								8	2
Assisted Living Facilities	PUD only															2	17	
Bed and Breakfast Lodging	S	S	S	S	S	S	S	S									1,8	18
Private (HOA) Recreational Facilities		P	P	P	P	P	P	P	P								9	5
B. ACCESSORY USES																		
Accessory Building	P	P	P	P	P	P	P	P	P								Sec. 3.27	n.a.
Carport	S	S	S	S	S	S	S	S	S								Sec. 3.27.C	n.a.
Home Occupations Uses	P	P	P	P	P	P	P	P	P								8	n.a.
Servants or Caretakers Quarters <u>Accessory Dwelling</u>	P	P	S	S	S										S		16	1
C. AGRICULTURAL USES																		
Commercial equestrian boarding stable and school	P	S															17	25
Crop Farming	P	P																n.a.
Livestock raising and breeding	P	P															12	n.a.
Private horse stables for domestic use	P	P	P	S	S													n.a.
Roadside produce stands (year round)	S	S	S	S	S	S	S	S	S									n.a.
D. UTILITY USES																		
Electrical Substations	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S			21

Commented [BB34]: Only applies to AG & RE districts

Public Utility Supply and Storage Yards	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	24	
Table 3.24.B- - Schedule of Permitted Principal Uses																		
Land Use Classification	Residential District										Non-Residential Districts						Special Land Use Standards	Parking Group
	AG	RE	R40	R30	R20	R15	RD	RMF	MH	CPO	CN	CC1	CC2	CC3	ML			
Solid Waste Disposal Sites															S		24	
Telecommunications Towers	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	3	21	
Water Pumping Stations	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		24	
Wind Driven Generators	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		n.a.	
E. PUBLIC AND INSTITUTIONAL USES																		
Colleges or Universities	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		12	
Community Centers or Recreation Centers	S	S	S	S	S	S	S	S	S	P	P	P	P	P	P		5	
Government Buildings, Offices and Facilities	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		8	
Fire Stations / Police Stations	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		16	
Golf Courses – Public Owned	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		22	
Government Maintenance Facilities	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		25	
Libraries										P	P	P	P	P	P		9	
Museums										P	P	P	P	P	P		8	
Post Office	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		10	
Parks and Open Space Areas	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		25	
Public Maintenance and Storage Buildings	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		25	
Private Schools – Elementary and Secondary	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		13	
Private Schools – High School	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		14	
Public Schools – Elementary and Secondary	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		13	
Public Schools – High School	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		14	
Religious Institutions	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		18	
F. OFFICE USES																		

Commented [BB35]: Not a desired use

Commented [BB36]: Not appropriate in residential districts

Accountant's Offices												P	P	P	P	P	P	8
Table 3.24.B- - Schedule of Permitted Principal Uses																		
Land Use Classification	Residential District									Non-Residential Districts						Special Land Use Standards	Parking Group	
	AG	RE	R40	R30	R20	R15	RD	RMF	MH	CPO	CN	CC1	CC2	CC3	ML			
Advertising Agencies										P	P	P	P	P	S		8	
Attorney Offices										P	P	P	P	P	S		8	
Chiropractic Clinics										P	P	P	P	P	S		8	
Emergency Clinic (24 hrs.)												S	P	P	S	10	6	
Engineering, Architect's, and Surveyor's Offices										P	P	P	P	P	S		8	
General Business Offices not elsewhere listed										P	P	P	P	P	S		8	
Insurance Agencies										P	P	P	P	P	S		8	
Management and Public Relations Services Offices										P	P	P	P	P	S		8	
Optometrist Office										P	P	P	P	P	S		8	
Psychologist Offices										P	P	P	P	P	S		8	
Physician's or Dentist's Offices										P	P	P	P	P	S	5	7	
Real Estate Agency Offices										P	P	P	P	P	S		8	
Security Broker Offices										P	P	P	P	P	S		8	
Telemarketing Offices												P	P	P	S		5	
Title Abstract Offices										P	P	P	P	P	S		8	
Trade or Business Schools												S	S	S	P		15	
Travel Agency / Airline Ticket Offices										P	P	P	P	P	S		8	
G. RETAIL AND SERVICE USES																		
Alcoholic Beverage Sales – (Beer and Wine Only) – Off-Premises Consumption												S	S	S		13	n.a.	
Alcoholic Beverage Sales – On-premises Consumption												S	S	S		13	n.a.	
Package Store Sales – Off-premises Consumption												S	S	S		13	n.a.	
Alcohol or Drug Treatment Center										S	S	S	S	S	S		24	

Commented [BB37]: Permitted in restaurant that meets 60/40 alcohol food ratio (no more than 60% of total receipts for alcohol)

Antique Stores															P	P	<u>P</u>			7
Table 3.24.B- - Schedule of Permitted Principal Uses																				
Land Use Classification	Residential District										Non-Residential Districts						Special Land Use Standards	Parking Group		
	AG	RE	R40	R30	R20	R15	RD	RMF	MH	CPO	CN	CC1	CC2	CC3	ML					
Apparel and Accessory Stores												P	P	<u>P</u>				7		
Arts and Crafts Stores and Hobby Shops												P	P	<u>P</u>				7		
Bakery Stores												P	P	<u>P</u>				7		
Banks, Credit Unions and Financial Institutions											P	P	P	<u>P</u>				8		
Barber Shops, Beauty Shops and Day Spas											P	P	P	<u>P</u>		10		7		
Bicycle Shops												P	P	<u>P</u>				7		
Book, Stationary or Greeting Card Shops												P	P	P				7		
Camera or Music Stores												P	P	<u>P</u>				7		
Carnivals and Circuses												S	S					24		
Cemeteries or Mausoleums										S	S	S	S	S	S			24		
Charitable Donation Station												S	S	S				24		
Civic, Social or Fraternal Organizations										S	S	P	P					7		
Convenience Stores with gasoline sales												S	S	S	S			7		
Copy Centers/Print Shops										S	S	P	P	P	P			7		
Dance Studios, <u>and</u> Martial Arts Studios, <u>and</u> <u>Cheerleading & Gymnastics Facilities</u>										S	S	P	P	<u>P</u>	<u>P</u>			7		
Day Care Centers										S	S	S	S	S		17		11		
Department Stores												P	P	<u>P</u>				7		
<u>Dog Boarding with indoor kennels</u>													<u>P</u>	<u>P</u>	<u>P</u>	<u>4</u>		<u>8</u>		
<u>Dog Boarding with outdoor kennels</u>													<u>S</u>	<u>S</u>	<u>S</u>			<u>8</u>		
<u>Dog Grooming</u>													<u>P</u>	<u>P</u>	<u>P</u>			<u>8</u>		
Dry Cleaner Pick-up Stations											S	P	P	<u>P</u>				7		
Dry Cleaners (up to 5,000 s. f. w/on-site laundry)												P	P	<u>P</u>				7		

Equipment Rental and Leasing Stores																S	P		7
Florist Shops											P	P	P	<u>P</u>					7
Food Catering													<u>P</u>	<u>S</u>	<u>P</u>	<u>P</u>			8
Funeral Homes												S	S	S					24
Furniture and Appliance Stores												P	P	P					9
<u>General Retail Store (not listed elsewhere)</u>												<u>S</u>	<u>S</u>	<u>S</u>					<u>7</u>

Table 3.24.B- - Schedule of Permitted Principal Uses

Land Use Classification	Residential District									Non-Residential Districts						Special Land Use Standards	Parking Group
	AG	RE	R40	R30	R20	R15	RD	RMF	MH	CPO	CN	CC1	CC2	CC3	ML		
Grocery Stores												P	P	<u>P</u>		18	7
Hardware, electrical & plumbing w/o outside display											P	P	P	P			
Hardware , electrical & plumbing with outside display													S	P	P		
Hospitals												S	S	S			24
Hotels and Motels												<u>S</u>	P	P			19
<u>Interior-Home</u> Decoration Stores										P	P	P	P	<u>P</u>			7
Jewelry Stores											P	P	P	<u>P</u>			7
Locksmiths											S	S	<u>S</u>	<u>S</u>	<u>P</u>		8
Mailing and Shipping Stores											P	P	P	P	<u>P</u>		7
Meat or Fish Market												P	P	P			7
Nurseries and Greenhouses with outside display													S	P	P		16
Pawn Shops															<u>P</u> <u>S</u>		7
Pet Stores												P	P	<u>P</u>			7
Pharmacy											S	P	P	P			7
Photography Studios										P	P	P	P	P	P		8

Commented [BB38]: Catch-All Category

Commented [BB39]: New use

Commented [BB40]: New use

Billiard Parlors													S	S	<u>S</u>		17	23
Commercial Recreation (outdoor)	S											S	S	S	S	S		24
Fitness Centers												<u>S</u>	P	P	P	<u>P</u>		7
Golf Courses – Privately Owned	<u>S</u>	<u>S</u>	<u>S</u>	<u>S</u>	<u>S</u>	<u>S</u>	<u>S</u>	<u>S</u>	<u>S</u>	<u>S</u>	P	P	P	P	P	P		22
Golf Driving Ranges												<u>S</u>	P	P	<u>S</u>	<u>S</u>		22
Miniature Golf Courses													P	P				20
Roller or Ice Skating Rinks												<u>S</u>	S	S				24
Theaters													P	P	<u>P</u>	<u>S</u>	7	18
I. AUTOMOTIVE AND TRANSPORTATION USES													<u>S</u>	<u>S</u>			<u>17</u>	<u>23</u>
Airports and Heliports	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		24
Auto Alarm / Stereo / Window Tinting Stores														P	P	P	13	7
Auto Lube Shops														S	P	P	13	9
Automotive and Motor Vehicle Sales														S	<u>S</u>	S	13	8

Table 3.24.B- - Schedule of Permitted Principal Uses

Land Use Classification	Residential District										Non-Residential Districts						Special Land Use Standards	Parking Group
	AG	RE	R40	R30	R20	R15	RD	RMF	MH	CPO	CN	CC1	CC2	CC3	ML			
Auto Parts and Accessory Stores												P	P	P	P	13	7	
Auto, Truck or Trailer Rental													S	S	S	13	8	
Auto Upholstery Shops														P	P	13	9	
Auto Parking Lots and Garages (free standing)										S	S	S	S	S	S		n.a.	
Auto Repair Shop													S	S	S	13	9	
Boat and Water-craft Sales and Service													S	S	S	13	8	
Bus or Passenger Train Stations												S	S	S	S		24	

Car Wash (self service and automatic)																		S	P		9
Commuter Transit Stations														S	S			S	S		24
Gasoline Service Stations																		S	S	13	7
LPG / CNG Dispensing Stations																		S	S		24
Motorcycle Sales and Service																		S	S	13	8
Paint and Body Shops																		S	S	13	9
Park and Ride Facilities														S	S			S	S		24
Railroad or Motor Freight Terminals																		S	S		24
Recreational Vehicle Sales and Service																		S	S	13	8
Tire and Battery Stores																		S	S	13	7
Truck and Heavy Equipment Sales and Service																		S	S	13	8
Vehicle Storage Yards or Facilities														S	S			S	S		24

J. HEAVY COMMERCIAL, INDUSTRIAL & MANUFACTURING USES

Appliance Repair Shops																		S	S		8
Building Material Sales with outside storage																		S	P		7

Table 3.24.B- - Schedule of Permitted Principal Uses

Land Use Classification	Residential District										Non-Residential Districts							Special Land Use Standards	Parking Group
	AG	RE	R40	R30	R20	R15	RD	RMF	MH	CPO	CN	CC1	CC2	CC3	ML				
Commercial Laundry															S	S			24
Contractor Office with storage yard															S	S			24
Contractor Office without storage yard															P	P			8
Electronic Assembly or Manufacturing																P			25
Exterminator Shop															S	S			24

Colleyville, Texas, Land Development Code

Food Packaging and Manufacturing																	S		24
Furniture and Cabinet Manufacturing																	P		25
Office Showroom																	P		25
Oil and Gas Extraction	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	See Ch. 3.1		24
Plumbing, HVAC and Electrical Trades Shops																	P	P	8
Printing and Publishing - Commercial																	P		8
Plumbing, HVAC and Electrical Trades Shops																	P	P	8
Printing and Publishing - Commercial																	P		8
Research and Development Labs																	P		8
Scientific Instrument Assembly and Manufacturing																	P		8
Self Storage Facilities (mini-warehouse)																	S		24
Upholstery and Furniture Repair Shops																	P	P	8
Warehouse and Distribution Facilities																	S		24
Wood, Paper or Leather Products																	P		25
Manufacturing not elsewhere listed																	S		24
Welding or Machine Shop																	P		25
<u>Wholesale Store/Supply</u>																	<u>P</u>		<u>25</u>
<u>Wholesale Store/Supply with outdoor storage</u>																	<u>S</u>		<u>24</u>

Commented [BB41]: Duplicate listings

Commented [BB42]: New Uses

C. Special Land Use Standards – The following Special Land Use: Standards, which are referenced in the Special Land Use Standards column of Table 3.24.B, Schedule of Permitted Principal Uses, refer to additional standards and requirements that are applicable to the listed land use.

1. Bed and Breakfast – a Certificate of Occupancy (C.O.) is required prior to occupancy of the premises as a bed & breakfast. The C.O. shall be obtained after an inspection has determined that the structure is in compliance with all applicable current codes and ordinances of the City of Colleyville and the following additional conditions:
 - a. The structure is structurally sound.
 - b. There are no clear and present dangers as to fire and fire safety.
 - c. The plumbing is in compliance with the currently adopted code requirements for the zoning district in which it is located.
 - d. The electrical system is in compliance with the currently adopted Electrical Code for the zoning district in which it is located.
 - e. Smoke detectors shall be placed in each individual bedroom which is offered for public use and smoke detectors shall also be placed in any hallway adjacent thereto.
 - f. Signs, not exceeding one and one-half (1-1/2) square feet, shall indicate only the address and the establishment name.
 - g. Off-street parking shall be located behind the front building line of the structure and shall be screened from public view, and shall be provided in the following manner: one space per bedroom offered for temporary rental in addition to that required for the zoning district in which it is located.
 - h. The total rental bedroom area of the structure shall not exceed twenty-five (25) percent of the total floor area of the dwelling.

Also, in order to continue operation:

- i. Annual inspections shall be required for each bed and breakfast facility to ensure ongoing compliance with the requirements of this Section.
 - ii. Food service shall comply with all provisions of the City Code.
 - iii. The structure shall comply with all current City Codes, including, but not limited to Building Codes, Plumbing Codes, Electrical Codes, Fire and Safety Codes, and others as may from time to time be adopted.
 - ix. The length of stay for any guest is limited to fifteen (15) consecutive days.
2. Assisted Living Facilities – A facility operated under a certificate of compliance document issued by the Texas Department of Aging and Disability Services, in which food, shelter, and person assistance or supervision are provided for a period of at least 14 days for four or more aged adults who do not require hospitalization or skilled or intermediate nursing care.
 3. Telecommunication Towers – Construction shall be of monopole design only; and
 - a. the distance between the base of the tower and any Agricultural (Ag) or residential district or use shall be not less than two (2) times the height of the tower; and
 - b. the site plan shall meet all other commercial development requirements of the City such as site plan review, landscaping, setbacks; and
 - c. a minimum of one paved parking space shall be provided at the site of the structure.
 4. Veterinarian Clinic with indoor kennels – A facility containing indoor kennels shall be subject to the following conditions.
 - a. The entire business must be conducted within a soundproofed building. Noise and odors created by activities within the building shall not be discernible beyond the property line.
 - b. No animals shall be kept outside the building.
 5. Medical and veterinary clinics – Outpatient services only.
 6. Archery & firearm ranges – An SUP required in every zoning district, except CN & CC, for sales activity over 9 mo. per year.

Commented [BB43]: Move to Ch. 2 - Definitions

7. Movie Theater Uses: A movie theater shall not contain more than six primary projection screens and two secondary executive viewing rooms and shall not exceed 28,500 square feet in total building size. For purpose of this regulation, a secondary executive viewing room shall not exceed a maximum of fifty (50) seats. (O-04-1454 / 4-16-04) (O-05-1538 / 09/06/05)

Commented [BB44]: Regulations deemed not needed

8. Home Occupation Uses:

- a. No person other than members of the family residing on the premises shall be engaged in such occupation;
- b. The use of the dwelling unit or accessory building for the home occupation shall be clearly incidental and subordinate to its use for residential purposes by its occupants, and not more than twenty-five (25) percent of the floor area of the dwelling unit shall be used in the conduct of the home occupation;
- c. There shall be no change in the outside appearance of the building or premises, or other visible evidence of the conduct of such home occupation other than one sign, not exceeding one (1) square foot in area, non-illuminated, and mounted flat against the wall of the principal building.
- d. No traffic shall be generated by such home occupation in greater volumes than would normally be expected in a residential neighborhood, and any need for parking generated by the conduct of such home occupation shall be met off the street on a driveway or other hard surface all weather area;
- e. No equipment or process shall be used in such home occupation which creates noise, vibration, glare, fumes, odors, or electrical interference detectable to the normal senses of any adjacent or nearby site occupant. In the case of electrical interference, no equipment or process shall be used which creates visual or audible interference in any radio or television receivers off the premises, or causes fluctuations in line voltage off the premises.
- f. Home occupation uses and activities shall be limited to the following: seamstress; accounting; bookkeeping and tax services; notary public; insurance and real estate; small-scale production of cosmetics and household sundries; private educational, music and dance tutoring; arts, crafts and home hobby shops; garage, yard and patio sales of short temporary duration; mail order brokerage; and other similar activities --- but excluding medical and law offices, auto repair, beauty shops, pet grooming services, kennels and other such activities.

g. If a home occupation is deemed to become a nuisance, the Administrative Official may halt the use of the home occupation.

Commented [BB45]: Clarification of uses, permitted & non-permitted

Commented [EW46]: Recommended language for clarity of activities allowed

9. Private (HOA) Recreational Facilities – Buildings or structures in which members of a neighborhood association may gather for social, educational or cultural activities that are intended to serve the site occupants and guests thereof.

Commented [BB47]: New proposed regulation

Commented [BB48]: Move to Ch. 2 - Definitions

10. Emergency Clinics – Outpatient services only.

11. Livestock Raising and Breeding – A Special Use Permit is required for swine farming.

12. Alcoholic Beverage and Package Store Sales – A Special Use Permit is required for the sale of alcoholic beverages. A package store shall require the approval of a separate Special Use Permit. Any existing Special Use Permit for the sale of alcoholic beverages for off-premise consumption shall only be for beer and/or wine as specified in the approving ordinance and shall not be considered as approval for a package store as defined in Chapter Two. Also refer to Chapter 6 of the Code of Ordinances for additional regulations regarding alcoholic beverage sales.

Commented [BB49]: A review of Ch. 6 needed to modify the alcohol to food ratio for total receipts

13. Vehicle Repair – Vehicle repair, including the repair of other motorized vehicles, are permitted in accordance with the Schedule of Permitted Uses, subject to the following conditions.

- a. All repairs and servicing shall be conducted within an enclosed building.
- b. A business that conducts vehicle repair and is located on property adjacent to a residential use shall provide an six~~eight~~-foot tall solid screen along the property line adjacent to the residential use.

- c. Except for wrecked vehicles, no more than two vehicles per bay or repair/inspection station that have been accepted for repair or servicing shall be parked/stored outside after regular business hours.
 - d. Wrecked or dismantled vehicles waiting for repair shall not be visible from the street or other residential property and shall be stored in an enclosed building or within a completely enclosed area behind a ~~six~~eight-foot tall solid masonry screening fence.
14. ~~Servants or Caretaker Family or Servants Quarters~~ Accessory Dwelling – ~~A secondary dwelling for use by family members or domestic servants employed on the premises of family members provided the gross habitable square feet of floor area shall not exceed six hundred (600) square feet complies with regulations found in Section 3.27 of this chapter.~~ 5% of the lot area. Such quarters may be housed within the principal residential dwelling, above a residential garage, or be part of an accessory building on the same premises, and shall comply with minimum standards for light, health, safety, and occupancy in conformance with other applicable City codes and ordinances.
15. Day Care Centers – A facility operated with a state license for the purpose of providing care, protection and guidance to more than twelve children under the age of fourteen years of age for less than a 24-hour period. This term does not include kindergartens and public and private educational facilities or any facility offering care to individuals for a full 24-hour period.
16. Grocery Stores – A special use permit is required for the use of gasoline pumps in conjunction with a grocery store.
17. Billiard Parlor – Compliance with Chapter 10 of the Code of Ordinances is required for a Billiard Parlor.
18. Wind Driven Generators – No wind driven generator shall be constructed without approval of a special use permit per Section 3.24 of the Land Development Code.
- a. All wind driven generator towers shall be of a monopole design. All wiring shall be buried underground by means of a conduit system.
 - b. A wind driven generator may be considered on lots measuring a minimum of 1.5 acres.
 - c. The maximum height of a wind driven generator shall be no greater than 50 feet, measured from the existing ground level to the highest point of the blades.
 - d. All wind energy structures, including tower and rotor, shall stand independent of any building or structure and shall have a minimum setback from any property line, right-of-way, power line, or other improvement of 1.5 times the height of the wind energy structure. It shall also be located entirely in the rear yard and shall not be located in any required setback.
 - e. The maximum noise level shall not exceed 50 dB(a), measured from the property line, adjacent to any residentially zoned property, and 60 dB(a) adjacent to all other zoning districts.
 - f. A wind tower and generator shall not be artificially lighted unless such lighting is required by the Federal Aviation Administration.
 - g. The wind tower must either (a) have a locked anti-climb device installed on the tower; or (b) be completely enclosed by a locked, protective fence at least 6 feet in height.
 - h. No signage or advertisements shall be allowed on the wind tower.
 - i. A maximum of one wind energy system, including the tower, shall be permitted per lot.
 - j. A wind driven generator, found to be non-productive or unused, for a period exceeding 180 days, shall be immediately removed from the premise and the site returned to its prior condition, at the expense of the property owner.
19. Portable Storage Structures – A portable storage structure is any container, storage unit, shed-like container or other portable structure, other than an accessory building as defined in Chapter Two of the Land Development Code, complying with all building codes and Land Development Code requirements, that can or is used for the storage of personal property of any kind and which is located for such purposes outside an enclosed building.

The use of portable storage structures are allowed under the following conditions:

- a. Seven Day Provision: Portable storage structures placed on private property for a period of not more than seven (7) days are hereby exempt from these regulations provided the view of any

Commented [EW50]: Recommended provisions

Commented [EW51]: Recommend change in heading for this section

Commented [EW52]: Same language but relocated to beginning of paragraph

Commented [BB53]: New standards for Accessory Dwellings

Commented [BB54]: Move to Ch. 2 - Definitions

vehicular traffic is not impeded in any way. A permit shall be required per the provisions of sub-section "b". However, there shall be no fee required for structures that are placed for seven (7) or fewer days.

- b. A temporary use permit for a portable storage structure shall be obtained from the Community Development Department prior to placement for any portable storage structure.
- c. There shall be no more than one (1) portable storage structure per property.
- d. The portable storage structure shall be no larger than ten (10) feet wide, twenty (20) feet long and ten (10) feet high.
- e. Notwithstanding the requirements of sub-sections "k" and "l" below, a portable storage structure shall not remain at a property in any zoning district in excess of thirty (30) consecutive days, and shall not be placed at any one property in a zoning district in excess of thirty (30) days in any calendar year.
- f. The portable storage structure shall be set back a minimum of five (5) feet from all property lines.
- g. The portable storage structure shall be set back a minimum of five (5) feet from the nearest wall of a building.
- h. Where a side facing garage or a garage that is located behind the principal structure exists, the portable storage structure shall be located behind the front line of the principal structure.
- i. The portable storage structure shall be placed on an asphalt or concrete surface. A gravel surface is permitted if the portable storage structure is located behind the principal structure.
- j. The portable storage structure shall not be placed upon any street or within any rights-of-way. Exception: Portable storage structures located in mixed-use, townhome, multifamily, or similar residential developments may locate within existing, striped on-street parking spaces provided there are no public safety or vehicular traffic issues caused by the location of the structure.
- k. Portable storage structures associated with construction of a new principal building at a site where a new building permit has been issued are permitted for the duration of construction and shall be removed from the site within fourteen (14) days of the end of construction. Portable storage structures associated with new construction are exempt from the aforementioned conditions.
- l. Portable storage structures associated with any construction that is not part of the construction of a new principal building, and only in conjunction with the issuance of a building permit, may be placed for a maximum period of 180 days or upon completion of construction, whichever occurs first. The fee assessment for a portable storage structure associated with this sub-section shall be as follows:

0 to 30 days:	standard fee
30 to 60 days:	double the standard fee
60 to 90 days:	three times the standard fee
90 to 120 days:	four times the standard fee
120 to 180 days:	six times the standard fee

- m. Any waivers to the conditions of this section shall be considered by the Zoning Board of Adjustment **Special Use Permit (SUP)** in accordance with Chapter One **Section 3.25 Special Use Permit** of the Land Development Code.

Commented [BB55]: Revised for SUP approval

D. Temporary Buildings and Uses (O-04-1497 / 12/21/04)

- 1. Temporary Use Permit – The Building Official may approve a permit for a temporary use specified in this Section for limited periods of time, provided evidence is furnished by the applicant that adequate measures are taken to satisfy public safety concerns and related site criteria concerns. All temporary

uses shall be subject to the regulations contained in this Section. The building official may recommend a temporary use permit application be considered by the City Council where it has been determined by the building official that the proposed temporary use may have significant public interests. A temporary use permit, as herein prescribed, shall not be required for neighborhood block parties held in conjunction with the annual National Night Out neighborhood celebration or for events approved by a municipal department where said event is conducted on municipally owned property.

- a. Revocation: The Building Official may revoke a temporary use permit if determined that:
 - i. The applicant has misrepresented any material fact on the application, or supporting materials.
 - ii. The temporary use fails or ceases to comply with applicable standards or criteria for issuance of a permit.
 - iii. The operation of the temporary use violates any statute, law, ordinance or regulation.
 - iv. The operation of the temporary use constitutes a nuisance or poses a real or potential threat to the health, safety or general welfare of the public.
2. Permit Conditions – The Building Official is hereby authorized to prescribe reasonable conditions upon a temporary use permit to protect the public health, safety, and general welfare of the community, with particular attention to areas adjacent to or in the vicinity of the permitted temporary use. Such conditions may include specific performance standards, noise mitigation measures, lighting restrictions, limitation on hours of operation, odor control measures, off-street parking requirements, traffic restrictions, or other standards designed to minimize adverse impacts on surrounding properties. In the event that a sponsor is dissatisfied with the Building Official's decision, the sponsor may appeal the decision to the City Council.
3. Construction Offices and Sales Offices – The Building Official may approve a permit for a temporary building for use as a construction office or a sales office for new home or lot sales in any zoning district during the construction phase of a permanent building or new subdivision, provided such temporary buildings comply with the following requirements:
 - a. No temporary used as a construction office or a sales office shall encroach within five (5) feet of a property line or encroach within the visibility triangle required in Section 3.26 of this Land Development Code.
 - b. A temporary building used as a construction office during the construction of a permanent building shall be removed within ten (10) days after the issuance of the certificate of occupancy of the permanent building, weather permitting, ~~weather permitting~~.
 - c. A temporary building used as a real estate sales office shall be removed within ten (10) days after ninety (90%) percent of the lots within the subdivision have been sold.
 - d. A temporary construction office or real estate sales office shall sit on a blocked foundation acceptable to the Building Official. No temporary construction office or real estate sales office shall be used that rests only on the wheels.
 - e. A model home may be used as a temporary real estate sales office and shall be exempt from paragraphs a, b, c, and d above.
4. Community Special Events – Outdoor events of public interest which are anticipated to attract less than 500 persons in attendance at any one time for a period of eight consecutive hours or more, such as business activities, carnivals, circuses, and similar temporary events or special fund-raising events, ~~sponsored by a public entity, civic or non-profit organization located within the City.~~ Events sponsored by the City shall be exempt from the requirements of this section. Special Events shall comply with the following:
 - a. Application and site plan for a Special Event shall be submitted at least ten (10) business days in advance of the proposed event
 - b. Events located in parking lots which cause the loss of existing parking spaces shall require the submittal of written approval from the owner

c. ~~A Special Event shall not extend greater than any time period over twothree (23) consecutive days.~~

d. ~~There shall be at least one hundred eighty (180) calendar days between events before another permit can be obtained by the business or organization. Any entity that is directly or indirectly affiliated with the previous permit holder shall require the minimum separation between permits. There shall be no more than four (4) special events allowed per location per calendar year. There shall be at least thirty (30) calendar days between events before another permit can be obtained for the location.~~

Commented [BB56]: Revised per Council direction

Commented [BB57]: Revised per Council direction

5. Tents – A temporary use or special event which includes the use of a tent shall require a separate permit in accordance with the standards contained in the Colleyville Fire Code.
6. Temporary Asphalt or Concrete Batch Plant – The Building Official shall approve a permit for a temporary asphalt or concrete batch plant to provide construction materials for the site on which the temporary batch plant is located during the construction phase of a permanent building, new residential subdivision or other project as authorized by the city manager, provided such temporary use comply with the following requirements:
 - a. The temporary batch plant shall receive an approved air quality permit from the State of Texas, and evidence must be presented at the time of application for the temporary use permit.
 - b. The temporary batch plant shall follow all State of Texas storm water run-off requirements. A copy of any required State documents must be on the site of the temporary batch plant at all times.
 - c. A location map, drawn to scale, shall be provided and indicate the following: the location of the batch plant on the subject property along with a defined plant boundary, the location of all related equipment including but not limited to batching equipment and containers, storage areas, hazardous materials storage if applicable. Another drawing, drawn to scale, shall be provided showing the closest habitable residences, schools and religious institutions. The minimum distances shall be 300 feet measured in a direct line from the boundary of the temporary batch plant, as indicated on the application, to the property boundary of the protected use.
 - d. The material delivery route shall be provided indicating routes for raw material delivery with details on the type and numbers of trucks per day. Said route shall require final approval by the City Manager or his/her designee.
 - e. The hours of operation shall follow the construction hours of operation as required in the Colleyville Code of Ordinances.
 - f. A letter of permission shall be provided by the property owner stating that the temporary batch plant will be used to provide concrete/asphalt for the same site where it is located and no other project(s). The letter must also state that the site will be left in good or better condition.
 - g. The application must state the amount of time that the temporary batch plant will be in operation. The permit duration shall not exceed 30 days from the date of issuance. The Administrative Official may extend the permit for an additional 30 days with good cause. Only one permit may be issued for a given parcel of property within a 12 month period.
 - i. The Public Works Director shall determine if additional materials testing is required and may determine the testing personnel required. Any cost of testing shall be paid by the applicant.
 - j. The batch plant shall not be used as a batching facility for any other site other than the site on which it is located and no concrete, asphalt and/or any raw materials may be sold from said plant.

- k. Any appeal or waiver from the requirements of this section shall require final approval by the City Council.

E. Outdoor Storage; Screening and Hours of Operations

Zoning Districts		Outdoor Storage Allowed	Screening Requirements Adjacent to Single Family	Hours of Operation	Commercial Building Design Standards
CPO	Professional Office Commercial	No	8'	Daytime only	30-25 pts.
CN	Neighborhood Commercial	No	8'	Daytime only	30-25 pts.
CC1	Village Retail	No	8'	24 hours	30 pts.
CC2	Shopping Center	No	8'	24 hours	30-25 pts.
CC3	Highway Commercial	Yes	8'	24 hours	30-20 pts.
ML	Light Manufacturing - Industrial	Yes	8'	24 hours	30 pts.

Commented [BB58]: Revised to match each district

F. District Regulation Notes *{renumber as needed}*

- ~~A. Where abutting a lot zoned or used for residential purposes (RE through MH) maximum building height shall not exceed requirements shown in Figure 1 "Height Zones for Commercial Districts Adjoining Residential Districts". The roofline within that 50 feet shall have a maximum height of 16' at the eave and the roof design shall be of a residential style.~~
- ~~B. No structure shall be erected in any zoning district in excess of the specified maximum building height either in the number of stories or feet, whichever is less, unless an exception to said maximum building height is contained in this Chapter, except as noted in note "C" below.~~
- ~~C. Heights of four (4) stories may be permitted in CC2 (Shopping Center) district if combined with a Planned Unit Development (PUD).~~
- D. To achieve the "urban village" design, front yards may be varied to as little as 10' from the front property line if required parking is setback not less than forty feet (40') from the front property line.
- E. Where abutting a lot zoned or used for residential purposes (RE through MH) there shall be a twenty-five (25') foot side yard.
- F. Side or rear yards not required where no windows or other openings for light or entry face the yard, and not adjacent to single family.
- ~~G. There shall be a ten foot (10') side yard set-back, unless an ordinance approving a planned unit development for the property in question specifies a different side yard set-back; however, where abutting a lot zoned for commercial or industrial use, no side yard shall be required, provided there are no window or other openings for light or entry in the encroaching walls facing the side yard.~~
- ~~H. There shall be a ten (10') foot side yard set-back, unless an ordinance approving a planned unit development for the property in question specifies a different side yard set-back.~~
- I. Where abutting a lot zoned or used for residential purposes (RE through MH) there shall be a twenty-five (25') foot rear yard.
- ~~J. There shall be a minimum twenty-five (25) foot rear yard set-back, unless an ordinance approving a planned unit development for the property in question specifies a different rear yard set-back; however, the rear yard set-back may be reduced to ten feet (10'), provided there are no window or other openings for light or entry in the encroaching walls facing the rear yard.~~
- ~~K. Where abutting a lot zoned or used for residential purposes there shall be a minimum twenty-five (25') foot rear yard set-back, unless an ordinance approving a planned unit development for the property in question specifies a different rear yard set-back, however, the rear yard set-back may be reduced to ten feet (10') where abutting a lot zoned or used for non-residential purposes.~~
- L. All regulations may vary when above districts are used as a base district for a PUD.

Commented [BB59]: These notes not needed, not included on the chart

Commented [BB60]: Not needed with removal of PUD lined from chart

Commented [BB61]: Not needed with removal of PUD lined from chart

Commented [BB62]: Not needed with removal of PUD lined from chart

Commented [BB63]: Move to footnotes section of the chart

SECTION 3.24.G - SCHEDULE OF DISTRICT REGULATIONS
MAXIMUM RESIDENTIAL DENSITY; MINIMUM LOT SIZE REQUIREMENTS; MINIMUM YARD REQUIREMENTS;
MAXIMUM BUILDING HEIGHT; MAXIMUM LOT COVERAGE; OUTDOOR STORAGE; SCREENING
AND HOURS OF OPERATION

(See District Regulations Notes following Section 3.24.F for explanation of letters in charts)

Zoning Districts		Max. [*] Res. Density	Minimum Lot Size Requirements					Minimum Yard Requirements				Max. Building Height		Max. Lot Coverage
Classification	DU/AC		Area (sq. ft.)		Min. Width in feet	Min. Depth in feet	Max. Lot Size	Front (feet)	Each Side (feet)	Rear (feet)	Stories	Feet	Percent	
			Per Family	Total										
AG	Agricultural	0.3	130,680	130,680	200'	300'	n.a.	40'	25'	40'	2.5	35'	20%	
RE	S. F. "Estate" Residential	0.5	80,000	80,000	200'	300'	n.a.	40'	25'	40'	2.5	35'	20%	
R-40	Single Family Residential	1.25	40,000	40,000	150'	150'	n.a.	40'	15'	25'	2.5	35'	20%	
R-30	Single Family Residential	1.5	30,000	30,000	125'	125'	n.a.	35'	10'	25'	2.5	35'	25%	
R-20	Single Family Residential	2.1	20,000	20,000	100'	125'	n.a.	30'	10'	25'	2.5	35'	30%	
R-15	Single Family Residential	3	15,000	15,000	100'	125'	n.a.	30'	10'	25'	2.5	35'	30%	
R-D	Two Family Residential	8	4,000	8,000	70'	115'	n.a.	25'	10'	25'	2.5	30'	50%	
R-MF	Multi-Family Residential (zoned after June 16, 1981)	8	2,700	18,000	70'	115'	n.a.	25'	10'	25'	2.0	30'	50%	
R-MF	Multi-Family Residential (zoned before June 16, 1981)	18	1,500	10,000	70'	115'	n.a.	25'	10'	25'	3.0	30'	75%	
MH	Mobile Home (Minimum size of mobile home park - 40 spaces)	2.1	20,000	20,000	100'	125'	n.a.	30'	10'	25'	2.5	30'	30%	
C-PO	Professional Office Commercial	n.a.	n.a.	7,200	100'	120'	1 acre	40'	15' (E / F)	10' (F / I)	2.0	35'	40%	
CN	Neighborhood Commercial	n.a.	n.a.	10,000	100'	120'	1 acre	40'	15' (E / F)	10' (F / I)	2.0	35'	40%	
CC1	Village Retail	n.a.	n.a.	15,000	150'	120'	5 acres	40' (D)	15' (E / F)	10' (F / I)	2.0	35'	50%	
CC2	Shopping Center	n.a.	n.a.	20,000	150'	120'	none	40' (D)	15' (E / F)	10' (F / I)	2.0	35'	60%	
CC3	Highway Commercial	n.a.	n.a.	10,000	150'	120'	none	40'	15' (E / F)	10' (F / I)	2.0	35'	70%	
ML	Light Manufacturing	n.a.	n.a.	10,000	100'	120'	none	40'	15' (E / F)	10' (F / I)	2.0	35'	60%	
POD-R	Planned Unit Dev. - Residential	n.a.	n.a.	10,000	100'	120'	n.a.	30'	10' (H)	25' (J)	3.0	30'	30%	
POD-C	Planned Unit Dev. - Commercial	n.a.	n.a.	7,200	70'	115'	n.a.	40'	10' (S)	10'	3.0 (S)	35'	50%	
POD-I	Planned Unit Dev. - Industrial	n.a.	n.a.	10,000	70'	115'	n.a.	40'	10' (S)	10'	3.0	30'	30%	

^{*} Maximum residential density is the number of dwelling units per acre, not including streets, alleys, or public space. R-MF zoned after June 16, 1981 - four units per building maximum.

^{**} 16,000 s.f. average

***All regulations may vary when above districts are used as a base district for a PUD**

Section 3.25 Special Use Permit

(O-02-1331 / 02-19-2002)

The purpose of a Special Use Permit is to allow a use not normally allowed in a zoning district, which could be of benefit in a particular case to the general welfare, provided adequate development standards, and special requirements are imposed to protect surrounding uses or to preserve the character of the neighborhood. Upon proper application and payment of the applicable fee, the City Council, after public hearing and proper notice to all parties affected and after recommendation from the Planning and Zoning Commission, may authorize a Special Use Permit for a use not allowed by right in *Section 3.24 "Schedule of Permitted Principal Uses"* in accordance with the following criteria.

1. Procedures – Every Special Use Permit application shall be reviewed and considered using the same procedures for reviewing and considering a rezoning application as specified in *Chapter 1 – General Provisions* of this Land Development Code.
2. Site Plan – The applicant must submit a site plan in the form and manner specified by the Administrative Official, showing the details of the proposed use and its relationship to surrounding properties.
3. Additional Information – The City Council and the Planning and Zoning Commission, in considering and determining its recommendation to the City Council on any request for a Special Use Permit, may require from the applicant, plans, information, operating data and expert evaluation concerning the location and function and characteristics of any building, structure or use proposed.
4. Conditions of Approval – The City Council may impose such safeguards, requirements and conditions as it deems are necessary to properly protect any surrounding property, surrounding use, or neighborhood character and to insure the appropriate conduct of the special permitted use, including, without limitation, imposing development standards, requiring public facility improvements and means of ingress and egress of public streets, establishing conditions of operation, establishing time limits, establishing location, arrangement and construction of any uses or structures, adopting regulations to protect the general welfare and adjacent property from excessive noise, vibration, dust, dirt, smoke, fumes, gas, odor, explosion, glare, offensive view of other undesirable or hazardous conditions. All conditions imposed by the City Council shall be complied with prior to the issuance of a Certificate of Occupancy.
5. Revocation Upon Failure to Develop – A special use permit approved by the Council shall become null and void one year from the date of approval by the City Council unless a building permit or certificate of occupancy, whichever is applicable, has been obtained on the property within said one year period. The City Council may in its adopting ordinance, shorten or lengthen the time in which a building permit or certificate of occupancy must be issued in order to preserve the special use permit. Any Special Use Permit in existence upon the passage of this ordinance shall become null and void one year after the passage of this ordinance, unless a building permit or certificate of occupancy, whichever is applicable, has been issued within said year.

Exception: The ordinance authorizing a Special Use Permit may provide for an alternate expiration period.

6. Termination and Abandonment of Use – In the event the building, premises or land uses authorized by a Special Use Permit are terminated or abandoned for a period of six (6) months or longer, the use of the same shall thereafter conform to the regulations applicable to the zoning district, unless a new and separate Special Use Permit is approved for continuation of the use.
7. Modification – No building or premises authorized by a Special Use Permit may be enlarged, modified, structurally altered, or otherwise significantly changed unless an amendment to the Special Use Permit is approved by the City Council using the procedures specified in *Chapter 1 – General Provisions* of this Land Development Code.
8. Violation – It shall be unlawful for property owner or tenant to violate any terms or conditions of the ordinance approving the Special Use Permit.

Section 3.25.1 Large-Commercial Buildings

(O-00-1249 / 11/08/00)

Commented [BB64]: Section to be moved to Chapter 6: Commercial Design Standards

- A. Applicability – The criteria in this Section shall be applicable to the construction of any new large commercial building proposed for construction on or after November 8, 2000. These criteria shall not be applicable to the following:
1. ~~The~~ use, re-use, modification or consolidation of existing commercial buildings developed prior to November 8, 2000, or to the expansion of commercial buildings existing as of November 8, 2000, provided expansion does not exceed ten percent (10%) of the existing building footprint, including the cumulative amount of all prior expansions, or
 2. ~~B~~ buildings constructed within the limits of the PUD-C established by ordinance O-99-1141.
- B. General Provision – No new large commercial building shall be permitted for construction within the city of Colleyville, except where allowed as follows:
1. Large Commercial Building shall be allowed by right in the ML – Light Manufacturing District.
 2. Large Commercial Building shall be allowed with approval of a Planned Unit Development – Commercial.
 3. No large commercial building shall be permitted within a previously approved Planned Unit Development – Commercial, unless the approving ordinance contains a specific provision for a large commercial building as provided in this Section. The requirements and procedures for a Planned Unit Development – Commercial contained elsewhere in the Colleyville Land Development Code and the additional requirements set forth in this Section shall be used in the review of an application for a large commercial building. The City Council may establish such terms and conditions as are necessary to protect life, health, property, public peace and the general welfare of the public and the adjacent properties. For purpose of this regulation, a commercial building which contains a building footprint of forty thousand (40,000) square feet, or more, shall be declared a large commercial building and be subject to these criteria.
- C. Application and Development Requirements – Every large commercial building must comply with the requirements of this Section. All site plan reviews required by the Colleyville Land Development Code or applications for a rezoning request for a Planned Unit Development – Commercial for a large commercial building shall include all the information outlined as follows.
1. Site Plan – A site plan, drawn to scale, showing the property boundary, all proposed buildings, water features, creek channels, the 100-year flood plain, outdoor display areas, proposed driveways, parking lots, landscaped areas, loading and delivery docks, refuse and recycling facilities and other physical features which may influence the development of the site.
 2. Elevation Drawings – Building elevation drawings, drawn to scale, indicating the type and percentage of each exterior building wall material.
- D. Development Requirements
1. Building Height, Set Back Requirements and Maximum Lot Coverage – The minimum front, side and rear building set back lines, maximum building height, and maximum lot coverage for a 40,000 square foot building footprint shall be in accordance with the following schedule:

Minimum Building Line Set Backs, Maximum Height and Maximum Lot Coverage for a 40,000 s.f. Large Commercial Building			
Minimum Building Set Back	Front:	40 ft.	(1) (2)
	Side:	40 ft.	(1) (2)
	Rear:	40 ft.	(1) (2)
Maximum Building Height		35 ft.	
Maximum Lot Coverage		40%	

Notes:

- (1) The minimum building set back line adjacent to a public street shall be increased one foot for each additional increment of 2,000 s.f. of building footprint over 40,000 square feet of building footprint.
 - (2) The minimum building set back line adjacent to a residential zoned property shall be a minimum of 50 feet and shall be increased one foot for each additional increment of 1,000 s.f. of building footprint over 50,000 square feet of building footprint with a maximum building setback of 250 feet. If a public road stands between the residential zoned property and the commercial establishment, the road width may be included in the setback calculation if the setback exceeds 100 feet.
 - (3) The setback requirements between two commercial zoned properties shall conform with the CC2 zoning requirements as outlined in the Land Development Code.
2. *Façade Articulation* – All large commercial buildings shall have facades which comply with the following requirements:
- a. *Horizontal Articulation* – No building façade which faces a public street shall extend horizontally greater than three (3) times the height of the wall without having an off-set of not less than fifteen (15%) percent of the wall's height as shown on the attached Exhibit "A", and such off-set shall continue for a minimum distance equal to at least twenty-five (25%) percent of the length of the longest adjacent plane.
 - b. *Vertical Articulation* – No building façade which faces a public street shall extend horizontally for a distance greater than three (3) times the height of the wall unless the wall contains at least one of the following features and every front building façade shall have no less than two of the following features:
 - (1) Parapets which change the roof line. The parapet height shall be a minimum of fifteen (15%) percent of the wall's height, and such height change shall continue for a minimum distance equal to at least twenty-five (25%) percent of the length of the longest adjacent plane.
 - (2) Overhanging eaves, extending no less than three (3) feet past the supporting walls.
 - (3) Sloping roofs that do not exceed the average height of the supporting walls, with an average slope greater than or equal to one (1) foot of vertical rise for every three (3) feet of horizontal run and less than or equal to one (1) foot of vertical rise for every one (1) foot of horizontal run.
 - (4) Three or more roof slope planes.
 - (5) A covered walkway along a minimum of fifty (50%) percent of the front façade length.
3. *Side and Rear Facade Features* – Side and rear building facades, which do not face a public street, shall include a minimum of three architectural changes, such as (1) a changing plane not less than five (5) feet in width and eighteen (18) inches in depth, (2) a surface material change of not more than thirty (30) feet in length, as measured horizontally, or (3) a combination of these elements.
4. *Building Design* – In addition to the building façade requirements contained herein, the site plan and building elevation plans shall comply with the requirements of *Chapter 6 – Building Design* of the Colleyville Land Development Code, except where modified by the requirements in this Section. The minimum building design score shall be 30 points.
5. *Exposed Columns* – Exposed structural support columns shall be constructed of, or clad in, the same masonry material as the principal structure. Architecturally significant columns (e.g. fluted, etc.) may be permitted.
6. *Exterior Surface Materials* – A minimum of ninety (90%) percent of each exterior wall surfaces, excluding door and window openings, shall be constructed of clay-fired brick, native stone, cast stone, or a combination of these materials. Tilt - up concrete construction is permitted, provided the

exterior surface is covered with clay-fired brick, native stone, cast stone, or a combination of these materials. Stucco and EIFS (Exterior Installation Finished System) are permitted for not more than ten (10%) percent of the exterior surface. Concrete block, split-faced block or cinder-block shall not be acceptable, except where a wall surface faces an adjacent non-residential building. Proposals for surface materials with similar durability and appearance of clay-fired brick, native stone, or cast stone may be considered.

7. *Exterior Surface Colors* – The exterior surfaces shall be of a natural finish, provided the colors are, subtle, or neutral colors. Trim and accent areas may be painted and feature brighter colors, including primary colors, but not more than ten (10%) percent of the wall surface area. High intensity or fluorescent colors are prohibited.
8. *General Landscaping Requirement* – The landscaping of the development shall comply with the requirements of Chapter 4 – Landscaping and Buffering of the Land Development Code, except where modified by the requirements of this Section. All ground surfaces not used for buildings, sidewalks, roadways or other impermeable surfaces shall be covered with live grass, turf, shrubbery, trees, ground cover, flowering plants or appropriate mulching. In order to insure for a variety of plant materials the following minimum requirements for grass, shrubs, and trees shall be provided:
 - a. *Minimum Landscaping Coverage*: Not less than twenty percent (20%) of the total land area of the development shall be, landscaped. At least fifty percent (50%) of the total landscaped area shall be located in the street yard(s). The overall minimum percentage of required landscaping may not be reduced by the application of landscaping enhancement credits.
 - b. *Trees*: Landscaping shall include the retention or planting of one (1) three-inch (3") caliper overstory shade tree per each forty (40) feet of street frontage. These trees to be planted within the landscaped buffer adjacent to each street frontage.
9. *Landscape Buffer and Screening Wall Adjacent to Residential Property* – Along the entire length of the common property line adjacent to residential property there shall be a landscape buffer, a minimum of forty (40) feet in width, and a solid screening wall constructed of clay-fired brick, native stone, cast stone, or a combination of these materials, not less than eight (8) feet in height nor more than ten (10) feet in height. The landscape buffer and the solid screening wall shall be provided along the entire length of any property line adjacent to any residential property. The landscaped buffer shall contain lawn grass or ground cover and be maintained as a permanent landscaped area. There shall be no buildings, parking areas, driveways, sidewalks or structures contained within the required buffer. The landscaping buffer shall include the retention or planting of one (1) three-inch (3") caliper overstory shade tree per each forty (40) feet of common property line with an adjacent residential property. Said screening wall shall be constructed generally along the common property line with the residential property, but its terminus shall not encroach nearer than twenty-five (25') to a street right-of-way.
10. *Landscape Buffer and Screening Adjacent to Public Streets* – There shall be a minimum forty (40) foot wide landscape buffer adjacent to all street rights-of-way. There shall be no buildings, parking areas, driveways, sidewalks or structures, except permanent signs, contained within the required landscape buffer. A driveway or sidewalk may cross the buffer to provide access to the site. Within the landscaped buffer, there shall be either one or a combination of the following landscaping features:
 - a. *Earthen Berms*: A minimum of thirty (30) inches in height with a maximum side slope of three feet to one foot of rise as shown on the attached Exhibit "B". The berm shall not extend parallel to the street right-of-way, but shall meander in a serpentine fashion and shall be entirely vegetated with lawn grass or groundcover.
 - b. *Shrubs*: A row of shrubs consisting of individual shrubs planted not more than thirty-six (36) inches on center which will form a solid continuous visual screen of not less than thirty (30) inches in height within a two year period after planting as shown on the attached Exhibit "C". Shrubs shall be maintained so as to not exceed six (6) feet in height. The shrub row shall be located along the portion of the landscaped buffer that is the furthest from the street right-of-way.

- c. *Low Solid Wall:* A solid wall constructed of clay-fired brick, native stone, cast stone, or a combination of these materials, not less than thirty (30) inches in height as shown on the attached Exhibit "D". Said wall shall be constructed generally parallel to and twenty (20) feet from the street right-of-way. The solid wall shall not constitute more than thirty (30) percent of the length of the abutting street frontage.
11. *Parking Lot Landscaping* – Parking areas shall contain a minimum of one (1) ~~landscaped~~ landscaped island per sixteen (16) parking spaces. No landscaped island shall be less than three-hundred (300) square feet. Every landscaped island shall include one (1) three-inch (3") caliper shade tree with the remaining area covered with grass, shrubs or ground cover. Landscaped planting areas shall be located so that no parking space shall be more than seventy-five (75) feet from the trunk of a shade tree. Where a landscaped island is adjacent to a landscaped buffer, the parking spaces adjacent to the landscaped island shall be paved with a pervious material pave-stone. The parking lot landscaping requirements contained in the paragraph shall not be applicable to the interior parking spaces of a parking garage.
12. *Parking Lot Walkways* – There shall be a pedestrian walkway a minimum of eight (8) feet in width for every four rows of parking within the parking area. Said walkway shall be constructed parallel to the parking rows as shown on the attached Exhibit "B". The walkway shall be paved with a hard surface.
13. *Curbing of Landscaped Areas* – All landscaped islands and landscaped areas shall be protected from vehicular encroachment by concrete curbs a minimum of six (6) inches in height.
14. *Permanent Ground Signs* – The development shall comply with the provisions of Chapter 7 – Sign Regulations of the Colleyville Land Development Code, except that only one monument sign per street frontage shall be allowed. The maximum height of the monument sign structure shall be eight (8) feet. The maximum area of the monument sign structure shall be one-hundred (100) square feet. Only external illumination shall be allowed. Each side of the monument sign structure shall contain an architectural feature of clay-fired brick, native stone, cast stone or a combination of these materials. The architectural feature shall be equivalent to fifteen (15%) percent of the total area of the sign structure.
15. *Attached Building Signs* – The development shall comply with the provisions of Chapter 7 – Sign Regulations of the Colleyville Land Development Code, except that the total square footage of all wall signs shall not exceed ten (10%) percent of the wall face.
16. *Tree Preservation* – The development shall comply with the provisions of Chapter 5 – Tree Preservation of the Colleyville Land Development Code.
17. *Off-Street Parking and Loading Requirements* – The development shall comply with the requirements of Section 3.29 – Off-Street Parking Requirements of the Colleyville Land Development Code. The maximum number of parking spaces shall be one (1) space per two-hundred (200) square feet of gross floor area.
18. *Delivery / Loading Spaces* – No delivery or loading space shall be located within one-hundred (100) feet of a residential property. All delivery and loading spaces shall be screened from public view from a street right-of-way or an adjacent residential property by an eight (8) foot to ten (10) foot tall solid screening wall constructed of like material to the building. Additional planting materials shall be provided so that no more than two-thirds of the surface area of the solid screening wall is visible from the street or residential property. The live plant screening shall consist of shrubs, a minimum of three (3) feet in height when planted, and which can be expected to reach six (6) feet or greater in height within three (3) years of planting. Shrubs shall be spaced so that there shall be no gap greater than four (4) feet between mature plant materials. No delivery or loading area shall be operated between the hours of 11:00 p.m. and 6:00 a.m. Parking of delivery vehicles shall not exceed 48 hours duration.
19. *Outdoor Display Areas* - Outside display of merchandise shall be allowed, provided that it shall be limited to an area within eight (8) feet of the front wall of the primary building and further provided that emergency pedestrian access to the building is not blocked. No merchandise shall be displayed between the hours of 11:00 p. m. and 6:00 a. m.

For purpose of this regulation, the front wall shall be the front containment wall of the structure and not the front of an overhanging walkway cover.

20. **Outside Storage and Sales Areas** –There shall be no outside storage or outside sales areas of landscaping materials, plants or general merchandise, except for an outside display area, as provided in the above paragraph. For purpose of this regulation, nothing shall prohibit the sale or display of landscaping materials, plants or general merchandise located behind an enclosed solid screening wall constructed of like material to the building, provided merchandise is not visible above the top of the screening wall.
21. **Refuse Collection** – No refuse collection shall occur within 100 feet of residential property. All refuse containers, including recycling containers, and trash compactors shall be screened from view from a public street and from adjacent residential properties by an enclosure constructed on three sides with an eight (8) foot high solid masonry screening wall constructed of like material to the building. Said screening enclosure shall include solid metal doors. When a refuse container, trash compactor or recycling container is situated adjacent to a residential property, the screening wall enclosure shall comply with the building setback lines established for the zoning district.
22. **Screening of Mechanical Equipment** - Roof or ground-mounted mechanical equipment shall be screened to mitigate noise and views in all directions from adjacent property. If roof mounted, the screening material shall be designed to conform architecturally with the design of the building. Ground-mounted mechanical equipment shall be screened by a solid masonry screening wall constructed of like material to the building and be of sufficient height to block the view and noise of the equipment from adjacent property.
23. **Cart Storage** – All shopping cart storage areas shall be contained within the primary building. Temporary shopping cart parking within parking areas shall be allowed, provided carts are removed to within the primary building on a frequent basis.
24. **Outdoor Lighting** – ~~Light poles situated within 300 feet of residential property shall not exceed twenty (20) feet in height. Exterior lighting must be High Intensity Discharge (HID) lights shielded and directed away from adjacent properties and shall produce light no greater than one foot candle at the property line, except at driveway entrances which shall be lighted adequately to provide for safe access to the property. The parking lot lighting system shall be designed to dim between the hours of 11:00 p.m. and 6:00 a.m. Wooden light poles shall be prohibited as an illumination standard. Security lighting at the rear and sides of the building shall be designed to reduce light pollution and to prevent objectionable glare onto any residential property.~~ [Exterior lighting shall comply with Chapter 6 \(Building Design Standards\) of the Land Development Code.](#)

Commented [EW65]: New Section 6.6 in Chapter 6 addresses exterior lighting in all commercial districts





Exhibit "A"


Façade Articulation

Berm




**Landscape Berm
Exhibit "B"**

Hedge




**Landscape Shrubs
Exhibit "C"**

**Masonry
wall**



**Solid Wall
Exhibit "D"**



Parking Lot Walkway
Exhibit "E"

Section 3.26 Fences, Free Standing Walls, and Screening Materials

A. Scope

1. This section is to regulate fences, free standing walls and other screening material in a manner so as to promote safety, preserve property values, promote the general welfare of the City of Colleyville, and to enhance the aesthetic quality of the community.
2. No fence, screen, freestanding wall or other visual barrier shall be constructed or placed in such a manner as would endanger the health or safety of the general public.
3. For administrative purposes, all references to fences or walls shall be interpreted to apply to free standing structures.

B. Definitions - Fence or Wall Placement

~~Perimeter Subdivision Fencing. A subdivision perimeter fence shall be construed to be any decorative or security fence along a substantial portion of the boundary or property line of any plat, replat or phase of a plat or replat or filing of a plat or replat as those terms are defined in Chapter 2 - Definitions of this Land Development Code, of any property (1) zoned other than CPO, CN, CC1, CC2, CC3, or ML and shown on an approved plat thereof, or (2) property that is zoned AG, RE, R40, R30, R20, R15, RD, RMF. The actual location of a fence or wall on a site is assumed to be to on the property or common property line and encroachments onto adjacent property are not expressly authorized by the Administrative Official or their representatives.~~

C. Maintenance

1. All fences erected as provided for in this section shall be maintained in good condition.
2. A fence shall not lean more than one inch out of vertical for each foot of height as measured from the top of the fence.
3. The owner shall replace broken, damaged, removed or missing parts of a fence within ten (10) days of the day the owner received notice from the Administrative Official; with the same material, or material with comparable composition, color, size, shape and quality of the original fence to which the repair is being made. No permit is required for repairs as defined in this ordinance. The Administrative Official may, upon written notice from the owner that unusual circumstances prevent the timely repair of a fence, extend the replacement time as required. The Administrative Official shall not extend the replacement time longer than reasonably necessary. The owner requesting a replacement time

Commented [EW66]: A sub-section for "Definitions" that contains only one definition is not necessary and should be located in Section 2 of LDC. Retitled this section as "Fence or Wall Placement".

Commented [BB67]: Move to Ch. 2 - Definitions

Commented [EW68]: Added disclaimer for when property owners dispute the fence is crossing property lines.

extension shall provide the Administrative Official a written scope and schedule detailing materials and estimated time period of the completed replacement for approval.

4. A fence shall be maintained in sound structural condition as a whole or completely removed, including post(s).
5. Property owners shall maintain fences, including those existing prior to the adoption of this Ordinance, at all times in a state of good repair, safe and secure condition, with all braces, bolts, nails, supporting frame and fastenings free from deterioration, termite infestation, rot, rust or loosening, and able to withstand at all times the wind pressure for which they were designed.
6. Property owners shall regularly paint fence supports, gates, structural members and exterior surfaces that are covered with paint to prevent rusting, peeling or blistering surfaces.
7. Existing fences that were constructed prior to the adoption of this Ordinance that were constructed with materials not currently permitted by this Ordinance may be maintained as long as no part of the fence is or becomes unsafe, dilapidated, or a public nuisance. If the Administrative Official determines the fence is unsafe, dilapidated, or a public nuisance the fence must be repaired with materials approved by this Ordinance or be removed.
8. The construction of a fence or wall on the property line shall not preclude the property owner's responsibility to maintain and keep the area between the fence and an adjacent fence on a neighboring property, the property line to the back of curb or edge of the pavement or center of alley, free and clear of debris and high weeds.

D. General Requirements/Prohibitions for all Fences and Free-standing Walls

1. *Screening Required in Residential Districts:*

- a. Nonresidential uses in a residential district shall be suitably screened from view of any adjacent residential lot or dwelling use along the side and rear property lines of such nonresidential use with a decorative masonry wall of not less than eight (8) feet in height. ~~Said screening requirements shall not be mandatory for public schools, parks or churches, except where active outdoor intensive use area (such as a playground) is adjacent to a residential lot or dwelling.~~ Off-street loading areas of any non-residential use shall be adequately screened from view of any residential dwelling or lot or of any other adjacent public or semi-public land use with a decorative masonry wall of not less than (8) feet in height or a landscaped berm.
- b. Where a multifamily or mobile home use abuts a one or two family district, or where a mobile home use abuts a one, two or multifamily use or district, the side and rear property lines of said multifamily or mobile home use or district shall be suitably screened from view of any adjacent dissimilar residential dwelling or lot with a decorative masonry wall of not less than eight (8) feet in height or a landscaped berm.
- c. Nothing in this section shall restrict the fencing of tennis courts with traditional fencing material to a maximum of twelve (12) feet.

2. *Screening Required in Non-Residential Districts:*

- a. Where a nonresidential use abuts a residential lot, use or district, the side and rear property lines abutting said residential lot, use or district shall be suitably screened, with a decorative masonry wall, by the nonresidential use so as to obscure the view from the residential lot, use or district to the nonresidential use to a height not less than eight (8) feet.
- b. Where a district boundary separating a residential district from a nonresidential district is along a street, and an automobile parking lot or parking area is located in the front yard of the nonresidential use, then said parking lot or parking area facing the residential lot, use or district shall be suitably screened to a height of not less than three and one-half (3-1/2) feet.

Commented [BB69]: Churches and schools should be expected to provide screening when adjacent to residential uses

- c. In all districts where open storage is permitted and the screening thereof is required, then such screening shall be provided around the exposed perimeter thereof of not less than six (6) feet in height and shall be composed of decorative masonry material
 - d. Off-street loading areas shall be adequately screened from view of any residential dwelling lot or of any other adjacent residential land use with a decorative masonry wall of not less than eight feet in height or a landscaped berm.
 - e. All roof mounted mechanical equipment and parapet wall structural supports shall be screened from view.
 - f. All required screening between residential and commercial, institutional, multifamily and mobile home uses shall be maintained in good condition by the property owner of the commercial, institutional, multifamily and mobile home use.
3. *Screening Requirements for Waste, Garbage, Compacting and Recycling Containers:* The following regulations shall apply to all multifamily, mixed-use, institutional and commercial uses where large containers are utilized for the storage or compacting of waste, garbage or recycling materials for any properties where the building permit for the primary structure was issued on or after April 17, 2013:
- a. All containers shall be fully enclosed by a decorative masonry wall.
 - b. Masonry materials shall match the masonry materials of the exterior wall of the primary structure on the property where the container is located.
 - c. The height of the screening wall shall be a minimum of six feet, or one foot above the height of the container/compactor, whichever is greater, and shall not exceed 10 feet in height.
 - d. The gate shall be composed of solid metal and shall be of a color that matches or complements the masonry wall.
 - e. The gate shall remain closed at all times. Exception: gates for recycling bins that are accessible to the public may remain open provided all recycling material is completely stored within the container.
 - f. Where possible, gates shall be oriented away from the view of any roadway traffic.
 - g. All enclosures and containers shall be located behind all required building setbacks.
 - ~~h. and All enclosures and containers shall be located a minimum of 25 feet from any properties zoned or used for non-multifamily residential purposes.~~
 - hi. Unless subject to a different requirement as part of an SUP or PUD ordinance, for properties where the building permit for the primary structure was issued before April 17, 2013, the required enclosure and gate may be composed of wood or masonry materials to a minimum height of six feet and the gate must remain closed at all times. Otherwise, said properties shall be exempt from the other provisions of this section. However, loss of any legal-nonconforming status for any property and/or building as described in Section 3.7 in the Land Development Code shall require full compliance with this section.
 - ij. The City shall have the right to remove any container in an enclosure that has been non-compliant with this sub-section for more than 30 days.
4. *Obstruction Prohibited:* No fence, screen, free standing wall or other visual barrier shall be so located or placed that it obstructs the vision of a motor vehicle driver approaching any street, alley or drive intersection. A visual barrier shall be deemed to be any fence, wall, hedge, shrubbery, etc., higher than thirty (30) inches above ground level at the property line, except single trees having single trunks, which are pruned to a height of seven (7) feet above ground level. See Exhibit "3-1".

Commented [BB70]: Separated into 2 regulations




Exhibit "3-1"
Obstructions Prohibited

5. *Twenty-Five (25) Foot Visibility Triangle Required:* No fence, screen, wall or visual barrier shall be located or placed where it obstructs the vision of motor vehicle drivers approaching any street intersection. At all street intersections, clear vision shall be maintained across the lot for a distance of twenty-five (25) feet back from the property corner along both streets. See Exhibit "3-2".




Exhibit "3-2"
Visibility Triangle

6. *Barbed Wire Prohibited:* Fences constructed of barbed wire and walls topped with broken glass or surfaced with any like material shall be prohibited except as provided below.

Barbed wire fences used in conjunction with permitted agricultural, livestock, and related activities, or in industrial districts are permitted without restrictions.

Barbed wire strands may be placed on the top of security fences in non-residential districts for the purpose of security from theft, entry and hazard such as around public utility substations and uses of a similar nature, provided the top strand is not higher than eight (8) feet nor the bottom strand lower than six (6) feet from the adjacent grade line.

7. *Electrical Fences:* Electrical fences and fence charging devices (Underwriters Laboratory approved) shall be plainly marked at a minimum of twenty-five (25) foot intervals as to the nature thereof.
8. *Eight (8) Foot Maximum Height:* No fence in a residential district shall exceed eight (8) feet in height above ground level at the fence line.
9. *Property Owners' Responsibility:* The construction of a fence or wall on the property line shall not preclude the property owner's responsibility to maintain and keep the area defined between the extension of the property lines to the back of curb or edge of pavement free and clear of debris and high weeds. See Exhibit "3-3".




Exhibit "3-3"
Property Owner's Responsibility

10. *Public Property:* No fence, guy wire, brace or any post of such fence shall be constructed upon or cause to protrude over property that the City or the general public has dominion and control over, owns or has an easement over, under, around or through, except upon drainage and utility easements which are permitted to be fenced.
11. *Floodway Permit Required:* The construction of a fence or wall in a floodway as shown on the most recent revision of the "Floodway - Flood Boundary and Floodway Map" prepared by the Federal Emergency Management Agency (FEMA) shall require a development permit as currently required in the City's drainage policies.
12. *Swimming Pools:* All swimming pools shall be fenced. A solid or chain link type fence or a barrier at least four (4) feet in height shall completely enclose every swimming pool to be constructed. There shall be no openings, holes, or gaps bigger than four (4) inch spaces and no openings whatsoever on horizontal picket type fences. All gates allowing access to the pool area shall be self-closing with self-latching devices located in the upper quarter of the gate. All entrances to the swimming pool area must be able to be secured by a combination or key locking device. A dwelling house, accessory building, or apartment building may be used as part of such enclosure provided that all entrances to the swimming pool are equipped with gates as described herein. All fences should conform to local governmental codes and restrictions.
13. *Pre-Formed Concrete:* Pre-formed concrete is a permitted masonry material provided the texture adequately mimics the intended style match, be it wood, brick, stone, etc. Pre-formed concrete fences shall be maintained in good condition including any painted fences. The building official shall approve the final finished surface and reserves the right to deny a fence permit application if the surface does not adhere to these regulations.
14. **General Construction Requirements for Wood Fences**
 - a. For commercial properties, all vertical posts on fences over four (4) feet in height shall be galvanized steel with a minimum two (2) and three-eighths (3/8") inch diameter, a minimum fifteen (15) gauge thickness, and set in a concrete footing. Picket fences, split rail fences, ranch style or agricultural fences, or other types of decorative fences approved by the Building Official or his/her designee shall be permitted to use wood posts.
 - b. Concrete footings shall be a minimum of eight (8) inches in diameter.
 - c. For fences less than seven (7) feet in height, posts shall be spaced at a maximum of eight (8) feet on center, set in a concrete footing of no less than twenty-four (24") inches deep.
 - d. For fences that are seven (7) feet or greater in height, posts shall be spaced at a maximum of six (6) feet on center, set in a concrete footing of no less than thirty-six (36") inches deep.
 - e. Fence posts attached to or supported by other structures, including retaining walls, shall be provided with foundation and anchorage to prevent movement of structure or retaining wall.

- f. All materials shall be securely fastened, vertical boards to horizontal stringers, stringers to vertical posts, top rail, to ensure an ongoing attractive appearance and safe condition, free from rot, rust, vandalism and other sources of decay.
- g. The bottom of the fence shall be designed to prevent ground to wood contact. This can be achieved through the use of a concrete strip poured between the fence supports or by raising the pickets to provide a minimum of two inches between the bottom of the pickets and the ground. Fences located within drainage easements must be approved by the Public Works Director per the requirements of Section 8-170 of the Land Development Code and shall be built such that required drainage and storm water run-off is not impeded.
- h. All wood material shall be stained, pressure treated, painted, or adequately sealed to prevent decay.

Commented [EW71]: "storm water" is two separate words

15. Perimeter Subdivision Fences: A fence along the perimeter of a subdivision is allowed under the following conditions:

- a. No setback shall be required from any street right-of-way line.
- b. No perimeter subdivision fence shall encroach into the required twenty-five (25) foot visibility triangle as defined above.
- c. The perimeter subdivision fence shall have a maximum height of eight (8) feet, to include any element associated with the fence.
- d. Materials along Street Frontage: The perimeter subdivision fence shall be decorative in nature and constructed of stone, brick, wrought-iron, or a combination of these materials for any portion along a perimeter street. The use of wood and composite materials shall be prohibited along the street frontage.

Commented [BB72]: Codified standards for perimeter subdivision fences

Commented [BB73R72]: After review, staff recommends approval of these standards. Revision was made to material standards along street frontages.

16. Sealed Plans Required for Masonry Walls, Columns and Fences: For all masonry walls, columns and fences authorized by this Section, required plans and specifications shall be prepared and sealed by a State of Texas registered engineer and shall consider the site's soil characteristics, wind loadings, and other environmental considerations. All field inspections and verifications for a new masonry wall, fence, and column must be approved by the design professional mentioned above or the professional's representative. Said inspection approval must be submitted to the Building Official in writing prior to the City's final inspection.

E. Fence and Free Standing Wall Setback Requirements

- 1. **Front Yards:** No fence or free standing wall greater than thirty (30) inches in height and no greater than twenty-five (25) percent ~~solid~~ opaque construction shall extend into the required yard on which the primary structure faces.
 - a. The primary fencing material shall be of wrought iron, pre-formed concrete, poured in place concrete, concrete masonry unit (CMU), brick, approved wood rail construction, a combination thereof or other similar material approved by the City Building Official. All poured in place concrete and CMU shall contain an architectural finish.
 - b. On a corner lot, a house shall be deemed to face on that street on which it has its least dimension unless otherwise determined by the Building Official.
 - c. Vehicle Gate setback: Any vehicle gate shall be set back a sufficient distance from the property line to allow vehicle queuing space in order to maintain safety and to prevent backup along the street pavement. Sufficient distance shall be determined by the Building Official.
 - d. Exceptions to front yard requirement: Lots containing a minimum of 40,000 square feet, and subdivisions, shall be allowed to construct a perimeter fence within the front yard setback. Said

Commented [EW74]: Provides consistency for term used throughout Subsection E

Commented [EW75]: Specifies that the section applies to vehicle gates – not pedestrian gates

fencing shall be no greater than eight (8) feet in height and shall have no greater than twenty-five (25) percent solid opaque construction within the front yard. Allowed construction materials shall be the same as paragraph "1.a" above. **This exception shall not apply to properties zoned as a PUD district.**

Commented [EW76]: Provides consistency for term used throughout Subsection E

2. Corner Side Yards: Except where allowed elsewhere in this chapter, fences and walls within a required side yard adjacent to a street right-of-way shall meet the following setback standards:

A privacy fence or wall (which shall be defined as any fence or wall greater than thirty inches (30") in height ~~or that is~~ greater than 25 percent opaque construction) within a required street side yard shall be subject to whichever of the following provisions a) through d) shall yield the greatest setback:


Commented [BB77]: This would allow for a fence that is not opaque (i.e. wrought iron) to be located along the property/ROW line and within the setback.

- a. If the subject lot has a street side yard which faces a dwelling front or lot front across the side street, the side yard privacy fence or wall shall be located not less than fifteen feet (15') from the property line, except on any lot having either a required side yard less than fifteen (15') feet or an existing primary structure setback less than fifteen (15') feet, then the fence or wall may be constructed with the same setback as the primary structure; or
- b. If the subject lot backs to the rear of another residential lot, the side yard privacy fence or wall shall be located not less than fifteen feet (15') from the side property line; or
- c. If the subject lot backs to the side of another residential lot, the side yard privacy fence or wall shall be located not closer to the side property line than the required front setback of the adjoining lot; or
- d. If the subject lot backs to an alley, the side yard privacy fence or wall shall be located not closer than fifteen feet (15') from the side property line.

A decorative wall or fence (which is defined as any wall or fence not greater than thirty inches in height and not greater than twenty-five percent opaque construction) within a required street side yard shall not be placed less than three feet (3') from the side property line, and shall not be subject to the provisions of the preceding sections (a) through (d).

3. *Adjacent to Undeveloped Property:* Except for perimeter subdivision fencing meeting the requirements in paragraph "1.a" above, no fence or wall greater than thirty (30) inches in height and no greater than twenty-five (25) percent solid ~~masonry~~ opaque construction, shall be located less than fifteen (15) feet from the side property line adjacent to the street which leads into undeveloped property. See Exhibit "3-4".

Commented [EW78]: Provides consistency with term used throughout Subsection E



(1) Set-back established
by district regulations

Exhibit "3-4"
Typical 15'-0" Fence Setbacks

4. *Rear Fence and Free Standing Wall Setbacks:* Fences and walls meeting all of the construction

requirements of paragraph "1.a" above and ~~the Uniform Building Code~~ other adopted standards may be erected on the rear property line except; however, lots whose rear property line abuts a public street on which one of the immediate adjacent lots maintains its required front yard, then no fence nor wall greater than thirty (30) inches in height shall be located within fifteen (15) feet of the subject lots rear property line. See Exhibit "3-4".

Commented [EW79]: Uniform codes are obsolete

5. Twenty-five Percent Opaque Construction: The intent of this provision in Subsection E is to discourage barriers that resemble a compound or fortress and the calculation shall be as follows: Every eight (8) linear feet of fencing shall be at least 75% open to view from the street or public way. The 25% opaque construction shall be calculated based on the area of each eight (8) foot linear segment of the barrier.


Commented [EW80]: This added provision attempts to specify how the calculation is applied to eliminate completely solid walls for longer runs and then installing wrought-iron on the ends

F. Security Gating Encroachments

~~A front yard fence or screening wall providing support for a security gate and not exceeding a maximum height of 6 feet, may encroach a maximum of 10 feet into the front yard setback of a residential lot when the fence or screening wall meets the following criteria and shown in Exhibit "A":~~

- ~~1. The fence or screening wall shall attach to a gated entry across the driveway;~~
- ~~2. The fence or screening wall shall attach to the dwelling unit not more than 10 feet from the driveway and extend toward the driveway;~~
- ~~3. The fence or screening wall shall extend to the nearest side property line;~~
- ~~4. The fence or screening wall shall not extend beyond 10 feet into the setback from the dwelling unit;~~
- ~~5. The fence or screening wall shall not enclose nor extend across the entire front yard;~~
- ~~6. The gate and columns may not extend beyond one foot in height above the fence;~~
- ~~7. A minimum setback distance of 20 feet from the fence, screening wall and gate to the front property line shall be maintained.~~

Exhibit "A"



G. Administration

1. Fence Permit Required - It shall be unlawful for any individual, partnership, company or corporation to erect or have erected a fence or any part of a fence of permanent construction in the city limits without first obtaining a fence permit from the Community Development Department.
2. Application for Permit - Any individual, partnership, company or corporation making application for a fence permit must sign an application for same showing the following information:
 - a. Applicants name, address, and in addition, if the applicant represents a company or corporation, the name and address of the supervisor or foreman of said company or corporation and the name of its president.
 - b. Name and owner of the property.

- c. Local address where fence is proposed to be erected.
- d. Materials and type of fence construction.
- e. Height of fence.
- f. Applicant shall provide engineering plans and specifications for those types of fences where such engineering is deemed appropriate by the Building Official. The engineering plans shall be reviewed and approved by the Building Official prior to issuance of a fence permit.
- g. Survey showing lot on which the fence is proposed to be erected and the location of adjoining or adjacent lots showing existing structures and fences. The proposed fence shall be delineated by a dark heavy line. In AG zoning districts a scaled plot plan can be submitted in lieu of a survey.

H. Variances

1. Any variance to the provisions of this section shall be heard by the Zoning Board of Adjustment.

Commented [BB81]: Redundant language

Section 3.27 Accessory Buildings and Residential Carport Regulations

The following regulations shall govern the location, size and use of accessory buildings:

A. Accessory Buildings Located in Residential Zoning Districts (O-00-1223 / 07/18/00)

1. Permit Required:

- a. A building permit shall be required for any accessory building which exceeds one hundred and twenty (120) square feet. However, all accessory buildings containing 120 square feet or less shall comply with the height and setback requirements of this Section. An accessory building shall only be allowed as an incidental structure to a principle building unless the accessory building is located in the Agricultural District.
- b. For the purpose of this Section, the term accessory building shall include detached residential garages, and pool houses, but shall exclude a carport (see Section 3.27.C), accessory dwellings, gazebos, cabanas, trellises, arbors, outdoor fireplaces/chimneys, or other shade structures. Exception: structures for specific use as playground assemblies and/or playhouses shall be exempt provided that minimum five (5) feet setbacks from property lines are maintained.

Commented [EW82]: Recommended expansion of language and provisions for children's structures

2. Maximum Size and Number of Buildings:

- a. The maximum number of accessory buildings allowed per lot shall be three (3) buildings. In addition, the combined square footage of all accessory buildings shall not exceed the maximum square footage specified in the following table. four percent (54%) of the aggregate area of the lot. Exemption: Lots containing a minimum of 80,000 square feet shall be exempt from the requirement for the maximum number of accessory buildings.

Commented [BB83]: Four percent (4%) is more in-line with current size allowances

Commented [EW84]: Allows for building sizes based on land area, not category

Commented [BB85]: Exemption added for large properties per Council direction

Maximum Square Footage of all Accessory Buildings				
Lot Size	Under .5 ac	.5 – .99 ac.	1 – 2.99 ac.	3+ ac.
Total s. f.	750 s. f.	1,000 s. f.	1,750 s. f.	2,500 s. f.

- b. Accessory dwellings allowed by the Land Development Code shall be limited in size to be no more than the most restrictive of the following:
 1. Fifty percent (50%) of the primary structure;

2. The maximum allowed square footage for accessory buildings on the lot; or
3. No more than twelve hundred (1,200) square feet

c. For the purpose of this Section, the size of an accessory building shall be the square footage of the building footprint each floor, mezzanine, covered porch, or shade structure.

ed. An application to exceed the total square footage shown in the above table authorized above may be approved as a Special Use Permit (SUP).

de. An existing accessory building may be remodeled or expanded provided the combined square footage of all accessory buildings does not exceed the maximum square footage allowed. However, an a legally-existing accessory building which exceeds the maximum square footage allowed may be remodeled or replaced with a new accessory building, but not expanded or increased in height.

ef. There shall be no physical connection between accessory buildings and a minimum separation of three (3) feet between accessory buildings.

3. **Setbacks:**

- a. No accessory building shall be erected in any required yard, as defined in *Chapter 2 – Definitions*, except as set forth herein.
- b. Attached accessory buildings – Accessory buildings erected ten (10) feet or closer to the principal building shall be considered attached, and shall comply with the setback lines established for the applicable zoning district. For the purpose of this regulation, the distance between buildings shall be measured between the nearest wall surfaces.
- c. Detached accessory buildings – A detached accessory building shall comply with the setback lines established for the applicable zoning district, unless the accessory building is located totally behind the rear of the principal building, then it shall not be placed closer than five (5) feet to any side or rear lot line.

4. **Maximum Height:** No accessory building shall penetrate a vertical height envelope defined as being a point five feet from a side or rear lot line and extending vertically 8 feet to a point, then extending at a 45° angle to the height of the primary building. (Potential option: No accessory building shall exceed one story or fourteen (14) feet in height unless zoned Agricultural.)

5. **Permitted Uses:** The use of an accessory building shall be consistent with the permitted uses of the applicable zoning district, except, no accessory building shall be used for dwelling purposes other than for domestic family or servants quartersan accessory dwelling employed for the premises, where permitted by the district regulations.

6. **Special Use Permit Provision:** Any request for a building permit for an accessory building which does not meet the criteria in this Section shall only be authorized after approval of a Special Use Permit by the City Council using the procedures contained elsewhere in this Land Development Code.

B. **For Accessory Buildings Located in Non-residential Zoning Districts**

1. No accessory building shall be erected in any required yard area except as set forth by this section.
2. No accessory building shall be erected within ten (10) feet of any other building unless such accessory building is used as a commercial kiosk, in which case such commercial kiosk cannot be located within fifty (50) feet of another building.
3. Commercial kiosks as accessory uses and/or buildings may be located within approved nonresidential districts subject to the following conditions:
 - a. Maximum size of two hundred-fifty (250) square feet.

Commented [BB86]: Size limitations for accessory dwellings

Commented [EW87]: Large accessory structures and extensions from accessory buildings should be accounted for.

Commented [EW88]: Non-compliance should be addressed in new Section 7 below - Variances

Commented [BB89R88]: Need to keep per City Council direction

Commented [EW90]: Provision that does not “grandfather” buildings that were constructed without permits or otherwise authorized

Commented [EW91]: Simplifies the requirement by eliminating an illogical calculation

Commented [EW92]: Matches definitions

- b. No inside sales or service or drive in sales or service; walk-up and/or drive-up service permitted.
- c. Exterior walls shall be of at least seventy-five percent (75%) masonry, glass, or other equivalent material, provided metal material does not exceed twenty-five percent (25%) of the exterior walls.
- d. Located within required setbacks and in conformance with this section.
- e. Located in such a manner as to not impede, impair or endanger vehicular traffic on the property where the kiosk is located and for vehicular traffic ingressing from and egressing to public rights-of-way.
- f. Submission of an acceptable site plan shall be required for consideration of the issuance of a building permit unless a current valid Certificate of Occupancy exists.
- g. Limited to one (1) kiosk per platted plot.

4. Accessory buildings on sites involving residential adjacency shall require approval of a Special Use Permit by City Council unless previously identified on an approval Site Plan.

C. Residential Carport Regulations – Carports located in zoning districts which permit single family residential dwellings shall comply with the regulations contained in this section.

1. *Approval by Special Use Permit Only:* In accordance with the Special Use Permit procedures contained in this Chapter of these zoning regulations, no carport shall be built in the City of Colleyville without approval by the City Council for a Special Use Permit to construct a carport in a zoning district that permits single family residential dwellings.
2. *Carport Standards:* A carport shall comply with the following regulations, unless the City Council in approving a Special Use Permit for a carport has imposed other requirements necessary in the particular case to protect the public interests.
 - a. *Size:* A carport shall not exceed 480 square feet in area. The longest dimension on a carport shall not exceed 24 feet.
 - b. *Height:* A carport shall not exceed a maximum height of 15 feet. The height shall be measured from the finished grade to the highest point of the roof.
 - c. *Setbacks:*
 - i. A carport located within ten (10) feet of the principal building shall comply with the front, side and rear yard setbacks of the zoning district. The distance shall be measured between the two closest points of the carport and principal building.
 - ii. A carport located 10 feet or more from a principal building may extend into a required side yard, provided all of the following conditions are satisfied:
 - (1) every part of such carport is unenclosed except for necessary structural supports;
 - (2) no part of the carport is less than five (5) feet from a side or rear lot line, and
 - (3) the carport is located completely within the rear yard area as defined in these zoning regulations.
 - d. *Maximum Number Per Lot:* one
 - e. *Paving and Street Access:*

The parking area of a carport shall be paved not less than nine feet (9') by eighteen feet (18') and provide access to a public street right-of-way. Said access shall be a minimum of nine feet (9') in width and paved. All paved surfaces shall be either concrete, asphalt or pave-stone.
 - f. *Design Criteria:*

Commented [EW93]: Recommended for protections of residentially zoned properties

Commented [BB94R93]: Needed?

- i. Roof - Carports shall have a pitched roof of at least 2:12. Flat roofs shall be prohibited.
 - ii. Posts - Posts shall be constructed of brick, stone, cedar or decorative metal, such as metal lattice. For purpose of this requirement, decorative metal shall consist of twenty-five (25) percent opaque surfaces. The dimension of each post as viewed from each primary elevation shall not be less than twelve inches (12") or more than forty-eight inches (48"). Any carport with two or more elevations that exceed the 48-inch criteria shall be considered an accessory building and be regulated as such. Wooden posts shall be ~~prohibited~~ wrapped using masonry stone or brick from the base to at least 50% of the post height.
- g. *Adequacy of Plans and Specifications:*

The applicant requesting a Special Use Permit to construct a carport shall submit plans and specifications of the proposed carport for review. Said plans and specifications shall contain sufficient information to allow the City Council to determine that the proposed carport complies with these regulations and the City Council may require additional information when necessary to clarify the applicant's request. At a minimum, the drawings shall contain a plot plan, elevation views and a description of the construction materials.

Commented [EW95]: Recommend allowing cedar as an approved material

Section 3.28 Supplementary District Regulations

- A. Reserved (O-00-1241 / 10/03/00)
- B. Erection of More Than One Principal Building on a Lot – In any district other than Agricultural zoning, ~~no~~ more than one (1) building housing a permitted or permissible principal use may be erected on a single lot.
- C. Buildings Constructed Across Lot Lines – No building may be constructed across existing platted lot lines unless a replat is filed and approved in accordance with applicable regulations of the city.
- D. Exceptions to Height Regulations
1. Schools, public buildings, and institutions may be erected to a height ~~not exceeding (85) feet~~ the maximum height in any district in which they are permitted, provided front and rear yards are increased in depth and side yards increased in width one (1) foot for each foot of height that the building exceeds the height regulations of the district in which it is located.
 2. The height regulations prescribed elsewhere in this Chapter shall not apply (except as may be applicable to paragraph d. hereof) to grain elevators, television and radio towers, church spires, belfries, cupolas, antennas, water tanks, ventilators, chimneys, ornamental towers, monuments, conveyors, fuel storage tanks, asphalt and concrete batch plant equipment not intended for human occupancy.
 3. Limitations on number of stories shall not apply to buildings used exclusively for manufacturing or storage purposes provided such buildings do not exceed the height in feet permitted in the district in which they are located.
 4. The permitted height of any occupied building shall be further restricted to the capability of the local fire fighting equipment to adequately handle any such building height.
 5. In CC and ML zoning districts, the City Council may vary the maximum height of a building if the City Council finds that the location and/or configuration of the building is such that it will conform to the surrounding area and provide adequate light and air under the circumstances. For each foot of proposed height over the standard, there shall be a foot increase in the front and rear yards or as approved by the council. The request for a variance shall be accompanied by a site plan of the property and an architectural drawing of the proposed building.

Commented [EW96]: Ag zoning district allows for a secondary dwelling

Commented [BB97]: The size of the property will dictate the maximum height of the structure

E. Projections of Buildings, Structures and Appurtenances into Required Yards

1. Open or lattice enclosed fire escapes may project into a required yard not to exceed fifteen (15) feet. The ordinary projections of chimneys and pilasters shall be permitted by the City's Building Official when placed so as not to obstruct light and ventilation.
2. Terraces, balconies, decks, ~~uncovered porches~~ and ornamental features above the floor level of the ground (first) story may project into a required side yard, provided these projections be at least five (5) feet from any adjacent side lot line.
3. ~~An uncovered porch in the front yard may not be more than eighty (80) square feet or project into the front yard setback for distance of more than eight (8) feet.~~ Fountains and other decorative features may project into the required front yard but shall not include structures used for occupancy such as guard sheds, shade structures, etc.
4. A porte-cochere or canopy may project into a required side yard, provided every part of such porte-cochere or canopy is unenclosed except for necessary structural supports, and not less than five (5) feet from any side lot line.
5. Every part of a required yard shall be open to the sky, unobstructed by a building, except for the ordinary projections of sills, belt courses, cornices, and ornamental features not exceeding twelve (12) inches, or as otherwise excepted in paragraph a. through d. above. Roof eaves may project into required side yards provided the projections be at least five (5) feet from any adjacent side lot line.
6. Gasoline filling station pumps and pump islands may be located or project into a required yard provided they are not less than twenty-five (25) feet distant from any street, highway or alley right-of-way line, and not less than fifty (50) feet distant from any residential property line.

Commented [EW98]: Uncovered flatwork has no effect on the requirement provided lot drainage is not impacted

Commented [EW99]: Uncovered flatwork, regardless of size, has no effect on aesthetics at the front of a property

Commented [EW100]: Provides for decorative features in a front yard

F. Minimum Width of Enclosed or Partially Enclosed Open Space – Where an open space is more than fifty (50) percent surrounded by a building, the minimum width of the open space shall be at least twenty (20) feet for one-story and one and a half-story buildings, thirty (30) feet for two-story buildings, and forty (40) feet for three or more story buildings.

G. Buildings and Structures to Have Access – Every building or structure hereafter erected or moved shall be on a lot adjacent to a public street, or with access to an approved private street, and all structures shall be so located on lots as to provide safe and convenient access for servicing, fire protection, and required off-street parking.

H. Parking; Storage or Use of Major Recreational Equipment and Vehicles – No major recreational equipment shall be parked or stored on any lot in a residential district except in a carport or enclosed building, or in a required side or rear yard on an all-weather hard surface driveway; provided, however, that such equipment may be parked anywhere on residential premises not to exceed twenty-four (24) hours during loading or unloading. No such equipment shall be used for living, sleeping, or housekeeping purposes when parked or stored on a residential lot, except for the temporary housing of guests not to exceed two (2) consecutive weeks.

Commented [EW101]: Prohibits parking RV's on the grass

For purposes of these regulations, major recreational equipment is defined as including boats and boat trailers, travel trailers, pick-up campers or coaches (designed to be mounted on automotive vehicles), motorized dwellings, tent trailers, and the like, and cases or boxes used for transporting recreational equipment, whether occupied by such equipment or not.

I. Parking and Storage of Vehicles in General

1. One commercial vehicle of not more than one ton capacity, except pick-up trucks, when used in the employ by the site occupant of a dwelling may be permitted on a residentially zoned lot, provided said parking space shall be in an enclosed garage, carport, or on an all-weather hard surface driveway, or in a side or rear yard on an all-weather surfaced driveway. Nothing in this Chapter shall prohibit the occasional overnight storage or parking of a commercial vehicle on residential property.

2. Off-street vehicle parking spaces shall not be located within ten (10) feet of existing proposed major thoroughfare street right-of-way lines in any commercial or industrial district. Such off-street parking spaces shall consist of a paved surface, i.e., concrete, HMAC, brick or paving stone approved by the city building official. All ten (10) foot buffer areas shall be landscaped and maintained to enhance esthetic qualities.
3. To avoid the unsightly appearance of junked and abandoned vehicles in residential districts, no vehicles may be parked or stored on a residential premise where visible to any adjacent residential use, unless a current state vehicle inspection sticker is displayed thereon.

J. Front Yard Adjustments – Front yard requirements as established in *Section 3.24 - Schedule of District Regulations* may be adjusted in the following cases:

1. Where forty (40) percent or more of the frontage on the same side of a street between two intersecting streets is presently developed or may hereafter be developed with buildings that have (with a variation of ten (10) feet or less), a front yard greater or lesser in depth than herein required, new buildings shall not be erected closer to the street than the average front yard so established by the existing buildings.
2. Where forty (40) percent or more of the frontage on one side of a street between two intersecting streets is presently developed or may hereafter be developed with buildings that do not have a front yard as described above, then:
 - a. —Where a building is to be erected on a parcel of land that is within one hundred (100) feet of existing buildings on both sides, the minimum front yard shall be a line drawn between the two closest front corners of the adjacent building on each side, or
 - b. —Where a building is to be erected on a parcel of land that is within one hundred (100) feet of an existing building on one side only, such building may be erected as close to the street as the existing adjacent buildings.
3. Interior lots abutting on two streets shall provide the required front yard on both streets.
4. On corner lots, a front yard shall be provided on each street frontage except for lots of record as described in this Chapter.
5. Front yard requirements in all districts adjacent to an existing or proposed major thoroughfare or secondary thoroughfare street, as designated in the City's latest Comprehensive Plan, shall be measured from such existing or proposed major thoroughfare or secondary thoroughfare street right-of-way line.

K. Side Yard Adjustments – Side yard requirements as established in *Section 3.24 - Schedule of District Regulations* may be adjusted in the following cases:

1. Commercial buildings used in part for dwelling purposes, where permitted, shall provide side yards not less than five (5) feet in width unless every dwelling unit therein opens directly upon a front yard, rear yard or court yard.
2. Whenever a lot of record at the time of the effective date of this Chapter has a width of less than fifty (50) feet, the side yard on each side of a building may be reduced to a width not less than ten (10) percent of the width of the lot, but in no instance shall such width be less than four (4) feet.
3. On corner lots of record the yard adjacent to the side street shall not be less than fifteen (15) feet.
4. For commercial or industrial lots abutting a lot zoned CC1, CC2, CC3, CN, CPO or ML, subject to the approval of the city building official, a zero lot line is permitted on one side, provided a four hour fire wall is constructed at said zero lot line.

L. Rear Yard Adjustments – Rear yard requirements as established in *Section 3.24 - Schedule of District Regulations* may be adjusted in the following case:

1. Where a lot abuts an alley, one-half the alley width may be considered as part of the required rear yard.
- M. Lot Area Per Family Adjustments – Lot area per family (dwelling unit) requirements as established in *Section 3.24. - Schedule of District Regulations* shall be adjusted in the following cases:
 1. Where a lot of record or a lot in a subdivision which the Planning and Zoning Commission and City Council have officially approved and agreed to accept at the time of the effective date of this Chapter has less area or width than herein required, in the district in which it is located, said lot may nonetheless be used for a residential or nonresidential use, whichever is applicable, in the district in which it is located.

Section 3.29 – Parking Requirements

- A. Purpose – The purpose of this section is to require off-street parking and loading facilities proportional to the need created by each use. Where the minimum number of required parking spaces can not be calculated in accordance with the parking group schedule, the Building Official shall be authorized to determine the minimum number of required parking spaces using acceptable industry comparables.
- B. General Provision – In all zoning districts, there shall be provided in connection with the appropriate permitted use, off-street parking spaces in accordance with the provision of this section, unless a different parking standard has been set forth as a condition of a Special Use Permit or Planned Unit Development for a specific site. Existing facilities being used for off-street parking shall not be reduced in capacity to less than the minimum number of spaces prescribed, or altered in design or function to less than the minimum standards prescribed herein.
- C. Location of Parking – All required parking spaces shall be provided on the same lot or tract occupied by the use being served, except that where an increase in the number of spaces is required by a change or enlargement of a non-residential use, the additional required parking spaces may be located off-premises in accordance with the shared parking requirements contained in this section, unless a different parking standard has been set forth as a condition of a Special Use Permit or Planned Unit Development for a specific site. Required parking spaces for a residential use shall be provided on the lot or tract occupied by the use being served.
- D. Parking Space Locations Prohibited – No off-street parking space shall be located, either in whole or in part, within any fire lane, driveway, driving lane, or maneuvering area. Furthermore, no required off-street parking space shall be located, either in whole or in part, in a public street, sidewalk, parkway, alley or other public right of way.
- E. Parking Space Dimensions – No required off-street parking space shall be less than nine (9) feet in width by eighteen (18) feet in length.
- F. Mixed Use Parking – The parking requirements for a lot or building containing a mixture of uses shall be the sum of the requirements for each type of use. No parking space provided for one type of use or building shall be included in the calculation of the parking requirements for any other use or building. For multi-tenant developments containing greater than 30,000 square feet of floor area, the sum of the total number of required parking spaces may be reduced by ten percent (10%).
- G. Shared Parking – Where an increase in the number of off-street parking spaces is required by a change or enlargement of use, the additional required spaces may be located on another property that is located on or adjacent to the site as defined by contiguous lot lines of a use not normally open and used or operated during the same hours, provided, that the following conditions are satisfied:
 1. The parking spaces are located within three-hundred feet from an entrance to the building or use being served, measured along the shortest available pedestrian route with public access.
 2. A copy of the written agreement, executed by the parties concerned, is furnished to the Building Official, assuring their retention for such purposes.

Commented [EW102]: Allows for an adjacent property to be used for shared parking

H. Building Renovations – When an existing building or use is enlarged, structurally altered, or remodeled to the extent of increasing or changing the use by more than ten percent (10%), but less than fifty percent (50%), of the existing square footage, additional off-street parking shall be provided for the incremental increase in accordance with the off-street parking regulations set forth herein. When an existing building or use is enlarged, structurally altered, or remodeled to the extent of increasing or changing the use by fifty percent (50%) or more of the existing square footage, the off-street parking requirements for the entire building shall be comply with the parking regulations set forth herein.

I. Supplemental Parking Space Requirements

1. Parking regulations are based on the gross floor area (GFA) of the building.
2. In determining the required number of parking spaces, fractional spaces shall be rounded to the nearest whole space. Parking spaces located in buildings used for repair garages or car washes, and spaces in drive-through lanes shall not be counted as meeting the required minimum number of parking spaces.
3. Wooden poles shall not be used for parking lot or site lighting for a non-residential use.
4. Except for single-family dwelling units, parking spaces shall be arranged so that vehicles shall not be required to back out of the parking spaces directly into a street.

5. A reduction of up to twenty percent (20%) may be approved by staff with a parking analysis report justifying the reduction is provided as part of a request for parking reduction.

J. Parking Group Schedule – The minimum number of off-street parking spaces to be provided in connection with the permitted use listed in Table 3-310, *Schedule of Permitted Principal Uses*, shall be in accordance with the following Table 3.29 – *Parking Group Schedule*.

Commented [BB103]: The percentage is up for discussion; this allows for greater flexibility for unique and/or large developments

Table 3.29 Parking Group Schedule	
Parking Group	Minimum Number of Off-Street Parking Spaces
1	1 per unit
2	2 per unit
3	2 per unit, exclusive of "in-garage" parking
4	1 per unit plus 1 guest space per every 5 units
5	1 per 100 sq. ft. of gross floor area
6	1 per 150 sq. ft. of gross floor area
7	1 per 200 sq. ft. of gross floor area
8	1 per 300 sq. ft. of gross floor area

9	1 per 400 sq. ft. of gross floor area
10	1 per 500 sq. ft. of gross floor area
11	1 per 5 pupils plus drop-off and pick-up areas
12	1 per classroom plus 1 per each 2 students
13	1 per classroom plus 1 per 400 sq. ft. of office space
14	1 per 1.5 students and staff, based on capacity
15	1 per 3 students
16	1 per 200 sq. ft. of gross floor area plus 1 per 5,000 sq. ft. of exterior nursery area
17	1 per living unit
18	1 per 3 seats in primary seating area
19	1 per guest room plus 1 per 300 sq. ft. of office area – parking for restaurant additional
20	2 per hole
21	1 space
22	5 per hole (one per tee area for driving ranges)
23	5 per alley or table
24	As set by the SUP or PUD approved ordinance
25	Determined by the Building Official using acceptable industry comparables

Section 3.29.1 –Parking Space Construction Standards

- A. Dimensions – No parking space shall be less than nine (9) feet in width by eighteen (18) feet in length. The design and dimensions of off-street parking areas shall be in accordance with the following Table 3.29.1 – *Table of Parking Space Dimensions*.

Table 3.29.1 Table of Parking Space Dimensions					
Angles (Degrees)	0	30	45	60	90
Stall, Parallel to Aisle	23.0	18.0	12.7	11.4	9.0
Stall, Perpendicular to Aisle	9.0	16.5	19.0	20.0	18.0
Aisle Width, One-Way (1)	12.0	12.0	12.0	16.0	22.0
Aisle Width, Two-Way	24.0	24.0	24.0	24.0	24.0

(1) Aisle width shall comply with the requirements of the fire code when the aisle serves as a fire lane

- B. Surfacing (New Structures) – All parking spaces, aisles and maneuvering areas shall be constructed of an all-weather surface composed of concrete, asphalt, brick or paving stone. Such paving shall meet the minimum construction standards contained in the Colleyville Building Code. Such all-weather surface shall be provided for all parking spaces, whether enclosed or unenclosed, and shall be connected by an all-weather surface driveway to a street or alley. Rock, gravel and dirt parking surfaces are prohibited.
- C. Striping – For all non-residential uses and multi-tenant residential uses, parking spaces shall be striped or otherwise clearly designated on the parking facility surface, as determined by the Building Official.
- D. Curbs, Wheel Stops and Islands – Parking spaces abutting on adjoining property lines or street right-of-way lines shall be provided with wheel guards or bumper guards so located that no part of a normally parked vehicle will extend beyond the property line.

Section 3.30 Off-Street Loading Requirements

- A. Purpose and Intent – The purpose and intent of these regulations are to secure safety from fire, panic and other dangers; to lessen congestion in the streets and alleys; to facilitate the adequate provision of transportation and circulation; to conserve the value of building and land uses; and to encourage the most appropriate use of land. To this end, in all zoned districts where applicable, there shall be provided at the

time any use is established or expanded, or any building is erected or structurally altered (except as otherwise provided elsewhere in this section) minimum off-street loading in conformance with the requirements established herein.

- B. Location of Loading Spaces – Off-street loading spaces shall be provided and maintained for all retail, commercial and industrial uses and structures for receiving and loading merchandise, supplies, and materials within a building or on the lot or tract adjacent thereto. Such spaces shall be marked with painted outline and may be adjacent to a public alley or private service drive or may consist of a truck berth within a building or structure, however no portion of the off-street loading space shall be located within or extend into any public street, highway or alley right-of-way. (O-00-1261 / 12/19/00)
- C. Computation of Off-street Loading Space Sizes – At least one-half of the required number of off-street loading spaces or truck berths shall have a minimum dimension of ten (10) feet by fifty (50) feet each and the remaining required spaces or berths shall have a minimum dimension of ten (10) feet by twenty-five (25) feet each - exclusive of turnaround and maneuvering space.
- D. Type of Parking Surface Required for Loading Space – All surface areas upon which vehicles and trucks are parked during unloading operations shall consist of a paved surface, i.e., concrete, HMA, brick, paving stone, approved by the city building official.
- E. Rules for the Computation of Off-street Loading Spaces
1. No building, structure or part thereof used for nonresidential purposes on any "CN" or "CC" district shall hereafter be enlarged or extended unless off-street loading space is provided in accordance with the provisions of this section.
 2. No building, structure or part thereof used for nonresidential purposes in any "ML" district shall hereafter be enlarged or extended to provide a gross floor area of 25,000 square feet or more unless off-street parking is provided in accordance with the provisions of this section.
- F. Number of Off-street Spaces Required – The minimum number of off-street loading spaces required shall be in conformance with the following schedules:
1. Retail, Service (except personal service), Commercial and Industrial Uses

Sq. Ft. of Floor Area in Building or Structure	Minimum Number of Off-Street Loading Spaces or Berths Required
0 to 9,999	None
10,000 to 49,999	1
50,000 to 99,999	2
100,000 to 199,999	3
Each additional 100,000	1 additional

2. Office Buildings, Hotels/Motels, Restaurants and Similar Establishments

Sq. Ft. of Floor Area in Building or Structure	Minimum Number of Off-Street Loading Spaces or Berths Required
0 to 49,999	None
50,000 to 149,999	1
150,000 to 299,999	2
300,000 to 499,999	3
500,000 to 999,999	4
Each additional 500,000	1 additional

Section 3.31 Duties of Administrative Official

- A. Administration and Enforcement – An Administrative Official designated by the City Manager shall administer and enforce this Chapter. Said person may be provided with the assistance of such other persons as the City Manager may direct.

If the Administrative Official finds that any of the provisions of this Chapter are being violated, he the Administrative Official or their representative shall notify in writing the person responsible for such violations, indicating the nature of the violation and ordering the action necessary to correct it. He The Administrative Official or their representative shall order discontinuance of illegal use of land, buildings, or structures, removal of illegal buildings or structures or of illegal additions, alterations, or structural changes; discontinuance of any illegal work being done, or shall take any other action authorized by this Chapter to ensure compliance with or to prevent violation of its provisions.

Commented [EW104]: Revised language that was gender-specific

- B. Building Permits Required – No building or other structure shall be erected, moved, added to, or structurally altered without a permit therefore where applicable, and issued by the Administrative Official. No building permit shall be issued by the Administrative Official except in conformity with the provisions of this Chapter, unless he receives a written order from the Zoning Board of Adjustment in the form of an administrative review, special exception, or variance as provided by this Chapter. No building permit shall be issued unless the property has been platted of record, except that a building permit may be issued for unplatted property meeting all of the following five criteria:

1. The parcel is a "lot of record" as defined herein; and
2. Right-of-way and easements sufficient for Master Plan roads or drainage/utility facilities exist; and
3. The parcel adjoins an approved public street; and
4. The parcel contains a principal residential use in a residential structure; and
5. The requested construction permit(s) and all construction permits issued for the parcel within the past three years allow improvements whose combined value does not exceed 50% of the appraised value of the parcel as shown in the current parcel record of the Tarrant County Appraisal District.

- ~~C. Application for Building Permit – All applications for building permits shall be accompanied by plans in triplicate drawn to scale, showing the actual dimensions and shape of the lot to be built upon; the exact sizes and locations on the lot of buildings already existing, if any, and the location and dimensions of the proposed building or alteration. The application shall include such other information as lawfully may be required by the Administrative Official, including existing or proposed building or alteration; existing or proposed uses of the building and land; the number of families, housekeeping units, or rental units the building is designed to accommodate; conditions existing on the lot; and such other matters as may be necessary to determine conformance with, and provide for the enforcement of, this and other city ordinances.~~

~~One copy of the plans shall be returned to the applicant by the Administrative Official, after he shall have marked such copy either as approved or disapproved and attested to same by his signature on such copy. The original and one copy of the plans, similarly marked, shall be retained by the Administrative Official.~~

Commented [EW105]: The adopted building codes already codify the requirements for building permit applications

- D. Site Plan Approval Required – Where the property is zoned CPO, CN, CC, ML, SU, PUD-C, or PUD-I, a site plan shall be submitted for review and approval to the Administrative Official prior to the issuance of a building permit. The site plan referred to herein shall contain the following:

1. The boundary lines and dimensions of the property, existing subdivision lots, available utilities, easements, roadways, sidewalks, fire lanes, and public rights-of-way.
2. Topography of the property proposed for development in contours of not less than two (2) feet, together with any proposed grade elevations, if different from existing elevations. If the natural contour of the land is to be altered or changed in any location on the property more than four (4) feet

then the site plan must provide detailed information on the proposed grading plan. This information shall include the correlation of the proposed grading plan to the surrounding properties and the use of surrounding properties, and shall include information indicating the drainage and line of sight effect the proposed grading plan will have on the surrounding properties.

3. The 100 year flood plain, water courses, wetlands, drainage areas, and other significant features including, but not limited to, rock outcroppings and tree groupings.
4. The location and use of all existing and proposed buildings or structures, including all refuse storage areas, and the minimum distance between buildings. Where building complexes are proposed, a site plan showing the location of each building and the minimum distance between buildings, and between buildings and the property line, street or curb line and/or alley shall be submitted.
5. Total number of off -street parking and loading spaces in accordance with Section 29 "Off-Street Parking Requirements", and Section 30 "Off-Street Loading Requirements" of this Chapter.
6. All points of vehicular ingress and egress and circulation within the property. Any special traffic regulation facilities, proposed or required, to assure the safe function of the circulation plan shall also be shown.
7. Setbacks, lot coverage, and when relevant, the relationships of the setbacks provided and the height of any existing or proposed building or structure.
8. The location, size, and arrangement of all outdoor signs, exterior auditory speakers and lighting.
9. A landscape plan prepared in accordance with the requirements of *Chapter 4 – Landscaping & Buffering* of this Land Development Code.
10. The location and height of fences or, screen plantings and the type of building materials or plantings to be used for fencing or screening in accordance with the requirements of Section 26 "Fences, Free Standing Walls, and Screening Materials" of this Chapter.
11. Note a soil erosion control plan for the period during which construction will be taking place.
12. Where multiple types of land uses are proposed, a land use plan delineating the specific areas to be devoted to various uses shall be required.
13. Vicinity map, north point, scale, name of the development, name of the owner, name of the planner, total acreage of the project, street address or common description of the property.
14. Current land uses and zoning district of the property and current land uses and zoning districts of the contiguous properties and buildings on the exterior of the site and within twenty-five (25) feet of all property lines.
15. The location and size of existing and proposed surface and subsurface drainage facilities.
16. A description of the type of land use that is proposed for the site including its Standard Industrial Classification (SIC) Code if there are any chemicals or toxic materials involved.

The Administrative Official may allow all of the foregoing to be contained within a single drawing if in the opinion of the Administrative official the drawing can be properly evaluated.

~~E. Expiration of Building Permit — If the work described in any building permit has not begun within (6) calendar months from the date of issuance thereof, said permit shall expire. It shall be cancelled by the Administrative Official, and written notice thereof shall be given to the persons affected, together with notice that further work as described in the cancelled permit shall not proceed unless and until a new building permit has been obtained. Further, the Administrative Official shall make an inspection of the work each (6) months, and if the work has not progressed, said permit shall expire.~~

~~F. Certificate of Occupancy Required: For New, Altered Changes in Use, or Non-conforming Uses — It shall be unlawful to use or occupy or permit the use or occupancy of any building or premises, or both, or part~~

Commented [EW106]: The adopted building codes already codify the requirements for expired permits

~~thereof hereafter created, erected, changed, converted, or wholly or partly altered or enlarged in its use or structure until a certificate of occupancy shall have been issued therefor by the Administrative Official stating that the proposed use of the principal building or land conforms to the requirements of this Chapter.~~

- ~~a. No nonconforming building or use shall be maintained, renewed, changed, or extended until a certificate of occupancy shall have been issued by the Administrative Official. The certificate of occupancy shall state specifically wherein the nonconforming use differs from the provisions of the ordinance.~~
- ~~b. No permit for erection, alteration, moving or structural repair of any building shall be issued until an application has been made for a certificate of occupancy, and the certificate shall be issued in conformity with the provisions of this Chapter upon completion of the work.~~
- ~~c. A temporary certificate of occupancy may be issued by the Administrative Official for a period not exceeding (6) months during alterations or partial occupancy of a building pending its completion, provided that said temporary certificate may include such conditions and safeguards as will protect the safety of the occupants and the public.~~
- ~~d. The Administrative Official shall maintain a public record of all certificates of occupancy.~~
- ~~e. Failure to obtain a certificate of occupancy shall be a violation of this Chapter and punishable under Chapter 1 – General Provisions of this Land Development Code.~~

Commented [EW107]: The adopted building codes already codify the requirements for a Certificate of Occupancy

- f. Construction and Use to be Provided in Applications, Plans, Permits and Certificate of Occupancy – Building permits or certificates of occupancy issued on the basis of plans and applications approved by the Administrative Official authorize only the use, arrangement, and construction set forth in such approved plans and applications, and no other use, arrangement, or construction. Use, arrangement, or construction at variance with that authorized shall be deemed violation of this Chapter, and punishable as provided by *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.32 Comprehensive Zoning Ordinance – Zoning Map

This Chapter when read together with the official Zoning Map of the City of Colleyville, Texas, shall constitute the comprehensive zoning ordinance for the City of Colleyville, Texas.

The Zoning Map, as submitted with Ordinance 0-70-15, revised and updated in 1976, a copy of which is on file in the City Secretary's office shall remain the official Zoning Map of the City of Colleyville, until a new map is established in accordance with the provisions contained in this Chapter.

Section 3.33 Amendments to This Chapter

Reserved for listing of amendments to this Chapter.

Ord. Number	Date	Subject
O-00-1223	07/18/00	Residential Accessory Buildings
O-00-1241	10/03/00	Temp. Construction Offices & Temp. Real Estate Offices
O-00-1249	11/08/00	Large Commercial Buildings
O-00-1261	12/19/00	Location of Loading Spaces / Non-conforming Uses, Lots and Buildings
O-02-1331	02/19/02	Established one year time limit on SUP performance
O-02-1330	02/26/02	Tents and other special events
O-04-1454	04/16/04	Maximum size and number of screens for movie theaters
O-04-1497	12/21/04	Temporary Buildings and Uses
O-05-1529	06/21/05	Amend PUD regulations
O-05-1532	07/19/05	Amend PUD side and rear yard set-back regulations

Colleyville, Texas, Land Development Code

O-05-1538	09/06/05	Amend movie theater regulations regarding viewing screens
O-07-1607	01/16/07	Update Land Use Table and Parking Schedule
O-07-1608	02/20/07	Security gating setback standards across driveways
O-07-1633	9/4/07	Amend Sections 3.17 to 3.22 and Section 3.24, Table of Permitted Uses
O-08-1656	02/05/08	Amend Section 3.24, Table of Permitted Uses
O-09-1708	02/17/09	Amend Sections 3.26 and 3.27
O-09-1709	02/17/09	Amend Section 3.24.C, Wind Driven Generators
O-10-1750	05/04/10	Addition of Package Store Use, Regulations and Provisions
O-12-1838	6/19/12	Amend Section 3.24, Table of Permitted Uses to include purchasing and/or resale of precious metals
O-13-1863	2/5/13	Amend Section 3.24, Table of Permitted Uses to include addition of medical office uses to CPO zoning district
O-13-1871	4/16/13	Addition of Portable Storage Structure standards to Section 3.24(C). Amendments to Section 3.26 regarding commercial screening and dumpster screening
O-14-1905	1/21/14	Addition of fence maintenance and construction standards
O-14-1914	4/15/14	Addition of Concrete/Asphalt batch plant standards

Chapter 4

Landscaping and Buffering

Rev. July 15, 2003

Section 4.1 Purpose of This Chapter

The purpose of this Chapter is to establish rules and regulations for the minimum placement of landscaping materials in certain zoning districts.

Section 4.2 Authorization for Adoption of This Chapter

The regulations contained in this Chapter have been adopted under the authority of *Chapter 51 – General Powers of Municipalities of the Texas Local Government Code*, which authorizes a municipality to adopt ordinances, rules, or police regulations that are for the good government, peace, or the trade and commerce of the municipality. This Chapter is also adopted under the authority of *the Home Rule Charter of the City of Colleyville*, which authorizes the City Council to exercise all powers granted to municipalities by the Constitution or the laws of the State of Texas.

Section 4.3 Applicability of This Chapter

The provisions of this Chapter shall be applicable as follows:

1. For all new construction; or,
2. When an existing building is proposed for remodeling, alteration, addition, or expansion, and the proposed construction value exceeds fifty (50%) percent of the current appraised value of the existing structures, excluding the value of the land; or,
3. When an existing building is proposed for an addition that will increase the square footage of the existing building by twenty (20%) percent or greater; or,
4. As a requirement of the approval of a Special Use Permit or Planned Unit Development.
5. For purpose of this regulation, the value shall be that shown on the most recent tax roll of the Tarrant Appraisal District.

Section 4.4 Variances and Appeals

Any person seeking approval of a development as required by this Land Development Code may request a variance from a requirement contained in this Chapter, or appeal a decision of an Administrative Official by submitting a request using the procedures described in Chapter 1 of this Land Development Code.

Commented [BB1]: Currently the ZBA; give authority to the P&Z Commission? Council?

Section 4.5 Definitions

Definitions applicable to this Chapter may be found in *Chapter 2 – Definitions* of this Land Development Code.

Section 4.6 Required Landscaping

For zoning districts "CPO, CN, CC1, CC2, CC3, ML, PUD-C, PUD-I" and institutional uses including churches, schools and governmental facilities in any district.

Commented [BB2]: Clarification to applicability

1. Intent - The intent of this ordinance is that landscaping shall not be limited to only the application of turf or grass; but landscaping shall include the coordinated planting (or retention) of grass, shrubs, ground cover, flowering plants, and trees and the grading or moving of earth to form a visually aesthetic and pleasing environment. The review of all site plans will consider the applicant's efforts in coordinating a variety of plant materials with the physical features of the property.
2. Landscaping Completed Prior to Issuance of Certificate of Occupancy - All landscaping shall be installed prior to the issuance of a Certificate of Occupancy. A permanent Certificate of Occupancy will be issued only when it is determined by the building official that all landscaping has been installed in accordance with the approved landscape plan. If it is determined, by the Building Official that planting of live material is hindered by adverse weather conditions, a temporary Certificate of Occupancy may be issued for a period up to three months.
3. Required Landscape Mixture - Twenty percent (20%) of the total land area in any proposed development shall be landscaped. At least fifty percent (50%) of the total landscaped area shall be located in the street yard(s) (Exhibit "4-A"). In order to insure for a variety of plant materials the following minimum requirements for grass, shrubs, and trees shall be provided:
 - a. All ground surfaces not used for buildings, sidewalks, roadways or other impermeable surfaces shall be covered with live grass, turf, shrubbery, trees, ground cover, flowering plants or appropriate mulching.
 - b. Shrubs: Shrubs shall be provided such that one 18" in height plant or five (5) gallon plant shall be planted on-site for each five (5) lineal feet of public street rights-of-way located adjacent to the property.
 - c. Trees: Landscaping shall include the retention or planting of one (1) three (3) inch caliper tree per each forty (40) feet of street frontage on collector streets, or larger, as shown on the Master Thoroughfare Plan, which shall be included in the twenty (20) percent required landscaping. These trees are to be planted on-along the street frontage.
 - d. Landscape Plans Required: Prior to the issuance of a building permit for any non-residential use, a Landscape Plan shall be submitted, as an element of the required site plan, to the City Manager or his appointed designee. The City Manager or his appointed designee, which may be either a staff member or other official body of the City, shall review such plans and shall approve same if the plans are in accordance with the criteria of these regulations. If the plans are not in accordance, they shall be disapproved and shall be accompanied by a written statement setting forth the changes necessary for compliance.
 - e. Content of Landscaping Plans: Landscaping Plans shall be prepared by a Texas Licensed landscape architect. Landscape Plans shall contain the following information:
 1. Minimum scale of one inch equals 40 feet except as approved by the City Manager or his approved designee;
 2. Location of all trees to be preserved;
 3. Location of all plants and landscaping material to be used including paving, benches, screens, fountains, statues, or other landscape features;
 4. Species of all plant material to be used;
 5. Size of all plant material to be used;
 6. Quantity and spacing of plant material where appropriate;
 7. A general layout and description of irrigation, sprinkler or water systems, including placement of water sources as designed by a licensed irrigator;
 8. Description of maintenance provisions for the Landscape Plan;
 9. All Landscape Plans to be sealed by a Texas Licensed Landscape Architect;
 10. Provide planting and irrigation specifications as part of the Landscape Plan;
 11. Provide name and address of the owner, location of the subject property, surrounding zoning, utility lines, water mains and easements, public or private streets and drives;
 12. Provide a general grading and drainage plan.

- f. Description of Planting Material: Landscape plant material may be selected from the following list, however the applicant may use other plant material not listed if it is determined to be an appropriate and functional element of the landscape plan.

1. Over-story Trees (Range from 30 to 60 feet)

Common Name	Botanical Name
Bald Cypress	<i>Taxodium distichum</i>
Cedar Elm	<i>Ulmus crassifolia</i>
Lacebark Elm	<i>Ulmus parvifolia</i>
Pecan	<i>Carya illinoensis</i>
Chinese Pistache	<i>Pistacia chinensis</i>
Bur Oak	<i>Quercus macrocarpa</i>
Red Oak	<i>Quercus shumardii</i>
Sweet Gum	<i>Liquidambar styraciflua</i>
Green Ash	<i>Fraxinus pennsylvanica</i>
Live Oak	<i>Quercus virginiana</i>

Common Name	Botanical Name
Western soapberry	<i>Sapindus drummondii</i>
Post Oak	<i>Quercus stallata</i>
Black Jack Oak	<i>Quercus marilandica</i>
Eastern Red Cedar	<i>Juniperus virginiana</i>
Southern magnolia	<i>Magnolia grandiflora</i>
Slash pine	<i>Pinus elliotii</i>
Japanese black pine	<i>Pinus thunbergii</i>
Austrian pine	<i>Pinus nigra</i>
Afgan pine	<i>Pinus eldarica</i>

2. Accent Trees (Range from 10 to 20 feet)

Common Name	Botanical Name
Redbud	<i>Cercis canadensis</i>
Crape myrtle	<i>Langerstroemia indica</i>
Yaupon holly	<i>Ilex vomitoria</i>
Bradford pear	<i>Pyrus calleryana</i>
Texas sophora	<i>Sophora affinis</i>
Wild plum	<i>Prunus americana</i>

Common Name	Botanical Name
Crab apple	<i>Malus angustifolia</i>
Deciduous holly	<i>Illex decidua</i>
Flameleaf sumac	<i>Rhus copallina</i>
Cherry-laurel	<i>Prunus caroliniana</i>
Chase tree	<i>Vitex angust-castus</i>

3. Shrubs (Range from 3 to 5 feet)

Common Name	Botanical Name
Dwarf crape myrtle	<i>Langerstoemia indica nana</i>
Dwarf buford holly	<i>Illex cornuta 'barfordii Nana'</i>
Dwarf Chinese holly	<i>Illex cornuta 'rotunda'</i>
Dwarf yaupon holly	<i>Illex vomitoria 'nana'</i>
Fraser's photinia	<i>Photinia Fraseri</i>
Purple sage	<i>Leucophyllum frutescens</i>

Common Name	Botanical Name
Purple leaf japanese barberry	<i>Berberis thunbergii 'atropurpurea'</i>
Pampus grass	<i>Cortaderia selloana</i>
Nandina	<i>Nandina domestica</i>
Juniper	<i>Juniperus chinensis spp</i>
Fountain grass	<i>Pennisetum spp</i>

4. Ground Cover (Ranges from 18 inches)

Common Name	Botanical Name
Juniper supp.	<i>Juniperus horizontalis</i> or <i>procumbens</i>
Periwinkle	<i>Vinca major</i>
Monkey Grass	<i>Liriope muscaria</i> spp
Asian jasmine	<i>Trachelospermum asiaticum</i>
Confederate Star Jasmine	<i>Trachelospermum jasminoides</i>
Monkey grass	<i>OP hipogon</i>

5. Vines

Common Name	Botanical Name
Coral honeysuckle	<i>Lonicera sempervirens</i>
Carolina yellow jasmine	<i>Gelsemium semper</i>
Lady banksia rose	<i>Rosa banksiae</i>
Cross vine	<i>Bignonia capreolata</i>
Sweet autumn clematis	<i>Clematis paniculata</i>
Virginia creeper	<i>Parthenocissus quinquefolia</i>
Boston ivy	<i>Parthenocissus tricuspidata</i>

6. Perennial and Annual Flowers

Common Name	Botanical Name
Chrysanthemum	<i>Chrysanthemum</i> spp
Canna	<i>Canna generalis</i>
Copper leaf	<i>Acalypha Wilkesiana</i>
Periwinkle	<i>Catharanthus roseus</i>
Iris	<i>Iris</i> supp.
Lantana	<i>Lantana Camera</i>
Daffodil	<i>Narcissus Jonquil,</i> <i>Tazetta, & King Alfred</i>

Common Name	Botanical Name
Petunia	<i>Petunia hybrida</i>
Marigold	<i>Tagetes</i> spp
Tulip	<i>Tulipa</i> spp
Zinnia	<i>Zinnia</i> spp
Caladium	<i>Caladium hortulanum</i> <i>'candidum' 'pink beauty'</i>
Moss rose or portulaca	<i>Portulaca grandiflora</i>
Wild Flowers	

- g. Landscaping Credit: Landscape credits may be applied to the overall landscape requirement, as indicated in Section ~~4-54.6.3~~ *Required Landscape Mixture*. However, in no instance shall the credits reduce the total amount of landscaping on a lot to less than fifteen (15) percent of the total land area. Credits will only be allowed if they are maintained as a permanent element of the landscape plan. Credits may be obtained as follows:

- For each two (2) square foot of area that is landscaped in the public street right-of-way, one (1) square foot of landscape credit will be applied to the overall landscaping requirement.
- For each one (1) square foot of area that is landscaped with flowering seasonal color, two (2) square foot of landscape credit will be applied to the overall landscaping requirement.
- Over and above the required shrub planting, for each newly planted shrub 18" in height or contained in a five (5) gallon container, which is maintained in a living and growing condition, fifteen (15) square feet of landscape credit will be applied to the overall landscape requirement.

Commented [BB3]: Corrected cross-reference

4. Over and above the required tree planting, for each newly planted or existing tree of at least three (3) inches in trunk diameter, measured twelve (12) inches above grade, which is maintained in a living and growing condition, one hundred (100) square feet of landscape credit will be applied to the overall landscape requirement. Planting of two (2) ornamental trees of eight (8) feet in height shall receive the same landscape credit as one (1) three (3) inch caliper tree.
 5. Over and above the required tree planting, for each newly planted or existing tree of at least six (6) inches in trunk diameter, measured twelve (12) inches above grade, which is maintained in a living and growing condition, two hundred fifty (250) square feet of landscape credit will be applied to the overall landscape requirement. Each additional one (1) inch diameter of tree over twelve (12) inches shall receive twenty (20) square feet of landscape credit.
- h. Maintenance of Landscaping: All landscaping maintenance shall be the responsibility of the property owner. The following minimum standards shall be required:
1. All landscaping shall be permanently maintained and shall have an underground irrigation system installed by a licensed irrigator and must meet all applicable requirements of the City.
 2. Irrigation systems may be buried on public street rights-of-way. The City or any franchised utility will not be responsible for damage to any landscaping material or equipment while performing repairs of maintenance to its system. However, landscaped right-of-ways shall be irrigated;
 3. Landscaped areas shall be kept free of trash, litter, weeds and other such material or plants not a part of the landscaping;
 4. All plant materials shall be maintained in a healthy and growing condition as is appropriate for the season of the year; ~~and~~
 5. Plant materials which die shall be replaced with plant material of similar variety and size within a six (6) month period; ~~and~~
 6. The maintenance requirement contained in this section shall be applicable regardless of the tenant occupancy status of any buildings on the property. (Ord. O-03-1408 / 07/15/03)
- i. Landscaping of Parking Lots: it is the intent of this section to encourage design and construction of parking areas in a manner whereby areas within the parking lot are landscaped as well as areas considered unusable for parking or maneuvering space. The following minimum requirements shall be observed:
1. Parking lots shall contain a minimum of one hundred forty (140) square feet of landscaped island per each eighteen (18) contiguous parking spaces required. This landscape island is to include one (1) three (3) inch caliper tree.
 2. Landscaped islands shall be irrigated by an underground system as indicated in *Paragraph h - Maintenance of Landscaping*. Irrigation of all landscaped areas adjacent to any parking and/or driving surfaces shall be accomplished such that a minimum amount of water is applied to parking and/or driving surfaces.
 3. All shrubbery, flowering plants, and trees planted in parking lot islands or adjacent to parking lots shall be set back three (3) feet from any curb and that provides for "head-in" automobile parking (Exhibit "4-B").
 4. Landscape material in parking lots shall include shrubs and trees or a combination thereof, which in turn may be planted with a combination of grass, ground cover, and/or flowering plants.

Commented [BB4]: This section likely to be moved to Chapter 6 Commercial Design Standards

5. All landscaping within the parking lot shall be located within a landscape island or module, delineated from the surrounding paved area by a curb or barrier, constructed of masonry or concrete, of not less than six (6) inches in height around the perimeter of the island or module.
6. At least three-fourths (3/4) of the tree drip line area must be in permeable area (See Exhibit "4-C").
7. For larger existing trees located in the parking area, which are being retained and incorporated into the landscape plan, an appropriate aeration system or an alternative method of protecting the tree must be provided and detailed in the landscape plan.
- j. Landscaping Adjacent to Residential Districts: For any development in "C-PO", "CN", "CC1", "CC2", "CC3", "ML", "PUD-C", "PUD-I" and institutional uses including churches, schools, and governmental facilities ~~(which includes all zoning) except residential districts and "AG" used for residential and pure agricultural uses, zoning districts~~ which abut districts zoned residential or mobile home there shall be a minimum twenty (20) foot wide green belt of "live plant material of the evergreen variety" which is expected to grow to six (6) feet height in two (2) years, a minimum of three (3) feet in height at the time of installation and planted on six (6) foot centers, for the entire distance along which the development abuts the residential district. Where a fire lane is required, the green belt may be reduced to five (5) feet (Exhibit "4-C"). Exception: When adjacent to institutional uses in residential districts and "AG" used for residential and pure agricultural uses.
- k. Landscaping Adjacent to Colleyville Boulevard: For any development which abuts Colleyville Boulevard there shall be a minimum ~~twenty ten (2010)~~ foot wide landscaped green belt of "live plant material", exclusive of access drives. On corner lots, the ~~twenty 10~~ feet ~~(20'10')~~ wide landscaping green belt will wrap around to the depth of the property. This area may be planted with trees and shrubs required at the front of the site noted elsewhere in this Chapter. Landscape planting shall not be erected or installed in such a manner as to interfere with traffic view or impose a safety hazard. (O-01-1295 / 08/21/01)
- l. Special Permits; Appeals; Exceptions: Any person aggrieved by this ordinance may appeal its effect to the Zoning Board of Adjustment on the basis of hardship.
- m. Existing Non-Conforming Uses and/or Structures: All uses that are in existence at the time of this Landscape ordinance, which do not meet the requirements provided herein, will be considered as being nonconforming to these landscape requirements. These nonconforming uses/structures will be subject to the non-conforming provisions of Chapter 3 – Land Use of this Land Development Code, unless otherwise provided for in this Section. A variance to landscaping requirements may be granted, regardless of areas of noncompliance, upon completion of the following:
 1. Provide the City Manager or his appointed designee with a landscape plan prepared by the landscape architect for review and approval.
 2. Said landscape plan will illustrate a plan to landscape area as available, provide for irrigation, and provide for completing the plan.
 3. The installation of landscaping as indicated by the landscape plan is completed and approved by the city manager or his appointed designee.

Commented [BB5]: Reworded paragraph to clarify intent

Commented [BB6]: Proposal to reduce down to 10 feet

Commented [BB7]: Give authority to P&Z Commission or City Council?

Section 4.7 Amendments to This Chapter

Reserved for listing of amendments to this Chapter.

Ord. Number	Date	Subject
O-01-1295	08/21/01	Landscaping adjacent to Colleyville Boulevard
O-03-1408	07/15/03	Maintenance regarding building vacancy




Exhibit "4-A" - Street Yard Landscaping Requirements




Exhibit "4-B"
Landscape Requirement for Head-in Parking

Exhibit "4-C"
Description of Dripline




Exhibit "4-D"
Rear and Side Landscape Buffer Requirements
With Fire Lane Provided




Exhibit "4-E"
Rear and Side Landscape Buffer Requirement
Without Fire Lane Provided

Chapter 6

Commercial Design Standards

Amended 12/13/2011

Section 6.1 Purpose of This Chapter

The purpose of this Chapter is to establish rules and regulations for development of commercial and institutional properties and for the exterior design and exterior building materials of commercial and institutional buildings in all zoning districts.

Section 6.2 Authorization for Adoption of This Chapter

The regulations contained in this Chapter have been adopted under the authority of the following:

1. *Chapter 51 – General Powers of Municipalities of the Texas Local Government Code*, which authorizes a municipality to adopt ordinances, rules, or police regulations that are for the good government, peace, or the trade and commerce of the municipality.
2. *Chapter 211 – Municipal Zoning Authority of the Texas Local Government Code*, which authorizes a municipality to divide a municipality into districts and, within each district, regulate the erection, construction, reconstruction, alteration, repair, or use of buildings, other structures, or land.
3. *The Home Rule Charter of the City of Colleyville*, which authorizes the City Council to exercise all powers granted to municipalities by the Constitution or the laws of the State of Texas.

Section 6.3 Definitions

Definitions applicable to this Chapter may be found in *Chapter 2 – Definitions* of this Land Development Code.

Section 6.4 Building Design Standards

1. Applicability: For any new commercial and institutional buildings, or additions or alterations exceeding 50% of the building improvement value based on the current certified tax roll, the following standards apply. For institutional buildings, if no relevant appraisal data exists on the certified tax roll, the building improvement value shall be obtained through an independent third party appraiser, paid by the building permit applicant, and provided to the City.
2. Facade Articulation - All large commercial buildings shall have facades which comply with the following requirements:
 - a. Horizontal Articulation – No building façade visible from a public street or parking area shall extend horizontally greater than three (3) times the height of the wall without having an off-set of not less than fifteen (15%) percent of the wall's height as shown on the attached Exhibit "A", and such off-set shall continue for a minimum distance equal to at least twenty-five (25%) percent of the length of the longest adjacent plane.
 - b. Vertical Articulation – No building façade visible from a public street or parking area shall extend horizontally for a distance greater than three (3) times the height of the wall unless the wall contains at least one of the following features and every front building façade shall have no less than two of the following features:

Commented [BB1]: These standards taken from the Large Commercial Building standards found in Chapter 3.

- (1) Parapets which change the roof line. The parapet height shall be a minimum of fifteen (15%) percent of the wall's height, and such height change shall continue for a minimum distance equal to at least twenty-five (25%) percent of the length of the longest adjacent plane.
 - (2) Overhanging eaves, extending no less than three (3) feet past the supporting walls.
 - (3) Sloping roofs that do not exceed the average height of the supporting walls, with an average slope greater than or equal to one (1) foot of vertical rise for every three (3) feet of horizontal run and less than or equal to one (1) foot of vertical rise for every one (1) foot of horizontal run.
 - (4) Three or more roof slope planes.
 - (5) A covered walkway along a minimum of fifty (50%) percent of the front façade length.
3. Side and Rear Facade Features – Side and rear building facades, which are not visible from a public street or parking area, shall include a minimum of three architectural changes, such as (1) a changing plane not less than five (5) feet in width and eighteen (18) inches in depth, (2) a surface material change of not more than thirty (30) feet in length, as measured horizontally, or (3) a combination of these elements.

6.4. REQUIREMENTS

~~For any new commercial and institutional buildings or, additions, or alterations exceeding 50% of the building improvement value based on the current certified tax roll, it shall be the duty of the administrative official responsible for review of site plans to calculate the design score for all commercial and institutional buildings as part of the building permit and site planning process. For institutional buildings, if no relevant appraisal data exists on the certified tax roll, the building improvement value shall be obtained through an independent third party appraiser, paid by the building permit applicant and provided to the City. Paragraphs A through G are the basis for the design calculation to meet the requirements of the design standards. The provided worksheet shall be attached to all commercial and institutional building plan submissions for review. The final design will be evaluated by the staff on a pass/fail basis.~~

Commented [BB2]: The calculations for building score are very complicated and very hard to understand.

Commercial/Institutional Building Design Factors Work Sheet

A. Façade Articulation Variables (10 total possible points – See Figure 1 and 2 below)

1. ~~**L** = Length in feet of building perimeter visible from the street. _____ ft.~~
2. ~~**F** = Length of the longest horizontal straight section of the exterior façade visible from the street. _____ ft.~~


~~In order to determine that any two horizontal straight sections of wall in the same plane are separate walls:~~


- a. ~~There shall be an intervening physical separation of space or other wall sections which separate the two subject walls by not less than three feet.~~
- b. ~~The average offset distance of the intervening space and/or wall section shall be not less than one foot from the subject plane.~~
- c. ~~The total perimeter beam length of the intervening space and/or wall section shall not be less than five feet.~~
- d. ~~Materials used within the intervening separation may not be identical to materials used in more than one of the two same plane test sections~~

e. Any two or more same-plane wall sections which do not meet all of the requirements of Paragraphs a, b and c above shall be determined to be part of one complete wall section.

3. $A =$ Articulation ratio or $L/F =$ _____

4. $Ka =$ Articulation Score $= A \times 2 =$ _____ (Sum)





B. Vertical Departure Variables (10 total possible points – See Figure 3 below)

1. **P** = Total surface area of a projection of all surfaces visible from the street and which are relative to the four vertical planes of an imaginary cube which would enclose the building. _____ s.f.

2. **R** = Total surface area of a projection of all sloping or vertical surfaces visible from the street of the building relative to the four vertical planes of an imaginary cube which would enclose the building. _____ s.f.

For the purpose of the calculation of "R";

a. Buildings with principal wall sections which are generally rectangular must be aligned so that principal wall sections are parallel to a face of the test cube.


b. Only those surfaces which slope at an angle of not less than 15 degrees nor more than 75 degrees from the vertical plane may be included in this area calculation.

c. Circular, convex or concave regular surfaces which are offset at the central point of the curve by not less than one foot from the vertical surface and have a central angle of not less than 60 degrees may also be included.

d. **Q** = Number of test cube vertical surface projections (1, 2, 3 or 4) visible from the street. _____


3. **V** = Vertical departure ratio or R/P = _____

4. **Kv** = Vertical Departure Score = $10 \times V$ = _____ (Sum)



C. ~~Shade Coverage Variables (10 total possible points – See Figure 4 below)~~

1. ~~S = Total covered but unenclosed structural exterior area attached to the building as measured in square feet on a horizontal plane. _____ s.f.~~
 - a. ~~The floor area of covered exterior balconies may be included. Attached canopies, porches, verandas, and other shade oriented structural design features may also be included.~~
 - b. ~~The area under detached canopies shall be excluded.~~
2. ~~G = Total area of the interior ground floor of the building. _____ s.f.~~
3. ~~C = Shade coverage ratio or S/G = _____~~
4. ~~Kc = Shade Score = 100 x C = _____ (Sum)~~



D. Horizontal and Diagonal Roof Planes Variables (10 total possible points – See Figure 5 below)

1. ~~F = "F" as previously calculated in Paragraph A(2) above. _____~~
~~5% of F = _____~~


2. ~~E = Total visible horizontal and diagonal eave planes, ridge planes and/or parapet top planes on the building. _____~~

~~For the purpose of this paragraph:~~

- ~~a. Two eaves in the same horizontal plane but which are separated by not less than 5 percent of "F" shall be considered separate planes.~~
- ~~b. Two parapets in the same horizontal plane but which are separated by not less than 5 percent of "F" shall be considered separate planes.~~
- ~~c. A parapet with a wall length of less than 5 percent of "F" shall be considered a crenellation and shall not be counted as a parapet.~~
- ~~d. For every five crenellations, regardless of elevation, one equivalent plane may be added to the calculation of total planes. In like manner, one crenellation shall equal 0.2 horizontal / diagonal planes.~~
- ~~e. For an eave, canopy or mansard which overhangs the vertical surface of the building by not less than 18 inches, one plane shall be counted for the outer edge of the eave and one plane shall be counted at the intersection of the eave and the wall.~~

- f. ~~One plane shall be counted for each diagonal ridge or edge of a sloped roof and, if the edge is also an eave which overhangs the wall by not less than eighteen (18") inches it shall be counted as two planes.~~
- g. ~~For mansards which wrap around a building corner, planes shall not be counted as separate unless there are actual changes in elevation.~~
- h. ~~Two parapet tops which intersect at 90 degrees in the same horizontal plane shall be counted as separate planes.~~
3. ~~Q = Total # of surfaces visible from the street as identified in Paragraph B(2)(d) above.~~

4. ~~H = Horizontal / Diagonal Planes Ratio or E/Q = _____ (Sum)~~



E. Fenestration Variables (10 total possible points)

1. ~~W = Total number of windows, doors, and other openings into the structure through which light may pass. _____~~

~~For the purpose of this paragraph each opening must be framed on the sides, top and/or bottom by structural building materials with a surface area equal in the aggregate to not less than 50 percent of the surface area of the opening.~~

2. ~~Q = As previously calculated in Paragraph B(2)(d) above. _____~~
3. ~~N = Fenestration Ratio = W/Q = _____ (Sum)~~

F. Total Design Score: Add all sum scores above to reach a total design score. The submission will be evaluated by the reviewer and a score provided. The reviewer will review as part of your submission your scoring provided based upon your design submission.

G. Minimum Design Score Requirement: Notwithstanding any variance per Section 6.6 below, the minimum design score for all commercial and institutional buildings constructed as provided for by this chapter shall be 30 in all zoning districts, except that the design score may require a higher or lower value as a condition of a Special Use Permit or Planned Unit Development zoning district as authorized by the City Council.

Zone—	CN	CPO	CC1	CC2	CC3	ML
Score—	30	30	30	30	30	30

Section 6.5 Exterior Building Color and Material Requirements

- Exterior Surface Materials – A minimum of ninety (90%) percent of each exterior wall surfaces, excluding door and window openings, shall be constructed of clay-fired brick, native stone, cast stone, or a combination of these materials. Tilt - up concrete construction is permitted, provided the exterior surface is covered with clay-fired brick, native stone, cast stone, or a combination of these materials. Stucco and EIFS (Exterior Installation Finished System) are permitted for not more than ten (10%) percent of the exterior surface. Concrete block, split-faced block or cinder-block shall not be acceptable. Proposals for surface materials with similar durability and appearance of clay-fired brick, native stone, or cast stone may be considered. Materials: The exterior walls of all commercial and institutional buildings constructed as provided for in this chapter shall be composed of 100% percent masonry, glass, or other equivalent material. However, building accents such as wood, EIFS, Hardie Plank or decorative metal trim are permitted such they do not exceed 15 percent of the total exterior wall surface area. Mixing of more than one type of masonry material for exterior walls is encouraged. For the purposes of this chapter, approved non-glass, masonry materials may include brick, finished concrete, stone (natural and man-made), and cementitious stucco. Unfinished concrete masonry unit products such as cinder block or tilt-wall sections are permitted but must have an architecturally finished surface such as split-face, rusticated, natural stone, etc.
- Exterior Surface Colors – The exterior surfaces shall be of a natural finish, provided the colors are subtle, or neutral colors. Trim and accent areas may be painted and feature brighter colors, including primary colors, but not more than ten (10%) percent of the wall surface area. High intensity or fluorescent colors are prohibited. Color: Primary exterior wall colors shall contain natural colors that reflect the natural environment of the cross-timbers prairie including soils and vegetation. Fluorescent colors are prohibited. Building elevations showing the proposed exterior wall color shall be submitted with the site plan application at the time of new construction as provided for by this chapter. Any applicant for a building that does not meet the requirement of this section as determined by the Community Development Director may request a variance to the Director's interpretation per Section 6.6 below.
 - For commercial and institutional buildings that exist as of the passage of this section, upon the repainting and/or alteration of any structure, the paint and material color shall comply with section 2 above.
- Exposed Columns – Exposed structural support columns shall be constructed of, or clad in, the same material as the principal structure. Architecturally significant columns (e.g. fluted, etc.) may be permitted.

Commented [BB3]: Taken from the Large Commercial Building standards in Chapter 3

Commented [BB4]: Corrected reference due to new sections

Section 6.6 Additional Development Regulations

- Low Solid Wall: A solid wall constructed of clay-fired brick, native stone, cast stone, or a combination of these materials, not less than thirty (30) inches in height as shown on the attached Exhibit "D". Said wall shall be constructed generally parallel to and twenty (20) feet from the street right-of-way. The solid wall shall not constitute more than thirty (30) percent of the length of the abutting street frontage.

Commented [BB5]: Taken from the Large Commercial Building standards in Chapter 3

2. Delivery / Loading Spaces – All delivery and loading spaces shall be screened from public view from a street right-of-way or an adjacent residential property by an eight (8) foot to ten (10) foot tall solid screening wall constructed of like material to the building. Additional planting materials shall be provided so that no more than two-thirds of the surface area of the solid screening wall is visible from the street or residential property. The live plant screening shall consist of shrubs, a minimum of three (3) feet in height when planted, and which can be expected to reach six (6) feet or greater in height within three (3) years of planting. Shrubs shall be spaced so that there shall be no gap greater than four (4) feet between mature plant materials. No delivery or loading area shall be operated between the hours of 11:00 p.m. and 6:00 a.m. Parking of delivery vehicles shall not exceed 48 hours duration.
3. Outdoor Display Areas – Outside display of merchandise shall not be allowed unless allowed by a Special Use Permit (SUP) approved by the City Council, provided that it shall be limited to an area within eight (8) feet of the front wall of the primary building and further provided that emergency pedestrian access to the building is not blocked. When allowed by SUP, no merchandise shall be displayed between the hours of 11:00 p. m. and 6:00 a. m.
- For purpose of this regulation, the front wall shall be the front containment wall of the structure and not the front of an overhanging walkway cover.
4. Outside Storage and Sales Areas – There shall be no outside storage or outside sales areas of landscaping materials, plants or general merchandise, except for an outside display area, as provided in the above paragraph. For purpose of this regulation, nothing shall prohibit the sale or display of landscaping materials, plants or general merchandise located behind an enclosed solid screening wall constructed of like materials to the building, provided merchandise is not visible above the top of the screening wall.
5. Cart Storage – All shopping cart storage areas shall be contained within the primary building. Temporary shopping cart parking within parking areas shall be allowed, provided the temporary enclosures shall be ornate and appropriately designed and that the carts are removed to within the primary building on a frequent basis.

Section 6.7 Non-Residential Outdoor Lighting Requirements

Commented [BB6]: New proposed Outdoor Lighting Standards

A. Purpose

Efficient and effective outdoor night lighting benefits everyone and enhances the City's nighttime character. New lighting technologies have produced lights that are extremely powerful, and these types of lights may be improperly installed so that they create problems of excessive glare and light trespass that reduce residents' privacy. Excessive glare can be annoying and may cause safety problems. There is a need for lighting requirements that recognize the benefits of efficient and effective outdoor lighting and provides clear guidelines for its installation so as to help maintain and complement the City's character and which strives to provide linkage between the built and natural environment and acknowledges and sustains the unique nature of the City's corporate-commercial, suburban and rural lifestyles. Appropriately regulated, and properly installed, outdoor lighting will contribute to the safety and welfare of the residents of the City.

B. Objectives

Outdoor lighting for nonresidential uses and multifamily uses has the following objectives:

1. It is intended to reduce the problems created by improperly designed and installed outdoor lighting in those areas zoned for nonresidential uses and multifamily uses;
2. It is intended to eliminate problems of glare and minimize light trespass by establishing regulations which limit the area that certain types of outdoor lighting fixtures can illuminate and by limiting the total allowable illumination of lots located in the town;

3. All lighting installed in nonresidential uses and multifamily uses should be designed with the idea of being a good neighbor, thereby eliminating or reducing unnecessary direct light from shining onto abutting properties or streets;

4. It is the declared purpose of this subdivision that nonconforming luminaries be eliminated and be required to conform to the regulations of this subdivision within a reasonable time.

C. Applicability

1. New fixtures or additional lighting. This subdivision shall apply to all installations of new fixtures or additional lighting to any new or existing nonresidential or multifamily use or structure.

2. Nonconforming Lighting. Luminaries installed prior to the adoption of the ordinance from which this subdivision is derived shall immediately be re-aimed or shielded such that the fixture no longer creates a nuisance as defined in section xx. Shielding may be accomplished by louvers, baffles, visors, or shields placed on the luminaries, or any other method whereby the light therefrom does not constitute a nuisance as defined in section xx

3. Exemptions:

(a) Street lighting installed by a governmental agency for public benefit on public rights-of-way; or

(b) Public outdoor recreational sport fields and sport courts complex.

D. Enforcement

The enforcement of the rules and the provisions of this subdivision shall be by the Administrative Official, or his duly appointed representative.

E. Measurement

1. Metering Equipment. Lighting levels shall be measured in footcandles with a direct-reading, portable light meter.

2. Method of footcandle measurement. The meter sensor shall be not more than six inches above ground level in a horizontal position. The reading shall be taken only after the cell has been exposed long enough to provide a constant reading.

F. Prohibited Lighting

The following lighting is prohibited. No owner or occupant of land shall permit any of the following conditions to exist:

1. An unshielded light source, including bare bulbs, above 15 watts, except for temporary seasonal lighting;

2. The operation of searchlights, strobes, or pulsating lights;

3. The use of low pressure sodium bulbs as a light source;

4. The use of a partial cutoff light source;

5. The use of a drop lens;

6. Luminaires located within the compatibility buffer between dissimilar uses;

7. Any luminaire that produces a disability glare;

8. Any light or combination of lighting that creates a nuisance as defined in section xx;

9. Any lighting installed to illuminate an unimproved surface or private outdoor recreational activities that exceeds requirements set forth in this statute without an approved variance, as set forth in this statute.

G. Height for light pole standards

Maximum height for light pole standards shall be as follows:

1. In parking areas containing zero to 150 parking spaces, maximum height of lighting pole standards shall not exceed 25 feet.
2. In parking areas containing 151 or more parking spaces, maximum height of lighting pole standards shall not exceed 35 feet.

H. Building mounted lighting

All building mounted luminaires exceeding 15 watts shall be directed down with a full cutoff fixture.

I. Floodlighting

1. Luminaires used for floodlighting shall not direct the luminance above the facade of the object being lighted.
2. Spotlights and floodlights mounted overhead on poles or building walls and used for area lighting, including but not limited to residential areas, shall be installed so that the fixture is full cutoff as defined herein, with no light above 90 degree nadir.

J. Building Entry Points

At all building entry points average projected footcandle readings as determined by the point method photometrics shall not exceed a measurement of five footcandles.

K. Canopy lighting

All canopy lighting shall be fully recessed fixtures with full cutoff lens and shall not exceed 45 footcandles at any point under the canopy.

L. Spacing

1. In parking areas containing zero to 150 parking spaces, minimum spacing of lighting pole standards shall be no less than two times the height of the standard.
2. In parking areas containing 151 or more parking spaces, minimum spacing of lighting pole standards shall be no less than four times the height of the light standard, a ratio of 4 to 1.

M. Parking area lighting

Parking area lighting shall not exceed a measurement of 15 footcandles at any point in the parking area. The average projected footcandle reading as determined by the point method photometrics shall not exceed two footcandles.

N. Residential Adjacency

Where properties with a residential use or zoning, other than Agricultural, are adjacent to a commercial site, the maximum lighting intensity shall not exceed 0.5 footcandles.

O. Penalty

1. Any person violating any provision of this section shall be deemed guilty of a misdemeanor and upon conviction thereof, shall be punished by a fine as provided in section 1-13. A separate offense shall be deemed committed of each day during or on which a violation or failure to comply occurs or continues to occur.

2. A footcandle reading, as performed in accordance with section 98-1124, in excess of those amounts defined as a nuisance in section 74-3, shall be prima facie evidence of a violation of this subdivision.

O. Variance

1. A variance as to the height restriction may be permitted by the town council for the replacement of luminaires installed prior to the adoption of the ordinance from which this subdivision is derived if such luminaires are damaged, destroyed, or otherwise become inoperable.
2. A variance is permissible for such replacement luminaires only in those situations where more than one luminaire existed prior to the adoption of the ordinance from which this subdivision is derived. The town council may grant a variance, upon application by the property owner or his designee, if the town council determines that the replacement of a damaged, destroyed, or otherwise inoperable luminaire with a luminaire conforming to the height requirement set forth in this subdivision would:
 - (a) Create a nuisance as defined in section 74-3; or
 - (b) Be aesthetically inconsistent with the remaining luminaires in determining whether a replacement luminaire would be aesthetically inconsistent, the City Council may consider the following factors:
 - The location of the replacement luminaire on the subject property;
 - The type of construction material of the replacement luminaire;
 - The location of the subject property; and
 - The outdoor lighting used on adjacent and surrounding property.
3. Notwithstanding these provisions, under no circumstances may the replacement luminaire exceed 35 feet in height.

Q. Architectural lighting of buildings and structures

For spotlights and floodlights mounted at or near ground level and used to light a building wall, sign, or other structure, the axis of illumination shall be adjusted to minimize the amount of light escaping above, below, and to the side of the illuminated object.

R. Architectural lighting of landscaping

Landscape lighting installed for nonresidential uses and multifamily uses shall be installed according to the following:

1. Any lighting that is to be placed in the canopy of a tree shall be directed in a downward position to simulate natural light received by the area.
2. The fixture shall be shielded so that all of the light is directed downward and shall not be directed toward the tree, to reduce light intrusion.
3. All proposed lighting that is to be placed in a tree shall be affixed to the trunk or branch through the use of an adjustable bracketing system that will allow for the continued growth of the tree.
4. The mounting height of landscape lighting shall not exceed 25 feet.
5. No lighting shall be bolted, nailed, or glued to the trunk or any appendages of the tree, and such unauthorized attachment will be treated as a violation of chapter 94, Vegetation, of the town's Code of Ordinances.

Section 6.6 6.8 Variances; Architectural Review Commission

Commented [EW7]: Re-number section

- A. A person may request a variance from a requirement contained in *Chapter 6 – Commercial Design Standards* by filing said request with the administrative official. A request for a variance shall be accompanied by a non-refundable application fee. A request for variance shall be referred for consideration to the Architectural Review Commission (ARC). The variance procedure shall proceed as follows:
1. Submit a variance application and pay applicable fee. No action shall be taken on any application submitted to the ARC until all applicable fees have been paid in full. No refund of any application fee shall be made after the request has been advertised and scheduled for consideration by the Commission.
 2. Not later than 30 days from date of the application, a quorum of the Architectural Review Commission (ARC) shall convene a meeting to review the variance request;
 3. Public Hearing and Written Notification – No action to approve or deny any application shall be taken until the Commission has held a public hearing and received comment, and only after written notice of the public hearing of the date, time and place where the variance request is to be considered has been sent to the owners of real property lying within two hundred (200) feet of the property where the application is being considered. Such notice shall be given to each property owner as listed on the last approved tax roll not less than ten (10) days before the date set for hearing by depositing letters properly addressed and postage paid in the United States Post Office
 4. Appeal to City Council – The decision by the ARC shall be final, unless the applicant submits a written notice of appeal within ten (10) days from the date of the action by the Commission. The administrative official shall re-notify all property owners lying within two hundred (200) feet of the area being considered and place the applicant's appeal request on the next available agenda for consideration by the City Council.

Section 6.7 6.9 Amendments to This Chapter

Commented [EW8]: Re-number section

Reserved for listing of amendments to this Chapter.

Ord. Number	Date	Subject
O-11-1818	12/13/2011	Amendments to design standards; addition of exterior material and color requirements; amendments to variance procedures and addition of architectural review committee

Ch. 1

* ~~Consideration of what goes to ZBA.~~

* Powers given to ZBA by the authority of City Council.

* Notification distance (300-1000)

- Applicant option
- Zoning case example
- Supermajority requirement

Ch. 3

* Pool/Pond fencing requirements

* PUD - open space requirement - 20%?

* Alcohol ratio

* Building score calc

* PUDs - district, overlay??
standards

* Large commercial buildings


* Perimeter Subdivision fences
- ROW set back

* Accessory structures - # of total?
- exception for large lots?

* Residential Carport Regs

* Parking requirements / Staff authority on reduction

Notification Map




DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

ZC18-002


1312 John McCain Road

-  Subject Property
-  200ft Buffer
-  Properties within 200ft



OBJECTID	Owner_Name	Owner_Addr	Owner_City	Owner_Zip	Situs_Addr
1	MOON, KENNETH W	1305 BELLEFONTE LN	COLLEYVILLE, TX	76034	1305 BELLEFONTE LN
2	COLE, HENRY TR	7206 BELLE MEADE DR	COLLEYVILLE, TX	76034	7206 BELLE MEADE DR
3	PEARCE, CHARLES A	7212 HOLLY LN	COLLEYVILLE, TX	76034	7212 HOLLY LN N
4	BRADEN, KENNETH A	1307 BELLEFONTE LN	COLLEYVILLE, TX	76034	1307 BELLEFONTE LN
5	ALLEN, MARK C	7305 TRIANON CT	COLLEYVILLE, TX	76034	7305 TRIANON CT
6	BRUNKEN, JOHN	7204 BELLE MEADE DR	COLLEYVILLE, TX	76034	7204 BELLE MEADE DR
7	TANGLEWOOD ESTATES HOA	7321 TRIANON CT	COLLEYVILLE, TX	76034	7107 TRIANON CT
8	FONVILLE, EARL R	1403 BELLEFONTE LN	COLLEYVILLE, TX	76034	1403 BELLEFONTE LN
9	HEFLIN, JUD	1407 BELLEFONTE LN	COLLEYVILLE, TX	76034	1407 BELLEFONTE LN
10	TANGLEWOOD ESTATES HOA	7321 TRIANON CT	COLLEYVILLE, TX	76034	7101 JOHN MCCAIN RD
11	HUFFMAN, JERRY M	7309 TRIANON CT	COLLEYVILLE, TX	76034	7309 TRIANON CT
12	TANGLEWOOD ESTATES MAINT	7321 TRIANON CT	COLLEYVILLE, TX	76034	7300 TRIANON CT
13	DAVIDSON, RICHARD	7304 HIX CT	COLLEYVILLE, TX	76034	7304 HIX CT
14	FLEMING, BRYAN A	7312 HIX CT	COLLEYVILLE, TX	76034	7312 HIX CT
15	PERONE, JOHN A	1216 HOLLY LN	COLLEYVILLE, TX	76034	1216 HOLLY LN N
16	ST CLAIR, DAVID J	1401 BELLEFONTE LN	COLLEYVILLE, TX	76034	1401 BELLEFONTE LN
17	TANGLEWOOD ESTATES MAINT	7321 TRIANON CT	COLLEYVILLE, TX	76034	7215 TRIANON CT
18	TANGLEWOOD ESTATES MAINT	7321 TRIANON CT	COLLEYVILLE, TX	76034	7217 TRIANON CT
19	MADY, CONSTANCE E	7301 TRIANON CT	COLLEYVILLE, TX	76034	7301 TRIANON CT
20	BOTIK, DON	7208 TRIANON CT	COLLEYVILLE, TX	76034	7208 TRIANON CT
21	SPENCER, MARC	1309 BELLEFONTE LN	COLLEYVILLE, TX	76034	1309 BELLEFONTE LN
22	COLLINS, BURK	1840 NORWOOD PLZ STE 101	HURST, TX	76054	7309 HOLLY LN N
23	VENNEMEYER, MICHAEL	7212 TRIANON CT	COLLEYVILLE, TX	76034	7212 TRIANON CT
24	NOWOTNIK, DAVID	1405 BELLEFONTE LN	COLLEYVILLE, TX	76034	1405 BELLEFONTE LN
25	PISTOR, ELISE A	7200 HOLLY LN	COLLEYVILLE, TX	76034	7200 HOLLY LN N
26	RIGNEY, THOMAS	7308 HIX CT	COLLEYVILLE, TX	76034	7308 HIX CT
27	PERONE, JOHN A	1216 HOLLY LN	COLLEYVILLE, TX	76034	1220 HOLLY LN N
28	COLLINS, BURK	1840 NORWOOD PLZ STE 101	HURST, TX	76054	1312 JOHN MCCAIN RD
29	TANGLEWOOD ESTATES MAINT	7321 TRIANON CT	COLLEYVILLE, TX	76034	7105 JOHN MCCAIN RD
30	JEANES, FREDRIC M	7200 BELLE MEADE DR	COLLEYVILLE, TX	76034	7200 BELLE MEADE DR
31	TANGLEWOOD ESTATES HOA	7321 TRIANON CT	COLLEYVILLE, TX	76034	7103 TRIANON CT
32	URRUTIA, MICHAEL	1311 BELLEFONTE LN	COLLEYVILLE, TX	76034	1311 BELLEFONTE LN
33	GRANT, RICHARD	1304 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	1304 JOHN MCCAIN RD
34	ST MARY'S COPTIC ORTHODOX C	1110 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	1300 JOHN MCCAIN RD
35	TANGLEWOOD ESTATES HOA	7321 TRIANON CT	COLLEYVILLE, TX	76034	7109 TRIANON CT
36	FONNER, ALAN D	7320 TRIANON CT	COLLEYVILLE, TX	76034	7320 TRIANON CT
37	GOTTFREDSON, MARK ALAN	7321 TRIANON CT	COLLEYVILLE, TX	76034	7317 TRIANON CT
38	WASHINGTON, DAVID	7309 HIX CT	COLLEYVILLE, TX	76034	7300 HIX CT
39	SMITH, NANCY BURSCH	7202 BELLE MEADE DR	COLLEYVILLE, TX	76034	7202 BELLE MEADE DR
40	KAUFFMAN, KURT H	1208 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	7150 EVANS RD
41	TIMARRON GOLF CLUB INC	3030 L B J FWY STE 600	DALLAS, TX	75234	201 E CONTINENTAL BLVD
42	CHEATWOOD, CHRIS	7313 TRIANON CT	COLLEYVILLE, TX	76034	7313 TRIANON CT
43	BRADSHAW, F THOMAS	7316 TRIANON CT	COLLEYVILLE, TX	76034	7316 TRIANON CT
44	HUDSON, LEONARD	7201 TRIANON CT	COLLEYVILLE, TX	76034	7201 TRIANON CT
45	CALDWELL'S CREEK ADDITION	P.O. Box 682	COLLEYVILLE, TX	76034	COURTESY NOTICE
46	PEBBLE HILL PLANTATION ESTAT	P.O. Box 911	COLLEYVILLE, TX	76034	COURTESY NOTICE
47	CARROLL ISD				STATE REQUIRES
48	GRAPEVINE COLLEYVILLE ISD				STATE REQUIRES

Notification Map



ZC18-002

1312 John McCain Road


DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

-  Subject Property
-  300ft Buffer
-  Properties within 300ft



OBJECTID	Owner_Name	Owner_Addr	Owner_City	Owner_Zip	Situs_Addr
1	MOON, KENNETH W	1305 BELLEFONTE LN	COLLEYVILLE, TX	76034	1305 BELLEFONTE LN
2	COLE, HENRY TR	7206 BELLE MEADE DR	COLLEYVILLE, TX	76034	7206 BELLE MEADE DR
3	PEARCE, CHARLES A	7212 HOLLY LN	COLLEYVILLE, TX	76034	7212 HOLLY LN N
4	BRADEN, KENNETH A	1307 BELLEFONTE LN	COLLEYVILLE, TX	76034	1307 BELLEFONTE LN
5	ALLEN, MARK C	7305 TRIANON CT	COLLEYVILLE, TX	76034	7305 TRIANON CT
6	FEAGAN, DENNIS J	1303 BELLEFONTE LN	COLLEYVILLE, TX	76034	1303 BELLEFONTE LN
7	BRUNKEN, JOHN	7204 BELLE MEADE DR	COLLEYVILLE, TX	76034	7204 BELLE MEADE DR
8	MEANS, BRADLEY W	7007 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	7007 WHIPPOORWILL CT
9	TANGLEWOOD ESTATES HOA	7321 TRIANON CT	COLLEYVILLE, TX	76034	7107 TRIANON CT
10	SAYRE, LARRY W	7300 BELLE MEADE DR	COLLEYVILLE, TX	76034	7300 BELLE MEADE DR
11	FONVILLE, EARL R	1403 BELLEFONTE LN	COLLEYVILLE, TX	76034	1403 BELLEFONTE LN
12	LINK, SCOTT A	7009 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7009 ORCHARD HILL CT
13	HEFLIN, JUD	1407 BELLEFONTE LN	COLLEYVILLE, TX	76034	1407 BELLEFONTE LN
14	TANGLEWOOD ESTATES HOA	7321 TRIANON CT	COLLEYVILLE, TX	76034	7101 JOHN MCCAIN RD
15	JANOSKY, JANE AMBER	7008 LISMORE CT	COLLEYVILLE, TX	76034	7008 LISMORE CT
16	HUFFMAN, JERRY M	7309 TRIANON CT	COLLEYVILLE, TX	76034	7309 TRIANON CT
17	TANGLEWOOD ESTATES MAINT E	7321 TRIANON CT	COLLEYVILLE, TX	76034	7300 TRIANON CT
18	DAVIDSON, RICHARD	7304 HIX CT	COLLEYVILLE, TX	76034	7304 HIX CT
19	FLEMING, BRYAN A	7312 HIX CT	COLLEYVILLE, TX	76034	7312 HIX CT
20	PERONE, JOHN A	1216 HOLLY LN	COLLEYVILLE, TX	76034	1216 HOLLY LN N
21	ST CLAIR, DAVID J	1401 BELLEFONTE LN	COLLEYVILLE, TX	76034	1401 BELLEFONTE LN
22	TANGLEWOOD ESTATES MAINT E	7321 TRIANON CT	COLLEYVILLE, TX	76034	7215 TRIANON CT
23	EUBANKS, JOHN T	7009 LISMORE CT	COLLEYVILLE, TX	76034	7009 LISMORE CT
24	TANGLEWOOD ESTATES MAINT E	7321 TRIANON CT	COLLEYVILLE, TX	76034	7217 TRIANON CT
25	MADY, CONSTANCE E	7301 TRIANON CT	COLLEYVILLE, TX	76034	7301 TRIANON CT
26	HAMILTON, ROBERT A	7306 BELLE MEADE DR	COLLEYVILLE, TX	76034	7306 BELLE MEADE DR
27	BOTIK, DON	7208 TRIANON CT	COLLEYVILLE, TX	76034	7208 TRIANON CT
28	SPENCER, MARC	1309 BELLEFONTE LN	COLLEYVILLE, TX	76034	1309 BELLEFONTE LN
29	COLLINS, BURK	1840 NORWOOD PLZ STE 101	HURST, TX	76054	7309 HOLLY LN N
30	VENNEMEYER, MICHAEL	7212 TRIANON CT	COLLEYVILLE, TX	76034	7212 TRIANON CT
31	NOWOTNIK, DAVID	1405 BELLEFONTE LN	COLLEYVILLE, TX	76034	1405 BELLEFONTE LN
32	PURDY, DONALD	7009 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	7009 WHIPPOORWILL CT
33	PISTOR, ELISE A	7200 HOLLY LN	COLLEYVILLE, TX	76034	7200 HOLLY LN N
34	QUAID CHRISTINE LIVING TRUST	7208 BELLE MEADE DR	COLLEYVILLE, TX	76034	7208 BELLE MEADE DR
35	PREWITT, RICHARD	1409 BELLEFONTE LN	COLLEYVILLE, TX	76034	1409 BELLEFONTE LN
36	CONROY, MICHAEL R	7010 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7010 ORCHARD HILL CT
37	RIGNEY, THOMAS	7308 HIX CT	COLLEYVILLE, TX	76034	7308 HIX CT
38	NAULT, MICHAEL J	7304 BELLE MEADE DR	COLLEYVILLE, TX	76034	7304 BELLE MEADE DR
39	PERONE, JOHN A	1216 HOLLY LN	COLLEYVILLE, TX	76034	1220 HOLLY LN N
40	COLLINS, BURK	1840 NORWOOD PLZ STE 101	HURST, TX	76054	1312 JOHN MCCAIN RD
41	TANGLEWOOD ESTATES MAINT A	7321 TRIANON CT	COLLEYVILLE, TX	76034	7105 JOHN MCCAIN RD
42	JEANES, FREDRIC M	7200 BELLE MEADE DR	COLLEYVILLE, TX	76034	7200 BELLE MEADE DR
43	SHERMAN, THOMAS C	7108 BELLE MEADE DR	COLLEYVILLE, TX	76034	7108 BELLE MEADE DR
44	TANGLEWOOD ESTATES HOA	7321 TRIANON CT	COLLEYVILLE, TX	76034	7103 TRIANON CT
45	URRUTIA, MICHAEL	1311 BELLEFONTE LN	COLLEYVILLE, TX	76034	1311 BELLEFONTE LN
46	GRANT, RICHARD	1304 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	1304 JOHN MCCAIN RD
47	ST MARY'S COPTIC ORTHODOX C	1110 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	1300 JOHN MCCAIN RD
48	GOTTFREDSON, MARK A	7321 TRIANON CT	COLLEYVILLE, TX	76034	7321 TRIANON CT
49	TANGLEWOOD ESTATES HOA	7321 TRIANON CT	COLLEYVILLE, TX	76034	7109 TRIANON CT
50	PARK, DANIEL	7011 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7011 ORCHARD HILL CT
51	FONNER, ALAN D	7320 TRIANON CT	COLLEYVILLE, TX	76034	7320 TRIANON CT
52	GOTTFREDSON, MARK ALAN	7321 TRIANON CT	COLLEYVILLE, TX	76034	7317 TRIANON CT
53	WASHINGTON, DAVID	7300 HIX CT	COLLEYVILLE, TX	76034	7300 HIX CT
54	LEACH, JOHN E	7302 BELLE MEADE DR	COLLEYVILLE, TX	76034	7302 BELLE MEADE DR
55	SMITH, NANCY BURSCH	7202 BELLE MEADE DR	COLLEYVILLE, TX	76034	7202 BELLE MEADE DR
56	KAUFFMAN, KURT H	1208 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	7150 EVANS RD
57	TIMARRON GOLF CLUB INC	3030 L B J FWY STE 600	DALLAS, TX	75234	201 E CONTINENTAL BLVD
58	UNIQUE LANDSCAPING DESIGN &	7111 COLLYVILLE BLVD # TX	COLLEYVILLE, TX	76034	7151 EVANS RD
59	CHEATWOOD, CHRIS	7313 TRIANON CT	COLLEYVILLE, TX	76034	7313 TRIANON CT
60	BRADSHAW, F THOMAS	7316 TRIANON CT	COLLEYVILLE, TX	76034	7316 TRIANON CT
61	HUDSON, LEONARD	7201 TRIANON CT	COLLEYVILLE, TX	76034	7201 TRIANON CT
62	CALDWELL'S CREEK ADDITION	P.O. Box 682	COLLEYVILLE, TX	76034	COURTESY NOTICE
63	PEBBLE HILL PLANTATION ESTAT	P.O. Box 911	COLLEYVILLE, TX	76034	COURTESY NOTICE
64	CARROLL ISD				STATE REQUIRES
65	GRAPEVINE COLLEYVILLE ISD				STATE REQUIRES

Notification Map




ZC18-002


1312 John McCain Road

DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

-  Subject Property
-  500ft Buffer
-  Properties within 500ft



Notification Map




ZC18-002

1312 John McCain Road

DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.


-  Subject Property
-  1000ft Buffer
-  Properties within 1000ft



OBJECTID	Owner_Name	Owner_Addr	Owner_City	Owner_Zip	Situs_Addr
1	MOON, KENNETH W	1305 BELLEFONTE LN	COLLEYVILLE, TX	76034	1305 BELLEFONTE LN
2	LEVINSON, BRUCE A	7000 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	7000 WHIPPOORWILL CT
3	COLE, HENRY TR	7206 BELLE MEADE DR	COLLEYVILLE, TX	76034	7206 BELLE MEADE DR
4	PEARCE, CHARLES A	7212 HOLLY LN	COLLEYVILLE, TX	76034	7212 HOLLY LN N
5	STONES, BLAKE R	7301 CEDAR CT	COLLEYVILLE, TX	76034	7301 CEDAR CT
6	BALL, MARK L	7003 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	7003 WHIPPOORWILL CT
7	BRADEN, KENNETH A	1307 BELLEFONTE LN	COLLEYVILLE, TX	76034	1307 BELLEFONTE LN
8	SISODIYA, KAMLESH	7003 GLADWYNE CT	COLLEYVILLE, TX	76034	7003 GLADWYNE CT
9	WARREN, MARK	7207 BELLE MEADE DR	COLLEYVILLE, TX	76034	7207 BELLE MEADE DR
10	WOOD, GAYLE S	7020 ROSEBROOK	COLLEYVILLE, TX	76034	7020 ROSEBROOK
11	DICARO, JOSEPH B	7006 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7006 ORCHARD HILL CT
12	SEXTON, KIMBERLY K	7001 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	7001 WHIPPOORWILL CT
13	KAUFFMAN, KURT H	1208 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	7198 EVANS RD
14	ALLEN, MARK C	7305 TRIANON CT	COLLEYVILLE, TX	76034	7305 TRIANON CT
15	PHILLIPS, RAMON D	7024 ROSEBROOK	COLLEYVILLE, TX	76034	7024 ROSEBROOK
16	STEPHENS, JOHN W	7208 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7208 PEBBLE HILL DR
17	FEGAN, DENNIS J	1303 BELLEFONTE LN	COLLEYVILLE, TX	76034	1303 BELLEFONTE LN
18	TANGLEWOOD ESTATES HOA	7321 TRIANON CT	COLLEYVILLE, TX	76034	7219 TRIANON CT
19	CALVERY, CRAIG R	7002 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	7002 WHIPPOORWILL CT
20	BRUNKEN, JOHN	7204 BELLE MEADE DR	COLLEYVILLE, TX	76034	7204 BELLE MEADE DR
21	BOSCO, RICHARD S	7404 BELLE MEADE DR	COLLEYVILLE, TX	76034	7404 BELLE MEADE DR
22	FILIPPI, RICHARD A	7206 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7206 PEBBLE HILL DR
23	ST MARY'S COPTIC ORTHODOX C	1110 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	1110 JOHN MCCAIN RD
24	MUNNELL, NANCY	7207 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7207 PEBBLE HILL DR
25	MAHMUD, FARHAT P	7002 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7002 ORCHARD HILL CT
26	RALPH, MICHAEL J	7003 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7003 ORCHARD HILL CT
27	MEANS, BRADLEY W	7007 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	7007 WHIPPOORWILL CT
28	AKSAMIT, PAUL V	7036 ROSEBROOK	COLLEYVILLE, TX	76034	7036 ROSEBROOK
29	COURCIER, STEVEN	7204 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7204 PEBBLE HILL DR
30	FROHM, ROBERT M	7008 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7008 ORCHARD HILL CT
31	ALEXANDER, CHARLES	7009 SHEPHERDS GLN	COLLEYVILLE, TX	76034	7009 SHEPHERDS GLEN
32	MCEACHERN, JASON	6905 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	6905 WHIPPOORWILL CT
33	TANGLEWOOD ESTATES HOA	7321 TRIANON CT	COLLEYVILLE, TX	76034	7107 TRIANON CT
34	CALDWELL'S CREEK LTD	PO BOX 611	COLLEYVILLE, TX	76034	1599 JOHN MCCAIN RD
35	UPHAM, CLIFTON	1204 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	1204 JOHN MCCAIN RD
36	SAYRE, LARRY W	7300 BELLE MEADE DR	COLLEYVILLE, TX	76034	7300 BELLE MEADE DR
37	AFKAMI, NARGES	7203 BELLE MEADE DR	COLLEYVILLE, TX	76034	7203 BELLE MEADE DR
38	SELLERS, FRANK DAVID BUD	7004 ROSEBROOK	COLLEYVILLE, TX	76034	7004 ROSEBROOK
39	CHINNI, SAKETH	7012 SHALIMAR CT	COLLEYVILLE, TX	76034	7012 SHALIMAR CT
40	CARBONARI, JOHN P	6907 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	6907 WHIPPOORWILL CT
41	KELLEY, KEVIN	7002 GLADWYNE CT	COLLEYVILLE, TX	76034	7002 GLADWYNE CT
42	ZHOU, YUCAI	7005 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7005 ORCHARD HILL CT
43	GUERNEY, PAUL R	1507 CALDWELL CREEK DR	COLLEYVILLE, TX	76034	1507 CALDWELL CREEK DR
44	RUBAL, BRIAN J	1401 CALDWELL CREEK DR	COLLEYVILLE, TX	76034	1401 CALDWELL CREEK DR
45	KOCUREK, KATHRYN	7007 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7007 ORCHARD HILL CT
46	PROTONO, MICHAEL	7006 SHEPHERDS GLN	COLLEYVILLE, TX	76034	7006 SHEPHERDS GLEN
47	GOLDSTEIN, JAY L	7011 SHEPHERDS GLN	COLLEYVILLE, TX	76034	7011 SHEPHERDS GLEN
48	ROGERS, BRIAN	7306 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7306 PEBBLE HILL DR
49	FARHAT, GEORGES	7013 SHALIMAR CT	COLLEYVILLE, TX	76034	7013 SHALIMAR CT
50	BALL, DONNA	7305 CEDAR RD	COLLEYVILLE, TX	76034	7305 CEDAR CT
51	DEFEQ, RONALD J	7008 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	7008 WHIPPOORWILL CT
52	FONVILLE, EARL R	1403 BELLEFONTE LN	COLLEYVILLE, TX	76034	1403 BELLEFONTE LN
53	ALJOE, MICHAEL C	7006 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	7006 WHIPPOORWILL CT
54	HAMPTON, W B	1501 CALDWELL CREEK DR	COLLEYVILLE, TX	76034	1501 CALDWELL CREEK DR
55	BERRY, JOEY W	7005 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	7005 WHIPPOORWILL CT
56	KAYEM, SAM A	1513 CALDWELL CREEK DR	COLLEYVILLE, TX	76034	1513 CALDWELL CREEK DR
57	LINK, SCOTT A	7009 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7009 ORCHARD HILL CT
58	BESGROVE, KATHY M	7303 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7303 PEBBLE HILL DR
59	HALL, GORDON J	7009 SHALIMAR CT	COLLEYVILLE, TX	76034	7009 SHALIMAR CT
60	ALLEN, PATRICK	7005 LISMORE CT	COLLEYVILLE, TX	76034	7005 LISMORE CT
61	HEFLIN, JUD	1407 BELLEFONTE LN	COLLEYVILLE, TX	76034	1407 BELLEFONTE LN
62	SLEDGE, CHARLES W	7317 CEDAR CT	COLLEYVILLE, TX	76034	7317 CEDAR CT
63	BHAYANI, NIKHIL	1206 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	1206 JOHN MCCAIN RD
64	GRIMM, DONALD R	7304 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7304 PEBBLE HILL DR
65	OLSON, STEVEN	7203 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7203 PEBBLE HILL DR
66	JONES, GREG R	7305 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7305 PEBBLE HILL DR
67	SEWING, CLIFFORD	7005 SHALIMAR CT	COLLEYVILLE, TX	76034	7005 SHALIMAR CT
68	NOVOTNY, DAVID L	1501 BELLEFONTE LN	COLLEYVILLE, TX	76034	1501 BELLEFONTE LN
69	WINTER, JAMES M	7004 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	7004 WHIPPOORWILL CT
70	CAMPBELL, RICKY J	7205 CEDAR CT	COLLEYVILLE, TX	76034	7205 CEDAR CT
71	GREEN, LINDA K	7205 BELLE MEADE DR	COLLEYVILLE, TX	76034	7205 BELLE MEADE DR
72	DECKER, SCOTT	7032 ROSEBROOK	COLLEYVILLE, TX	76034	7032 ROSEBROOK
73	SHALIMAR HOMEOWNERS ASSO	PO BOX 423	COLLEYVILLE, TX	76034	7020 SHALIMAR CT
74	TANGLEWOOD ESTATES HOA	7321 TRIANON CT	COLLEYVILLE, TX	76034	7101 JOHN MCCAIN RD
75	SCHRECK, STEPHEN J	7000 SHEPHERDS GLEN	COLLEYVILLE, TX	76034	7000 SHEPHERDS GLEN
76	COUSIN, LARRY D	7004 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7004 ORCHARD HILL CT
77	SHANE, PAUL J	1405 CALDWELL CREEK DR	COLLEYVILLE, TX	76034	1405 CALDWELL CREEK DR
78	LEHMAN, KEVIN	7006 LISMORE CT	COLLEYVILLE, TX	76034	7006 LISMORE CT
79	JANOSKY, JANE AMBER	7008 LISMORE CT	COLLEYVILLE, TX	76034	7008 LISMORE CT
80	HUFFMAN, JERRY M	7309 TRIANON CT	COLLEYVILLE, TX	76034	7309 TRIANON CT
81	ANDUJAR, MARCOS	7017 SHALIMAR CT	COLLEYVILLE, TX	76034	7017 SHALIMAR CT
82	WEIR, JOE D	7012 SHEPHERDS GLN	COLLEYVILLE, TX	76034	7012 SHEPHERDS GLEN
83	GENCO, FRANK R	1104 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	1104 JOHN MCCAIN RD
84	JUELE, MARC	501 SYCAMORE LN APT 1025	EULESS, TX	76039	7000 LISMORE CT
85	PINEIDER, PAUL J	1503 CALDWELL CREEK DR	COLLEYVILLE, TX	76034	1503 CALDWELL CREEK DR
86	SIPPLE, GEOFFREY R	7008 ROSEBROOK	COLLEYVILLE, TX	76034	7008 ROSEBROOK
87	ESKANDER, AWAD	1112 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	1112 JOHN MCCAIN RD
88	TANGLEWOOD ESTATES MAINT	7321 TRIANON CT	COLLEYVILLE, TX	76034	7300 TRIANON CT
89	STEINBERG, JAMISON	7004 LISMORE CT	COLLEYVILLE, TX	76034	7004 LISMORE CT
90	DAVIDSON, RICHARD	7304 HIX CT	COLLEYVILLE, TX	76034	7304 HIX CT
91	REISLING, MAX G	7007 LISMORE CT	COLLEYVILLE, TX	76034	7007 LISMORE CT
92	MARSHALL, ERIC J	1503 BELLEFONTE LN	COLLEYVILLE, TX	76034	1503 BELLEFONTE LN
93	PITZER, RODNEY	7002 LISMORE CT	COLLEYVILLE, TX	76034	7002 LISMORE CT
94	FLEMING, BRYAN A	7312 HIX CT	COLLEYVILLE, TX	76034	7312 HIX CT
95	PERONE, JOHN A	1216 HOLLY LN	COLLEYVILLE, TX	76034	1216 HOLLY LN N
96	SHAH, NADIA	7209 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7209 PEBBLE HILL DR
97	JOHNSON, BRENT JOSEPH	7209 BELLE MEADE DR	COLLEYVILLE, TX	76034	7209 BELLE MEADE DR
98	MOSS, JOSEPH	7016 SHALIMAR CT	COLLEYVILLE, TX	76034	7016 SHALIMAR CT
99	ST CLAIR, DAVID J	1401 BELLEFONTE LN	COLLEYVILLE, TX	76034	1401 BELLEFONTE LN
100	TANGLEWOOD ESTATES MAINT	7321 TRIANON CT	COLLEYVILLE, TX	76034	7215 TRIANON CT
101	EUBANKS, JOHN T	7009 LISMORE CT	COLLEYVILLE, TX	76034	7009 LISMORE CT
102	SHALIMAR HOMEOWNERS ASSO	PO BOX 423	COLLEYVILLE, TX	76034	7006 SHALIMAR CT
103	STRICKLAND, LARRY G	7007 SHEPHERDS GLN	COLLEYVILLE, TX	76034	7007 SHEPHERDS GLEN
104	WEBBER, BRENNAN	7307 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7307 PEBBLE HILL DR
105	SONNEBORN, WALTER	1403 CALDWELL CREEK DR	COLLEYVILLE, TX	76034	1403 CALDWELL CREEK DR
106	ZAMBORY, JOHN M	7003 SHEPHERDS GLN	COLLEYVILLE, TX	76034	7003 SHEPHERDS GLEN

107	TANGLEWOOD ESTATES MAINT	7321 TRIANON CT	COLLEYVILLE, TX	76034	7217 TRIANON CT
108	MADY, CONSTANCE E	7301 TRIANON CT	COLLEYVILLE, TX	76034	7301 TRIANON CT
109	MAY, MIKE	1409 CALDWELL CREEK DR	COLLEYVILLE, TX	76034	1409 CALDWELL CREEK DR
110	KING, JAMES	6906 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	6906 WHIPPOORWILL CT
111	GUMM, CLAYTON C	6907 SHEPHERDS GLEN	COLLEYVILLE, TX	76034	6907 SHEPHERDS GLEN
112	THERRIEN, CHRISTOPHER	7013 SHEPHERDS GLEN	COLLEYVILLE, TX	76034	7013 SHEPHERDS GLEN
113	HILLSIDE CAPITAL PARTNERS LL	7278 GLENVIEW DR	NORTH RICHLAND HILLS, TX	76180	7008 SHEPHERDS GLEN
114	HOLLAND, H BRIAN	6909 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	6909 WHIPPOORWILL CT
115	NEWTON, RICHARD W	1208 HOLLY LN	COLLEYVILLE, TX	76034	1208 HOLLY LN N
116	SHALIMAR HOMEOWNERS ASSO	PO BOX 423	COLLEYVILLE, TX	76034	6700 SHALIMAR CT
117	SACKSON, TIMOTHY M	1511 CALDWELL CREEK DR	COLLEYVILLE, TX	76034	1511 CALDWELL CREEK DR
118	ACOVENO, JOE F	7309 CEDAR CT	COLLEYVILLE, TX	76034	7309 CEDAR CT
119	ROLLINS, DAVID	1407 CALDWELL CREEK DR	COLLEYVILLE, TX	76034	1407 CALDWELL CREEK DR
120	MCCARTHY, AINE	7004 SHEPHERDS GLN	COLLEYVILLE, TX	76034	7004 SHEPHERDS GLEN
121	VEERAPPAN, BALAJI	7005 SHEPHERDS GLN	COLLEYVILLE, TX	76034	7005 SHEPHERDS GLEN
122	SHEPARD, CHARLES	7309 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7309 PEBBLE HILL DR
123	MAYFIELD, RALPH	7403 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7403 PEBBLE HILL DR
124	STOKES, RICKY L	7303 BELLE MEADE DR	COLLEYVILLE, TX	76034	7303 BELLE MEADE DR
125	VERGARA, RICARDO	6910 SHEPHERDS GLN	COLLEYVILLE, TX	76034	6910 SHEPHERDS GLEN
126	HAMILTON, ROBERT A	7306 BELLE MEADE DR	COLLEYVILLE, TX	76034	7306 BELLE MEADE DR
127	FAIS, WILLIAM C	7302 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7302 PEBBLE HILL DR
128	LEEPER, JOHN A	7401 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7401 PEBBLE HILL DR
129	PITZELE, BRAD	7106 BELLE MEADE DR	COLLEYVILLE, TX	76034	7106 BELLE MEADE DR
130	GAMMON, ROBERT J	PO BOX 794	COLLEYVILLE, TX	76034	7205 PEBBLE HILL DR
131	BOTIK, DON	7208 TRIANON CT	COLLEYVILLE, TX	76034	7208 TRIANON CT
132	SPENCER, MARC	1309 BELLEFONTE LN	COLLEYVILLE, TX	76034	1309 BELLEFONTE LN
133	APODACA, SANTIAGO	7003 LISMORE CT	COLLEYVILLE, TX	76034	7003 LISMORE CT
134	SCHON REVOCABLE TRUST	7004 GLADWYNE CT	COLLEYVILLE, TX	76034	7004 GLADWYNE CT
135	COLLINS, BURK	1840 NORWOOD PLZ STE 101	HURST, TX	76054	7309 HOLLY LN N
136	VENNEMEYER, MICHAEL	7212 TRIANON CT	COLLEYVILLE, TX	76034	7212 TRIANON CT
137	WEBER, GLENN C	7028 ROSEBROOK	COLLEYVILLE, TX	76034	7028 ROSEBROOK
138	TRENOR, GREGG	7405 JO WILL ST	COLLEYVILLE, TX	76034	7405 JO WILL ST
139	CALDWELL'S CREEK HMNOWRS	1503 BELLEFONTE LN	COLLEYVILLE, TX	76034	6800 SHEPHERDS GLEN # B
140	PALLUTH, EDWARD	1212 HOLLY LN	COLLEYVILLE, TX	76034	1212 HOLLY LN N
141	BARNHART, TERRY D	1116 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	1116 JOHN MCCAIN RD
142	SEIFERT, NELDA E	2849 VOLTERRA WAY	KELLER, TX	76248	7012 ROSEBROOK
143	NOWOTNIK, DAVID	1405 BELLEFONTE LN	COLLEYVILLE, TX	76034	1405 BELLEFONTE LN
144	STONES, BLAKE R	7308 CEDAR CT	COLLEYVILLE, TX	76034	7308 CEDAR CT
145	CARR, MICHAEL PARTIRCK	7002 SHEPHERDS GLN	COLLEYVILLE, TX	76034	7002 SHEPHERDS GLEN
146	FEDAK, JAN	7301 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7301 PEBBLE HILL DR
147	PURDY, DONALD	7009 WHIPPOORWILL CT	COLLEYVILLE, TX	76034	7009 WHIPPOORWILL CT
148	PISTOR, ELISE A	7200 HOLLY LN	COLLEYVILLE, TX	76034	7200 HOLLY LN N
149	DELAHOZ, ALFONSO	7005 GLADWYNE CT	COLLEYVILLE, TX	76034	7005 GLADWYNE CT
150	BRAASCH, ROBERT M	7001 SHEPHERDS GLN	COLLEYVILLE, TX	76034	7001 SHEPHERDS GLEN
151	QUAD CHRISTINE LIVING TRUST	7208 BELLE MEADE DR	COLLEYVILLE, TX	76034	7208 BELLE MEADE DR
152	PREWITT, RICHARD	1409 BELLEFONTE LN	COLLEYVILLE, TX	76034	1409 BELLEFONTE LN
153	GRAY, TRAVIS P	7407 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7407 PEBBLE HILL DR
154	MURRAY, MICHAEL J	7300 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7300 PEBBLE HILL DR
155	TRUJILLO, IVAN	7010 SHEPHERDS GLN	COLLEYVILLE, TX	76034	7010 SHEPHERDS GLEN
156	CONROY, MICHAEL R	7010 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7010 ORCHARD HILL CT
157	RIGNEY, THOMAS	7308 HIX CT	COLLEYVILLE, TX	76034	7308 HIX CT
158	SHALIMAR HOMEOWNERS ASSO	PO BOX 423	COLLEYVILLE, TX	76034	7014 SHALIMAR CT
159	STOLFI, DAVID F	7001 GLADWYNE CT	COLLEYVILLE, TX	76034	7001 GLADWYNE CT
160	NAULT, MICHAEL J	7304 BELLE MEADE DR	COLLEYVILLE, TX	76034	7304 BELLE MEADE DR
161	FINDLEY, DAVID V	7016 ROSEBROOK	COLLEYVILLE, TX	76034	7016 ROSEBROOK
162	PERONE, JOHN A	1216 HOLLY LN	COLLEYVILLE, TX	76034	1220 HOLLY LN N
163	COLLINS, BURK	1840 NORWOOD PLZ STE 101	HURST, TX	76054	1312 JOHN MCCAIN RD
164	ROBBINS, MARK B	7327 CEDAR CT	COLLEYVILLE, TX	76034	7327 CEDAR CT
165	TANGLEWOOD ESTATES MAINT	7321 TRIANON CT	COLLEYVILLE, TX	76034	7105 JOHN MCCAIN RD
166	BYERLY, JEFFREY S	7109 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7109 PEBBLE HILL DR
167	JEANES, FREDRIC M	7200 BELLE MEADE DR	COLLEYVILLE, TX	76034	7200 BELLE MEADE DR
168	BUTLER, BARTLEY	1509 CALDWELL CREEK DR	COLLEYVILLE, TX	76034	1509 CALDWELL CREEK DR
169	KEY, MARGE A	7405 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7405 PEBBLE HILL DR
170	SHERMAN, THOMAS C	7108 BELLE MEADE DR	COLLEYVILLE, TX	76034	7108 BELLE MEADE DR
171	TANGLEWOOD ESTATES HOA	7321 TRIANON CT	COLLEYVILLE, TX	76034	7103 TRIANON CT
172	URRUTIA, MICHAEL	1311 BELLEFONTE LN	COLLEYVILLE, TX	76034	1311 BELLEFONTE LN
173	BHATKI, LEAH S	7323 CEDAR CT	COLLEYVILLE, TX	76034	7323 CEDAR CT
174	GRANT, RICHARD	1304 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	1304 JOHN MCCAIN RD
175	ST MARY'S COPTIC ORTHODOX C	1110 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	1300 JOHN MCCAIN RD
176	KAUFFMAN, KURT H	1208 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	7198 EVANS RD
177	CONNELL, BERNARD	7001 SHALIMAR CT	COLLEYVILLE, TX	76034	7001 SHALIMAR CT
178	GOTTFREDSON, MARK A	7321 TRIANON CT	COLLEYVILLE, TX	76034	7321 TRIANON CT
179	VILLAS AT CALDWELL CREEK HO	PO BOX 293	COLLEYVILLE, TX	76034	7040 ROSEBROOK
180	TANGLEWOOD ESTATES HOA	7321 TRIANON CT	COLLEYVILLE, TX	76034	7109 TRIANON CT
181	SHALIMAR HOMEOWNERS ASSO	PO BOX 423	COLLEYVILLE, TX	76034	7018 SHALIMAR CT
182	EKSTAM, CHRISTOPHER L	7315 HIX CT	COLLEYVILLE, TX	76034	7315 HIX CT
183	DEPUJE, EDWARD	1505 CALDWELL CREEK DR	COLLEYVILLE, TX	76034	1505 CALDWELL CREEK DR
184	AGHAZADEH, JENNIFER	7000 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7000 ORCHARD HILL CT
185	PARK, DANIEL	7011 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7011 ORCHARD HILL CT
186	FONNER, ALAN D	7320 TRIANON CT	COLLEYVILLE, TX	76034	7320 TRIANON CT
187	CHANDLER, JUDITH D	7001 LISMORE CT	COLLEYVILLE, TX	76034	7001 LISMORE CT
188	GOTTFREDSON, MARK ALAN	7321 TRIANON CT	COLLEYVILLE, TX	76034	7317 TRIANON CT
189	STREIT, PETER NORBERT	7000 GLADWYNE CT	COLLEYVILLE, TX	76034	7000 GLADWYNE CT
190	SCHWINDT, MICHAEL	7301 BELLE MEADE DR	COLLEYVILLE, TX	76034	7301 BELLE MEADE DR
191	BROWN, ORVAL	7402 BELLE MEADE DR	COLLEYVILLE, TX	76034	7402 BELLE MEADE DR
192	WASHINGTON, DAVID	7300 HIX CT	COLLEYVILLE, TX	76034	7300 HIX CT
193	KOPER, DENNIS	7331 CEDAR CT	COLLEYVILLE, TX	76034	7331 CEDAR CT
194	STITES, ASHLEE	7001 ORCHARD HILL CT	COLLEYVILLE, TX	76034	7001 ORCHARD HILL CT
195	QUINN, GARRY	7107 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7107 PEBBLE HILL DR
196	CALDWELL'S CREEK HMNOWRS	1503 BELLEFONTE LN	COLLEYVILLE, TX	76034	1515 CALDWELL CREEK DR
197	KAUFFMAN, KURT H	1208 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	7198 EVANS RD
198	MEHAN, COURTNEY E	6917 SHALIMAR CT	COLLEYVILLE, TX	76034	6917 SHALIMAR CT
199	GLENN, WILLIAM DANIEL	7312 CEDAR CT	COLLEYVILLE, TX	76034	7312 CEDAR CT
200	LEACH, JOHN E	7302 BELLE MEADE DR	COLLEYVILLE, TX	76034	7302 BELLE MEADE DR
201	SMITH, NANCY BURSCH	7202 BELLE MEADE DR	COLLEYVILLE, TX	76034	7202 BELLE MEADE DR
202	KAUFFMAN, KURT H	1208 JOHN MCCAIN RD	COLLEYVILLE, TX	76034	7150 EVANS RD
203	BROUSSARD, JAMES C	7201 PEBBLE HILL DR	COLLEYVILLE, TX	76034	7201 PEBBLE HILL DR
204	KHAN, ATIQUE A	7308 BELLE MEADE DR	COLLEYVILLE, TX	76034	7308 BELLE MEADE DR
205	SHALIMAR HOMEOWNERS ASSO	PO BOX 423	COLLEYVILLE, TX	76034	7021 SHALIMAR CT
206	TIMARRON GOLF CLUB INC	3030 L B J FWY STE 600	DALLAS, TX	75234	201 E CONTINENTAL BLVD
207	UNIQUE LANDSCAPING DESIGN &	7111 COLLYVILLE BLVD # TX	COLLEYVILLE, TX	76034	7151 EVANS RD
208	BROWN, RODNEY	7400 BELLE MEADE DR	COLLEYVILLE, TX	76034	7400 BELLE MEADE DR
209	CHEATWOOD, CHRIS	7313 TRIANON CT	COLLEYVILLE, TX	76034	7313 TRIANON CT
210	PARKER, ROBERT A	6904 SHEPHERDS GLN	COLLEYVILLE, TX	76034	6904 SHEPHERDS GLEN
211	RAMAN CHANDLER PROPERTIES	PO BOX 611	COLLEYVILLE, TX	76034	7030 ROSEBROOK
212	BRADSHAW, F THOMAS	7316 TRIANON CT	COLLEYVILLE, TX	76034	7316 TRIANON CT
213	HUDSON, LEONARD	7201 TRIANON CT	COLLEYVILLE, TX	76034	7201 TRIANON CT
214	CALDWELL'S CREEK ADDITION	P.O. Box 682	COLLEYVILLE, TX	76034	COURTESY NOTICE
215	PEBBLE HILL PLANTATION ESTAT	P.O. Box 911	COLLEYVILLE, TX	76034	COURTESY NOTICE
216	CARROLL ISD				STATE REQUIRES
217	GRAPEVINE COLLEYVILLE ISD				STATE REQUIRES

Notification Map



ZC18-007

2313 Hall Johnson Road


DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

-  Subject Property
-  200ft Buffer
-  Properties within 200ft



OBJECTID	Owner_Name	Owner_Addr	Owner_City	Owner_Zip	Situs_Addr
1	SHARP, JOHN R	5605 SYCAMORE DR	COLLEYVILLE, TX	76034	5605 SYCAMORE DR
2	KELLY, IAN	2301 BALLANTRAE DR	COLLEYVILLE, TX	76034	2301 BALLANTRAE DR
3	PHELAN, A J	2307 BALLANTRAE DR	COLLEYVILLE, TX	76034	2307 BALLANTRAE DR
4	ZHU, JUN	5705 SYCAMORE DR	COLLEYVILLE, TX	76034	5705 SYCAMORE DR
5	JAY, JOHN	2309 HALL JOHNSON RD	COLLEYVILLE, TX	76034	2309 HALL JOHNSON RD
6	NORTHEAST PROPERTIES INC	PO BOX 611	COLLEYVILLE, TX	76034	2319 HALL JOHNSON RD
7	BROWN, LARRY	5603 SYCAMORE DR	COLLEYVILLE, TX	76034	5603 SYCAMORE DR
8	PARHAM, THOMAS C	2305 BALLANTRAE DR	COLLEYVILLE, TX	76034	2305 BALLANTRAE DR
9	HALL, CHARLIE W	4200 GLADE RD	COLLEYVILLE, TX	76034	5606 AMADOR TR
10	ROLAND, ANTHONY J	2309 BALLANTRAE DR	COLLEYVILLE, TX	76034	2309 BALLANTRAE DR
11	BRANDED C VENTURES LTD	4117 LAMPTON CT	ROANOKE, TX	76262	2313 HALL JOHNSON RD
12	WATSON, BRANDON	5609 SYCAMORE DR	COLLEYVILLE, TX	76034	5609 SYCAMORE DR
13	BRANDED C VENTURES LTD	4117 LAMPTON CT	ROANOKE, TX	76262	2317 HALL JOHNSON RD
14	LITTLE BEAR INVESTMENTS INC	PO BOX 611	COLLEYVILLE, TX	76034	2321 HALL JOHNSON RD
15	ISELL, ROGER K	5701 SYCAMORE DR	COLLEYVILLE, TX	76034	5701 SYCAMORE DR
16	ASGHAR, PAMELA	5709 SYCAMORE DR	COLLEYVILLE, TX	76034	5709 SYCAMORE DR
17	VAN OVER, JAMES L	2303 BALLANTRAE DR	COLLEYVILLE, TX	76034	2303 BALLANTRAE DR
18	ARBOR ESTATES	5506 Sycamore Drive	COLLEYVILLE, TX	76034	COURTESY NOTICE
19	ARBOR ESTATES II	5506 Sycamore Drive	COLLEYVILLE, TX	76034	COURTESY NOTICE
20	ENCLAVE AT ARBOR ESTATES, TH	P.O. Box 1824	COLLEYVILLE, TX	76034	COURTESY NOTICE
21	HIGHLAND MEADOWS ADDN	2101 High Gate Drive	COLLEYVILLE, TX	76034	COURTESY NOTICE
22	GRAPEVINE COLLEYVILLE ISD				STATE REQUIRES

Notification Map




ZC18-007


2313 Hall Johnson Road

DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

-  Subject Property
-  300ft Buffer
-  Properties within 300ft



Notification Map




ZC18-007

2313 Hall Johnson Road


DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

-  Subject Property
-  500ft Buffer
-  Properties within 500ft



OBJECTID	Owner_Name	Owner_Addr	Owner_City	Owner_Zip	Situs_Addr
1	ENCLAVE AT ARBOR ESTATES HC	PO BOX 1824	COLLEYVILLE, TX	76034	2401 ARBOR GATE LN
2	DAVIDOVICH, AVRY	2401 SPRUCE CT	COLLEYVILLE, TX	76034	2401 SPRUCE CT
3	SHARP, JOHN R	5605 SYCAMORE DR	COLLEYVILLE, TX	76034	5605 SYCAMORE DR
4	ROPER, JEFFREY L	5700 ARBOR GATE LN	COLLEYVILLE, TX	76034	5700 ARBOR GATE LN
5	CASE, GARY	5607 POPLAR CT W	COLLEYVILLE, TX	76034	5607 POPLAR CT W
6	HARTNETT, JOHN	2407 BALLANTRAE DR	COLLEYVILLE, TX	76034	2407 BALLANTRAE DR
7	DONNELL, JOHN ROBERT	5712 SYCAMORE DR	COLLEYVILLE, TX	76034	5712 SYCAMORE DR
8	KALAMKAR SHAH REVOCABLE LI	2413 ARBOR GATE LN	COLLEYVILLE, TX	76034	2413 ARBOR GATE LN
9	SCHAMP, RICK	PO BOX 213	COLLEYVILLE, TX	76034	2404 ARBOR GATE LN
10	KELLY, IAN	2301 BALLANTRAE DR	COLLEYVILLE, TX	76034	2301 BALLANTRAE DR
11	ANDERSON, ROBERT S	5704 ARBOR GATE LN	COLLEYVILLE, TX	76034	5704 ARBOR GATE LN
12	BLENDEEN, PAMELA S	PO BOX 560326	DALLAS, TX	75356	2403 BALLANTRAE DR
13	MADDOCK, SIMON D	5801 MONTFORD DR	COLLEYVILLE, TX	76034	5801 MONTFORD DR
14	PHELAN, A J	2307 BALLANTRAE DR	COLLEYVILLE, TX	76034	2307 BALLANTRAE DR
15	GREENE, ROBERT	2408 ARBOR GATE LN	COLLEYVILLE, TX	76034	2408 ARBOR GATE LN
16	NEMATI, PARDISE	2405 ARBOR GATE LN	COLLEYVILLE, TX	76034	2405 ARBOR GATE LN
17	DRAUDT, DOUGLAS A	5708 SYCAMORE DR	COLLEYVILLE, TX	76034	5708 SYCAMORE DR
18	LEWIS, MICHAEL B	2308 MULBERRY CT	COLLEYVILLE, TX	76034	2308 MULBERRY CT
19	ZHU, JUN	5705 SYCAMORE DR	COLLEYVILLE, TX	76034	5705 SYCAMORE DR
20	JAY, JOHN	2309 HALL JOHNSON RD	COLLEYVILLE, TX	76034	2309 HALL JOHNSON RD
21	BRIGGS, JON D	2409 ARBOR GATE LN	COLLEYVILLE, TX	76034	2409 ARBOR GATE LN
22	SMARTIS, DANIEL H	5800 W WHITEHAVEN DR	COLLEYVILLE, TX	76034	5800 WHITEHAVEN W
23	WICKSTROM, JEFFRY K	5801 WHITEHAVEN DR	COLLEYVILLE, TX	76034	5801 WHITEHAVEN W
24	NORTHEAST PROPERTIES INC	PO BOX 611	COLLEYVILLE, TX	76034	2319 HALL JOHNSON RD
25	DAVIS, JOSHUA	2400 ARBOR GATE LN	COLLEYVILLE, TX	76034	2400 ARBOR GATE LN
26	STITES, ROBERT W	2309 MULBERRY CT	COLLEYVILLE, TX	76034	2309 MULBERRY CT
27	FOREMAN, NATHAN	2402 SPRUCE CT	COLLEYVILLE, TX	76034	2402 SPRUCE CT
28	BROWN, LARRY	5603 SYCAMORE DR	COLLEYVILLE, TX	76034	5603 SYCAMORE DR
29	CANNON, KENNETH	2207 BALLANTRAE DR	COLLEYVILLE, TX	76034	2207 BALLANTRAE DR
30	PARHAM, THOMAS C	2305 BALLANTRAE DR	COLLEYVILLE, TX	76034	2305 BALLANTRAE DR
31	HOWELL, MICHAEL G	5601 SYCAMORE DR	COLLEYVILLE, TX	76034	5601 SYCAMORE DR
32	PRIMROSE, RANDALL	5506 SYCAMORE DR	COLLEYVILLE, TX	76034	5506 SYCAMORE DR
33	WALKER, JOSEPH SP	2401 BALLANTRAE DR	COLLEYVILLE, TX	76034	2401 BALLANTRAE DR
34	HALL, CHARLIE W	4200 GLADE RD	COLLEYVILLE, TX	76034	5606 AMADOR TR
35	COBURN, KEITH BARON	5505 SYCAMORE DR	COLLEYVILLE, TX	76034	5505 SYCAMORE DR
36	WILLIAMS, EARL M	5803 MONTFORD DR	COLLEYVILLE, TX	76034	5803 MONTFORD DR
37	HOUGH, RHONDA	5708 ARBOR GATE LN	COLLEYVILLE, TX	76034	5708 ARBOR GATE LN
38	HILL, MARK	5507 SYCAMORE DR	COLLEYVILLE, TX	76034	5507 SYCAMORE DR
39	ROLAND, ANTHONY J	2309 BALLANTRAE DR	COLLEYVILLE, TX	76034	2309 BALLANTRAE DR
40	BRANDED C VENTURES LTD	4117 LAMPTON CT	ROANOKE, TX	76262	2313 HALL JOHNSON RD
41	WATSON, BRANDON	5609 SYCAMORE DR	COLLEYVILLE, TX	76034	5609 SYCAMORE DR
42	BRANDED C VENTURES LTD	4117 LAMPTON CT	ROANOKE, TX	76262	2317 HALL JOHNSON RD
43	LITTLE BEAR INVESTMENTS INC	PO BOX 611	COLLEYVILLE, TX	76034	2321 HALL JOHNSON RD
44	LAQUEY, ROBERT	5802 W WHITEHAVEN DR	COLLEYVILLE, TX	76034	5802 WHITEHAVEN W
45	MOZEK, WILLIAM	2203 BALLANTRAE DR	COLLEYVILLE, TX	76034	2203 BALLANTRAE DR
46	ISELL, ROGER K	5701 SYCAMORE DR	COLLEYVILLE, TX	76034	5701 SYCAMORE DR
47	ASGHAR, PAMELA	5709 SYCAMORE DR	COLLEYVILLE, TX	76034	5709 SYCAMORE DR
48	FISCHER, ERIC K	2404 BALLANTRAE DR	COLLEYVILLE, TX	76034	2404 BALLANTRAE DR
49	ENCLAVE AT ARBOR ESTATES HC	PO BOX 1824	COLLEYVILLE, TX	76034	5712 ARBOR GATE LN
50	WRIGHT, LARRY L	5800 MONTFORD DR	COLLEYVILLE, TX	76034	5800 MONTFORD DR
51	VAN OVER, JAMES L	2303 BALLANTRAE DR	COLLEYVILLE, TX	76034	2303 BALLANTRAE DR
52	SOPKIN, MICHAEL	2400 SPRUCE CT	COLLEYVILLE, TX	76034	2400 SPRUCE CT
53	PFEIFFER, JAY J	5602 SYCAMORE DR	COLLEYVILLE, TX	76034	5602 SYCAMORE DR
54	TIAN, YOUQIN	5605 POPLAR CT W	COLLEYVILLE, TX	76034	5605 POPLAR CT W
55	BURROUGH, CHARLES M	5600 SYCAMORE DR	COLLEYVILLE, TX	76034	5600 SYCAMORE DR
56	NEWMAN, ERRIN	5803 W WHITEHAVEN	COLLEYVILLE, TX	76034	5803 WHITEHAVEN W
57	MORGAN, LARRY J	2405 BALLANTRAE DR	COLLEYVILLE, TX	76034	2405 BALLANTRAE DR
58	JARRETT, ANDREW	5704 SYCAMORE DR	COLLEYVILLE, TX	76034	5704 SYCAMORE DR
59	WHITE, MARY	2205 BALLANTRAE DR	COLLEYVILLE, TX	76034	2205 BALLANTRAE DR
60	MADDEN, ROBERT	5802 MONTFORD DR	COLLEYVILLE, TX	76034	5802 MONTFORD DR
61	FARISS, ROBERT E	5604 POPLAR CT W	COLLEYVILLE, TX	76034	5604 POPLAR CT W
62	NAJA, NICOLE	5606 POPLAR CT W	COLLEYVILLE, TX	76034	5606 POPLAR CT W
63	ARBOR ESTATES	5506 Sycamore Drive	COLLEYVILLE, TX	76034	COURTESY NOTICE
64	ARBOR ESTATES II	5506 Sycamore Drive	COLLEYVILLE, TX	76034	COURTESY NOTICE
65	ENCLAVE AT ARBOR ESTATES, TI	P.O. Box 1824	COLLEYVILLE, TX	76034	COURTESY NOTICE
66	HIGHLAND MEADOWS ADDN	2101 High Gate Drive	COLLEYVILLE, TX	76034	COURTESY NOTICE
67	GRAPEVINE COLLEYVILLE ISD				STATE REQUIRES

Notification Map



ZC18-007

2313 Hall Johnson Road

DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.


-  Subject Property
-  1000ft Buffer
-  Properties within 1000ft



OBJECTID	Owner_Name	Owner_Addr	Owner_City	Owner_Zip	Situs_Addr
1	ENCLAVE AT ARBOR ESTATES HC	PO BOX 1824	COLLEYVILLE, TX	76034	2401 ARBOR GATE LN
2	DAVIDOVICH, AVRY	2401 SPRUCE CT	COLLEYVILLE, TX	76034	2401 SPRUCE CT
3	MCCURRY, THOMAS	PO BOX 730	COLLEYVILLE, TX	76034	5601 MONTCLAIR DR
4	MANTEL, RONALD P	2417 ARBOR GATE LN	COLLEYVILLE, TX	76034	2417 ARBOR GATE LN
5	DOTSON, JOYCE M	5903 MEADOWHILL DR	COLLEYVILLE, TX	76034	5903 MEADOWHILL DR
6	BLACK, CHRIS	5508 WINDING TR	COLLEYVILLE, TX	76034	5508 WINDING TR
7	BOLTON, JEFFREY M	2304 ARBOR TR	COLLEYVILLE, TX	76034	2304 ARBOR TR
8	HARRIS, THOMAS R	2403 SPRUCE CT	COLLEYVILLE, TX	76034	2403 SPRUCE CT
9	FRANKLIN, MICHAEL S	5907 MONTFORD DR	COLLEYVILLE, TX	76034	5907 MONTFORD DR
10	SHARP, JOHN R	5605 SYCAMORE DR	COLLEYVILLE, TX	76034	5605 SYCAMORE DR
11	GENTILE, FRANK	2105 BALLANTRAE DR	COLLEYVILLE, TX	76034	2105 BALLANTRAE DR
12	ROPER, JEFFREY L	5700 ARBOR GATE LN	COLLEYVILLE, TX	76034	5700 ARBOR GATE LN
13	CAMPBELL, JEFF T	5804 MEADOWHILL DR	COLLEYVILLE, TX	76034	5804 MEADOWHILL DR
14	MUELLER, STEVEN E	2408 N WHITEHAVEN DR	COLLEYVILLE, TX	76034	2408 WHITEHAVEN N
15	CASE, GARY	5607 POPLAR CT W	COLLEYVILLE, TX	76034	5607 POPLAR CT W
16	HARTNETT, JOHN	2407 BALLANTRAE DR	COLLEYVILLE, TX	76034	2407 BALLANTRAE DR
17	WYLIE, C TODD	5603 POPLAR CT W	COLLEYVILLE, TX	76034	5603 POPLAR CT W
18	DONNELL, JOHN ROBERT	5712 SYCAMORE DR	COLLEYVILLE, TX	76034	5712 SYCAMORE DR
19	KALAMKAR SHAH REVOCABLE LN	2413 ARBOR GATE LN	COLLEYVILLE, TX	76034	2413 ARBOR GATE LN
20	ARITA, JON	2401 POPLAR CT E	COLLEYVILLE, TX	76034	2401 POPLAR CT E
21	SUEDMEIER, MICHAEL	2301 MULBERRY CT	COLLEYVILLE, TX	76034	2301 MULBERRY CT
22	SCHAMP, RICK	PO BOX 213	COLLEYVILLE, TX	76034	2404 ARBOR GATE LN
23	AUSTIN, TAMARA L	2407 N WHITEHAVEN DR	COLLEYVILLE, TX	76034	2407 WHITEHAVEN N
24	KELLY, IAN	2301 BALLANTRAE DR	COLLEYVILLE, TX	76034	2301 BALLANTRAE DR
25	HALL FAMILY TRUST	5503 SYCAMORE DR	COLLEYVILLE, TX	76034	5503 SYCAMORE DR
26	OLIVO, GARY D	5801 SCOTSDALE DR	COLLEYVILLE, TX	76034	5801 SCOTSDALE DR
27	WILLIAMS, DAVID E	5904 MEADOWHILL DR	COLLEYVILLE, TX	76034	5904 MEADOWHILL DR
28	ANDERSON, ROBERT S	5704 ARBOR GATE LN	COLLEYVILLE, TX	76034	5704 ARBOR GATE LN
29	JAHNER, TOM P	5901 W WHITEHAVEN DR	COLLEYVILLE, TX	76034	5901 WHITEHAVEN W
30	BLENDEN, PAMELA S	PO BOX 560326	DALLAS, TX	75356	2403 BALLANTRAE DR
31	TAYLOR, THOMAS P	2301 POPLAR LN	COLLEYVILLE, TX	76034	2301 POPLAR LN
32	MADDOCK, SIMON D	5801 MONTFORD DR	COLLEYVILLE, TX	76034	5801 MONTFORD DR
33	JORDON, CHARLES	5501 SYCAMORE DR	COLLEYVILLE, TX	76034	5501 SYCAMORE DR
34	PHILAN, A J	2307 BALLANTRAE DR	COLLEYVILLE, TX	76034	2307 BALLANTRAE DR
35	HALICI, DERSIV	2201 HALL JOHNSON RD	COLLEYVILLE, TX	76034	2201 HALL JOHNSON RD
36					5609 MONTCLAIR DR
37	GREENE, ROBERT	2408 ARBOR GATE LN	COLLEYVILLE, TX	76034	2408 ARBOR GATE LN
38	NEMATI, PARADISE	2405 ARBOR GATE LN	COLLEYVILLE, TX	76034	2405 ARBOR GATE LN
39	TU, YIDONG	5613 ARBOR GATE LN	COLLEYVILLE, TX	76034	5613 ARBOR GATE LN
40	MACAULAY, ANDREW	5509 MONTCLAIR DR	COLLEYVILLE, TX	76034	5509 MONTCLAIR DR
41	ROORDA, BROCK	2406 N WHITEHAVEN DR	COLLEYVILLE, TX	76034	2406 WHITEHAVEN N
42	BRITTEN, LACY	2501 N WHITEHAVEN DR	COLLEYVILLE, TX	76034	2501 WHITEHAVEN N
43	SLATEN, JO ANN	2404 N WHITEHAVEN DR	COLLEYVILLE, TX	76034	2404 WHITEHAVEN N
44	MCCHESENEY, JOHN	5907 MEADOWHILL DR	COLLEYVILLE, TX	76034	5907 MEADOWHILL DR
45	COLE, WILLIE G	5902 MONTFORD DR	COLLEYVILLE, TX	76034	5902 MONTFORD DR
46	SMALLWOOD, DAN LEE	2421 ARBOR GATE LN	COLLEYVILLE, TX	76034	2421 ARBOR GATE LN
47	MACCAMMOND, JAMES	5410 SYCAMORE CT	COLLEYVILLE, TX	76034	5410 SYCAMORE CT
48	HUSSAIN, MUNSOOR	5900 W WHITEHAVEN DR	COLLEYVILLE, TX	76034	5900 WHITEHAVEN W
49	SCHMIDT, LARRY	5904 MONTFORD DR	COLLEYVILLE, TX	76034	5904 MONTFORD DR
50	WHALEN, GARY L	5903 MONTFORD DR	COLLEYVILLE, TX	76034	5903 MONTFORD DR
51	DRAUDT, DOUGLAS A	5708 SYCAMORE DR	COLLEYVILLE, TX	76034	5708 SYCAMORE DR
52	DUNN, JERRY D	5800 N BALLANTRAE DR	COLLEYVILLE, TX	76034	5800 N BALLANTRAE DR
53	PASQUALE, CAJETAN	2306 ARBOR TR	COLLEYVILLE, TX	76034	2306 ARBOR TR
54	WOOD, OK IM	5709 ARBOR GATE LN	COLLEYVILLE, TX	76034	5709 ARBOR GATE LN
55	RICE, GREG S	5901 SCOTSDALE DR	COLLEYVILLE, TX	76034	5901 SCOTSDALE DR
56	CLARK, CHRISTOPHER G	2300 ARBOR TR	COLLEYVILLE, TX	76034	2300 ARBOR TR
57	MCCLURE, GARY M	2405 SPRUCE CT	COLLEYVILLE, TX	76034	2405 SPRUCE CT
58	LEWIS, MICHAEL B	2308 MULBERRY CT	COLLEYVILLE, TX	76034	2308 MULBERRY CT
59	ZHU, JUN	5705 SYCAMORE DR	COLLEYVILLE, TX	76034	5705 SYCAMORE DR
60	JAY, JOHN	2309 HALL JOHNSON RD	COLLEYVILLE, TX	76034	2309 HALL JOHNSON RD
61	BURNS, SHERRY E	2113 HALL JOHNSON RD	COLLEYVILLE, TX	76034	2113 HALL JOHNSON RD
62	BRIGGS, JON D	2409 ARBOR GATE LN	COLLEYVILLE, TX	76034	2409 ARBOR GATE LN
63	GILES, BARBARA L	2505 BALLANTRAE DR	COLLEYVILLE, TX	76034	2505 BALLANTRAE DR
64	WALLACE, MATTHEW	5600 POPLAR CT W	COLLEYVILLE, TX	76034	5600 POPLAR CT W
65	BOTHE, H DONALD	5902 W WHITEHAVEN LN	COLLEYVILLE, TX	76034	5902 WHITEHAVEN W
66	SMARTIS, DANIEL H	5800 W WHITEHAVEN DR	COLLEYVILLE, TX	76034	5800 WHITEHAVEN W
67	GOODMAN, DEBORAH	2307 POPLAR LN	COLLEYVILLE, TX	76034	2307 POPLAR LN
68	WICKSTROM, JEFFRY K	5801 WHITEHAVEN DR	COLLEYVILLE, TX	76034	5801 WHITEHAVEN W
69					5617 MONTCLAIR DR
70	HICKS, RUSSELL	2304 MULBERRY CT	COLLEYVILLE, TX	76034	2304 MULBERRY CT
71	NORTHEAST PROPERTIES INC	PO BOX 611	COLLEYVILLE, TX	76034	2319 HALL JOHNSON RD
72	DAVIS, JOSHUA	2400 ARBOR GATE LN	COLLEYVILLE, TX	76034	2400 ARBOR GATE LN
73	ENTY, DON	5513 MONTCLAIR DR	COLLEYVILLE, TX	76034	5513 MONTCLAIR DR
74	JACKSON, DANIEL	2404 POPLAR CT E	COLLEYVILLE, TX	76034	2404 POPLAR CT E
75	CUCA, ANDREW J	5705 ARBOR GATE LN	COLLEYVILLE, TX	76034	5705 ARBOR GATE LN
76	TOCE, BRIAN M	5906 W WHITEHAVEN DR	COLLEYVILLE, TX	76034	5906 WHITEHAVEN W
77	STITES, ROBERT W	2309 MULBERRY CT	COLLEYVILLE, TX	76034	2309 MULBERRY CT
78	FOREMAN, NATHAN	2402 SPRUCE CT	COLLEYVILLE, TX	76034	2402 SPRUCE CT
79	BROWN, LARRY	5603 SYCAMORE DR	COLLEYVILLE, TX	76034	5603 SYCAMORE DR
80	HARPER, DOUGLAS R	2405 N WHITEHAVEN DR	COLLEYVILLE, TX	76034	2405 WHITEHAVEN N
81	WOLF, KIM R	5901 LANSFORD LN	COLLEYVILLE, TX	76034	5901 LANSFORD LN
82	CANNON, KENNETH	2207 BALLANTRAE DR	COLLEYVILLE, TX	76034	2207 BALLANTRAE DR
83	YIN, HAI-KUANG	2501 KINGS CT	COLLEYVILLE, TX	76034	2501 KINGS CT
84	HEBERT, MICHAEL A	5504 DUSTY CT	COLLEYVILLE, TX	76034	5504 DUSTY CT
85	PARHAM, THOMAS C	2305 BALLANTRAE DR	COLLEYVILLE, TX	76034	2305 BALLANTRAE DR
86	LEITENBERGER, JOHN R	5905 MONTFORD DR	COLLEYVILLE, TX	76034	5905 MONTFORD DR
87					5613 MONTCLAIR DR
88	WIESE, KARL P	5500 SYCAMORE DR	COLLEYVILLE, TX	76034	5500 SYCAMORE DR
89	SCHUCHMANN, MARK	2406 BALLANTRAE DR	COLLEYVILLE, TX	76034	2406 BALLANTRAE DR
90	VITEK, MICHAEL M	5803 SCOTSDALE DR	COLLEYVILLE, TX	76034	5803 SCOTSDALE DR
91	D'AMICO, JOSEPH	5701 ARBOR GATE LN	COLLEYVILLE, TX	76034	5701 ARBOR GATE LN
92	BIEL, RICHARD K	2303 POPLAR LN	COLLEYVILLE, TX	76034	2303 POPLAR LN
93	CARTER, MEGAN ETVIRE WILBUR	2109 BALLANTRAE DR	COLLEYVILLE, TX	76034	2109 BALLANTRAE DR
94	TOOKEY, RICHARD S	5601 POPLAR CT W	COLLEYVILLE, TX	76034	5601 POPLAR CT W
95	BLYTHE, GWENDOLYN	5502 SYCAMORE DR	COLLEYVILLE, TX	76034	5502 SYCAMORE DR
96	PARKER, WILLIAM	5905 MEADOWHILL DR	COLLEYVILLE, TX	76034	5905 MEADOWHILL DR
97	HOWELL, MICHAEL G	5601 SYCAMORE DR	COLLEYVILLE, TX	76034	5601 SYCAMORE DR
98	PRIMROSE, RANDALL	5506 SYCAMORE DR	COLLEYVILLE, TX	76034	5506 SYCAMORE DR
99	WALKER, JOSEPH SP	2401 BALLANTRAE DR	COLLEYVILLE, TX	76034	2401 BALLANTRAE DR
100	SWAN, STANLEY	PO BOX 1744	COLLEYVILLE, TX	76034	5609 ARBOR GATE LN
101	HALL, CHARLIE W	4200 GLADE RD	COLLEYVILLE, TX	76034	5606 AMADOR TR
102	COBURN, KEITH BARON	5505 SYCAMORE DR	COLLEYVILLE, TX	76034	5505 SYCAMORE DR
103	WILLIAMS, EARL M	5803 MONTFORD DR	COLLEYVILLE, TX	76034	5803 MONTFORD DR
104	SHORT, ANTHONY K	2402 POPLAR CT E	COLLEYVILLE, TX	76034	2402 POPLAR CT E

105 LANCASTER, STEVEN K	2207 HALL JOHNSON RD	COLLEYVILLE, TX	76034	2207 HALL JOHNSON RD
106 LOVERING, KIMBERLY	5801 LANSFORD LN	COLLEYVILLE, TX	76034	5801 LANSFORD LN
107 HOUGH, RHONDA	5708 ARBOR GATE LN	COLLEYVILLE, TX	76034	5708 ARBOR GATE LN
108 CORREA, FRANCOSSCO	5506 WINDING TR	COLLEYVILLE, TX	76034	5506 WINDING TR
109 HILL, MARK	5507 SYCAMORE DR	COLLEYVILLE, TX	76034	5507 SYCAMORE DR
110 ROLAND, ANTHONY J	2309 BALLANTRAE DR	COLLEYVILLE, TX	76034	2309 BALLANTRAE DR
111 CIPRIANO, GILDA	5902 MEADOWHILL DR	COLLEYVILLE, TX	76034	5902 MEADOWHILL DR
112 BRANDED C VENTURES LTD	4117 LAMPTON CT	ROANOKE, TX	76262	2313 HALL JOHNSON RD
113 SPEER, STEPHEN L	5900 MEADOWHILL DR	COLLEYVILLE, TX	76034	5900 MEADOWHILL DR
114 LEENHOUTS, MICHAEL	5901 MONTFORD DR	COLLEYVILLE, TX	76034	5901 MONTFORD DR
115				
116 VOELKLE, ALBERT	2501 BALLANTRAE DR	COLLEYVILLE, TX	76034	2501 BALLANTRAE DR
117 SHARKEY, MILES	2503 BALLANTRAE DR	COLLEYVILLE, TX	76034	2503 BALLANTRAE DR
118 BROWN, KELLEY A	2201 BALLANTRAE DR	COLLEYVILLE, TX	76034	2201 BALLANTRAE DR
119 LEMMON, S CRAIG	2305 MULBERRY CT	COLLEYVILLE, TX	76034	2305 MULBERRY CT
120 WATSON, BRANDON	5609 SYCAMORE DR	COLLEYVILLE, TX	76034	5609 SYCAMORE DR
121 LAMB, MARCUS D	5417 MONTCLAIR DR	COLLEYVILLE, TX	76034	5417 MONTCLAIR DR
122 WEBER, REX ALLEN	5901 MEADOWHILL DR	COLLEYVILLE, TX	76034	5901 MEADOWHILL DR
123 CHEEK, TERRY T	5909 MONTFORD DR	COLLEYVILLE, TX	76034	5909 MONTFORD DR
124 BRANDED C VENTURES LTD	4117 LAMPTON CT	ROANOKE, TX	76262	2317 HALL JOHNSON RD
125 WALLS, DAVID F	5805 MEADOWHILL DR	COLLEYVILLE, TX	76034	5805 MEADOWHILL DR
126 DICKERSON, JAMES	2402 N WHITEHAVEN DR	COLLEYVILLE, TX	76034	2402 WHITEHAVEN N
127 LITTLE BEAR INVESTMENTS INC	PO BOX 611	COLLEYVILLE, TX	76034	2321 HALL JOHNSON RD
128 ANTONETTI, ALFREDO	2300 MULBERRY CT	COLLEYVILLE, TX	76034	2300 MULBERRY CT
129 PENNINGTON, DAVID FRAN	2516 HALL JOHNSON RD	COLLEYVILLE, TX	76034	2516 HALL JOHNSON RD
130 WIMMER, MARTIN A	5700 WINDING TR	COLLEYVILLE, TX	76034	5700 WINDING TR
131 LAQUEY, ROBERT	5802 W WHITEHAVEN DR	COLLEYVILLE, TX	76034	5802 WHITEHAVEN W
132 MOZEK, WILLIAM	2203 BALLANTRAE DR	COLLEYVILLE, TX	76034	2203 BALLANTRAE DR
133 HALLMARK, SANDRA	2305 POPLAR LN	COLLEYVILLE, TX	76034	2305 POPLAR LN
134 SWEATT, THOMAS	2403 POPLAR CT E	COLLEYVILLE, TX	76034	2403 POPLAR CT E
135 ISBELL, ROGER K	5701 SYCAMORE DR	COLLEYVILLE, TX	76034	5701 SYCAMORE DR
136 ASGHAR, PAMELA	5709 SYCAMORE DR	COLLEYVILLE, TX	76034	5709 SYCAMORE DR
137 FISCHER, ERIC K	2404 BALLANTRAE DR	COLLEYVILLE, TX	76034	2404 BALLANTRAE DR
138 STRENGTH, CARLI	5501 MONTCLAIR DR	COLLEYVILLE, TX	76034	5501 MONTCLAIR DR
139 LEWIS, ERIN	2500 BALLANTRAE DR	COLLEYVILLE, TX	76034	2500 BALLANTRAE DR
140 ENCLAVE AT ARBOR ESTATES HC	PO BOX 1824	COLLEYVILLE, TX	76034	5712 ARBOR GATE LN
141 ENCLAVE AT ARBOR ESTATES HC	PO BOX 1824	COLLEYVILLE, TX	76034	5713 ARBOR GATE LN
142 DEAN, DIANA	5602 POPLAR CT W	COLLEYVILLE, TX	76034	5602 POPLAR CT W
143 SPILKER, LEE W	5803 MEADOWHILL DR	COLLEYVILLE, TX	76034	5803 MEADOWHILL DR
144 WRIGHT, LARRY L	5800 MONTFORD DR	COLLEYVILLE, TX	76034	5800 MONTFORD DR
145 HORN, FLOYD	5903 SCOTSDALE DR	COLLEYVILLE, TX	76034	5903 SCOTSDALE DR
146 ZITRICK, SHARON L	5900 MONTFORD DR	COLLEYVILLE, TX	76034	5900 MONTFORD DR
147 VAN OVER, JAMES L	2303 BALLANTRAE DR	COLLEYVILLE, TX	76034	2303 BALLANTRAE DR
148 PURIFOY, BRAD A	5408 SYCAMORE CT	COLLEYVILLE, TX	76034	5408 SYCAMORE CT
149 SOPKIN, MICHAEL	2400 SPRUCE CT	COLLEYVILLE, TX	76034	2400 SPRUCE CT
150 HOWARD, BRIAN	5802 MEADOWHILL DR	COLLEYVILLE, TX	76034	5802 MEADOWHILL DR
151 PFEIFFER, JAY J	5602 SYCAMORE DR	COLLEYVILLE, TX	76034	5602 SYCAMORE DR
152 DAVIS, PHILLIP	2107 BALLANTRAE DR	COLLEYVILLE, TX	76034	2107 BALLANTRAE DR
153				5605 MONTCLAIR DR
154 JEFFERS, MARK J	2406 SPRUCE CT	COLLEYVILLE, TX	76034	2406 SPRUCE CT
155 REGULA, ANDREA S	2406 POPLAR CT E	COLLEYVILLE, TX	76034	2406 POPLAR CT E
156 SHUMATE, LORA LEIGH	2407 SPRUCE CT	COLLEYVILLE, TX	76034	2407 SPRUCE CT
157 BRUNER, MELISSA L	5704 WINDING TRL	COLLEYVILLE, TX	76034	5704 WINDING TR
158 HUTCHINGS, JENNIFER	2404 SPRUCE CT	COLLEYVILLE, TX	76034	2404 SPRUCE CT
159 TIAN, YOUQIN	5605 POPLAR CT W	COLLEYVILLE, TX	76034	5605 POPLAR CT W
160 GEHLER, CHRISTOPHER	5602 CREEKSIDE CT	COLLEYVILLE, TX	76034	5602 CREEKSIDE CT
161 VELLA, DAVID M	2405 POPLAR CT E	COLLEYVILLE, TX	76034	2405 POPLAR CT E
162 KRAMEROV, GEORGE	5903 W WHITEHAVEN DR	COLLEYVILLE, TX	76034	5903 WHITEHAVEN W
163 BURROUGH, CHARLES M	5600 SYCAMORE DR	COLLEYVILLE, TX	76034	5600 SYCAMORE DR
164 ROBINSON, HENRY	5803 LANSFORD LN	COLLEYVILLE, TX	76034	5803 LANSFORD LN
165 JACH, ANTHONY	2302 ARBOR TR	COLLEYVILLE, TX	76034	2302 ARBOR TR
166 NEWMAN, ERRIN	5803 W WHITEHAVEN	COLLEYVILLE, TX	76034	5803 WHITEHAVEN W
167 MORGAN, LARRY J	2405 BALLANTRAE DR	COLLEYVILLE, TX	76034	2405 BALLANTRAE DR
168 JARRETT, ANDREW	5704 SYCAMORE DR	COLLEYVILLE, TX	76034	5704 SYCAMORE DR
169 WHITE, MARY	2205 BALLANTRAE DR	COLLEYVILLE, TX	76034	2205 BALLANTRAE DR
170 LANG, JOEL R	5409 SYCAMORE CT	COLLEYVILLE, TX	76034	5409 SYCAMORE CT
171 MADDEN, ROBERT	5802 MONTFORD DR	COLLEYVILLE, TX	76034	5802 MONTFORD DR
172 THE CREWS FAMILY TRUST	5702 WINDING TRL	COLLEYVILLE, TX	76034	5702 WINDING TR
173 MAXEY, SUSIE R	5906 MONTFORD DR	COLLEYVILLE, TX	76034	5906 MONTFORD DR
174 PEARSON, PATRICK L	2500 KINGS CT	COLLEYVILLE, TX	76034	2500 KINGS CT
175 TURNER, SABRINA	5411 SYCAMORE CT	COLLEYVILLE, TX	76034	5411 SYCAMORE CT
176 CELINSKI, TODD	5504 SYCAMORE DR	COLLEYVILLE, TX	76034	5504 SYCAMORE DR
177 GREENE, PERRY F	2400 N WHITEHAVEN DR	COLLEYVILLE, TX	76034	2400 WHITEHAVEN N
178 FARISS, ROBERT E	5604 POPLAR CT W	COLLEYVILLE, TX	76034	5604 POPLAR CT W
179 HARRISON, GARY L	5604 CREEKSIDE CT	COLLEYVILLE, TX	76034	5604 CREEKSIDE CT
180 NAJA, NICOLE	5606 POPLAR CT W	COLLEYVILLE, TX	76034	5606 POPLAR CT W
181 MARRS, ROBERT	2400 POPLAR CT E	COLLEYVILLE, TX	76034	2400 POPLAR CT E
182 SCHELLEN, MICHAEL C	5904 W WHITEHAVEN DR	COLLEYVILLE, TX	76034	5904 WHITEHAVEN W
183 KUPPER, CASEY M	5600 CREEKSIDE CT	COLLEYVILLE, TX	76034	5600 CREEKSIDE CT
184 EARLY, STEVEN A	5606 CREEKSIDE CT	COLLEYVILLE, TX	76034	5606 CREEKSIDE CT
185 ARBOR ESTATES	5506 Sycamore Drive	COLLEYVILLE, TX	76034	COURTESY NOTICE
186 ARBOR ESTATES II	5506 Sycamore Drive	COLLEYVILLE, TX	76034	COURTESY NOTICE
187 ENCLAVE AT ARBOR ESTATES, TI	P.O. Box 1824	COLLEYVILLE, TX	76034	COURTESY NOTICE
188 HIGHLAND MEADOWS ADDN	2101 High Gate Drive	COLLEYVILLE, TX	76034	COURTESY NOTICE
189 GRAPEVINE COLLEYVILLE ISD				STATE REQUIRES


Notification Map



ZC18-001
5713 Colleyville Blvd


-  Subject Property
-  200ft Buffer
-  Properties within 200ft

DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.



OBJECTID	Owner_Name	Owner_Addr	Owner_City	Owner_Zip	Situs_Addr
1	COLLIER, CHARLIE G	5616 COVENTRY CT	COLLEYVILLE, TX	76034	5616 COVENTRY CT
2	MITCHELL, MICHAEL	1804 ARRINGTON GREEN	COLLEYVILLE, TX	76034	1804 ARRINGTON GREEN
3	WADE, DANIEL	1804 STRATTON GRN	COLLEYVILLE, TX	76034	1804 STRATTON GREEN
4	TEXADA, RICKY	1801 ARRINGTON GREEN	COLLEYVILLE, TX	76034	1801 ARRINGTON GREEN
5	BLUEBONNET HILLS CEMETARY	PO BOX 367	COLLEYVILLE, TX	76034	5713 COLLEYVILLE BLVD
6	TERRY DAVID & PENELOPE D JOI	1801 CAMDEN GREEN	COLLEYVILLE, TX	76034	1801 CAMDEN GREEN
7	SULZER, STEFAN R	1804 CAMDEN GRN	COLLEYVILLE, TX	76034	1804 CAMDEN GREEN
8	USSERY, MICHAEL J	1800 ARRINGTON GRN	COLLEYVILLE, TX	76034	1800 ARRINGTON GREEN
9	SWAIM, SHELLY	1700 GATEHOUSE CT	COLLEYVILLE, TX	76034	1700 GATEHOUSE CT
10	KELLEY, BRENT A	1801 STRATTON GRN	COLLEYVILLE, TX	76034	1801 STRATTON GREEN
11	RUCKER, RICHARD B	1704 GATEHOUSE CT	COLLEYVILLE, TX	76034	1704 GATEHOUSE CT
12	RUSSELL, REX	1805 CAMDEN GRN	COLLEYVILLE, TX	76034	1805 CAMDEN GREEN
13	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
14	HEIDEL, RUTH V	1712 GATEHOUSE CT	COLLEYVILLE, TX	76034	1712 GATEHOUSE CT
15	COLLEYVILLE, CITY OF	100 MAIN ST	COLLEYVILLE, TX	76034	1601 HALL JOHNSON RD
16	COLLEYVILLE, CITY OF	100 MAIN ST	COLLEYVILLE, TX	76034	1601 HALL JOHNSON RD
17	DIXON, DAVID	1800 STRATTON GRN	COLLEYVILLE, TX	76034	1800 STRATTON GREEN
18	SINUNU, STEPHEN A	1813 CAMDEN GRN	COLLEYVILLE, TX	76034	1813 CAMDEN GREEN
19	BLUEBONNET HILLS CEMETERY	PO BOX 11250	NEW ORLEANS, LA	70181	5713 COLLEYVILLE BLVD
20	CASEY, ROBERT E	1805 STRATTON GRN	COLLEYVILLE, TX	76034	1805 STRATTON GREEN
21	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
22	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
23	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 CAMDEN GREEN
24	BLUEBONNET HILLS CEMETERY	PO BOX 130548	HOUSTON, TX	77219	5713 COLLEYVILLE BLVD
25	GLASSCOCK, D L	1708 GATEHOUSE CT	COLLEYVILLE, TX	76034	1708 GATEHOUSE CT
26	BOYD, LARRY G	PO BOX 279	COLLEYVILLE, TX	76034	1805 ARRINGTON GREEN
27	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 STRATTON GREEN
28	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 ARRINGTON GREEN
29	MILLER, DENNIS	1800 CAMDEN GRN	COLLEYVILLE, TX	76034	1800 CAMDEN GREEN
30	AL-SHMAISANI, ISSAM	5608 NORMANDY DR	COLLEYVILLE, TX	76034	5700 NORMANDY DR
31	WAYPOINT MONTESSORI	1513 HALL JOHNSON RD	COLLEYVILLE, TX	76034	1513 HALL JOHNSON RD
32	THIBODEAUX, NELSON J	5612 COVENTRY CT	COLLEYVILLE, TX	76034	5612 COVENTRY CT
33	MOORE, BOBBY FAMILY LTD PRTI	6113 COLLYVILLE BLVD	COLLEYVILLE, TX	76034	6113 COLLEYVILLE BLVD
34	SMART, BROOKE	1809 CAMDEN GRN	COLLEYVILLE, TX	76034	1809 CAMDEN GREEN
35	BROUGHTON	2557 SW Grapevine Pkwy Suite 100	GRAPEVINE, TX	76051	COURTESY NOTICE
36	MONTCLAIR PARC ADDITION	1108 W. Pioneer Parkway	ARLINGTON, TX	76013	COURTESY NOTICE
37	STONE CREST ESTATES	P.O. Box 332	COLLEYVILLE, TX	76034	COURTESY NOTICE
38	GRAPEVINE COLLEYVILLE ISD				STATE REQUIRES


Notification Map



DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.


ZC18-001
5713 Colleyville Blvd

-  Subject Property
-  300ft Buffer
-  Properties within 300ft



OBJECTID	Owner_Name	Owner_Addr	Owner_City	Owner_Zip	Situs_Addr
1	WHITE, KEITH M	5608 COVENTRY CT	COLLEYVILLE, TX	76034	5608 COVENTRY CT
2	COLLIER, CHARLIE G	5616 COVENTRY CT	COLLEYVILLE, TX	76034	5616 COVENTRY CT
3	RAJWANI, ABDUL AZIZ	1805 GROSVENOR GRN	COLLEYVILLE, TX	76034	1805 GROSVENOR GREEN
4	MITCHELL, MICHAEL	1804 ARRINGTON GREEN	COLLEYVILLE, TX	76034	1804 ARRINGTON GREEN
5	WADE, DANIEL	1804 STRATTON GRN	COLLEYVILLE, TX	76034	1804 STRATTON GREEN
6	VES ESTATE	1808 STRATTON GREEN	COLLEYVILLE, TX	76034	1808 STRATTON GREEN
7	TEXADA, RICKY	1801 ARRINGTON GREEN	COLLEYVILLE, TX	76034	1801 ARRINGTON GREEN
8	BLUEBONNET HILLS CEMETARY	PO BOX 367	COLLEYVILLE, TX	76034	5713 COLLEYVILLE BLVD
9	TERRY DAVID & PENELOPE D JOI	1801 CAMDEN GREEN	COLLEYVILLE, TX	76034	1801 CAMDEN GREEN
10	SULZER, STEFAN R	1804 CAMDEN GRN	COLLEYVILLE, TX	76034	1804 CAMDEN GREEN
11	CAMPBELL, GREGORY A	1817 CAMDEN GRN	COLLEYVILLE, TX	76034	1817 CAMDEN GREEN
12	USSERY, MICHAEL J	1800 ARRINGTON GRN	COLLEYVILLE, TX	76034	1800 ARRINGTON GREEN
13	SWAIM, SHELLEY	1700 GATEHOUSE CT	COLLEYVILLE, TX	76034	1700 GATEHOUSE CT
14	KELLEY, BRENT A	1801 STRATTON GRN	COLLEYVILLE, TX	76034	1801 STRATTON GREEN
15	RUCKER, RICHARD B	1704 GATEHOUSE CT	COLLEYVILLE, TX	76034	1704 GATEHOUSE CT
16	RUSSELL, REX	1805 CAMDEN GRN	COLLEYVILLE, TX	76034	1805 CAMDEN GREEN
17	FULTZ, JAMES E	1809 STRATTON GRN	COLLEYVILLE, TX	76034	1809 STRATTON GREEN
18	BENZICK, ARTHUR E	1808 CAMDEN GRN	COLLEYVILLE, TX	76034	1808 CAMDEN GREEN
19	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
20	WILBUR FAMILY TRUST	1705 GATEHOUSE CT	COLLEYVILLE, TX	76034	1705 GATEHOUSE CT
21	HEIDEL, RUTH V	1712 GATEHOUSE CT	COLLEYVILLE, TX	76034	1712 GATEHOUSE CT
22	COLLEYVILLE, CITY OF	100 MAIN ST	COLLEYVILLE, TX	76034	1601 HALL JOHNSON RD
23	COLLEYVILLE, CITY OF	100 MAIN ST	COLLEYVILLE, TX	76034	1601 HALL JOHNSON RD
24	DIXON, DAVID	1800 STRATTON GRN	COLLEYVILLE, TX	76034	1800 STRATTON GREEN
25	SINUNU, STEPHEN A	1813 CAMDEN GRN	COLLEYVILLE, TX	76034	1813 CAMDEN GREEN
26	BLUEBONNET HILLS CEMETERY	PO BOX 11250	NEW ORLEANS, LA	70181	5713 COLLEYVILLE BLVD
27	CASEY, ROBERT E	1805 STRATTON GRN	COLLEYVILLE, TX	76034	1805 STRATTON GREEN
28	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
29	BICE, LEROY	1701 GATEHOUSE CT	COLLEYVILLE, TX	76034	1701 GATEHOUSE CT
30	YOUSAF, MOHAMMAD	1809 ARRINGTON GRN	COLLEYVILLE, TX	76034	1809 ARRINGTON GREEN
31	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
32	CHEATHAM, STEPHANIE	1716 GATEHOUSE CT	COLLEYVILLE, TX	76034	1716 GATEHOUSE CT
33	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 CAMDEN GREEN
34	BLUEBONNET HILLS CEMETERY	PO BOX 130548	HOUSTON, TX	77219	5713 COLLEYVILLE BLVD
35	GLASSCOCK, D L	1708 GATEHOUSE CT	COLLEYVILLE, TX	76034	1708 GATEHOUSE CT
36	HOBBS, THOMAS R	1801 GROSVENOR GRN	COLLEYVILLE, TX	76034	1801 GROSVENOR GREEN
37	BOYD, LARRY G	PO BOX 279	COLLEYVILLE, TX	76034	1805 ARRINGTON GREEN
38	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 STRATTON GREEN
39	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 ARRINGTON GREEN
40	MILLER, DENNIS	1800 CAMDEN GRN	COLLEYVILLE, TX	76034	1800 CAMDEN GREEN
41	CORAZE, MATHIEU	1709 GATEHOUSE CT	COLLEYVILLE, TX	76034	1709 GATEHOUSE CT
42	AL-SHMAISANI, ISSAM	5608 NORMANDY DR	COLLEYVILLE, TX	76034	5700 NORMANDY DR
43	WAYPOINT MONTESSORI	1513 HALL JOHNSON RD	COLLEYVILLE, TX	76034	1513 HALL JOHNSON RD
44	LUJAN, ALBERT C	1713 GATEHOUSE CT	COLLEYVILLE, TX	76034	1713 GATEHOUSE CT
45	THIBODEAUX, NELSON J	5612 COVENTRY CT	COLLEYVILLE, TX	76034	5612 COVENTRY CT
46	MOORE, BOBBY FAMILY LTD PARTI	6113 COLLYVILLE BLVD	COLLEYVILLE, TX	76034	6113 COLLEYVILLE BLVD
47	SMART, BROOKE	1809 CAMDEN GRN	COLLEYVILLE, TX	76034	1809 CAMDEN GREEN
48	BONDY, NEAL	1808 ARRINGTON GRN	COLLEYVILLE, TX	76034	1808 ARRINGTON GREEN
49	BROUGHTON	2557 SW Grapevine Pkwy Suite 100	GRAPEVINE, TX	76051	COURTESY NOTICE
50	MONTCLAIR PARC ADDITION	1108 W. Pioneer Parkway	ARLINGTON, TX	76013	COURTESY NOTICE
51	STONE CREST ESTATES	P.O. Box 332	COLLEYVILLE, TX	76034	COURTESY NOTICE
52	GRAPEVINE COLLEYVILLE ISD				STATE REQUIRES


Notification Map



DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.


ZC18-001
5713 Colleyville Blvd

-  Subject Property
-  500ft Buffer
-  Properties within 500ft



OBJECTID	Owner_Name	Owner_Addr	Owner_City	Owner_Zip	Situs_Addr
1	WHITE, KEITH M	5608 COVENTRY CT	COLLEYVILLE, TX	76034	5608 COVENTRY CT
2	COLLIER, CHARLIE G	5616 COVENTRY CT	COLLEYVILLE, TX	76034	5616 COVENTRY CT
3	RAJWANI, ABDUL AZIZ	1805 GROSVENOR GRN	COLLEYVILLE, TX	76034	1805 GROSVENOR GREEN
4	DAMEK, PAUL	1812 CAMDEN GREEN	COLLEYVILLE, TX	76034	1812 CAMDEN GREEN
5	MITCHELL, MICHAEL	1804 ARRINGTON GREEN	COLLEYVILLE, TX	76034	1804 ARRINGTON GREEN
6	KRUZEL, THOMAS M	1816 CAMDEN GRN	COLLEYVILLE, TX	76034	1816 CAMDEN GREEN
7	ANNIS, BARNARD H	5604 COVENTRY CT	COLLEYVILLE, TX	76034	5604 COVENTRY CT
8	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
9	WADE, DANIEL	1804 STRATTON GRN	COLLEYVILLE, TX	76034	1804 STRATTON GREEN
10	WHITAKER, DAVID	1905 HALL JOHNSON RD	COLLEYVILLE, TX	76034	1905 HALL JOHNSON RD
11	SCHAECHER, GREGORY C	1821 CAMDEN GRN	COLLEYVILLE, TX	76034	1821 CAMDEN GREEN
12	VES ESTATE	1808 STRATTON GREEN	COLLEYVILLE, TX	76034	1808 STRATTON GREEN
13	TEXADA, RICKY	1801 ARRINGTON GREEN	COLLEYVILLE, TX	76034	1801 ARRINGTON GREEN
14	FORSLUND, BRADLEY	1813 STRATTON GREEN	COLLEYVILLE, TX	76034	1813 STRATTON GREEN
15	UNITED STATES POSTAL SERVICI	PO BOX 667160	DALLAS, TX	75266	1501 HALL JOHNSON RD
16	BLUEBONNET HILLS CEMETARY	PO BOX 367	COLLEYVILLE, TX	76034	5713 COLLEYVILLE BLVD
17	TERRY DAVID & PENELOPE D JOI	1801 CAMDEN GREEN	COLLEYVILLE, TX	76034	1801 CAMDEN GREEN
18	SULZER, STEFAN R	1804 CAMDEN GRN	COLLEYVILLE, TX	76034	1804 CAMDEN GREEN
19	CAMPBELL, GREGORY A	1817 CAMDEN GRN	COLLEYVILLE, TX	76034	1817 CAMDEN GREEN
20	CARMONA, ENRIQUE	1700 CRESTEDGE CT	COLLEYVILLE, TX	76034	1700 CRESTEDGE CT
21	USSERY, MICHAEL J	1800 ARRINGTON GRN	COLLEYVILLE, TX	76034	1800 ARRINGTON GREEN
22	GONZALEZ, ADOLFO	1813 GROSVENOR GRN	COLLEYVILLE, TX	76034	1813 GROSVENOR GREEN
23	SWAIM, SHELLY	1700 GATEHOUSE CT	COLLEYVILLE, TX	76034	1700 GATEHOUSE CT
24	CHELLGREN, PAUL	1820 CAMDEN GRN	COLLEYVILLE, TX	76034	1820 CAMDEN GREEN
25	KELLEY, BRENT A	1801 STRATTON GRN	COLLEYVILLE, TX	76034	1801 STRATTON GREEN
26	NELSON, MICHAEL JAY	5600 COVENTRY CT	COLLEYVILLE, TX	76034	5600 COVENTRY CT
27	RUCKER, RICHARD B	1704 GATEHOUSE CT	COLLEYVILLE, TX	76034	1704 GATEHOUSE CT
28	RUSSELL, REX	1805 CAMDEN GRN	COLLEYVILLE, TX	76034	1805 CAMDEN GREEN
29	AL-SHMAISANI, ISSAM	5608 NORMANDY DR	COLLEYVILLE, TX	76034	5608 NORMANDY DR
30	DEBEUCKELAER, JAN	5606 NORMANDY DR	COLLEYVILLE, TX	76034	5606 NORMANDY DR
31	FULTZ, JAMES E	1809 STRATTON GRN	COLLEYVILLE, TX	76034	1809 STRATTON GREEN
32	BENZICK, ARTHUR E	1808 CAMDEN GRN	COLLEYVILLE, TX	76034	1808 CAMDEN GREEN
33	CAREY, MATTHEW	1809 GROSVENOR GRN	COLLEYVILLE, TX	76034	1809 GROSVENOR GREEN
34	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
35	WILBUR FAMILY TRUST	1705 GATEHOUSE CT	COLLEYVILLE, TX	76034	1705 GATEHOUSE CT
36	HEIDEL, RUTH V	1712 GATEHOUSE CT	COLLEYVILLE, TX	76034	1712 GATEHOUSE CT
37	CLEMENS, K R	1712 CRESTEDGE CT	COLLEYVILLE, TX	76034	1712 CRESTEDGE CT
38	HOELLER, BRYAN	1817 GROSVENOR GREEN	COLLEYVILLE, TX	76034	1817 GROSVENOR GREEN
39	COLLEYVILLE, CITY OF	100 MAIN ST	COLLEYVILLE, TX	76034	1601 HALL JOHNSON RD
40	COLLEYVILLE, CITY OF	100 MAIN ST	COLLEYVILLE, TX	76034	1601 HALL JOHNSON RD
41	DIXON, DAVID	1800 STRATTON GRN	COLLEYVILLE, TX	76034	1800 STRATTON GREEN
42	COLLEYVILLE, CITY OF	100 MAIN ST	COLLEYVILLE, TX	76034	1900 HALL JOHNSON RD
43	SINUNU, STEPHEN A	1813 CAMDEN GRN	COLLEYVILLE, TX	76034	1813 CAMDEN GREEN
44	GOFF HOMES INC	1108 W PIONEER PKWY	ARLINGTON, TX	76013	5701 NORMANDY DR
45	BLUEBONNET HILLS CEMETERY	PO BOX 11250	NEW ORLEANS, LA	70181	5713 COLLEYVILLE BLVD
46	CASEY, ROBERT E	1805 STRATTON GRN	COLLEYVILLE, TX	76034	1805 STRATTON GREEN
47	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
48	BICE, LEROY	1701 GATEHOUSE CT	COLLEYVILLE, TX	76034	1701 GATEHOUSE CT
49	YOUSAF, MOHAMMAD	1809 ARRINGTON GRN	COLLEYVILLE, TX	76034	1809 ARRINGTON GREEN
50	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
51	CHEATHAM, STEPHANIE	1716 GATEHOUSE CT	COLLEYVILLE, TX	76034	1716 GATEHOUSE CT
52	PRINS, ORVILLE	1812 STRATTON GRN	COLLEYVILLE, TX	76034	1812 STRATTON GREEN
53	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 CAMDEN GREEN
54	BLUEBONNET HILLS CEMETERY	PO BOX 130548	HOUSTON, TX	77219	5713 COLLEYVILLE BLVD
55	GLASSCOCK, D L	1708 GATEHOUSE CT	COLLEYVILLE, TX	76034	1708 GATEHOUSE CT
56	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1803 GROSVENOR GREEN
57	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 ARRINGTON CT
58	HOBBS, THOMAS R	1801 GROSVENOR GRN	COLLEYVILLE, TX	76034	1801 GROSVENOR GREEN
59	BOYD, LARRY G	PO BOX 279	COLLEYVILLE, TX	76034	1805 ARRINGTON GREEN
60	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 STRATTON GREEN
61	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 GROSVENOR GREEN
62	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 ARRINGTON GREEN
63	MILLER, DENNIS	1800 CAMDEN GRN	COLLEYVILLE, TX	76034	1800 CAMDEN GREEN
64	CORAZE, MATHIEU	1709 GATEHOUSE CT	COLLEYVILLE, TX	76034	1709 GATEHOUSE CT
65	CRISCI, FRANK	1812 ARRINGTON GRN	COLLEYVILLE, TX	76034	1812 ARRINGTON GREEN
66	AL-SHMAISANI, ISSAM	5608 NORMANDY DR	COLLEYVILLE, TX	76034	5700 NORMANDY DR
67	WAYPOINT MONTESSORI	1513 HALL JOHNSON RD	COLLEYVILLE, TX	76034	1513 HALL JOHNSON RD
68	LUJAN, ALBERT C	1713 GATEHOUSE CT	COLLEYVILLE, TX	76034	1713 GATEHOUSE CT
69	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1824 BROUGHTON DR
70	THIBODEAUX, NELSON J	5612 COVENTRY CT	COLLEYVILLE, TX	76034	5612 COVENTRY CT
71	IDELL, GLEN E	1708 CRESTEDGE CT	COLLEYVILLE, TX	76034	1708 CRESTEDGE CT
72	MOORE, BOBBY FAMILY LTD PRTI	6113 COLLYVILLE BLVD	COLLEYVILLE, TX	76034	6113 COLLEYVILLE BLVD
73	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	5801 BURNHAM CIR
74	SMART, BROOKE	1809 CAMDEN GRN	COLLEYVILLE, TX	76034	1809 CAMDEN GREEN
75	BONDY, NEAL	1808 ARRINGTON GRN	COLLEYVILLE, TX	76034	1808 ARRINGTON GREEN
76	BROCK, MANDI	1704 CRESTEDGE CT	COLLEYVILLE, TX	76034	1704 CRESTEDGE CT
77	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
78	MERHAB, MOHANNAD	5707 MORLAIX CT	COLLEYVILLE, TX	76034	5707 MORLAIX CT
79	BOUGHTON MAINTENANCE ASSO	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
80	BROUGHTON	2557 SW Grapevine Pkwy Suite 100	GRAPEVINE, TX	76051	COURTESY NOTICE
81	MONTCLAIR PARC ADDITION	1108 W. Pioneer Parkway	ARLINGTON, TX	76013	COURTESY NOTICE
82	STONE CREST ESTATES	P.O. Box 332	COLLEYVILLE, TX	76034	COURTESY NOTICE
83	GRAPEVINE COLLEYVILLE ISD				STATE REQUIRES

Notification Map



DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

ZC18-001
5713 Colleyville Blvd




Subject Property



1000ft Buffer




Properties within 1000ft



OBJECTID	Owner_Name	Owner_Addr	Owner_City	Owner_Zip	Situs_Addr
1	SILVEROAK REAL EST GROUP LL	8240 MID CITIES BLVD	NORTH RICHLAND HILLS, TX	76180	1717 ROCK DOVE CIR
2	WHITE, KEITH M	5608 COVENTRY CT	COLLEYVILLE, TX	76034	5608 COVENTRY CT
3	BROWN, DANA KAY	5500 COVENTRY CT	COLLEYVILLE, TX	76034	5500 COVENTRY CT
4	BUI, CHRIS	1913 ARRINGTON CT	COLLEYVILLE, TX	76034	1913 ARRINGTON CT
5	BOBROWSKI, SHELLEY	1913 GROSVENOR LN	COLLEYVILLE, TX	76034	1913 GROSVENOR LN
6	COLLIER, CHARLIE G	5616 COVENTRY CT	COLLEYVILLE, TX	76034	5616 COVENTRY CT
7	DANIEL, JOSE	1917 ARRINGTON CT	COLLEYVILLE, TX	76034	1917 ARRINGTON CT
8	FLETCHER FAMILY REVOCABLE L	1705 CRESTEDGE CT	COLLEYVILLE, TX	76034	1705 CRESTEDGE CT
9	BREWER, JANE E	1912 STRATTON CT	COLLEYVILLE, TX	76034	1912 STRATTON CT
10	RAJWANI, ABDUL AZIZ	1805 GROSVENOR GRN	COLLEYVILLE, TX	76034	1805 GROSVENOR GREEN
11	CAPELO, RODERICK	1908 CAMDEN CT	COLLEYVILLE, TX	76034	1908 CAMDEN CT
12	NISBET, JAY	1909 GROSVENOR LN	COLLEYVILLE, TX	76034	1909 GROSVENOR LN
13	DAMEK, PAUL	1812 CAMDEN GREEN	COLLEYVILLE, TX	76034	1812 CAMDEN GREEN
14	MITCHELL, MICHAEL	1804 ARRINGTON GREEN	COLLEYVILLE, TX	76034	1804 ARRINGTON GREEN
15	SHELL, EDDIE	6113 ROCK DOVE CIR	COLLEYVILLE, TX	76034	6113 ROCK DOVE CIR
16	ETHERIDGE, EDGAR D	3324 DUSTIN TR	HURST, TX	76054	6007 COLLEYVILLE BLVD
17	ALLEN, WALTRAUD	5600 MIRAMAR LN	COLLEYVILLE, TX	76034	5600 MIRAMAR LN
18	GUEVARA, JOSE	1713 CRESTEDGE CT	COLLEYVILLE, TX	76034	1713 CRESTEDGE CT
19	ARANA, WANDA TRUSTEE	36 ARANA CIR	SAUSALITO, CA	94865	6200 COLLEYVILLE BLVD
20	KRUZEL, THOMAS M	1816 CAMDEN GRN	COLLEYVILLE, TX	76034	1816 CAMDEN GREEN
21	SCHILLER, ADAM	2001 HALL JOHNSON RD	COLLEYVILLE, TX	76034	2001 HALL JOHNSON RD
22	MOORE, RACHEL	6108 PONDEROSA ST	COLLEYVILLE, TX	76034	6108 PONDEROSA ST
23	ANNIS, BARNARD H	5604 COVENTRY CT	COLLEYVILLE, TX	76034	5604 COVENTRY CT
24	CABRERA, CHARLES	5604 NORMANDY DR	COLLEYVILLE, TX	76034	5604 NORMANDY DR
25	ERICKSON, CHAD	5508 COVENTRY CT	COLLEYVILLE, TX	76034	5508 COVENTRY CT
26	LEPISTO FAMILY REVOCABLE TR	1506 KINGSWOOD LN	COLLEYVILLE, TX	76034	1506 KINGSWOOD LN
27	AVALON COMM PROPERTIES LLC	3145 GEARY BLVD STE 737	SAN FRANCISCO, CA	94118	6219 COLLEYVILLE BLVD
28	BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
29	WADE, DANIEL	1804 STRATTON GRN	COLLEYVILLE, TX	76034	1804 STRATTON GREEN
30	WHITAKER, DAVID	1905 HALL JOHNSON RD	COLLEYVILLE, TX	76034	1905 HALL JOHNSON RD
31	SCHAECHER, GREGORY C	1821 CAMDEN GRN	COLLEYVILLE, TX	76034	1821 CAMDEN GREEN
32	COUCH, KEVIN T	5501 COVENTRY CT	COLLEYVILLE, TX	76034	5501 COVENTRY CT
33	COX, GEORGE B	1602 KINGSWOOD LN	COLLEYVILLE, TX	76034	1602 KINGSWOOD LN
34	BLUEBONNET HILLS MEMORIAL F	PO BOX 130548	HOUSTON, TX	77219	5713 COLLEYVILLE BLVD
35	VES ESTATE	1808 STRATTON GREEN	COLLEYVILLE, TX	76034	1808 STRATTON GREEN
36	TEXADA, RICKY	1801 ARRINGTON GREEN	COLLEYVILLE, TX	76034	1801 ARRINGTON GREEN
37	FORSLUND, BRADLEY	1813 STRATTON GREEN	COLLEYVILLE, TX	76034	1813 STRATTON GREEN
38	KELLER, JOHN D	1821 GROSVENOR GRN	COLLEYVILLE, TX	76034	1821 GROSVENOR GREEN
39	CLINE, KIMBERLY A	6109 ROCK DOVE CIR	COLLEYVILLE, TX	76034	6109 ROCK DOVE CIR
40	ARPEY, GERARD	1713 ROCK DOVE CIR	COLLEYVILLE, TX	76034	1713 ROCK DOVE CIR
41	UNITED STATES POSTAL SERVIC	PO BOX 667160	DALLAS, TX	75266	1501 HALL JOHNSON RD
42	WILLIAMSON, JEFF	5509 JANET LN	COLLEYVILLE, TX	76034	5509 JANET LN
43	NGUYEN, BANG K	5608 MIRAMAR LN	COLLEYVILLE, TX	76034	5608 MIRAMAR LN
44	RAY, RONALD D	5602 NORMANDY DR	COLLEYVILLE, TX	76034	5602 NORMANDY DR
45	OSIRIS PROPERTIES INC	301 BANK ST	SOUTHLAKE, TX	76092	5505 NORMANDY DR
46	KIRKING, LEWIS	6108 ROCK DOVE CIR	COLLEYVILLE, TX	76034	6108 ROCK DOVE CIR
47	COLLEYVILLE COMMERCIAL PRO	1468 SANDHILL CT	ROANOKE, TX	76262	6114 COLLEYVILLE BLVD
48	WILKISON, GREGORY S	5412 COVENTRY CT	COLLEYVILLE, TX	76034	5412 COVENTRY CT
49	BLUEBONNET HILLS CEMETARY	PO BOX 367	COLLEYVILLE, TX	76034	5713 COLLEYVILLE BLVD
50	BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 ARRINGTON GREEN
51	TYLER, KENT	1908 ARRINGTON CT	COLLEYVILLE, TX	76034	1908 ARRINGTON CT
52	DAVIS, RANDALL T	1901 STRATTON CT	COLLEYVILLE, TX	76034	1901 STRATTON CT
53	CRAWFORD, ADAM	1904 CAMDEN CT	COLLEYVILLE, TX	76034	1904 CAMDEN CT
54	TERRY DAVID & PENELOPE D JOI	1801 CAMDEN GREEN	COLLEYVILLE, TX	76034	1801 CAMDEN GREEN
55	INGLIS, WENDI	1912 CAMDEN CT	COLLEYVILLE, TX	76034	1912 CAMDEN CT
56	SULZER, STEFAN R	1804 CAMDEN GRN	COLLEYVILLE, TX	76034	1804 CAMDEN GREEN
57	SCHILLER, ADAM	2001 HALL JOHNSON RD	COLLEYVILLE, TX	76034	2001 HALL JOHNSON RD
58	DACUS, RANDALL	1709 ROCK DOVE CIR	COLLEYVILLE, TX	76034	1709 ROCK DOVE CIR
59	CAMPBELL, GREGORY A	1817 CAMDEN GRN	COLLEYVILLE, TX	76034	1817 CAMDEN GREEN
60	LONG REVOCABLE TRUST	1904 ARRINGTON CT	COLLEYVILLE, TX	76034	1904 ARRINGTON CT
61	SAIYED, FARID	1600 KINGSWOOD LN	COLLEYVILLE, TX	76034	1600 KINGSWOOD LN
62	CARMONA, ENRIQUE	1700 CRESTEDGE CT	COLLEYVILLE, TX	76034	1700 CRESTEDGE CT
63	BLUEBONNET HILLS MEMORIAL F	PO BOX 130548	HOUSTON, TX	77219	5713 COLLEYVILLE BLVD
64	VELOCIS COLLEYVILLE LP	3131 MCKINNEY AVE # 10	DALLAS, TX	75204	5655 BLUEBONNET DR
65	LAWN FIRM PROPERTIES LLC	PO BOX 1377	COLLEYVILLE, TX	76034	1605 HALL JOHNSON RD
66	COLLEYVILLE PROPERTIES LLC	3145 GEARY BLVD STE 737	SAN FRANCISCO, CA	94118	6213 COLLEYVILLE BLVD
67	GUTOWSKI, JOSEPH	1901 CAMDEN CT	COLLEYVILLE, TX	76034	1901 CAMDEN CT
68	USSERY, MICHAEL J	1800 ARRINGTON GRN	COLLEYVILLE, TX	76034	1800 ARRINGTON GREEN
69	GONZALEZ, ADOLFO	1813 GROSVENOR GRN	COLLEYVILLE, TX	76034	1813 GROSVENOR GREEN
70	PROCOD HOLDINGS INC	PO BOX 208	COLLEYVILLE, TX	76034	5900 COLLEYVILLE BLVD
71	GORE, FRANK C	6112 ROCK DOVE CIR	COLLEYVILLE, TX	76034	6112 ROCK DOVE CIR
72	HARDISTER, HAROLD	5507 NORMANDY DR	COLLEYVILLE, TX	76034	5507 NORMANDY DR
73	MEHTA, CHARLES R	1716 CRESTEDGE CT	COLLEYVILLE, TX	76034	1716 CRESTEDGE CT
74	CAMPO SAN ANTONIO LLC	PO BOX 15697	NEWPORT BEACH, CA	92659	6207 COLLEYVILLE BLVD
75	DACY, TIMOTHY	5705 MORLAIX CT	COLLEYVILLE, TX	76034	5705 MORLAIX CT
76	GOWDER, AMY	5709 MORLAIX CT	COLLEYVILLE, TX	76034	5709 MORLAIX CT
77	SWAIM, SHELLEY	1700 GATEHOUSE CT	COLLEYVILLE, TX	76034	1700 GATEHOUSE CT
78	SARRAT, CHRISTINA	1709 CRESTEDGE CT	COLLEYVILLE, TX	76034	1709 CRESTEDGE CT
79	GOLDEN, DENNIS A	1606 KINGSWOOD LN	COLLEYVILLE, TX	76034	1606 KINGSWOOD LN
80	CHELLGREN, PAUL	1820 CAMDEN GRN	COLLEYVILLE, TX	76034	1820 CAMDEN GREEN
81	KELLEY, BRENT A	1801 STRATTON GRN	COLLEYVILLE, TX	76034	1801 STRATTON GREEN
82	PALMERSHEIM, JAMES	1820 GROSVENOR GRN	COLLEYVILLE, TX	76034	1820 GROSVENOR GREEN
83	MARTIN, LINDA	6104 BRAZOS CT	COLLEYVILLE, TX	76034	6104 BRAZOS CT
84	DODSON, DAVID PAUL	1508 KINGSWOOD LN	COLLEYVILLE, TX	76034	1508 KINGSWOOD LN
85	ALFORD, BRENT	5600 NORMANDY DR	COLLEYVILLE, TX	76034	5600 NORMANDY DR
86	NELSON, MICHAEL JAY	5600 COVENTRY CT	COLLEYVILLE, TX	76034	5600 COVENTRY CT
87	SHEA, THOMAS P	1909 STRATTON CT	COLLEYVILLE, TX	76034	1909 STRATTON CT
88	HENDRIX, TERRY L	1610 KINGSWOOD LN	COLLEYVILLE, TX	76034	1610 KINGSWOOD LN
89	BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
90	CAPOBIANCO, ERNEST R	1900 GROSVENOR LN	COLLEYVILLE, TX	76034	1900 GROSVENOR LN
91	SANDERS, MARK R	1913 CAMDEN CT	COLLEYVILLE, TX	76034	1913 CAMDEN CT
92	BLUE BONNET HILLS	PO BOX 130548	HOUSTON, TX	77219	6001 COLLEYVILLE BLVD
93	RUCKER, RICHARD B	1704 GATEHOUSE CT	COLLEYVILLE, TX	76034	1704 GATEHOUSE CT
94	VELOCIS COLLEYVILLE LP	3131 MCKINNEY AVE # 10	DALLAS, TX	75204	5655 BLUEBONNET DR
95	CAMACHO, ANTHONY RANDALL	1904 GROSVENOR LN	COLLEYVILLE, TX	76034	1904 GROSVENOR LN
96	GIBSON, GERALD D	6100 BRAZOS CT	COLLEYVILLE, TX	76034	6100 BRAZOS CT
97	SULLIVAN, KIMBERLY	1804 GROSVENOR GRN	COLLEYVILLE, TX	76034	1804 GROSVENOR GREEN
98	RUSSELL, REX	1805 CAMDEN GRN	COLLEYVILLE, TX	76034	1805 CAMDEN GREEN
99	AL-SHMAISANI, ISSAM	5608 NORMANDY DR	COLLEYVILLE, TX	76034	5608 NORMANDY DR
100	DEBEUCKELAER, JAN	5606 NORMANDY DR	COLLEYVILLE, TX	76034	5606 NORMANDY DR
101	FULTZ, JAMES E	1809 STRATTON GRN	COLLEYVILLE, TX	76034	1809 STRATTON GREEN
102	GREEN REVOCABLE TRUST	1721 ROCK DOVE CIR	COLLEYVILLE, TX	76034	1721 ROCK DOVE CIR
103	JENKINS, WILLIAM	1913 STRATTON CT	COLLEYVILLE, TX	76034	1913 STRATTON CT
104	TANNA, NITIN	1905 GROSVENOR LN	COLLEYVILLE, TX	76034	1905 GROSVENOR LN
105	BENZICK, ARTHUR E	1808 CAMDEN GRN	COLLEYVILLE, TX	76034	1808 CAMDEN GREEN
106	WEWERS, MARK	5508 NORMANDY DR	COLLEYVILLE, TX	76034	5508 NORMANDY DR
107	WATSON, RICHARD	1900 STRATTON CT	COLLEYVILLE, TX	76034	1900 STRATTON CT
108	CAREY, MATTHEW	1809 GROSVENOR GRN	COLLEYVILLE, TX	76034	1809 GROSVENOR GREEN
109	BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
110	HINES, BRENT A	5504 COVENTRY CT	COLLEYVILLE, TX	76034	5504 COVENTRY CT
111	WILBUR FAMILY TRUST	1705 GATEHOUSE CT	COLLEYVILLE, TX	76034	1705 GATEHOUSE CT

112 HEIDEL, RUTH V	1712 GATEHOUSE CT	COLLEYVILLE, TX	76034	1712 GATEHOUSE CT
113 LOCKAMY, FRANKLIN D	1905 CAMDEN CT	COLLEYVILLE, TX	76034	1905 CAMDEN CT
114 KUNNEMAN, DALE	505 NORMANDY DR	COLLEYVILLE, TX	76034	5605 NORMANDY DR
115 WEINBERG, VICKIE	5603 NORMANDY DR	COLLEYVILLE, TX	76034	5603 NORMANDY DR
116 BLUEBONNET HILLS MEMORIAL F	PO BOX 130548	HOUSTON, TX	77219	5725 COLLEYVILLE BLVD
117 LAWN FIRM PROPERTIES LLC	PO BOX 1377	COLLEYVILLE, TX	76034	1605 HALL JOHNSON RD
118 VILLAS AT OAK POINTE HOA INC	6308 WESTCOAT DR	COLLEYVILLE, TX	76034	1731 FOUNTAIN PASS DR
119 CLEMENS, K R	1712 CRESTEDGE CT	COLLEYVILLE, TX	76034	1712 CRESTEDGE CT
120 DENNIS, KEN M	6104 ROCK DOVE CIR	COLLEYVILLE, TX	76034	6104 ROCK DOVE CIR
121 HOELLER, BRYAN	1817 GROSVENOR GREEN	COLLEYVILLE, TX	76034	1817 GROSVENOR GREEN
122 MODY, ALKA	1802 INDUSTRIAL BLVD	COLLEYVILLE, TX	76034	5601 NORMANDY DR
123 COLLEYVILLE, CITY OF	100 MAIN ST	COLLEYVILLE, TX	76034	1601 HALL JOHNSON RD
124 PULMONARY POB LTD	4504 BOAT CLUB RD STE 800	FORT WORTH, TX	76135	6000 COLLEYVILLE BLVD
125 LANGENBAHN, PAUL	1705 ROCK DOVE CIR	COLLEYVILLE, TX	76034	1705 ROCK DOVE CIR
126 COLLEYVILLE, CITY OF	100 MAIN ST	COLLEYVILLE, TX	76034	1601 HALL JOHNSON RD
127 G & J BRILLHART INC	817 S JEFFERSON ST	PERRYTON, TX	79670	6110 COLLEYVILLE BLVD
128 DIXON, DAVID	1800 STRATTON GRN	COLLEYVILLE, TX	76034	1800 STRATTON GREEN
129 FALI HOLDINGS INC	2326 W AIRPORT FWY	IRVING, TX	75062	6205 COLLEYVILLE BLVD
130 COLLEYVILLE, CITY OF	100 MAIN ST	COLLEYVILLE, TX	76034	1900 HALL JOHNSON RD
131 HAMMER, JOHN	1808 GROSVENOR GRN	COLLEYVILLE, TX	76034	1808 GROSVENOR GREEN
132 VAN BUSKIRK PROPERTIES LLC	107 BELMONT PLACE CIR	SOUTHLAKE, TX	75092	6118 COLLEYVILLE BLVD
133 SINUNU, STEPHEN A	1813 CAMDEN GRN	COLLEYVILLE, TX	76034	1813 CAMDEN GREEN
134 ROTH, THOMAS R	101 CROFTON AVE APT 100	SAN ANTONIO, TX	78210	5512 COVENTRY CT
135 ALKHERSAM, HUSAM H	1908 STRATTON CT	COLLEYVILLE, TX	76034	1908 STRATTON CT
136 COMER, CLARENCE	1901 GROSVENOR LN	COLLEYVILLE, TX	76034	1901 GROSVENOR LN
137 GOFF HOMES INC	1108 W PIONEER PKWY	ARLINGTON, TX	76013	5701 NORMANDY DR
138 BLUEBONNET HILLS CEMETERY	PO BOX 11250	NEW ORLEANS, LA	70181	5713 COLLEYVILLE BLVD
139 CASEY, ROBERT E	1805 STRATTON GRN	COLLEYVILLE, TX	76034	1805 STRATTON GREEN
140 BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
141 BICE, LEROY	1701 GATEHOUSE CT	COLLEYVILLE, TX	76034	1701 GATEHOUSE CT
142 MCMANUS, LUCY K	1701 CRESTEDGE CT	COLLEYVILLE, TX	76034	1701 CRESTEDGE CT
143 MONTCLAIR PARC INC	1108 W PIONEER PKWY	ARLINGTON, TX	76013	5710 MIRAMAR LN
144 TRAN, MICHAEL V	629 MATLOCK CENTRE CIR	ARLINGTON, TX	76015	1800 GROSVENOR GREEN
145 JONES, KENNETH L	1908 GROSVENOR LN	COLLEYVILLE, TX	76034	1908 GROSVENOR LN
146 YOUSAF, MOHAMMAD	1809 ARRINGTON GRN	COLLEYVILLE, TX	76034	1809 ARRINGTON GREEN
147 BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
148 VILLAS AT OAK POINTE HOA INC	6308 WESTCOAT DR	COLLEYVILLE, TX	76034	1712 ROCK DOVE CIR
149 CHEATHAM, STEPHANIE	1716 GATEHOUSE CT	COLLEYVILLE, TX	76034	1716 GATEHOUSE CT
150 PRINS, ORVILLE	1812 STRATTON GRN	COLLEYVILLE, TX	76034	1812 STRATTON GREEN
151 OLSON MICHAEL F S.T.D., BISHOI	800 W LOOP 820 S	FORT WORTH, TX	76108	6125 COLLEYVILLE BLVD
152 MCMASTER, JOSEPH	1912 ARRINGTON CT	COLLEYVILLE, TX	76034	1912 ARRINGTON CT
153 MULLINAX, DONALD R	6100 ROCK DOVE CIR	COLLEYVILLE, TX	76034	6100 ROCK DOVE CIR
154 BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 CAMDEN GREEN
155 BROCCO, CARLOS E	5613 VERSAILLES CT	COLLEYVILLE, TX	76034	5613 VERSAILLES CT
156 BLUEBONNET HILLS CEMETERY	PO BOX 130548	HOUSTON, TX	77219	5713 COLLEYVILLE BLVD
157 GLASSCOCK, D L	1708 GATEHOUSE CT	COLLEYVILLE, TX	76034	1708 GATEHOUSE CT
158 BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 GROSVENOR GREEN
159 GHALIBAF, AMIR A	5700 MIRAMAR LN	COLLEYVILLE, TX	76034	5700 MIRAMAR LN
160 BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 ARRINGTON CT
161 ROOYEN, DANIEL V	1604 KINGSWOOD LN	COLLEYVILLE, TX	76034	1604 KINGSWOOD LN
162 HOBBS, THOMAS R	1801 GROSVENOR GRN	COLLEYVILLE, TX	76034	1801 GROSVENOR GREEN
163 BOYD, LARRY G	PO BOX 279	COLLEYVILLE, TX	76034	1800 ARRINGTON GREEN
164 THE BENEFIT LINK INC	9117 BELSHIRE DR	NORTH RICHLAND HILLS, TX	76182	6208 COLLEYVILLE BLVD
165 PMT PARTNERS IX LTD	1565 KAPOLANI BLVD STE 1110	HONOLULU, HI	96814	6201 COLLEYVILLE BLVD
166 COLLEYVILLE SQUARE PTNRS II	99 MAIN ST STE 200	COLLEYVILLE, TX	76034	6201 COLLEYVILLE BLVD
167 BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 STRATTON GREEN
168 BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1829 GROSVENOR GREEN
169 VILLAS AT OAK POINTE HOA INC	6308 WESTCOAT DR	COLLEYVILLE, TX	76034	1728 ROCK DOVE CIR
170 BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1828 ARRINGTON GREEN
171 CWIKLA, THOMAS	1900 CAMDEN CT	COLLEYVILLE, TX	76034	1900 CAMDEN CT
172 PERFECT, DONALD	1909 CAMDEN CT	COLLEYVILLE, TX	76034	1909 CAMDEN CT
173 HEPPENSTALL, KARI	5701 MORLAIX CT	COLLEYVILLE, TX	76034	5701 MORLAIX CT
174 TOSELLO, PAUL A	PO BOX 1004	COLLEYVILLE, TX	76034	5413 COVENTRY CT
175 MILLER, DENNIS	1800 CAMDEN GRN	COLLEYVILLE, TX	76034	1800 CAMDEN GREEN
176 BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
177 GANESA, SAI	1812 GROSVENOR GRN	COLLEYVILLE, TX	76034	1812 GROSVENOR GREEN
178 JINDAL, RAKESH	1900 ARRINGTON CT	COLLEYVILLE, TX	76034	1900 ARRINGTON CT
179 CORAZE, MATHIEU	1709 GATEHOUSE CT	COLLEYVILLE, TX	76034	1709 GATEHOUSE CT
180 CRISCI, FRANK	1812 ARRINGTON GRN	COLLEYVILLE, TX	76034	1812 ARRINGTON GREEN
181 AL-SHMAISANI, ISSAM	5608 NORMANDY DR	COLLEYVILLE, TX	76034	5700 NORMANDY DR
182 WAYPOINT MONTESSORI	1513 HALL JOHNSON RD	COLLEYVILLE, TX	76034	1513 HALL JOHNSON RD
183 LUJAN, ALBERT C	1713 GATEHOUSE CT	COLLEYVILLE, TX	76034	1713 GATEHOUSE CT
184 BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1824 BROUGHTON DR
185 SRW KINGSTON COLLEYVILLE LF	1306 LAKESIDE CT	BARTONVILLE, TX	76226	6203 COLLEYVILLE BLVD
186 THIBODEAUX, NELSON J	5612 COVENTRY CT	COLLEYVILLE, TX	76034	5612 COVENTRY CT
187 IDELL, GLEN E	1708 CRESTEDGE CT	COLLEYVILLE, TX	76034	1708 CRESTEDGE CT
188 MOORE, BOBBY FAMILY LTD PRT	6113 COLLYVILLE BLVD	COLLEYVILLE, TX	76034	6113 COLLEYVILLE BLVD
189 PULMONARY POB LTD	4504 BOAT CLUB RD STE 800	FORT WORTH, TX	76135	6100 COLLEYVILLE BLVD
190 JONES, ROBERT E	1608 KINGSWOOD LN	COLLEYVILLE, TX	76034	1608 KINGSWOOD LN
191 BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	5801 BURNHAM CIR
192 SMART, BROOKE	1809 CAMDEN GRN	COLLEYVILLE, TX	76034	1809 CAMDEN GREEN
193 WILSON, SUSAN	1904 STRATTON CT	COLLEYVILLE, TX	76034	1904 STRATTON CT
194 BONDY, NEAL	1808 ARRINGTON GRN	COLLEYVILLE, TX	76034	1808 ARRINGTON GREEN
195 BONAIRE QUEST LLC	6215 COLLEYVILLE BLVD	COLLEYVILLE, TX	76034	6215 COLLEYVILLE BLVD
196 BROCK, MANDI	1704 CRESTEDGE CT	COLLEYVILLE, TX	76034	1704 CRESTEDGE CT
197 DUFFIE, DOUGLAS	1816 GROSVENOR GRN	COLLEYVILLE, TX	76034	1816 GROSVENOR GREEN
198 STOVALL, DANITA K	1701 ROCK DOVE CIR	COLLEYVILLE, TX	76034	1701 ROCK DOVE CIR
199 BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
200 MERHAB, MOHANNAD	5707 MORLAIX CT	COLLEYVILLE, TX	76034	5707 MORLAIX CT
201 ADAMS, RONALD	1725 ROCK DOVE CIR	COLLEYVILLE, TX	76034	1725 ROCK DOVE CIR
202 BOUGHTON MAINTENANCE ASSC	1800 PRESTON PARK BLVD STE 101	PLANO, TX	75093	1800 BROUGHTON DR
203 BUTTS, RICK L	1504 KINGSWOOD LN	COLLEYVILLE, TX	76034	1504 KINGSWOOD LN
204 AMACHER, AARON G	1909 ARRINGTON CT	COLLEYVILLE, TX	76034	1909 ARRINGTON CT
205 KANJI, SHIRAZALI	1905 STRATTON CT	COLLEYVILLE, TX	76034	1905 STRATTON CT
206 MADDOX, RICHARD	PO BOX 1646	COLLEYVILLE, TX	76034	5607 NORMANDY DR
207 STONE CREST HOA INC	1712 CRESTEDGE CT	COLLEYVILLE, TX	76034	5505 COVENTRY CT
208 MEEK, KARL W	6204 ROCK DOVE CIR	COLLEYVILLE, TX	76034	6204 ROCK DOVE CIR
209 BROUGHTON	2557 SW Grapevine Pkwy Suite 100	GRAPEVINE, TX	76051	COURTESY NOTICE
210 MONTCLAIR PARC ADDITION	1108 W. Pioneer Parkway	ARLINGTON, TX	76013	COURTESY NOTICE
211 STONE CREST ESTATES	P.O. Box 332	COLLEYVILLE, TX	76034	COURTESY NOTICE
212 GRAPEVINE COLLEYVILLE ISD				STATE REQUIRES

Notification Map



DISCLAIMER:

This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

ZC17-023

8060 Precinct Line Road




Subject Property



200ft Buffer




Properties within 200ft



OBJECTID	Owner_Name	Owner_Addr	Owner_City	Owner_Zip	Owner_Zip4	Situs_Addr
1	CARRINGTON, WADE	6004 STERLING DR	COLLEYVILLE, TX	76034	7632	6004 STERLING DR
2	TOV VENTURE LTD	16950 DALLAS PKWY STE 120	DALLAS, TX	75248	1942	8070 PRECINCT LINE RD
3	GRACE, STEPHEN	6000 STERLING DR	COLLEYVILLE, TX	76034		6000 STERLING DR
4	MILLS, ANDREW E	6008 STERLING DR	COLLEYVILLE, TX	76034		6008 STERLING DR
5	EMERALD PARK H A INC	400 COUNTRY PL	COLLEYVILLE, TX	76034		6012 STERLING DR
6	ADLER, KEITH	1112 GLADE RD	COLLEYVILLE, TX	76034	4227	8080 PRECINCT LINE RD
7	SIMMONS, DAVID	5924 STERLING DR	COLLEYVILLE, TX	76034	7631	5924 STERLING DR
8	JONES, JERRELL W	11111 ABBEYWOOD	OKLAHOMA CITY, OK	73170	3208	8050 PRECINCT LINE RD
9	KWUN, SUN T	5928 STERLING DR	COLLEYVILLE, TX	76034	7631	5928 STERLING DR
10	EMERALD PARK H A INC	400 COUNTRY PL	COLLEYVILLE, TX	76034		5802 CRESCENT LN
11	WILLIAM D SOUDER INVESTMENT	2729 CRYSTAL RIDGE CIR	HURST, TX	76054		PRECINCT LINE RD
12	STANLEY, LARRY J EST	1101 LAVACA TR	COLLEYVILLE, TX	76034	7561	1101 LAVACA TR
13						8078 PRECINCT LINE RD
14						8074 PRECINCT LINE RD
15	EMERALD PARK ADDITION -COLLI	5837 Crescent	COLLEYVILLE, TX	76034		COURTESY NOTICE
16	LAVACA TRAIL ESTATES		COLLEYVILLE, TX	76034		COURTESY NOTICE
17	Keller ISD					STATE REQUIRES

Notification Map




ZC17-023

8060 Precinct Line Road


DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

-  Subject Property
-  300ft Buffer
-  Properties within 300ft



OBJECTID	Owner_Name	Owner_Addr	Owner_City	Owner_Zip	Situs_Addr
1	CARRINGTON, WADE	6004 STERLING DR	COLLEYVILLE, TX	76034	6004 STERLING DR
2	TOV VENTURE LTD	16950 DALLAS PKWY STE 120	DALLAS, TX	75248	8070 PRECINCT LINE RD
3	GRACE, STEPHEN	6000 STERLING DR	COLLEYVILLE, TX	76034	6000 STERLING DR
4	MILLS, ANDREW E	6008 STERLING DR	COLLEYVILLE, TX	76034	6008 STERLING DR
5	EMERALD PARK H A INC	400 COUNTRY PL	COLLEYVILLE, TX	76034	6012 STERLING DR
6	ADLER, KEITH	1112 GLADE RD	COLLEYVILLE, TX	76034	8080 PRECINCT LINE RD
7	SIMMONS, DAVID	5924 STERLING DR	COLLEYVILLE, TX	76034	5924 STERLING DR
8	GRASSI, KAREN	6005 STERLING DR	COLLEYVILLE, TX	76034	6005 STERLING DR
9	ROTHROCK, ANGEL	5920 STERLING DR	COLLEYVILLE, TX	76034	5920 STERLING DR
10	EMERALD PARK H A INC	400 COUNTRY PL	COLLEYVILLE, TX	76034	5800 CRESCENT LN
11	LARSEN, SCOTT R	6016 STERLING DR	COLLEYVILLE, TX	76034	6016 STERLING DR
12	JONES, JERRELL W	11111 ABBEYWOOD	OKLAHOMA CITY, OK	73170	8050 PRECINCT LINE RD
13	KWUN, SUN T	5928 STERLING DR	COLLEYVILLE, TX	76034	5928 STERLING DR
14	EMERALD PARK H A INC	400 COUNTRY PL	COLLEYVILLE, TX	76034	5802 CRESCENT LN
15	WILLIAM D SOUDER INVESTMENT	2729 CRYSTAL RIDGE CIR	HURST, TX	76054	8060 PRECINCT LINE RD
16	CAREY, DEVIN J	6020 STERLING DR	COLLEYVILLE, TX	76034	6020 STERLING DR
17	STANLEY, LARRY J EST	1101 LAVACA TR	COLLEYVILLE, TX	76034	1101 LAVACA TR
18					8078 PRECINCT LINE RD
19	FEGAN, DENNIS J	1303 BELLEFONTE LN	COLLEYVILLE, TX	76034	1013 LAVACA TR
20					8074 PRECINCT LINE RD
21	EMERALD PARK ADDITION -COLLI 5837 Crescent		COLLEYVILLE, TX	76034	COURTESY NOTICE
22	LAVACA TRAIL ESTATES		COLLEYVILLE, TX	76034	COURTESY NOTICE
23	KELLER ISD				STATE REQUIRES

Notification Map



ZC17-023

8060 Precinct Line Road


DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

-  Subject Property
-  500ft Buffer
-  Properties within 500ft



OBJECTID	Owner_Name	Owner_Addr	Owner_City	Owner_Zip	Situs_Addr
1	CARRINGTON, WADE	6004 STERLING DR	COLLEYVILLE, TX	76034	6004 STERLING DR
2	TISSERA, SHIMAL A	5921 STERLING DR	COLLEYVILLE, TX	76034	5921 STERLING DR
3	BRICE, TONY J	6021 STERLING DR	COLLEYVILLE, TX	76034	6021 STERLING DR
4	TOV VENTURE LTD	16950 DALLAS PKWY STE 120	DALLAS, TX	75248	8070 PRECINCT LINE RD
5	GRACE, STEPHEN	6000 STERLING DR	COLLEYVILLE, TX	76034	6000 STERLING DR
6	SMITH, FERMAN P	5918 CRESCENT LN	COLLEYVILLE, TX	76034	5918 CRESCENT LN
7	EISENBARTH, JENNIFER L	6032 STERLING DR	COLLEYVILLE, TX	76034	6032 STERLING DR
8	MILLS, ANDREW E	6008 STERLING DR	COLLEYVILLE, TX	76034	6008 STERLING DR
9	PIETROBON, JOHN	5916 STERLING DR	COLLEYVILLE, TX	76034	5916 STERLING DR
10	OLIPHANT, NEKESHA	5909 STERLING DR	COLLEYVILLE, TX	76034	5909 STERLING DR
11	PANCHAL, PRINCE H	6024 STERLING DR	COLLEYVILLE, TX	76034	6024 STERLING DR
12	NEILSON, HOWARD S	5922 CRESCENT LN	COLLEYVILLE, TX	76034	5922 CRESCENT LN
13	EMERALD PARK H A INC	400 COUNTRY PL	COLLEYVILLE, TX	76034	6012 STERLING DR
14	VU, DON C	5908 STERLING DR	COLLEYVILLE, TX	76034	5908 STERLING DR
15	SINGLES, BRANDON S	5912 STERLING DR	COLLEYVILLE, TX	76034	5912 STERLING DR
16	SAKURAI, KAORU	5917 STERLING DR	COLLEYVILLE, TX	76034	5917 STERLING DR
17	DUDDING, MICHAEL	6025 STERLING DR	COLLEYVILLE, TX	76034	6025 STERLING DR
18	ADLER, KEITH	1112 GLADE RD	COLLEYVILLE, TX	76034	8080 PRECINCT LINE RD
19	SPRING, AYESHANILL	5913 STERLING DR	COLLEYVILLE, TX	76034	5913 STERLING DR
20	SIMMONS, DAVID	5924 STERLING DR	COLLEYVILLE, TX	76034	5924 STERLING DR
21	GRASSI, KAREN	6005 STERLING DR	COLLEYVILLE, TX	76034	6005 STERLING DR
22	ROTHROCK, ANGEL	5920 STERLING DR	COLLEYVILLE, TX	76034	5920 STERLING DR
23	CROWE, DANIEL L	6028 STERLING DR	COLLEYVILLE, TX	76034	6028 STERLING DR
24	EMERALD PARK H A INC	400 COUNTRY PL	COLLEYVILLE, TX	76034	5800 CRESCENT LN
25	LARSEN, SCOTT R	6016 STERLING DR	COLLEYVILLE, TX	76034	6016 STERLING DR
26	JONES, JERRELL W	11111 ABBEYWOOD	OKLAHOMA CITY, OK	73170	8050 PRECINCT LINE RD
27	KWUN, SUN T	5928 STERLING DR	COLLEYVILLE, TX	76034	5928 STERLING DR
28	EMERALD PARK H A INC	400 COUNTRY PL	COLLEYVILLE, TX	76034	5802 CRESCENT LN
29	WILLIAM D SOUDER INVESTMENT	2729 CRYSTAL RIDGE CIR	HURST, TX	76054	8060 PRECINCT LINE RD
30	CAREY, DEVIN J	6020 STERLING DR	COLLEYVILLE, TX	76034	6020 STERLING DR
31	JAETZOLD, CORY B	6204 EMMAS CT	COLLEYVILLE, TX	76034	6204 EMMAS CT
32	THE BIG EASY BLUES AND CARE	6112 EMMAS CT	COLLEYVILLE, TX	76034	6112 EMMAS CT
33	L T ESTATES HOA INC	215 W COLLEGE ST	GRAPEVINE, TX	76051	6100 EMMAS CT
34	WARRICK, DAVID	6104 EMMAS CT	COLLEYVILLE, TX	76034	6104 EMMAS CT
35	PATEL, SHAILESH	6108 EMMAS CT	COLLEYVILLE, TX	76034	6108 EMMAS CT
36	PAL, ROHAN	6200 EMMAS CT	COLLEYVILLE, TX	76034	6200 EMMAS CT
37	STANLEY, LARRY J EST	1101 LAVACA TR	COLLEYVILLE, TX	76034	1101 LAVACA TR
38					8078 PRECINCT LINE RD
39	FEGAN, DENNIS J	1303 BELLEFONTE LN	COLLEYVILLE, TX	76034	1013 LAVACA TR
40	LINLES PROPERTIES LTD	2601 HIGHLAND MEADOW DR	COLLEYVILLE, TX	76034	8090 PRECINCT LINE RD
41					8086 PRECINCT LINE RD
42					8074 PRECINCT LINE RD
43	EMERALD PARK ADDITION -COLLI 5837 Crescent		COLLEYVILLE, TX	76034	COURTESY NOTICE
44	LAVACA TRAIL ESTATES		COLLEYVILLE, TX	76034	COURTESY NOTICE
45	KELLER ISD				STATE REQUIRES

Notification Map



ZC17-023

8060 Precinct Line Road

DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

-  Subject Property
-  1000ft Buffer
-  Properties within 1000ft



OBJECTID	Owner_Name	Owner_Addr	Owner_City	Owner_Zip	Situs_Addr
1	POTTER, MARGARET G	6220 CIMMARON TR	COLLEYVILLE, TX	76034	6220 CIMMARON TR
2	CARRINGTON, WADE	6004 STERLING DR	COLLEYVILLE, TX	76034	6004 STERLING DR
3	APGAR FAMILY TRUST	6209 CIMMARON TR	COLLEYVILLE, TX	76034	6209 CIMMARON TR
4	VILLAS OF COLLEYVILLE HOA LLC	1108 W PIONEER PKWY	ARLINGTON, TX	76013	6205 CIMMARON TR
5	STEVENSON-DUPUY LIVING TRUS	5828 STERLING DR	COLLEYVILLE, TX	76034	5828 STERLING DR
6	LAVACA PARC HOMEOWNERS AS	1540 KELLER PKWY STE 108-151	KELLER, TX	76248	6201 LANTANA CT
7	STROUD, HAROLD	6212 CIMMARON TRL	COLLEYVILLE, TX	76034	6212 CIMMARON TR
8	TISSERA, SHIMAL A	5921 STERLING DR	COLLEYVILLE, TX	76034	5921 STERLING DR
9	COLLINS, IRMA V	5849 CRESCENT LN	COLLEYVILLE, TX	76034	5849 CRESCENT LN
10	TAYLOR, TOLLESON	5907 CRESCENT LN	COLLEYVILLE, TX	76034	5907 CRESCENT LN
11	SCOTT, ROBERT L	5846 CRESCENT LN	COLLEYVILLE, TX	76034	5846 CRESCENT LN
12	PEREIRA, VERNON	5842 CRESCENT LN	COLLEYVILLE, TX	76034	5842 CRESCENT LN
13	RISHIEL, ROBERT	5912 ST ANDREWS CT	COLLEYVILLE, TX	76034	5912 ST ANDREWS CT
14	SANDERS, JEFFREY J	1916 FAIR FIELD DR	GRAPEVINE, TX	76051	6004 ST ANDREWS CT
15	BRICE, TONY J	6021 STERLING DR	COLLEYVILLE, TX	76034	6021 STERLING DR
16	TOV VENTURE LTD	16950 DALLAS PKWY STE 120	DALLAS, TX	75248	8070 PRECINCT LINE RD
17	MORRIS, SCOTT	5902 CRESCENT LN	COLLEYVILLE, TX	76034	5902 CRESCENT LN
18	GRACE, STEPHEN	6000 STERLING DR	COLLEYVILLE, TX	76034	6000 STERLING DR
19	SMITH, FERMAN P	5918 CRESCENT LN	COLLEYVILLE, TX	76034	5918 CRESCENT LN
20	EISENBARTH, JENNIFER L	6032 STERLING DR	COLLEYVILLE, TX	76034	6032 STERLING DR
21	BUTCHART, MICHAEL J	5923 CRESCENT LN	COLLEYVILLE, TX	76034	5923 CRESCENT LN
22	MILLS, ANDREW E	6008 STERLING DR	COLLEYVILLE, TX	76034	6008 STERLING DR
23	PIETROBON, JOHN	5916 STERLING DR	COLLEYVILLE, TX	76034	5916 STERLING DR
24	OLIPHANT, NEKESHA	5909 STERLING DR	COLLEYVILLE, TX	76034	5909 STERLING DR
25	LESKINEN, OLIVIA K	5911 CRESCENT LN	COLLEYVILLE, TX	76034	5911 CRESCENT LN
26	STRITTMATTER, MARTIN	6213 CIMMARON TR	COLLEYVILLE, TX	76034	6213 CIMMARON TR
27	LAVACA PARC HOMEOWNERS AS	1540 KELLER PKWY STE 108-151	KELLER, TX	76248	6200 LANTANA CT
28	SHARP, JAMES	5905 STERLING DR	COLLEYVILLE, TX	76034	5905 STERLING DR
29	GIEBLER, TERRY L	5820 STERLING DR	COLLEYVILLE, TX	76034	5820 STERLING DR
30	ANDREOLA, DANIEL	5839 STERLING DR	COLLEYVILLE, TX	76034	5839 STERLING DR
31	HSU, LISA L W	6204 LANTANA CT	COLLEYVILLE, TX	76034	6204 LANTANA CT
32	JUMA, SAMIR	5835 STERLING DR	COLLEYVILLE, TX	76034	5835 STERLING DR
33	CURTIS, ANTHONY L	5915 CRESCENT LN	COLLEYVILLE, TX	76034	5915 CRESCENT LN
34	BURLESON, RHONDA	5914 CRESCENT LN	COLLEYVILLE, TX	76034	5914 CRESCENT LN
35	MARTINEZ, CHARLES	5832 STERLING DR	COLLEYVILLE, TX	76034	5832 STERLING DR
36	PANCHAL, PRINCE H	6024 STERLING DR	COLLEYVILLE, TX	76034	6024 STERLING DR
37	NEILSON, HOWARD S	5922 CRESCENT LN	COLLEYVILLE, TX	76034	5922 CRESCENT LN
38	THE NEUFELD FAMILY REVOCABL	5831 STERLING DR	COLLEYVILLE, TX	76034	5831 STERLING DR
39	EMERALD PARK H A INC	400 COUNTRY PL	COLLEYVILLE, TX	76034	6012 STERLING DR
40	CHERNLY REVOCABLE TRUST	5843 STERLING DR	COLLEYVILLE, TX	76034	5843 STERLING DR
41	VILLAS OF COLLEYVILLE HOA LLC	1108 W PIONEER PKWY	ARLINGTON, TX	76013	6200 CIMMARON TR
42	VU, DON C	5908 STERLING DR	COLLEYVILLE, TX	76034	5908 STERLING DR
43	SINGLES, BRANDON S	5912 STERLING DR	COLLEYVILLE, TX	76034	5912 STERLING DR
44	WALTER, CRAIG A	5910 CRESCENT LN	COLLEYVILLE, TX	76034	5910 CRESCENT LN
45	SAKURAI, KAORU	5917 STERLING DR	COLLEYVILLE, TX	76034	5917 STERLING DR
46	DUDDING, MICHAEL	6025 STERLING DR	COLLEYVILLE, TX	76034	6025 STERLING DR
47	RICKSTREW, EMERSON	5927 CRESCENT LN	COLLEYVILLE, TX	76034	5927 CRESCENT LN
48	GUGLIUZZA, DOMENICO A	6208 CIMMARON TR	COLLEYVILLE, TX	76034	6208 CIMMARON TR
49	ADLER, KEITH	1112 GLADE RD	COLLEYVILLE, TX	76034	8080 PRECINCT LINE RD
50	GALLOWAY, JOHN W	5847 STERLING DR	COLLEYVILLE, TX	76034	5847 STERLING DR
51	RAMUNDI, KRISTY	5309 BRAEDON LN	COLLEYVILLE, TX	76034	6204 CIMMARON TR
52	SCULL, DIANE	5900 STERLING DR	COLLEYVILLE, TX	76034	5900 STERLING DR
53	SPRING, AYESHANILL	5913 STERLING DR	COLLEYVILLE, TX	76034	5913 STERLING DR
54	SIMMONS, DAVID	5924 STERLING DR	COLLEYVILLE, TX	76034	5924 STERLING DR
55	MOLSON, ALAN H	6205 CIMMARON TR	COLLEYVILLE, TX	76034	6205 CIMMARON TR
56	RIEWE, KERMIT M	6217 CIMMARON TR	COLLEYVILLE, TX	76034	6217 CIMMARON TR
57	WILLIS LIVING TRUST	5906 CRESCENT LN	COLLEYVILLE, TX	76034	5906 CRESCENT LN
58	CHOUDHARY, ASHWANI	5840 STERLING DR	COLLEYVILLE, TX	76034	5840 STERLING DR
59	SHAW, CHRISTOPHER	6216 CIMMARON TR	COLLEYVILLE, TX	76034	6216 CIMMARON TR
60	COFFIN, ROBERT	5845 CRESCENT LN	COLLEYVILLE, TX	76034	5845 CRESCENT LN
61	GRASSI, KAREN	6005 STERLING DR	COLLEYVILLE, TX	76034	6005 STERLING DR
62	RAMIREZ-ROMERO, EDUARDO	5903 CRESCENT LN	COLLEYVILLE, TX	76034	5903 CRESCENT LN
63	DAMRON, MELANIE K	5830 CRESCENT LN	COLLEYVILLE, TX	76034	5830 CRESCENT LN
64	TARVER, RUSSELL	6205 LANTANA CT	COLLEYVILLE, TX	76034	6205 LANTANA CT
65	ROTHROCK, ANGEL	5920 STERLING DR	COLLEYVILLE, TX	76034	5920 STERLING DR
66	SHIPLEY, JENNIFER	5919 CRESCENT LN	COLLEYVILLE, TX	76034	5919 CRESCENT LN
67	MELHART, LAUREN E	5844 STERLING DR	COLLEYVILLE, TX	76034	5844 STERLING DR
68	CROWE, DANIEL L	6028 STERLING DR	COLLEYVILLE, TX	76034	6028 STERLING DR
69	OLEARY, BRYAN J	5837 CRESCENT LN	COLLEYVILLE, TX	76034	5837 CRESCENT LN
70	MARKHAM, DIAN L ETAL	5000 GADSDEN AVE	FORT WORTH, TX	76244	8000 PRECINCT LINE RD
71	OSTENDORF LIVING TRUST	5904 STERLING DR	COLLEYVILLE, TX	76034	5904 STERLING DR
72	WHITE, RUSSELL F	5834 CRESCENT LN	COLLEYVILLE, TX	76034	5834 CRESCENT LN
73	OSWALD, JENNY F	5841 CRESCENT LN	COLLEYVILLE, TX	76034	5841 CRESCENT LN
74	EMERALD PARK H A INC	400 COUNTRY PL	COLLEYVILLE, TX	76034	5800 CRESCENT LN
75	HONZA, CALVIN D	5838 CRESCENT LN	COLLEYVILLE, TX	76034	5838 CRESCENT LN
76	LARSEN, SCOTT R	6016 STERLING DR	COLLEYVILLE, TX	76034	6016 STERLING DR
77	JONES, JERRELL W	11111 ABBEYWOOD	OKLAHOMA CITY, OK	73170	8050 PRECINCT LINE RD
78	KWUN, SUN T	5928 STERLING DR	COLLEYVILLE, TX	76034	5928 STERLING DR
79	EMERALD PARK H A INC	400 COUNTRY PL	COLLEYVILLE, TX	76034	5802 CRESCENT LN
80	WILLIAM D SOUDER INVESTMENT	2729 CRYSTAL RIDGE CIR	HURST, TX	76054	8060 PRECINCT LINE RD
81	TEMESGEN, ADAMU	5935 CRESCENT LN	COLLEYVILLE, TX	76034	5935 CRESCENT LN
82	SMITH, GREG	5836 STERLING DR	COLLEYVILLE, TX	76034	5836 STERLING DR
83	LANTZ, KRISTAL	5901 STERLING DR	COLLEYVILLE, TX	76034	5901 STERLING DR
84	OUR COUNTRY HOMES INC	700 W HARWOOD RD STE G2	HURST, TX	76054	6000 ST ANDREWS CT
85	VARGHESE, GEORGE	5824 STERLING DR	COLLEYVILLE, TX	76034	5824 STERLING DR
86	CAREY, DEVIN J	6020 STERLING DR	COLLEYVILLE, TX	76034	6020 STERLING DR
87	ROBBINS, DONALD	5931 CRESCENT LN	COLLEYVILLE, TX	76034	5931 CRESCENT LN
88	ELLISON, JOHN	5905 KAYS CT	COLLEYVILLE, TX	76034	5905 KAYS CT
89	PHINNEY, JASON	6213 EMMAS CT	COLLEYVILLE, TX	76034	6213 EMMAS CT
90	YAZDANI, SAEED	6101 EMMAS CT	COLLEYVILLE, TX	76034	6101 EMMAS CT
91	JAETZOLD, CORY B	6204 EMMAS CT	COLLEYVILLE, TX	76034	6204 EMMAS CT
92	L T ESTATES HOA INC	215 W COLLEGE ST	GRAPEVINE, TX	76051	6215 EMMAS CT
93	THE BIG EASY BLUES AND CARE F	6112 EMMAS CT	COLLEYVILLE, TX	76034	6112 EMMAS CT
94	CHANDLER, CHARLOTTE	6205 EMMAS CT	COLLEYVILLE, TX	76034	6205 EMMAS CT
95	BOOTS, BRIAN	5900 KAYS CT	COLLEYVILLE, TX	76034	5900 KAYS CT
96	AJBANI, VIVEK	6212 EMMAS CT	COLLEYVILLE, TX	76034	6212 EMMAS CT
97	SIDHU, SHELLY	5908 KAYS CT	COLLEYVILLE, TX	76034	5908 KAYS CT
98	AKINMERESE, OLAWALE	5912 KAYS CT	COLLEYVILLE, TX	76034	5912 KAYS CT
99	DURHAM, RAYMOND	5917 KAYS CT	COLLEYVILLE, TX	76034	5917 KAYS CT
100	L T ESTATES HOA INC	215 W COLLEGE ST	GRAPEVINE, TX	76051	6100 EMMAS CT
101	L T ESTATES HOA INC	215 W COLLEGE ST	GRAPEVINE, TX	76051	5812 KAYS CT
102	WARRICK, DAVID	6104 EMMAS CT	COLLEYVILLE, TX	76034	6104 EMMAS CT
103	DINH, NHUNG	5913 KAYS CT	COLLEYVILLE, TX	76034	5913 KAYS CT
104	GOLDSMITH, SAGE	5904 KAYS CT	COLLEYVILLE, TX	76034	5904 KAYS CT
105	MOTI, SALEEM	6216 EMMAS CT	COLLEYVILLE, TX	76034	6216 EMMAS CT
106	L T ESTATES HOA INC	215 W COLLEGE ST	GRAPEVINE, TX	76051	6218 EMMAS CT

107 NYKIEL, STEPHEN	5909 KAYS CT	COLLEYVILLE, TX	76034	5909 KAYS CT
108 HOGAN, EDWARD L	6201 EMMAS CT	COLLEYVILLE, TX	76034	6201 EMMAS CT
109 PATEL, SHAILESH	6108 EMMAS CT	COLLEYVILLE, TX	76034	6108 EMMAS CT
110 RIFFE, BRYAN D	6208 EMMAS CT	COLLEYVILLE, TX	76034	6208 EMMAS CT
111 STRICKLAND, JEFFREY S	6113 EMMAS CT	COLLEYVILLE, TX	76034	6113 EMMAS CT
112 PAL, ROHAN	6200 EMMAS CT	COLLEYVILLE, TX	76034	6200 EMMAS CT
113 CROSSNO, DAWN	6109 EMMAS CT	COLLEYVILLE, TX	76034	6109 EMMAS CT
114 ANDERSEN, ROBERT	6105 EMMAS CT	COLLEYVILLE, TX	76034	6105 EMMAS CT
115 GEORGE, ANISH	6209 EMMAS CT	COLLEYVILLE, TX	76034	6209 EMMAS CT
116 MOSS, PAUL	PO BOX 171676	ARLINGTON, TX	76003	8092 PRECINCT LINE RD
117 LDAC PROPERTIES LLC	610 UVALDE DR	KELLER, TX	76248	8096 PRECINCT LINE RD
118 MOSS, PAUL	PO BOX 171676	ARLINGTON, TX	76003	8098 W LAVACA TRL
119 WELLTOWER INC	4500 DORR ST	TOLEDO, OH	43615	8100 PRECINCT LINE RD
120 STANLEY, LARRY J EST	1101 LAVACA TR	COLLEYVILLE, TX	76034	1101 LAVACA TR
121				8078 PRECINCT LINE RD
122 FEGAN, DENNIS J	1303 BELLEFONTE LN	COLLEYVILLE, TX	76034	1013 LAVACA TR
123 LINES PROPERTIES LTD	2601 HIGHLAND MEADOW DR	COLLEYVILLE, TX	76034	8090 PRECINCT LINE RD
124 LEGACY AT COLLEYVILLE LLC THE	PO BOX 92747	SOUTHLAKE, TX	76092	6112 LEGACY TR
125 LEGACY AT COLLEYVILLE LLC THE	PO BOX 92747	SOUTHLAKE, TX	76092	812 LEGACY TR
126				
127 KM PROPERTIES INC	PO BOX 44	HURST, TX	76053	6200 LEGACY TR
128 HATWATER LLC	508 RANCHO LAREDO TR	SOUTHLAKE, TX	76092	6116 LEGACY TR
129 REATA BROKERAGE SERVICES LL	4323 GLOSTER RD	DALLAS, TX	75220	6104 LEGACY TR
130 REATA BROKERAGE SERVICES LL	4323 GLOSTER RD	DALLAS, TX	75220	905 LYNDSLEY WAY
131 REATA BROKERAGE SERVICES LL	4323 GLOSTER RD	DALLAS, TX	75220	6108 LEGACY TR
132 OUR COUNTRY HOMES INC	700 W HARWOOD RD	HURST, TX	76054	913 LYNDSLEY WAY
133 REATA BROKERAGE SERVICES LL	4323 GLOSTER RD	DALLAS, TX	75220	6100 LEGACY TR
134				8086 PRECINCT LINE RD
135				8074 PRECINCT LINE RD
136 EMERALD PARK ADDITION -COLLE	5837 Crescent	COLLEYVILLE, TX	76034	COURTESY NOTICE
137 LAVACA TRAIL ESTATES		COLLEYVILLE, TX	76034	COURTESY NOTICE
138 KELLER ISD				STATE REQUIRES







Street View - Jun 2015

