



City of Colleyville Planning and Zoning Commission Agenda

City Hall
100 Main Street
Colleyville, Texas 76034
817. 503.1000
www.colleyville.com

Monday, August 13, 2018

City Council Chambers

**PRE COMMISSION MEETING
6:15 P.M.
EXECUTIVE CONFERENCE ROOM
THIRD FLOOR**

**LEGAL BRIEFING BY CITY ATTORNEY REGARDING PLANNING, ZONING,
PLATTING, AND LAND USE**

**REVIEW OF REGULAR AGENDA ITEMS AND DISCUSSION OF PREVIOUS
MEETING MINUTES**

**DISCUSSION OF ITEMS TO BE PLACED ON FUTURE AGENDAS AND
UPDATES ON DEVELOPMENT TRENDS, PROGRESS AND CITY COUNCIL
ACTIONS ON PAST AGENDA ITEMS**

**EXECUTIVE SESSION – In accordance with Texas Government Code
Chapter 551, Subchapter D, Section 551.071 – Legal – Consultation with
attorney on legal issues raised by public hearing or action items on the
agenda**

**7:00 P.M. - REGULAR MEETING
CALL TO ORDER AND ROLL
INVOCATION: COMMISSIONER BEVILL
PLEDGE OF ALLEGIANCE**

- 1. CITIZEN COMMENTS/PRESENTATIONS REGARDING ITEMS NOT ON
THE AGENDA**
- 2. PUBLIC HEARING AGENDA ITEMS**
 - 2a** Consideration of a Special Use Permit for an Automotive Repair Shop
on Lot 1A, Block 1, of the Highway 26 Industrial, located at 6804
Colleyville Boulevard, Case ZC18-020

- 2b** Consideration of a zoning change from AG to R-30 on Tract 2A01 & 2A02, Abstract 1543, in the George W Teeter Survey, located at 1309 Glade Road, Case ZC18-023
- 2c** Consideration of a combination Preliminary/Final Plat of Tract 2A01 & 2A02, Abstract 1543, in the George W Teeter Survey, located at 1309 Glade Road, Case PC18-012
- 2d** Consideration of amendments to the Land Development Code, specifically Chapter 3 – Land Use, Chapter 8 – Plat Review Procedures, and Chapter 9 – Subdivision Design & Public Facilities

3. ADJOURNMENT

I hereby certify this agenda was posted on City Hall bulletin boards on August 10, 2018 by 5:00 p.m.



Araceli Botello
Planning Technician

A quorum of the Colleyville City Council may be in attendance at this meeting.

Any matter on this agenda may, at the discretion of the governing body, be opened for public comment and discussion.

If you plan to attend this public meeting and have a disability that requires special accommodations, please advise the City Secretary at least 48 hours in advance at 817.503.1133, and reasonable accommodations will be made to assist you.



City of Colleyville Planning and Zoning Commission Agenda Briefing

City Hall
100 Main Street
Colleyville, Texas 76034
www.colleyville.com

Agenda Number 2a	Agenda Date 08/13/2018	Number
Type Public Hearing Agenda Items		
Department Community Development		

Title

Consideration of a Special Use Permit for an Automotive Repair Shop on Lot 1A, Block 1, of the Highway 26 Industrial, located at 6804 Colleyville Boulevard, Case ZC18-020

Explanation

Jerry DeFeo, the applicant, has submitted a request for a Special Use Permit (SUP) for an Automotive Repair Shop on Lot 1A, Block 1, of the Highway 26 Industrial addition, being approximately 0.95 acres, and zoned ML Light Manufacturing district. The purpose is to allow for automotive repair services at the business under the name of Colleyville JHCC LLC, dba Joe Hudson's Collision Center.

Existing Conditions/Background: The subject property, at 6804 Colleyville Boulevard, has ML Light Manufacturing and is located on the southwest corner of Tension Parkway and Colleyville Boulevard. The subject property is currently operating as Lone Star Collision.

Proposed Special Use Permit:

Request – The applicant is requesting approval of an SUP to allow for Joe Hudson's Collision Center to operate an automotive repair shop. Conditions were placed on the use with approval of the previous SUP, which include:

1. This Special Use Permit shall apply only to Building B, as shown on the attached Zoning Exhibit.
2. The hours of operation shall be Monday through Friday from 7:00 a.m. to 7:00 p.m. and Saturday 8:00 a.m. to noon.
3. Overnight parking of vehicles shall be allowed outside the building, provided that the vehicles parked to the rear of Building B, as shown on the attached Zoning Exhibit. Vehicles such as boats, recreational vehicles and trailer shall not be parked or stored in the outside parking area.
4. All vehicles waiting for repair shall be parked to the rear of the building.
5. No storage of parts or containers shall be allowed outside the building.
6. All repair work shall be done inside the building.
7. This Special Use Permit shall automatically expire upon the abandonment of the business, change in use, a change in ownership or upon the expiration or termination of the Certificate of Occupancy.
8. All requirements of the Land Development Code shall be met, except where

amended herein.

Analysis: The requested SUP is required by the Land Development Code with City Council approval for approval of an Auto Repair Shop at this location due to a change of ownership. The applicant intends to use the location in the same capacity as it is currently being utilized. They are not requesting any changes to the current conditions on site, just a change in the ownership of the business.

Surrounding Development: The property to the north across Tennison Parkway is zoned PUD-R district and is developed as office commercial, the property to the south is zoned ML Light Manufacturing and developed as an auto sales , the property to the west is zoned PUD-R and is undeveloped, and the property to the east is Colleyville Boulevard.

Comprehensive Plan: The City's comprehensive plan, *Destination Colleyville*, identifies the subject property as part of the 'Colleyville Boulevard Corridor' and is designated as a 'sales tax preferred' intersection.

Public Notification: Staff mailed notices to all property owners within 200 feet as well as any Homeowners Associations within 500 feet of the subject property regarding this request. Grapevine-Colleyville ISD, where the subject property is located, was notified per State law. Notice was published in the *Fort Worth Star-Telegram* as required by State law and the Land Development Code. To date, no correspondence has been received.

Staff Recommendation: The proposed Special Use Permit (SUP) would authorize the continuation of an auto repair shop with a new operator. This use is compliant for the preference for uses that generate sales tax revenue for the city. The proposed business is consistent with the nearby uses in the ML Light Manufacturing District and should not adversely impact surrounding uses. Staff recommends approval of the proposed SUP for an auto repair shop and maintaining the existing SUP conditions and including them with this SUP.

Recommendation

Approve

Attachments

1. Aerial Map
2. Zoning Map
3. Future Land Use Map
4. Statement of Planning Objectives
5. Zoning Exhibit
6. SUP Ordinance (O-10-1752)
7. Notification Map

8. Notification List
9. Property Owner Notification
10. Draft Ordinance


Aerial Map




ZC18-020
6804 Colleyville Blvd

DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

 Subject Property



Zoning Map




ZC18-020

6804 Colleyville Blvd




DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

 Subject Property




Future Land Use Map



DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

ZC18-020 6804 Colleyville Blvd

-  Subject Property
-  Sales_Tax_Preferred_Intersection
-  Residential
-  Colleyville Blvd Corridor
-  Open Space; Parks



Statement of Planning Objectives

6804 COLLEYVILLE BOULEVARD

STATEMENT OF PLANNING OBJECTIVES

This Property is currently an Automotive Collision Center working under a SUP that was issued to Danny LaPier dba Lone Star Collision. Mr LaPier is wishing to retire and sell his Family owned business to Colleyville JHCC LLC, which will operate as Joe Hudson's Collision Centers; a National Collision Center Chain with a very strong presence in Texas. Based on Colleyville Ordinance, Colleyville JHCC LLC will have to have a SUP in their name in order to operate as an Automotive Collision Center in this location. The current Zoning is ML, Light Manufacturing. The purpose of operating as Joe Hudson's Collision Center is it is a National Branding which offers an established reputation, and Nation-Wide Warranty Service. However, the SUP would be in the name of the Owner, Colleyville JHCC LLC.


The Schedule for opening as Colleyville JHCC LLC dba Joe Hudson's Collision Center would be ASAP after gaining the SUP and Title Co closing.

The existing center is located on 0.95 Acres, and is comprised of Two Buildings; a very attractive Brick w/Standing Seam Metal Roof Office of approximately 2000 sq ft, and a highly functional Metal Building of approximately 4800 sq ft situated directly behind the Office; being not visible from the street when looking straight on.

The existing Annual Sales is in the \$2,000,000 range. The anticipated Annual Sales using proven updated techniques and national buying power is between \$3.5 and \$4,000,000. The City of Colleyville should see a Two-fold increase in Sales Tax Revenue in this Location.

The anticipated Traffic Count is about 50 to 60 Cars per day, being only about 25 Cars per day more than now. This should be no problem for SH 26.

Zoning Exhibit



PROPERTY DESCRIPTION

BEING all that certain lot, tract or parcel of land situated in the Absalom J. Lott Survey, Abstract No. 963, and being part of Lot 1, Block 1, of Highway 26 Industrial Addition, an addition to the City of Colleyville, Texas, according to the map thereof recorded in Volume A, Page 152, of the Plat Records of Tarrant County, Texas, some being part of a tract of land conveyed to H.B. Jung by deed recorded in Instrument No. D206020581 of the Deed Records of Tarrant County, Texas, and being more particularly described by the metes and bounds as follows;

BEGINNING at a "X" found in the northwest right-of-way line of Colleyville Boulevard (State Highway No. 26) (variable width right-of-way) and in the north line of Lot 2, Block 1 of D&W Addition an addition to the City of Colleyville, Tarrant County, Texas, according to the plat thereof recorded in Volume 388-192, Page 87 of the Plat Records of Tarrant County, Texas, same being the southeast corner of herein described tract;

THENCE North 89 degrees 31 minutes 30 seconds West along the north line of said Lot 2, Block 1 of D&W Addition a distance of 321.75 feet to a 1/2 inch iron rod found in the east line of Lot 1X, Block 4, Private Open Space, of Monterra, an addition to the City of Colleyville, Tarrant County, Texas, according to the plat thereof recorded in Cabinet A, Slide 5743 of the Plat Records of Tarrant County, Texas, same being the southwest corner of herein described tract;

THENCE North 00 degrees 20 minutes 50 seconds East along the east line of said Lot 1X, Block 4 of Monterra a distance of 116.71 feet to a 5/8 inch iron rod found at the southwest corner of said Lot 2X, Block 1 of Monterra, same being the northwest corner of herein described tract;

THENCE South 89 degrees 31 minutes 30 seconds East along the south line of said Lot 2X, Block 4 of Monterra a distance of 389.84 feet to a 1/2 inch iron rod set with yellow plastic cap stamped DCA INC. in the southwest right-of-way line of said Colleyville Boulevard, same being the northeast corner of herein described tract;

THENCE South 14 degrees 58 minutes 04 seconds East along the southwest right-of-way line of said Colleyville Boulevard a distance of 1.15 feet to a "X" found, for corner;

THENCE South 30 degrees 59 minutes 39 seconds West along the southwest right-of-way line of said Colleyville Boulevard a distance of 134.19 feet to the POINT OF BEGINNING and containing 41,579.09 square feet or 0.9545 acres of land.

SURVEYOR'S CERTIFICATE

This survey is made relying on information provided by (REUNION TITLE) in connection with the transaction described in GF# (07R29849). The undersigned Registered Professional Land Surveyor (Bryan Connally) hereby certifies to (DANNY LAPIER, REUNION TITLE AND FIRST AMERICAN TITLE INSURANCE COMPANY) that, (a) this plat of survey and the property description set forth herein were prepared from an actual on-the-ground survey of the real property (6804 COLLEYVILLE BOULEVARD) described in (INSTRUMENT NO. D206020581), and shown hereon; (b) such survey was conducted by the Surveyor, or under his direction; (c) all monuments shown hereon actually existed on the date of the survey, and the location, size and type of material thereof are correctly shown; (d) except as shown hereon there are no observable protrusions on to the Property or observable protrusions there from, there are no observable discrepancies, conflicts, shortages in area or boundary line conflicts; (e) the size, location and type of improvements, are shown hereon, and all are located within the boundaries of the Property and setback from the Property lines the distances indicated; (f) the distance from the nearest intersection street or road is as shown; (g) the Property has apparent access to and from a public roadway; (h) recorded easements listed herein have been labeled and platted hereon; (i) the boundaries, dimensions and other details shown hereon are shown to the appropriate accuracy standards of the State of Texas; (j) the Property is not located in a 100 Year Flood Plain, however, does lie in a 500 Year Flood Plain, as defined by the U. S. Department of Housing and Urban Development (Flood Insurance Rate Map No. 48439C0195 H) pursuant to the Flood Disaster Protection Act of 1973.

The surveyor expressly understands and agrees that (DANNY LAPIER, REUNION TITLE AND FIRST AMERICAN TITLE INSURANCE COMPANY) are entitled to rely on this survey as having been performed to the appropriate standards of the current (1999 Edition) Texas Society of Professional Surveyors Standards and Specifications for a Texas Land Title Survey as set forth by the Texas Board of Professional Land Surveying.

Use of this survey by any other parties and/or for other purposes shall be at user's own risk and any loss resulting from other use shall not be the responsibility of the undersigned.

Executed this 22ND day of OCTOBER, 2007

Bryan Connally
Bryan Connally
Registered Professional Land Surveyor No. 5513

NOTE: BEARINGS ARE BASED ON RECORDED PLAT AND ALL EASEMENTS ARE BY RECORDED PLAT UNLESS OTHERWISE NOTED.
SUBJECT TO LACK OF ACCESS TO ROAD ADJUTING PROPERTY RECORDED IN COUNTY CLERK'S FILE NO. D027062822, REAL PROPERTY RECORDS, TARRANT COUNTY, TEXAS.

NOTE: According to the F.I.R.M. in Map No. 48439C0195 H, this property does lie in Zone X, and DOES NOT lie within the 100 year flood zone, EXCEPT AS SHOWN where does lie in 500 year flood zone.

ACCEPTED BY: _____ SIGNATURE _____ DATE _____ SIGNATURE _____ DATE _____

REVISIONS		
DATE	BY	NOTES

LEGEND	
	POWER POLE
	BRICK COLUMN
	A/C - AIR CONDITIONING
	FIRE HYDRANT
	COVERED PORCH, DECK OR CARPORT
	OVERHEAD ELECTRIC SERVICE
	OVERHEAD POWER LINE
	CONCRETE PAVING

DOUG CONNALLY & ASSOC., INC. 11545 PAGEMILL RD., SUITE #200 DALLAS, TEXAS 75243 PHONE:(214) 349-9485 FAX:(214) 349-2216 www.dcadfw.com				
SCALE	DATE	JOB NO.	G.F. NO.	DRAWN
1"=20'	10-22-07	0706726-1	07R29849	LP

TEXAS LAND TITLE SURVEY	
PART OF LOT 1, BLOCK 1 OF HIGHWAY 26 INDUSTRIAL ADDITION	
CITY OF COLLEYVILLE, TARRANT COUNTY, TEXAS	
6804 COLLEYVILLE BOULEVARD	

ORDINANCE O-10-1752

AN ORDINANCE AMENDING THE LAND DEVELOPMENT CODE OF THE CITY OF COLLEYVILLE, TEXAS, BY AUTHORIZING A SPECIAL USE PERMIT FOR AN AUTO REPAIR SHOP ON LOT 1, BLOCK 1, HIGHWAY 26 INDUSTRIAL ADDITION; PROVIDING FOR THE VIOLATION OF THIS ORDINANCE; PROVIDING A SAVINGS CLAUSE; PROVIDING FOR INJUNCTIVE RELIEF; PROVIDING A SEVERABILITY CLAUSE; PROVIDING A PENALTY OF FINE NOT TO EXCEED THE SUM OF TWO THOUSAND DOLLARS (\$2,000.00) FOR EACH OFFENSE; AND PROVIDING AN EFFECTIVE DATE

WHEREAS, the City of Colleyville has received an application for rezoning under Case No. ZC10-007; and

WHEREAS, the City of Colleyville deems it necessary, for the purpose of promoting the health, safety, morals, or general welfare of the City to enact a new zoning ordinance; and

WHEREAS, the City Council has appointed a Planning and Zoning Commission to recommend the boundaries of the various original zoning districts and appropriate regulations be enforced therein and to recommend a new zoning ordinance; and

WHEREAS, the Planning and Zoning Commission has divided the City into districts and has prepared regulations pertaining to such districts in accordance with a comprehensive plan designed to lessen congestion in the streets; to secure safety from fire, panic and other dangers; to promote health, general welfare; to provide adequate light and air; to prevent the overcrowding of land; to avoid undue concentration of population; to facilitate the adequate provision of transportation, water, sewerage, schools, parks and other public requirements; and

WHEREAS, the Planning and Zoning Commission, has given reasonable consideration to, among other things, the character of the districts and their peculiar suitability for particular uses, with a view to conserving the value of buildings and encouraging the most appropriate use of land throughout the City; and

WHEREAS, the Planning and Zoning Commission of the City of Colleyville and the City of Colleyville City Council, in compliance with the Charter of the City of Colleyville, and State Law with reference to changes to zoning classifications under the Zoning Ordinance Regulations and Zoning Map, having given the requisite notices by publication and otherwise, and after holding due hearings and affording a full and fair hearing to all the property owners generally, and to the persons interested and situated in

the affected area and in the vicinity thereof, the governing body of the City of Colleyville is of the opinion that said change in zoning should be made.

NOW, THEREFORE, BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF COLLEYVILLE, TEXAS:

- Sec. 1. THAT all the foregoing premises and findings are found to be true and correct and are incorporated into the body of this ordinance as if copied in their entirety.
- Sec. 2. THAT the Comprehensive Zoning Ordinance of the City of Colleyville, Texas, be, and the same is hereby amended by changing the zoning of approximately 2.0 acres on Lot 1, Block 1, Highway 26 Industrial Addition, depicted on the attached Exhibit "A" and Exhibit "B".
- Sec. 3. THAT the above described tract of land shall be used only in the manner and for the purposes provided by the Comprehensive Zoning Ordinance of the City of Colleyville as heretofore amended, and as amended herein.
- Sec. 4. THAT the above described tract of land shall be subject to the following conditions:

1. GENERAL

- a. This Special Use Permit shall apply only to Building B, as shown on the Zoning Exhibit attached as Exhibit "B".
- b. The hours of operation shall be Monday through Friday from 7:00 a.m. to 7:00 p.m. and Saturday 8:00 a.m. to noon.
- c. Overnight parking of vehicles shall be allowed outside the building, provided that the vehicles are parked to the rear of Building B, as shown on the attached Exhibit "B". Vehicles such as boats, recreational vehicles and trailers shall not be parked or stored in the outside parking area.
- d. All vehicles waiting for repair shall be parked to the rear of the building.
- e. No storage of parts or containers shall be allowed outside the building.
- f. All repair work shall be done inside the building.
- g. Work shall not be performed on any vehicle larger than a 2-ton pickup truck.
- h. No vehicles for sale shall be parked in front of the building adjacent to Colleyville Boulevard.

- i. This Special Use Permit shall automatically expire upon the abandonment of the business, change in the use, a change in ownership or upon the expiration or termination of the Certificate of Occupancy.
- j. All requirements of the Land Development Code shall be met, except where amended herein.


- Sec. 5. THAT any person, firm or corporation violating any of the provisions or terms of this ordinance shall be subject to the same penalty as provided for in the Comprehensive Zoning Ordinance of the City of Colleyville, and upon conviction shall be punishable by a fine not to exceed the sum of Two Thousand Dollars (\$2,000.00) for each offense.
- Sec. 6. THAT if any section, paragraph, subdivision, clause, phrase or provision of this ordinance shall be judged invalid or unconstitutional, the same shall not affect the validity of this ordinance as a whole or any portion thereof other than that portion so decided to be invalid or unconstitutional.
- Sec. 7. THAT in addition to and accumulative of all other penalties, the City shall have the right to seek injunctive relief for any and all violations of this ordinance.
- Sec. 8. THAT it has been found that there has been a change in conditions in the above described property, it is now necessary that it be given the above zoning classification in order to permit its proper development and in order to protect the public interest, comfort and general welfare, and requires that this ordinance shall take effect immediately from and after its passage.

AND IT IS SO ORDERED.

The first reading and public hearing being conducted on the 1st day of June 2010.


The second reading and public hearing being conducted on the 15th day of June 2010.

ATTEST:




Cynthia Singleton, TRMC, CMC
City Secretary

CITY OF COLLEYVILLE



David Kelly
Mayor

APPROVED AS TO FORM AND LEGALITY:

A handwritten signature in black ink, appearing to read "Matt C. G. Boyle". The signature is stylized with a large "M" and a cursive "Boyle".

Matthew C. G. Boyle
City Attorney

Exhibit "A" - Location and Zoning Map






Exhibit “B” – Site Plan



Notification Map



DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

ZC18-020

6804 Colleyville Blvd




Subject Property



200ft Buffer



Properties within 200ft



Notification List

Owner Name	Owner Address	Owner City	Owner Zip	Situs Address
HART, NEIL J	6703 COLLEYVILLE BLVD	COLLEYVILLE, TX	76034	6703 COLLEYVILLE BLVD
COLLEYVILLE CREME DE LA CREME	8400 E PRENTICE AVE STE 1320	GREENWOOD VILLAGE, CO	80111	6801 COLLEYVILLE BLVD
CAIRNS, CRAIG	1617 DOUGLAS AVE	COLLEYVILLE, TX	76034	1617 DOUGLAS AVE
MONTERRA HOME OWNER'S ASSOC	6707 BRENTWOOD STR RD	FORT WORTH, TX	76112	1799 TENNISON PKWY
JOHNSON, STEVEN	1613 DOUGLAS AVE	COLLEYVILLE, TX	76034	1613 DOUGLAS AVE
3 J GREEN LIMITED PARTNERSHIP	6620 COLLEYVILLE BLVD STE 100	COLLEYVILLE, TX	76034	6630 COLLEYVILLE BLVD
SHELTER E320 LLC	1700 TENNISON PKWY # 100	COLLEYVILLE, TX	76034	1700 TENNISON PKWY
MONTERRA HOME OWNER'S ASSOC	6707 BRENTWOOD STR RD	FORT WORTH, TX	76112	1699 TENNISON PKWY
LANI PROPERTIES LLC	3317 STONECREST DR	GRAPEVINE, TX	76051	6707 COLLEYVILLE BLVD
HART, NEIL	1600 GLADE RD	COLLEYVILLE, TX	76034	6525 COLLEYVILLE BLVD
LANI PROPERTIES LLC	3317 STONECREST DR	GRAPEVINE, TX	76051	6705 COLLEYVILLE BLVD
STRATEGY REAL ESTATE HOLDING	1817 LAKESHORE CT	MCKINNEY, TX	75070	6800 COLLEYVILLE BLVD
RADDE GROUP LLC	101 COUNTRYSIDE CT	SOUTHLAKE, TX	76092	6700 COLLEYVILLE BLVD
LFP PROPERTIES INC	7505 GLENVIEW DR STE 150	RICHLAND HILLS, TX	76180	1704 TENNISON PKWY
STANLEY, CALLI	1609 DOUGLAS AVE	COLLEYVILLE, TX	76034	1609 DOUGLAS AVE
FELLER-DAVIS ENTERPRISES LLC	3300 SPRING VALLEY DR	BEDFORD, TX	76021	6900 COLLEYVILLE BLVD
LONE STAR COLLISON LTD	6804 COLLYVILLE BLVD	COLLEYVILLE, TX	76034	6804 COLLEYVILLE BLVD
MONTERRA HOME OWNER'S ASSO	6707 BRENTWOOD STAIR RD	FORT WORTH, TX	76112	1690 TENNISON PKWY
MONTERRA ADDITION	6811 MILTON DR	COLLEYVILLE, TX	76034	COURTESY NOTICE
ROSS DOWNS ESTATES	4113 GATEWAY DRIVE #100	COLLEYVILLE, TX	76034	COURTESY NOTICE
GRAPEVINE COLLEYVILLE ISD	3051 IRA E WOODS AVE	GRAPEVINE, TX	76051	STATE REQUIRED
DEFEO, JERRY	646 E I-30	GARLAND, TX	75043	APPLICANT

Public hearing notices were mailed July 27, 2018 by Araceli Botello



NOTICE OF PUBLIC HEARING

Zoning Case Number: ZC18-020
Owner: Danny Lapier
Applicant: Jerry DeFeo
Location: 6804 Colleyville Boulevard
Property Description: Lot 1A, Block 1, of the Highway 26 Industrial
Present Zoning: ML Light Manufacturing
Request: Consideration of a Special Use Permit for an Automotive Repair Shop. Specifically the purpose of the request is to allow for the existing business, Lone Star Collision, to have a change in ownership to Joe Hudson's Collision Centers with no alterations to the existing facilities.

The City of Colleyville has scheduled public hearings concerning the above referenced request on the following dates and location:

Planning and Zoning Commission Meeting: Monday, August 13, 2018 at 7:00 p.m.
City Council Meeting: Tuesday, September 4, 2018 & Tuesday, September 18, 2018 at 7:30 p.m.
3rd floor of City Hall, 100 Main Street, Colleyville, Texas

This notice has been sent to all owners of real property within 200 feet of the request as such ownership appears on the last approved tax roll and all homeowners associations within 500 feet. Approval by the Planning and Zoning Commission serves as a recommendation to the City Council and is not a final action on the request. Denial of the proposal by the Commission is final, unless the applicant submits a written notice of appeal within 10 days from the date of action by the Commission. If appealed, the request will be placed on the next available City Council agenda as listed above. Rezoning requests, zoning amendments and conditions recommended by the Commission for approval by the City Council may be more restrictive than those described in this notice.

All interested persons are encouraged to attend the public hearing and express their opinions on the zoning change request. If you are unable to attend, but wish to have your opinions made a part of the public record, please submit written comments prior to the public hearing, to the address below:

**Community Development Department
City of Colleyville
100 Main Street
Colleyville, TX 76034**

If the property owners of 20% or more of the land within the 200 foot notification area file a written protest prior to the public hearing, State law provides that the approval of the zoning change request shall require the approval of a super majority vote by City Council.

The application is on file for public examination in the Community Development Department at 100 Main Street, Colleyville, Texas. A brief project description can be found online on the Active Development Case map: <https://www.colleyville.com/zoning.html>. For additional information, please contact the Community Development Department at 817.503.1052. Please reference the zoning case number when requesting information.

Ben Bryner
Director of Community Development
bbryner@colleyville.com

ORDINANCE O-18-XXXX

AMENDING THE ZONING ORDINANCE AND THE OFFICIAL ZONING MAP BY CHANGING THE ZONING ON LOT 1A, BLOCK 1, HIGHWAY 26 INDUSTRIAL ADDITION, LOCATED AT 6804 COLLEYVILLE BOULEVARD, BY AUTHORIZING A SPECIAL USE PERMIT FOR AN AUTO REPAIR SHOP; PROVIDING A PENALTY OF FINE NOT TO EXCEED THE SUM OF TWO THOUSAND DOLLARS (\$2,000.00); AND PROVIDING AN EFFECTIVE DATE

WHEREAS, the City of Colleyville has received an application for on-premise consumption of alcohol under Case No. ZC18-020; and

WHEREAS, the City of Colleyville deems it necessary, for the purpose of promoting the health, safety, morals, or general welfare of the City to enact a new zoning ordinance; and

WHEREAS, the City Council has appointed a Planning and Zoning Commission to recommend the boundaries of the various original zoning districts and appropriate regulations be enforced therein and to recommend a new zoning ordinance; and

WHEREAS, the Planning and Zoning Commission has divided the City into districts and has prepared regulations pertaining to such districts in accordance with a comprehensive plan and designed to lessen congestion in the streets; to secure safety from fire, panic, and other dangers; to promote health, general welfare; to provide adequate light and air; to prevent the overcrowding of land; to avoid undue concentration of population; to facilitate the adequate provision of transportation, water, sewerage, schools, parks, and other public requirements; and

WHEREAS, the Planning and Zoning Commission, has given reasonable consideration to, among other things, the character of the districts and their peculiar suitability for particular uses, with a view to conserving the value of buildings and encouraging the most appropriate use of land throughout the City; and

WHEREAS, the Planning and Zoning Commission of the City of Colleyville and the City of Colleyville City Council, in compliance with the Charter of the City of Colleyville, and State Law with reference to changes to zoning classifications under the Zoning Ordinance Regulations and Zoning Map, having given the requisite notices by publication and otherwise, and after holding due hearings and

affording a full and fair hearing to all the property owners generally, and to the persons interested and situated in the affected area and in the vicinity thereof, the governing body of the City of Colleyville is of the opinion that said change in zoning should be made.

NOW, THEREFORE, BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF COLLEYVILLE, TEXAS:

- Sec. 1. THAT all the foregoing premises and findings are found to be true and correct and are incorporated into the body of this ordinance as if copied in their entirety.
- Sec. 2. THAT the Comprehensive Zoning Ordinance of the City of Colleyville, Texas, be, and the same is hereby amended by changing the zoning on Lot 1A, Block 1, of the Highway 26 Industrial addition, located at 6804 Colleyville Boulevard, by authorizing a Special Use Permit for an Auto Repair Shop, as depicted on Exhibit "A" and Exhibit "B".
- Sec. 3. THAT the above described tract of land shall be used only in the manner and for the purposes provided by the Comprehensive Zoning Ordinance of the City of Colleyville as heretofore amended, and as amended herein.
- Sec. 4. THAT the above described tract of land shall be subject to the following conditions:

1. GENERAL

- a. This Special Use Permit shall apply only to Building B, as shown on the Zoning Exhibit attached as Exhibit "B".
- b. The hours of operation shall be Monday through Friday from 7:00 a.m. to 7:00 p.m. and Saturday 8:00 a.m. to noon.
- c. Overnight parking of vehicles shall be allowed outside the building, provided that the vehicles are parked to the rear of Building B, as shown on the attached Exhibit "B". Vehicles such as boats, recreational vehicles and trailers shall not be parked or stored in the outside parking area.
- d. All vehicles waiting for repair shall be parked to the rear of the building.

- e. No storage of parts or containers shall be allowed outside the building.
- f. All repair work shall be done inside the building.
- g. Work shall not be performed on any vehicle larger than a 2-ton pickup truck.
- h. No vehicles for sale shall be parked in front of the building adjacent to Colleyville Boulevard.
- i. This Special Use Permit shall automatically expire upon the abandonment of the business, change in the use, a change in ownership or upon the expiration or termination of the Certificate of Occupancy.
- j. All requirements of the Land Development Code shall be met, except where amended herein.

Sec. 5. THAT any person, firm or corporation violating any of the provisions or terms of this ordinance shall be subject to the same penalty as provided for in the Comprehensive Zoning Ordinance of the City of Colleyville, and upon conviction shall be punishable by a fine not to exceed the sum of Two Thousand Dollars (\$2,000.00) for each offense.

Sec. 6. THAT it has been found that there has been a change in conditions in the above described property, it is now necessary that it be given the above zoning classification in order to permit its proper development and in order to protect the public interest, comfort and general welfare, and requires that this ordinance shall take effect immediately from and after its passage.

AND IT IS SO ORDERED.

The first reading and public hearing being conducted on the 4th day of September 2018.

The second reading and public hearing being conducted on the 18th day of September 2018.

PASSED AND APPROVED BY A VOTE OF ____ AYES, ____ NAYS, AND ____
ABSTENTIONS ON THIS THE 18TH DAY OF SEPTEMBER 2018.

Mayor Richard Newton	_____	Mayor Pro Tem Bobby Lindamood	_____
Place 1, Tammy Nakamura	_____	Place 5, Chuck Kelley	_____
Place 3, Kathy Wheat	_____	Place 6, Callie Rigney	_____
Place 4, George Dodson	_____		

ATTEST:

CITY OF COLLEYVILLE


Christine Loven, TRMC
City Secretary

Richard Newton
Mayor

APPROVED AS TO FORM AND LEGALITY:

Whitt Wyatt
City Attorney

Exhibit "A" – Zoning Map




ZC18-020
6804 Colleyville Blvd

DISCLAIMER:
 This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

 Subject Property



Exhibit "B" – Zoning Exhibit





City of Colleyville Planning and Zoning Commission Agenda Briefing

City Hall
100 Main Street
Colleyville, Texas 76034
www.colleyville.com

Agenda Number 2b	Agenda Date 08/13/2018	Number
Type Public Hearing Agenda Items		
Department Community Development		

Title

Consideration of a zoning change from AG to R-30 on Tract 2A01 & 2A02, Abstract 1543, in the George W Teeter Survey, located at 1309 Glade Road, Case ZC18-023

Explanation

Rome Barnes, the applicant, has submitted a request for a zoning change from the AG Agricultural to the R-30 Single Family Residential district on Tracts 2A01 & 2A02, Abstract 1543, in the George W Teeter Survey, being approximately 4.369 acres. The purpose of the request is to allow for development of 5 new single-family residential lots.

Existing Conditions/Background: The subject property, 1309 Glade Road, resides on the south side of Glade Road and the east side of Carmel Place, across from the existing subdivision called Carmel Place zoned Planned Unit Development – Residential (PUD-R). The property currently has Agricultural (AG) zoning and remains undeveloped except for a single house on the property which is planned to be removed.

Proposed Zoning:

Request – The applicant requests to create a single-family residential subdivision consisting of five (5) lots, ranging from 32,615 square feet to 44,334 square feet. The two large one acre lots fronting Glade Road have lot widths under the required 125 feet. Therefore, a lot width waiver is being requested with the associated plat. All lots will meet the required minimum front yard setback of thirty-five (35) feet, side yard setbacks of ten (10) feet, and rear yard setback of twenty-five (25) feet with a maximum building height of thirty-five (35) feet.

Overall, this would result in a development covering a total of 4.3968 acres with 5 residential lots, achieving a density of 1.14 units per acre which is below the R-30 residential density requirement of 1.45 dwellings per acre.

The minimum standards for the R-30 zoning district are as follows:

Minimum Lot Size:	30,000 square feet
Minimum Lot Width:	125 feet
Minimum Lot Depth:	125 feet
Front Building Line:	35 feet

Side Building Line:	10 feet
Rear Building Line:	25 feet
Maximum Lot Coverage:	25 percent

The five (5) lots will have the following minimum lot areas:

Lot 1:	44,334 square feet
Lot 2:	44,031 square feet
Lot 3:	32,667 square feet
Lot 4:	32,615 square feet
Lot 5:	32,632 square feet

If zoning is approved, the applicant anticipates home construction to begin in late 2018 with the average home size to be 5,200 square feet with an approximate price point of \$950,000.

Analysis: The requested rezoning allows the applicant to develop the lots in a manner complementary to the approved PUD-R on the west side of Carmel Place while also being compatible with the neighborhood surrounding it.

All homes are required to have fire sprinklers regardless of square footage due to the limited size of Glade Road, which could impede the fire department's ability to fight a potential fire, and the length of Carmel Place.

Surrounding Development: The properties to the south, east and west (adjacent to Carmel Place) have R-20 zoning and have developed with single-family residential structures. Properties across Glade Road to the north have PUD-R zoning and have developed with single-family residential structures. Lots directly across the Carmel Place have an existing PUD-R which the applicant proposes to compliment with their project's design.

Comprehensive Plan: The City's comprehensive plan, *Destination Colleyville*, identifies the subject property for single-family residential development. The proposed R-30 does not conflict with any portion of the comprehensive plan. The proposed R-30 facilitates the maximum desired residential density of 1.45 units per net acre.

Public Notification: Staff mailed notices to all property owners within 200 feet as well as any Homeowners Associations within 500 feet of the subject property regarding this request. Grapevine-Colleyville ISD, where the subject property is located, was notified per State law. Notice was published in the *Fort Worth Star-Telegram* as required by State law and the Land Development Code. To date, no correspondence has been received.

Staff Recommendation: Staff recommends approval for the applicant's request based on the following findings:

1. The proposed zoning meets the intent of the residential designation assigned in the Destination Colleyville comprehensive plan.
2. The R-30 zoning complements the zoning districts surrounding the subject property.


Recommendation

Approve

Attachments

1. Aerial Map
2. Zoning Map
3. Future Land Use Map
4. Statement of Planning Objectives
5. Zoning Exhibit
6. Notification Map
7. Notification List
8. Property Owner Notification
9. Draft Ordinance

Aerial Map




ZC18-023

1309 Glade Road

DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

 Subject Property



Zoning Map




ZC18-023

1309 Glade Road

DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

 Subject Property



Future Land Use Map




ZC18-023

1309 Glade Road

DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

 Subject Property



Statement of Planning Objectives

ZONING APPLICATION NARRATIVE

CARMEL PLACE ESTATES EAST

1309 GLADE ROAD, COLLEYVILLE, TX 76034

STATEMENT OF PLANNING OBJECTIVES

Centurion Acquisitions, LLC is requesting rezoning of a 4.3968-acre site (191,524 square feet) located at 1309 Glade Road abutting the eastern portion of Carmel Place within the City of Colleyville, from **AG-Agriculture** to **R30-Single Family Residential District (R30)**. The rezoning objective is to create five residential lots meeting or exceeding the R30 minimum lot size. The abutting residential area is zoned R20 and PUD-R; however, at the request of the City, Carmel Place Estates East rezoning request is being submitted under the R30 zoning district.

- The residential density will be 1.14 dwellings per acre, well below the R30 residential density of 1.45 dwellings per acre.
- The R30 minimum residential lot size is 30,000 square feet; the five residential lots will have the following minimum lot area:
 - Lot 1 – 44,334 square feet
 - Lot 2 – 44,031 square feet
 - Lot 3 – 32,667 square feet
 - Lot 4 – 32,615 square feet
 - Lot 5 – 32,632 square feet
- The R30 required minimum lot width is 125 feet; three of the lots meet and exceed the minimum lot width; however, the two large 1-acre lots fronting Glade Road have lot widths of 116 feet, 9 feet shy of the required minimum lot width (would meet minimum 100-foot lot width required by the adjacent R20 zoning district). **A lot width waiver is being requested for these two lots.**
- All lots will meet the required minimum front yard setback of 35 feet, side yard setback of 10 feet, and rear yard setback of 25 feet and the required maximum building height of 35 feet.

Statement of Planning Objectives

DEVELOPMENT SCHEDULE

It is anticipated that home construction will begin on the five residential lots sometime in late 2018.

Once a building permit is issued, time for completion is estimated from 10-12 months.

ECONOMIC DEVELOPMENT INFORMATION

The average home size is anticipated to be around 5200 square feet at a price point of \$950,000. Using Tarrant County Appraisal District's tax estimator, the City of Colleyville's ad valorem tax rate of .33834 for a home valued at \$950,000 would generate \$3,214 in City taxes and another \$13,269 (tax rate of 1.39670) in taxes to support the City's school system, the Grapevine/Colleyville Independent School District. Five homes built at this price point would generate \$16,070 in ad valorem taxes for the City and \$66,345 for the City's school system. This is an estimate and could change based on specific criteria considered by the Tax Assessor's office.

TRAFFIC IMPACT ANALYSIS


A Traffic Impact Analysis is not required since only five homes are proposed which would fall below the projected generation rate of 1000 vehicle trips per day.

DRAINAGE ANALYSIS

A drainage analysis completed for Carmel Place Estates by Thomas Hoover Engineering, LLC dated 6-23-14 is submitted with the Zoning Application. Carmel Place Estates East land area is included in the drainage area of Carmel Place Estates, thus issues related to drainage impacts have already been assessed. Specific lot drainage for the five lots in Carmel Place Estates East will be a part of the engineering plans and will be consistent with the already submitted drainage analysis.

Statement of Planning Objectives

EXHIBIT A – LOCATION AND ZONING MAP



Statement of Planning Objectives

EXHIBIT B – LEGAL DESCRIPTION

Being a tract of land out of George W. Teeter Survey, Abstract No. 1543 and situated in the City of Colleyville, Tarrant County, Texas, and surveyed by Miller Surveying, Inc. of Hurst, Texas in November 2017, said tract being a portion of the same tract of land described in the deed to Robert Gene Hubbard et ux, Peggy Hubbard recorded in Volume 4069, Page 406 in the Deed Records of Tarrant County, Texas and being more particularly described by metes and bounds as follows:

Beginning at a 5/8 inch steel rod found in the southerly right-of-way line of Glade Road (Co. Rd. 3036), said rod being in the northerly boundary line of "Tract No. 1" of said Hubbard Deed and also being the most northerly northwest corner of Lot 1, Block 1, Greener Acres, an addition to the City of Colleyville, Texas according to the plat thereof recorded in Cabinet A, Slide 4936 of the Plat Records of said County;

Thence South 00 degrees 14 minutes 15 seconds East with the westerly boundary line of said Lot 1 a distance of 553.09 feet to a 1/2 inch "MILLER 5665" capped steel rod set for an inner corner thereof;

Thence South 89 degrees 25 minutes 35 seconds West continuing with said westerly boundary line a distance of 58.10 feet to a 1/2 inch steel rod found for an outer point thereof;


Thence South 00 degrees 12 minutes 14 seconds West continuing with said westerly boundary line a distance of 415.82 feet to a 1/2 inch steel rod found for the southwest corner of said Lot 1, said rod being in the northerly boundary line of Block 1, The Lakes of Somerset, an addition to the City of Colleyville, Texas according to the plat thereof recorded in Cabinet A, Slide 312 of said plat records;

Thence North 89 degrees 46 minutes 39 seconds West with said northerly boundary line a distance of 151.92 feet to a point in a fence post found in the easterly boundary line of Carmel Place Estates, an addition to the City of Colleyville, Texas according to the plat thereof recorded as Instrument No. D217142798 of the Official Public Records of said County;

Thence North 01 degrees 25 minutes 38 seconds West with said easterly boundary line a distance of 985.17 feet to a cross in concrete set for the northwest corner of said Tract 1, said cross being in said southerly right-of-way line;

Thence North 89 degrees 53 minutes 54 seconds East with the northerly boundary line of said Tract 1 and with said southerly right-of-way line a distance of 233.33 feet to the point of beginning and containing 4.3968 acres of land, more or less.

Zoning Exhibit



VICINITY MAP
NOT TO SCALE

Zoning Exhibit - Carmel Place Estates East

1309 Glade Road, Colleyville, TX. 76034

Overall Parcel Gross Area	4.3968 Acres - 191,524 SF
Existing Buildings	Dwelling and out Buildings - all to be removed
Existing Zoning	AG
Street Area Proposed	Not applicable
Sidewalks Proposed	Not applicable
Open Space SF and percent	Not applicable
Proposed Dwelling Lots	5
Proposed Dwellings	1.14 dwellings per acre
Proposed Dwelling Type	Single Family Residential

Metes & Bounds

Tract 1 - 4.3968 ACRES

Being a tract of land out of George W. Teeter Survey, Abstract No. 1543 and situated in the City of Colleyville, Tarrant County, Texas, and surveyed by Miller Surveying, Inc. of Hurst, Texas in November 2017, said tract being a portion of the same tract of land described in the deed to Robert Gene Hubbard et al, Peggy Hubbard recorded in Volume 4069, Page 406 in the Deed Records of Tarrant County, Texas and being more particularly described by metes and bounds as follows:

Beginning at a 5/8 inch steel rod found in the southerly right-of-way line of Glade Road (Co. Rd. 3036), said rod being in the northerly boundary line of "Tract No. 1" of said Hubbard Deed and also being the most northerly northwest corner of Lot 1, Block 1, Greener Acres, an addition to the City of Colleyville, Texas according to the plat thereof recorded in Cabinet A, Slide 4936 of the Plat Records of said County;

Thence South 00 degrees 14 minutes 15 seconds East with the westerly boundary line of said Lot 1 a distance of 553.09 feet to a 1/2 inch "MILLER 5665" capped steel rod set for an inner corner thereof;

Thence South 89 degrees 25 minutes 35 seconds West continuing with said westerly boundary line a distance of 58.10 feet to a 1/2 inch steel rod found for an outer point thereof;

Thence South 00 degrees 12 minutes 14 seconds West continuing with said westerly boundary line a distance of 415.82 feet to a 1/2 inch steel rod found for the southwest corner of said Lot 1, said rod being in the northerly boundary line of Block 1, The Lakes of Somerset, an addition to the City of Colleyville, Texas according to the plat thereof recorded as instrument No. D217142798 of the Official Public Records of said County;

Thence North 89 degrees 46 minutes 39 seconds West with said northerly boundary line a distance of 151.92 feet to a point in a fence post found in the easterly boundary line of Carmel Place Estates, an addition to the City of Colleyville, Texas according to the plat thereof recorded as instrument No. D217142798 of the Official Public Records of said County;

Thence North 01 degrees 25 minutes 38 seconds West with said easterly boundary line a distance of 985.17 feet to a cross in concrete set for the northwest corner of said Tract 1, said cross being in said southerly right-of-way line;

Thence North 89 degrees 53 minutes 54 seconds East with the northerly boundary line of said Tract 1 and with said southerly right-of-way line a distance of 233.33 feet to the point of beginning and containing 4.3968 acres of land, more or less.

PROPERTY OWNER

CENTURION ACQUISITIONS, LLC
1800 Valley View Lane
Suite 300
Farmers Branch, TX 75234
817.584.5982
Contact: Rome Barnes

ENGINEER

ION DESIGN GROUP, LLC F-6701
7075 Twin Hills Ave
Suite 350
Dallas, TX 75231
214.370.3470 Ph
Contact: Bryan Klein

SURVEYOR


MILLER SURVEYING, INC.
430 Mid Cities Blvd.
Hurst, TX 76054
817.577.1050 Ph
817.577.0972 Fx
Contact: Jason Rawlings

© Copyright 2018 Ion Design Group, LLC. All rights reserved.




Ion Design Group
7075 Twin Hills Ave
Suite 350
Dallas, Texas 75231
Firm TX F6701
214.370.3470 Ph

Scale: 1" = 50'




Notification Map



ZC18-023

1309 Glade Road

- Subject Property
- 200ft Buffer
- Properties within 200ft



DISCLAIMER:

This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

Notification List

Owner Name	Owner Address	Owner City	Owner Zip	Situs Address
ARCLAND INVESTMENTS LLC	1300 GLADE RD	COLLEYVILLE, TX	76034	1300 GLADE RD
MAUNEY, KEITH	1216 CHATSWORTH DR	COLLEYVILLE, TX	76034	1216 CHATSWORTH DR
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4916 CARMEL PL
SMITH, DENIS J	1308 CHATSWORTH CT E	COLLEYVILLE, TX	76034	1308 CHATSWORTH CT E
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4908 CARMEL PL
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4816 CARMEL PL
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4828 CARMEL PL
WILLIAMS, JAMES P	4700 STAFFORD DR	COLLEYVILLE, TX	76034	4700 STAFFORD DR
LOGAN, EMORY M	1313 GLADE RD	COLLEYVILLE, TX	76034	1313 GLADE RD
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4804 CARMEL PL
HAUTANEN, OSMO A	1304 CHATSWORTH CT E	COLLEYVILLE, TX	76034	1304 CHATSWORTH CT E
EMLER LIVING TRUST	1300 CHATSWORTH CT E	COLLEYVILLE, TX	76034	1300 CHATSWORTH CT E
HICKSON, HEATHER J	1315 GLADE RD	COLLEYVILLE, TX	76034	1317 GLADE RD
HUBBARD, ROBERT GENE	PO BOX 575	ALBA, TX	75410	1309 GLADE RD
FRANKLIN, BRENT	2800 HIGHLAND PARK CT	COLLEYVILLE, TX	76034	4912 CARMEL PL
PRESERVATION HOA INC	101 CLARIDEN RANCH RD	SOUTHLAKE, TX	76092	1405 BLUEBONNET DR
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4808 CARMEL PL
K HOVNANIAN HOMES - DFW LLC	5808 W PLANO PKWY	PLANO, TX	75093	4900 PRESERVATION AVE
HICKSON, STEVEN A	1315 GLADE RD	COLLEYVILLE, TX	76034	1315 GLADE RD
SNYDER, JOHN	1701 ROYAL LN #1202	DALLAS, TX	75229	4812 CARMEL PL
FOUNTAINS AT RIVERWALK OFFICE	704 KENT CT	SOUTHLAKE, TX	76092	1301 STONEBRIDGE DR
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4800 CARMEL PL
CHELIND LLC	1312 GLADE RD	COLLEYVILLE, TX	76034	1312 GLADE RD
HSV RETREAT LLC	5013 PRESERVATION AVE	COLLEYVILLE, TX	76034	1308 GLADE RD
ROACH, ALISHA	1312 CHATSWORTH CT E	COLLEYVILLE, TX	76034	1312 CHATSWORTH CT E
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4920 CARMEL PL
SIENA HOMES LLC	1800 VALLEY VIEW LN STE 400	FARMERS BRNCH, TX	75234	4820 CARMEL PL
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4824 CARMEL PL
BRIDGES AT RIVERWALK ADDITION	P.O. BOX 1183	COLLEYVILLE, TX	76034	COURTESY NOTICE
LAKES OF SOMERSET, THE	1104 CHATSWORTH COURT WEST	COLLEYVILLE, TX	76034	COURTESY NOTICE
RIVERWALK AT COLLEYVILLE	P.O. BOX 1031	COLLEYVILLE, TX	76034	COURTESY NOTICE
GRAPEVINE-COLLEYVILLE ISD	3051 IRA E. WOODS AVE	GRAPEVINE, TX	76051	STATE REQUIRED
BARNES, ROME	1800 VALLEY VIEW LANE, STE 300	FARMERS BRANCH, TX	75234	APPLICANT

Public hearing notices were mailed July 27, 2018 by Araceli Botello



NOTICE OF PUBLIC HEARING

Zoning Case Number: ZC18-023
Applicant: Rome Barnes
Owner: CADG Carmel Place, LLC
Location: 1309 Glade Road
Property Description: Tract 2A01 & 2A02, Abstract 1543, in the George W Teeter Survey
Present Zoning: AG Agricultural
Request: Consideration of a zoning change from the AG Agricultural zoning district to the R-30 Single Family Residential zoning district. The purpose is to allow for development of 5 new single-family residential lots.

The City of Colleyville has scheduled public hearings concerning the above referenced request on the following dates and location:

Planning and Zoning Commission Meeting: Monday, August 13, 2018 at 7:00 p.m.

City Council Meetings: Tuesday, September 4, 2018 & Tuesday, September 18, 2018 at 7:30 p.m.
3rd floor of City Hall, 100 Main Street, Colleyville, Texas

This notice has been sent to all owners of real property within 200 feet of the request as such ownership appears on the last approved tax roll and all homeowners associations within 500 feet. Approval by the Planning and Zoning Commission serves as a recommendation to the City Council and is not a final action on the request. Denial of the proposal by the Commission is final, unless the applicant submits a written notice of appeal within 10 days from the date of action by the Commission. If appealed, the request will be placed on the next available City Council agenda as listed above. Rezoning requests, zoning amendments and conditions recommended by the Commission for approval by the City Council may be more restrictive than those described in this notice.

All interested persons are encouraged to attend the public hearing and express their opinions on the zoning change request. If you are unable to attend, but wish to have your opinions made a part of the public record, please submit written comments prior to the public hearing, to the address below:

**Community Development Department
City of Colleyville
100 Main Street
Colleyville, TX 76034**

If the property owners of 20% or more of the land within the 200 foot notification area file a written protest prior to the public hearing, State law provides that the approval of the zoning change request shall require the approval of a super majority vote by City Council.

The application is on file for public examination in the Community Development Department at 100 Main Street, Colleyville, Texas. A brief project description can be found online on the Active Development Case map: <https://www.colleyville.com/zoning.html>. For additional information, please contact the Community Development Department at 817.503.1052. Please reference the zoning case number when requesting information.

Ben Bryner
Director of Community Development
bbryner@colleyville.com

ORDINANCE O-18-xxxx

AMENDING THE ZONING ORDINANCE AND THE OFFICIAL ZONING MAP OF THE CITY OF COLLEYVILLE, TEXAS, BY CHANGING THE ZONING ON 4.369 ACRES, BEING TRACTS 2A01 & 2A02, ABSTRACT 1543, IN THE GEORGE W TEETER SURVEY, LOCATED AT 1309 GLADE ROAD, FROM THE AG AGRICULTURAL DISTRICT TO THE R-30 SINGLE FAMILY RESIDENTIAL DISTRICT; PROVIDING A PENALTY OF FINE NOT TO EXCEED THE SUM OF TWO THOUSAND DOLLARS (\$2,000.00); AND PROVIDING AN EFFECTIVE DATE

WHEREAS, the City of Colleyville has received an application for rezoning under Case ZC18-023; and

WHEREAS, the City of Colleyville deems it necessary, for the purpose of promoting the health, safety, morals, or general welfare of the City to enact a new zoning ordinance; and

WHEREAS, the City Council has appointed a Planning and Zoning Commission to recommend the boundaries of the various original zoning districts and appropriate regulations be enforced therein and to recommend a new zoning ordinance; and

WHEREAS, the Planning and Zoning Commission has divided the City into districts and has prepared regulations pertaining to such districts in accordance with a comprehensive plan designed to lessen congestion in the streets; and to secure safety from fire, panic, and other dangers; to promote health, general welfare; to provide adequate light and air; to prevent the overcrowding of land; to avoid undue concentration of population; to facilitate the adequate provision of transportation, water, sewerage, schools, parks, and other public requirements; and

WHEREAS, the Planning and Zoning Commission, has given reasonable consideration to, among other things, the character of the districts and their peculiar suitability for particular uses, with a view to conserving the value of buildings and encouraging the most appropriate use of land throughout the City; and

WHEREAS, the Planning and Zoning Commission of the City of Colleyville and the City of Colleyville City Council, in compliance with the Charter of the City of Colleyville, and State Law with reference to changes to zoning classifications under the Zoning Ordinance Regulations and Zoning Map, having given the requisite notices

by publication and otherwise, and after holding due hearings and affording a full and fair hearing to all the property owners generally, and to the persons interested and situated in the affected area and in the vicinity thereof, the governing body of the City of Colleyville is of the opinion that said change in zoning should be made.

NOW, THEREFORE, BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF COLLEYVILLE, TEXAS:

- Sec. 1. THAT all the foregoing premises and findings are found to be true and correct and are incorporated into the body of this ordinance as if copied in their entirety.
- Sec. 2. THAT the Comprehensive Zoning Ordinance of the City of Colleyville, Texas, be, and the same is hereby amended by changing the zoning on 4.369 acres, being Tracts 2A01 & 2A02, Abstract 1543, in the George W Teeter Survey, located at 1309 Glade Road, from the AG Agricultural district to the R-30 Single Family Residential district, as depicted in the attached Exhibit "A" and Exhibit "B".
- Sec. 3. THAT the above described tract of land shall be used only in the manner and for the purposes provided by the Comprehensive Zoning Ordinance of the City of Colleyville as heretofore amended, and as amended herein.
- Sec. 4. THAT any person, firm or corporation violating any of the provisions or terms of this ordinance shall be subject to the same penalty as provided for in the Comprehensive Zoning Ordinance of the City of Colleyville, and upon conviction shall be punishable by a fine not to exceed the sum of Two Thousand Dollars (\$2,000.00) for each offense.
- Sec. 5. THAT if any section, paragraph, subdivision, clause, phrase or provision of this ordinance shall be judged invalid or unconstitutional, the same shall not affect the validity of this ordinance as a whole or any portion thereof other than that portion so decided to be invalid or unconstitutional.
- Sec. 6. THAT in addition to and accumulative of all other penalties, the City shall have the right to seek injunctive relief for any and all violations

of this ordinance.

Sec. 7. THAT it has been found that there has been a change in conditions in the above described property, it is now necessary that it be given the above zoning classification in order to permit its proper development and in order to protect the public interest, comfort and general welfare, and requires that this ordinance shall take effect immediately from and after its passage.

AND IT IS SO ORDERED.

The first reading and public hearing being conducted on the 4th day of September 2018.

The second reading and public hearing being conducted on the 18th day of September 2018.

PASSED AND APPROVED BY A VOTE OF ____ AYES, ____ NAYS, AND ____ ABSTENTIONS ON THIS THE 18TH DAY OF SEPTEMBER 2018.

Mayor Richard Newton	_____	Mayor Pro Tem Bobby Lindamood	_____
Place 1, Tammy Nakamura	_____	Place 5, Chuck Kelley	_____
Place 3, Kathy Wheat	_____	Place 6, Callie Rigney	_____
Place 4, George Dodson	_____		

ATTEST:

CITY OF COLLEYVILLE

Christine Loven, TRMC
City Secretary

Richard Newton
Mayor

APPROVED AS TO FORM AND LEGALITY:

Whit Wyatt
City Attorney

Exhibit "A"- Zoning Map



ZC18-023

1309 Glade Road

DISCLAIMER:

This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

 Subject Property




Exhibit "B"- Metes & Bounds Description

Tract 1 – 4.3968 ACRES

Being a tract of land out of George W. Teeter Survey, Abstract No. 1543 and situated in the City of Colleyville, Tarrant County, Texas, and surveyed by Miller Surveying, Inc. of Hurst, Texas in November 2017, said tract being a portion of the same tract of land described in the deed to Robert Gene Hubbard et ux, Peggy Hubbard recorded in Volume 4069, Page 406 in the Deed Records of Tarrant County, Texas and being more particularly described by metes and bounds as follows:

Beginning at a 5/8 inch steel rod found in the southerly right-of-way line of Glade Road (Co. Rd. 3036), said rod being in the northerly boundary line of "Tract No. 1" of said Hubbard Deed and also being the most northerly northwest corner of Lot 1, Block 1, Greener Acres, an addition to the City of Colleyville, Texas according to the plat thereof recorded in Cabinet A, Slide 4936 of the Plat Records of said County;

Thence South 00 degrees 14 minutes 15 seconds East with the westerly boundary line of said Lot 1 a distance of 553.09 feet to a 1/2 inch "MILLER 5665" capped steel rod set for an inner corner thereof;

Thence South 89 degrees 25 minutes 35 seconds West continuing with said westerly boundary line a distance of 58.10 feet to a 1/2 inch steel rod found for an outer point thereof;

Thence South 00 degrees 12 minutes 14 seconds West continuing with said westerly boundary line a distance of 415.82 feet to a 1/2 inch steel rod found for the southwest corner of said Lot 1, said rod being in the northerly boundary line of Block 1, The Lakes of Somerset, an addition to the City of Colleyville, Texas according to the plat thereof recorded in Cabinet A, Slide 312 of said plat records;

Thence North 89 degrees 46 minutes 39 seconds West with said northerly boundary line a distance of 151.92 feet to a point in a fence post found in the easterly boundary line of Carmel Place Estates, an addition to the City of Colleyville, Texas according to the plat thereof recorded as Instrument No. D217142798 of the Official Public Records of said County;

Thence North 01 degrees 25 minutes 38 seconds West with said easterly boundary line a distance of 985.17 feet to a cross in concrete set for the northwest corner of said Tract 1, said cross being in said southerly right-of-way line;

Thence North 89 degrees 53 minutes 54 seconds East with the northerly boundary line of said Tract 1 and with said southerly right-of-way line a distance of 233.33 feet to the point of beginning and containing 4.3968 acres of land, more or less.



City of Colleyville Planning and Zoning Commission Agenda Briefing

City Hall
100 Main Street
Colleyville, Texas 76034
www.colleyville.com

Agenda Number 2c	Agenda Date 08/13/2018	Number
Type Public Hearing Agenda Items		
Department Community Development		

Title

Consideration of a combination Preliminary/Final Plat of Tract 2A01 & 2A02, Abstract 1543, in the George W Teeter Survey, located at 1309 Glade Road, Case PC18-012

Explanation

Rome Barnes, the applicant, has submitted a request for a Preliminary/Final Plat on Tracts 2A01 & 2A02, Abstract 1543, in the George W Teeter Survey, being approximately 4.369 acres, and zoned AG Agricultural. The purpose is to allow for development of 5 new single-family residential lots.

Existing Conditions/Background: The subject property, 1309 Glade Road, is located on the east side of Carmel Place across from an existing Planned Unit Development – Residential (PUD-R) subdivision called Carmel Place. The property currently has Agricultural zoning (AG) and remains undeveloped except for a single house on the property which is planned to be removed.

Surrounding Development: All of the surrounding property has developed with single family residences using a variety of zoning classifications, which include R-20 and PUD-R (Planned Unit Development – Residential).

Drainage: A drainage analysis was completed for Carmel Place Estates and the area for Carmel Place Estates East was included in the analysis. Specific lot drainage for the five lots will be part of the engineering plans and consistent with the already submitted drainage analysis.

Analysis: The requested Preliminary/Final Plat allows the applicant to develop the lots in a manner complementary to the approved PUD-R on the west side of Carmel Place while also being compatible with the neighborhood surrounding it.

Plat waivers are needed for the lot widths of Lots one (1) and two (2), which are shown as 116.43 feet because a 125' lot width is required for R-30 zoning.

Fees: Park Land Dedication fees are required in the amount of \$1,802 per residential lot. Park Land Dedication fees are due prior to filing the plat for record. Impact Fees are also required per Chapter 13 (Impact Fees) of the Land Development Code and are due prior to the issuance of a Building Permit.

Tree Preservation: Any subdivision of the subject property must comply with Chapter 5 (Tree Preservation) of the Land Development Code. Where any tree is slated for removal, no site grading, dirt disturbance or new construction may occur on the property until a Tree Removal Permit has been issued that is associated with an approved Tree Preservation Plan.

In addition to the requirements for submittal of a Tree Removal Permit and Tree Preservation Plan, future development on the site must maintain the minimum existing protected tree canopy coverage as required in Chapter 5.

Comprehensive Plan: The City's comprehensive plan, *Destination Colleyville*, identifies the subject property for single-family residential development. The proposed R-30 does not conflict with any portion of the comprehensive plan. The proposed R-30 facilitates the maximum desired residential density of 1.45 units per net acre.

Public Notification: Staff mailed notices to all property owners within 200 feet, Homeowners Associations within 500 feet, and Grapevine Colleyville ISD on Friday, July 27, 2018 regarding this request, per state law. Notice was also published in the *Fort Worth Star-Telegram* on July 28, 2018, as required by State law and the Land Development Code. To date staff has not received any formal responses.

Staff Recommendation: The proposed Preliminary/Final Plat will meet the requirements of the Land Development Code if the zoning is approved. Staff recommends approval with a plat waiver to lot width for Lots 1 and 2.


Recommendation

Approve

Attachments

1. Aerial Map
2. Zoning Map
3. Future Land Use Map
4. Plat Exhibit
5. Notification Map
6. Notification List
7. Property Owner Notification
8. Draft Resolution

Aerial Map




PC18-012

1309 Glade Road

DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

 Subject Property



Zoning Map




PC18-012

1309 Glade Road

DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

 Subject Property



Future Land Use Map




PC18-012


1309 Glade Road

DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

 Subject Property



Plat Exhibit



OWNER:
CADG CARMEL PLACE, LLC
1800 VALLEY VIEW LANE, SUITE 300
FARMERS BRANCH, TEXAS 75234
CONTACT: MEHRDAD MOAYEDI

ENGINEER/APPLICANT:
ION DESIGN GROUP, INC.
7075 TWIN HILLS AVENUE, SUITE 350
DALLAS, TX 75231
CONTACT: BRYAN KLEIN/JASON TRAFTON, PE
214-370-3470

STATE OF TEXAS
COUNTY OF TARRANT

OWNER'S DEDICATION AND CERTIFICATE

WHEREAS CADG Carmel Place, LLC, acting by and through the undersigned agent thereof, is the owners Being a tract of land out of the George W. Teeter Survey, Abstract No. 1543 and situated in the City of Colleyville, Tarrant County, Texas, and surveyed by Miller Surveying, Inc. of Hurst, Texas in November 2017, said tract being a portion of the same tract of land described in the deed to Robert Gene Hubbard et ux, Peggy Hubbard recorded in Volume 4008, Page 406 in the Deed Records of Tarrant County, Texas and being more particularly described by metes and bounds as follows:

Beginning at a 5/8 inch steel rod found in the southerly right-of-way line of Glade Road (Co. Rd. 3036), said rod being in the northerly boundary line of "Tract No. 1" of said Hubbard Deed and also being the most northerly northwest corner of Lot 1, Block 1, Greener Acres, an addition to the City of Colleyville, Texas according to the plat thereof recorded in Cabinet A, Slide 4936 of the Plat Records of said County;

Thence South 00 degrees 14 minutes 15 seconds East with the westerly boundary line of said Lot 1 a distance of 553.09 feet to a 1/2 inch "MILLER 5665" capped steel rod set for an inner corner thereof;

Thence South 89 degrees 25 minutes 35 seconds West continuing with said westerly boundary line a distance of 58.10 feet to a 1/2 inch steel rod found for an outer point thereof;

Thence South 00 degrees 12 minutes 14 seconds West continuing with said westerly boundary line a distance of 415.82 feet to a 1/2 inch steel rod found for the southwest corner of said Lot 1, said rod being in the northerly boundary line of Block 1, The Lakes of Somerset, an addition to the City of Colleyville, Texas according to the plat thereof recorded in Cabinet A, Slide 312 of said plat records;

Thence North 89 degrees 46 minutes 39 seconds West with said northerly boundary line a distance of 151.92 feet to a point in a fence post found in the easterly boundary line of Carmel Place Estates, an addition to the City of Colleyville, Texas according to the plat thereof recorded as Instrument No. 0217142798 of the Official Public Records of said County;

Thence North 01 degrees 25 minutes 38 seconds West with said easterly boundary line a distance of 968.78 feet to a cross in concrete set for the northwest corner of said Tract 1, said cross being in said southerly right-of-way line;

Thence North 89 degrees 53 minutes 54 seconds East with the northerly boundary line of said Tract 1 and with said southerly right-of-way line a distance of 233.33 feet to the point of beginning and containing 4.3968 acres of land, more or less.

NOW THEREFORE, KNOW ALL MEN BY THESE PRESENTS:

That CADG Carmel Place, LLC, acting by and through the undersigned agent thereof, do hereby adopt this plat designating the hereinbefore described property as **CARMEL PLACE ESTATES EAST**, an addition to the City of Colleyville, Tarrant County, Texas, and do hereby dedicate fee simple to the public use forever all streets, rights-of-way, and alleys shown thereon, and do hereby reserve the easements shown on this plat for the mutual use and accommodation of all public utilities desiring to use or using the same. Any public utility shall have the right to remove and keep removed all or part of any buildings, fences, trees, shrubs or other improvements or growths in which any way endanger or interfere with the construction, maintenance or efficiency of its respective systems on any of these easements, and any public utility shall at all times have the right of ingress and egress to and from and upon the said easement for the purpose of constructing, reconstructing, inspecting, and patrolling, without the necessity at any time of procuring the permission of anyone. This plat approved subject to all platting ordinances, rules regulations, and resolutions of the City of Colleyville, Texas.

Witness my hand this ____ day of _____, 20____.

CADG Carmel Place, LLC

STATE OF TEXAS §
COUNTY OF TARRANT §

Before me, the undersigned, a Notary Public in and for said County and State on this date appeared _____, known to me to be the person whose name is subscribed to the foregoing instrument and acknowledged to me that she executed the same for the purpose and considerations therein expressed, and in the capacity therein stated.

Given under my hand and seal of office this ____ day of _____, 20____.

Notary Public for the State of Texas

PLANNING AND ZONING COMMISSION APPROVAL

WHEREAS The Planning and Zoning Commission of the City of Colleyville, Texas voted affirmatively on this the ____ day of _____, 20____, to approve this Plat.

Chairman, Planning and Zoning Commission _____

Attest: Secretary, Planning and Zoning Commission _____

Preliminary Plat

LOTS 1 THRU 5, BLOCK A
CARMEL PLACE ESTATES EAST
an addition to the City of Colleyville, Tarrant County, Texas

Consisting of 5 lots and being 4.3968 acres of land out of the
GEORGE W. TEETER SURVEY, ABSTRACT NO. 1543
Surveyed in March of 2018


KNOW ALL MEN BY THESE PRESENTS:

That I, Jason B. Rawlings, Registered Professional Land Surveyor No. 5665 licensed in the State of Texas, do hereby certify that this Plat is true and correct and was prepared from an actual survey made under my supervision on the ground. Further, this survey conforms to the general rules of procedures and practices of the most current Professional Land Surveying Practices Act.

Jason B. Rawlings Date _____

MILLER
Surveying, Inc.
Commercial • Residential • Municipal
430 Mid Cities Blvd. 817-577-1052
Hurst, Texas 76054 TxLSF No. 10100400
mllersurvey.net


Notification Map



PC18-012

1309 Glade Road

- Subject Property
- 200ft Buffer
- Properties within 200ft



DISCLAIMER:
This map and information contained in it were developed exclusively for use by the City of Colleyville. Any use or reliance on this map by anyone else is at that party's risk and without liability to the City of Colleyville, its officials or employees for any discrepancies, errors, or variances which may exist.

Notification List

Owner Name	Owner Address	Owner City	Owner Zip	Situs Address
ARCLAND INVESTMENTS LLC	1300 GLADE RD	COLLEYVILLE, TX	76034	1300 GLADE RD
MAUNEY, KEITH	1216 CHATSWORTH DR	COLLEYVILLE, TX	76034	1216 CHATSWORTH DR
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4916 CARMEL PL
SMITH, DENIS J	1308 CHATSWORTH CT E	COLLEYVILLE, TX	76034	1308 CHATSWORTH CT E
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4908 CARMEL PL
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4816 CARMEL PL
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4828 CARMEL PL
WILLIAMS, JAMES P	4700 STAFFORD DR	COLLEYVILLE, TX	76034	4700 STAFFORD DR
LOGAN, EMORY M	1313 GLADE RD	COLLEYVILLE, TX	76034	1313 GLADE RD
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4804 CARMEL PL
HAUTANEN, OSMO A	1304 CHATSWORTH CT E	COLLEYVILLE, TX	76034	1304 CHATSWORTH CT E
EMLER LIVING TRUST	1300 CHATSWORTH CT E	COLLEYVILLE, TX	76034	1300 CHATSWORTH CT E
HICKSON, HEATHER J	1315 GLADE RD	COLLEYVILLE, TX	76034	1317 GLADE RD
HUBBARD, ROBERT GENE	PO BOX 575	ALBA, TX	75410	1309 GLADE RD
FRANKLIN, BRENT	2800 HIGHLAND PARK CT	COLLEYVILLE, TX	76034	4912 CARMEL PL
PRESERVATION HOA INC	101 CLARIDEN RANCH RD	SOUTHLAKE, TX	76092	1405 BLUEBONNET DR
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4808 CARMEL PL
K HOVNANIAN HOMES - DFW LLC	5808 W PLANO PKWY	PLANO, TX	75093	4900 PRESERVATION AVE
HICKSON, STEVEN A	1315 GLADE RD	COLLEYVILLE, TX	76034	1315 GLADE RD
SNYDER, JOHN	1701 ROYAL LN #1202	DALLAS, TX	75229	4812 CARMEL PL
FOUNTAINS AT RIVERWALK OFFICE	704 KENT CT	SOUTHLAKE, TX	76092	1301 STONEBRIDGE DR
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4800 CARMEL PL
CHELIND LLC	1312 GLADE RD	COLLEYVILLE, TX	76034	1312 GLADE RD
HSV RETREAT LLC	5013 PRESERVATION AVE	COLLEYVILLE, TX	76034	1308 GLADE RD
ROACH, ALISHA	1312 CHATSWORTH CT E	COLLEYVILLE, TX	76034	1312 CHATSWORTH CT E
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4920 CARMEL PL
SIENA HOMES LLC	1800 VALLEY VIEW LN STE 400	FARMERS BRNCH, TX	75234	4820 CARMEL PL
CADG CARMEL PLACE LLC	1800 VALLEY VIEW LN STE 300	FARMERS BRNCH, TX	75234	4824 CARMEL PL
BRIDGES AT RIVERWALK ADDITION	P.O. BOX 1183	COLLEYVILLE, TX	76034	COURTESY NOTICE
LAKES OF SOMERSET, THE	1104 CHATSWORTH COURT WEST	COLLEYVILLE, TX	76034	COURTESY NOTICE
RIVERWALK AT COLLEYVILLE	P.O. BOX 1031	COLLEYVILLE, TX	76034	COURTESY NOTICE
GRAPEVINE-COLLEYVILLE ISD	3051 IRA E. WOODS AVE	GRAPEVINE, TX	76051	STATE REQUIRED
BARNES, ROME	1800 VALLEY VIEW LANE, STE 300	FARMERS BRANCH, TX	75234	APPLICANT

Public hearing notices were mailed July 27, 2018 by Araceli Botello



NOTICE OF PUBLIC HEARING

Zoning Case Number: PC18-012

Applicant: Rome Barnes

Owner: CADG Carmel Place, LLC

Location: 1309 Glade Road

Property Description: Tract 2A01 & 2A02, Abstract 1543, in the George W Teeter Survey

Present Zoning: AG Agricultural

Request: Consideration of a combination Preliminary/Final Plat for Lots 1-5, Block A, of the Carmel Place Estates East, located at 1309 Glade Road. The purpose is to allow for development of 5 new single-family residential lots.

The City of Colleyville has scheduled public hearings concerning the above referenced request on the following dates and location:

Planning and Zoning Commission Meeting: Monday, August 13, 2018 at 7:00 p.m.
City Council Meetings: Tuesday, September 18, 2018 at 7:30 p.m.
3rd floor of City Hall, 100 Main Street, Colleyville, Texas

This notice has been sent to all owners of real property within 200 feet of the request as such ownership appears on the last approved tax roll and all homeowners associations within 500 feet. Action by the Planning and Zoning Commission serves as a recommendation to the City Council and is not a final action on the request.

The application is on file for public examination in the Community Development Department at 100 Main Street, Colleyville, Texas. A brief project description can be found online on the Active Development Case map: <https://www.colleyville.com/government/departments-a-l/community-development/active-development-cases>. For additional information, please contact the Community Development Department at 817.503.1052. Please reference the zoning case number when requesting information.

Ben Bryner
Community Development Director
bbryner@colleyville.com

RESOLUTION R-18-XXXX

A RESOLUTION APPROVING A PRELIMINARY/FINAL PLAT FOR LOTS 1 - 5, BLOCK A, OF THE CARMEL PLACE ESTATES EAST ADDITION

WHEREAS, the Planning and Zoning Commission recommended approval of the Preliminary/Final Plat for Lots 1-5, Block A, of the Carmel Place Estates East Addition on August 13, 2018.

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF COLLEYVILLE, TEXAS:

Sec. 1. THAT the Preliminary/Final Plat for Lots 1-5, Block A, of the Carmel Place Estates East Addition on approximately 4.396 acres, attached as Exhibit "A" - Plat Exhibit, is hereby approved with the following plat waivers:

1. Lot Width: A lot width of approximately 116 feet shall be allowed for Lots 1 & 2.

AND IT IS SO RESOLVED.

APPROVED BY A VOTE OF ____ AYES, ____ NAYS, AND ____ ABSTENTIONS ON THIS THE 4th DAY OF SEPTEMBER 2018.

Mayor Richard Newton _____
Place 1, Tammy Nakamura _____
Place 3, Kathy Wheat _____
Place 4, George Dodson _____

Mayor Pro Tem Bobby Lindamood _____
Place 5, Chuck Kelley _____
Place 6, Callie Rigney _____

ATTEST:

CITY OF COLLEYVILLE

Christine Loven, TRMC
City Secretary

Richard Newton
Mayor

[illegible]



City of Colleyville Planning and Zoning Commission Agenda Briefing

City Hall
100 Main Street
Colleyville, Texas 76034
www.colleyville.com

Agenda Number 2d	Agenda Date 08/13/2018	Number
Type Public Hearing Agenda Items		
Department Community Development		

Title

Consideration of amendments to the Land Development Code, specifically Chapter 3 – Land Use, Chapter 8 – Plat Review Procedures, and Chapter 9 – Subdivision Design & Public Facilities

Explanation

The City Council had instructed staff to review and propose amendments to each chapter within the City's Land Development Code (LDC). City staff has already reviewed the attached chapters with the City Council at a recent worksession meeting. The process for adopting amendments to the LDC include formal review and recommendation by the Planning and Zoning Commission followed by formal review and approval by the City Council.

The attached chapters are a continuation of the formal adoption process. Any remaining chapters will be brought forward over the next several months until the entire Land Development Code has been reviewed.

Recommendation

Approve

Attachments

1. Ch. 03 Land Use - Redline v3 (06.21.18)

Chapter 3 Land Use

Rev. 04/15/2014

Section 3.1 – Purpose of This Chapter

The zoning regulations and districts herein established have been made in accordance with a comprehensive plan for the purpose of promoting health, safety, morals and general welfare of the City of Colleyville. They have been designed to lessen congestion in the streets; to secure safety from fire, panic and other dangers; to provide adequate light and air; to prevent the overcrowding of land; to avoid undue concentration of population; to facilitate the adequate provision of transportation, water, sewage, schools, parks and other public facilities. The zoning districts have been created with reasonable consideration, among other things, of the character of the district and its peculiar suitability for the particular uses and with a view of conserving the value of buildings and encouraging the most appropriate use of land throughout the community.

Section 3.2 – Authorization for Adoption of This Chapter

The regulations contained in this Chapter have been adopted under the authority of *Chapter 211 – Municipal Zoning Authority of the Texas Local Government Code*, which authorizes a municipality to divide a municipality into districts and, within each district, regulate the erection, construction, reconstruction, alteration, repair, or use of buildings, other structures, or land. This Chapter is also adopted under the authority of the *Home Rule Charter of the City of Colleyville*, which authorizes the City Council to exercise all powers granted to municipalities by the Constitution or the laws of the State of Texas.

Section 3.3 – Variances and Appeals

Any person seeking approval of a development as required by this Land Development Code may request a variance from a requirement contained in this Chapter, or appeal a decision of an Administrative Official by submitting a request using the procedures described in *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.4 – Definitions

Definitions applicable to this Chapter may be found in *Chapter 2 - Definitions* of this Land Development Code.

Section 3.5 – Establishment of Districts

- A. Official Zoning Map – The City is hereby divided into zones, or districts, as shown on the Official Zoning Map which, together with all explanatory matter thereon, is hereby adopted by reference and declared to be a part of this Chapter. The Official Zoning Map shall be identified by the signature of the Mayor, attested by the City Secretary, and bearing the seal of the City under the following words: "This is to certify that this is the Official Zoning Map referred to in Ordinance No. 0-77-248 of the City of Colleyville, Texas," together with the date of adoption of this Chapter.
1. The Official Zoning Map shall be made current from time to time to reflect the changes and amendments, if any, that are approved by the City Council. Any such notations to bring said map current shall include, but not be limited to, the following: Ordinance number of zoning change, date of minutes of passage of said ordinance, boundary of zoning change, zoning classification declared by changing ordinance, and the initial of the City Secretary amending the map. Any unauthorized change of whatever kind to the Official Zoning Map by any person shall be and the same is prohibited.

2. The Official Zoning Map is not intended to control the procedural prerequisites applicable and the ordinances should be looked to as the authoritative source for all zoning. The Official Zoning Map shall be located and displayed in the Colleyville City Hall.
- B. Replacement of Official Zoning Map – In the event that the Official Zoning Map becomes damaged, destroyed, lost, or difficult to interpret because of the nature or number of changes and additions, the City Council may by resolution adopt a new Official Zoning Map which shall supersede the prior Official Zoning Map. The new Official Zoning Map may correct drafting or other errors or omissions in the prior Official Zoning Map and bring the Official Zoning Map up-to-date to reflect any and all amendments or changes in the same.
- C. Rules for Interpretation of District Boundaries – Where uncertainty exists as to the boundaries of districts as shown on the Official Zoning Map, the following rules shall apply:
 1. Boundaries indicated as approximately following the centerlines of streets, highways, or alleys shall be construed to follow such centerlines.
 2. Boundaries indicated as approximately following platted lot lines shall be construed as following such lot lines.
 3. Boundaries indicated as approximately following City Limits shall be construed as following City Limits.
 4. Boundaries indicated as following railroad lines shall be construed to be midway between the main tracks.
 5. Boundaries indicated as following shore lines shall be construed to follow such shore lines, and in the event of change in the shore line shall be construed as moving with the actual shore line; boundaries indicated as approximately following the centerlines of streams, drainage courses, creeks, canals, lakes, or other bodies of water shall be construed to follow such centerlines.
 6. Boundaries indicated as parallel to, or extensions of, features indicated in paragraphs 1 through 5 above shall be so construed. Distances not specifically indicated on the Official Zoning Map shall be determined by the scale of the map.
 7. Where physical or cultural features existing on the ground are at variance with those shown on the Official Zoning Map or in other circumstances not covered by paragraphs 1 through 6 above, the Zoning Board of Adjustment shall interpret the district boundaries.
 8. Where a district boundary line divides a lot which was in single ownership at the time of passage of the original zoning ordinance, the Zoning Board of Adjustment may permit, as a special exception, the extension of the regulations for either portion of the lot not to exceed fifty (50') feet beyond the district line into the remaining portion of the lot to either side of said district line.

Section 3.6 – Application of District Regulations; Classification of New and Unlisted Uses; and Platting of Property Not Properly Zoned

- A. Application – The regulations set by this Chapter within each district shall be minimum regulations and shall apply uniformly to each class or kind of structure or land and particularly except as hereinafter provided:
 1. No building, structure, or land shall hereafter be used or occupied, and no building or structure or part thereof shall hereafter be erected, constructed, re-constructed, moved, or structurally altered unless in conformity with all of the regulations herein specified for the district in which it is located.
 2. No building or other structure shall hereafter be erected or altered:

- a. to exceed the height;
 - b. to accommodate or house a greater number of families;
 - c. to occupy a greater percentage of lot area;
 - d. to have narrower or smaller rear yards, front yards, side yards, or other open spaces than herein required; or in any other manner contrary to the provisions of this Chapter.
 3. No part of a yard, other open space, or off-street parking or loading space required about or in connection with any building for the purpose of complying with this Chapter shall be included as part of a yard, open space, or off-street parking or loading space similarly required for any other building except as specified in the "Off-Street Parking Requirements." of this Chapter.
 4. No yard or lot existing at the time of passage of this Chapter shall be reduced in dimension or area below the minimum requirements set forth herein. Yards or lots created after the effective date of the original zoning ordinance shall meet at least the minimum requirements established by this Chapter.
 5. In every dwelling unit the density of occupancy shall not exceed 1.5 persons per room.
 6. All territory which hereafter is annexed to the City shall automatically be considered to be in the AG - Agricultural District, unless otherwise classified by the City Council after public hearing and upon recommendation from the Planning and Zoning Commission.
- B. Classification of New and Unlisted Uses – It is recognized that new types of land may develop and forms of land use not anticipated herein may seek to locate in the City. In order to provide for such changes and contingencies, a determination as to the appropriate classification of any new or unlisted form of land and use shall be made as follows:
1. The Administrative Official shall refer the question concerning any new or unlisted use to the Planning and Zoning Commission requesting an interpretation as to the proper zoning classification into which such use should be placed. The use interpretation question shall be determined as to the nature of the use and whether it involves dwelling activity, sales, processing, type of product, storage and the amount and nature thereof, (i.e., enclosed or open storage), anticipated employment, transportation requirements, the general degree of noise, odor, fumes, dust, toxic material and vibration likely to be generated, if any, and the general requirements for public utilities such as water and sanitary sewer.
 2. The Planning and Zoning Commission shall consider the nature and described performance of the proposed use and its compatibility with the uses permitted in the various zoning districts, and determine the zoning district or districts within which such use should be permitted.
 3. The Planning and Zoning Commission shall transmit its findings and recommendations to the City Council as to the classification proposed for any new or unlisted use. The City Council shall approve the recommendation of the Planning and Zoning Commission, or make such other determination concerning the classification of such use as appropriate, based upon its findings of fact, and amend this Chapter to reflect said findings and decisions.
- C. Platting of Property not Properly Zoned – No plat of any residential or non-residential subdivision within the City, or that which is being annexed to the City, shall be approved unless and until the area covered by the proposed plat is or shall be zoned to the proper zoning classification by the City Council, upon recommendation from the Planning and Zoning Commission. A public hearing by the Planning and Zoning Commission on a proposed annexation, zoning classification, and plat approval, or any combination thereof, may be held simultaneously.

Section 3.7 – Non-conforming Uses, Lots and Buildings

- A. Intent – Within the districts established by this Chapter, or amendments that may later be adopted, there exist lots and uses of land, buildings and structures, uses of land and buildings in combination, and characteristics of use which were lawful before the original zoning ordinance was passed or amended, but which would be prohibited, regulated, or restricted under the terms of this Chapter or future amendment. It is the intent of this Chapter to permit these non-conformities to continue until they are

Commented [BB1]: Needs further review

removed, but not to encourage their survival. It is further the intent of this Chapter that such non-conformities shall not be enlarged upon, expanded or extended, nor be used as ground for adding other buildings and structures or uses prohibited elsewhere in the same district.

Non-conforming uses are declared by this Chapter to be incompatible with permitted uses in the districts involved. A non-conforming use of a building or structure, a non-conforming use of land, or a non-conforming use of buildings and land in combination shall not be extended or enlarged after passage of this Chapter by attachment on a building or premises or by the addition of other uses of a nature which would be prohibited generally in the district involved.

To avoid undue hardship, nothing in this Chapter shall be deemed to require a change in the plans, construction, or designated use of any building on which actual construction was lawfully begun prior to the effective date of adoption or amendment of this Chapter and upon which actual building construction has been carried on diligently. Actual construction is hereby defined to include the placing of construction materials in permanent position and fastened in a permanent manner. Where excavation or demolition or removal of an existing building has been substantially begun preparatory to rebuilding, such excavation or demolition or removal shall be deemed to be actual construction, provided that work shall be carried on diligently.

- B. Non-conforming Lots of Record – In any zoning district in which single-family dwellings or commercial buildings are permitted, a single-family dwelling or commercial building and customary accessory buildings may be erected on any single lot of record at the effective date of adoption or amendment of this Chapter, notwithstanding limitations imposed by other provisions of this Chapter. Such lot must be in separate ownership and not of continuous frontage with other lots in the same ownership. This provision shall apply even though such lot fails to meet the requirements for area or width, or both, that are generally applicable in the district, provided that yard dimensions and requirements other than those applying to area or width, or both, of the lot shall conform to the regulations for the district in which such lot is located. Variance of yard requirements shall be obtained only through action of the Zoning Board of Adjustment.
- C. Non-conforming Uses of Land (or Land with Minor Building Only) – Where at the time of passage of this Chapter lawful use of land exists which would not be permitted by the regulations imposed by this Chapter, and where such use involves no individual structure with a replacement cost exceeding one thousand dollars (\$1,000), the use may be continued so long as it remains otherwise lawful, provided:
1. No such nonconforming use shall be enlarged or increased, nor extended to occupy a greater area of land than was occupied at the effective date of adoption or amendment of the original zoning ordinance;
 2. No such nonconforming use shall be moved in whole or in part to any portion of the same lot or parcel other than that occupied by such use at the effective date of adoption or amendment of the original zoning ordinance;
 3. If any such nonconforming use of land ceases for any reason for a period of more than ninety (90) consecutive days, any subsequent use of such land shall conform to the regulations specified by this Chapter for the district in which such land is located;
 4. No additional building not conforming to the requirements of this Chapter shall be erected in connection with such nonconforming use of land.
- D. Non-conforming Buildings – Where a lawful building exists at the effective date of adoption or amendment of this Chapter that could not be built under the terms of this Chapter by reason of restrictions on area, lot coverage, height, yards, its location on the lot, or other requirements concerning the building, such building may be continued so long as it remains otherwise lawful, subject to the following provisions:
1. No such non-conforming building may be enlarged or altered in a way which increases its nonconformity, but any building or portion thereof may be altered to decrease its nonconformity or to comply with City building codes.

2. Should such non-conforming building or non-conforming portion of a building be destroyed by any means to an extent of more than fifty (50) percent of its replacement cost at time of destruction; it shall not be reconstructed except in conformity with the provisions of this Chapter, or when approved by the Zoning Board of Adjustment, after public hearing thereon, when the Board's findings, having due regard for the property rights of persons affected, were considered in the light of public welfare and the character of the area surrounding the nonconforming building and the conservation and protection of property.
 3. Should such building be moved for any reason any distance whatever, it shall thereafter conform to the regulations of the district in which it is located after it is moved.
- E. Non-conforming Uses of Buildings or of Buildings and Premises in Combination – If lawful use involving individual buildings with a replacement cost of one thousand dollars (\$1,000.00) or more, or of buildings and premises in combination, exist at the effective date of adoption or amendment of this Chapter that would not be allowed in a particular district under the terms of this Chapter, the lawful use may be continued so long as it remains otherwise lawful, subject to the following provisions:
1. No existing building devoted to a use not permitted by this Chapter in the district in which it is located shall be enlarged, extended, constructed, reconstructed, moved, or structurally altered except in changing the use of the building to a use permitted in the district in which it is located, or to comply with City building codes.
 2. Any non-conforming use may be extended throughout any parts of a building which were manifestly arranged or designed for such use at the time of adoption or amendment of this Chapter, but no such use shall be extended to occupy any land outside such building.
 3. If no structural alterations are made, except as required by the City's building codes, any non-conforming use of a building, or building and premises, may, as a special exception, be changed to another non-conforming use provided that the Zoning Board of Adjustment, either by general rule or by making findings in the specific case, shall find that the proposed use is equally appropriate or more appropriate to the district than the existing non-conforming use. In permitting such change, the Zoning Board of Adjustment may require appropriate conditions and safeguards in accord with the provisions of this Chapter.
 4. Any building, or building and land in combination, in or on which a non-conforming use is superseded by a permitted use, shall thereafter conform to the regulations for the district, and the non-conforming use may not thereafter be resumed.
 5. When a non-conforming use of a building, or building and premises in combination, is discontinued or abandoned for six (6) consecutive months or for eighteen (18) months during any three-year period (except when government action impedes access to the premises), the building, or building and premises in combination, shall not thereafter be used except in conformity with the regulations of the district in which it is located.
 6. Where non-conforming use status applies to a building and premises in combination, removal or destruction of the building shall eliminate the non-conforming status and any new construction shall be in accordance with the zoning regulations applicable to the district. Destruction for the purpose of this subsection is defined as damage to an extent of more than fifty (50) percent of the replacement cost at time of destruction. (O-00-1261 / 12/19/00)
- F. Repairs and Maintenance – On any non-conforming building or portion of a building containing a non-conforming use, work may be done in any period of twelve (12) consecutive months on ordinary repairs, or on repair or replacement of non-bearing walls, fixtures, wiring, or plumbing, to an extent not exceeding ten (10) percent of the current replacement cost of the non-conforming building or non-conforming portion of the building as the case may be, provided that the cubic content existing when it became non-conforming shall not be increased.

If a non-conforming building or portion of a building containing a non-conforming use becomes physically

unsafe or unlawful due to lack of repairs and maintenance, and is declared by any duly authorized City official to be unsafe or unlawful by reason of physical condition, it shall not thereafter be restored, repaired, or rebuilt except in conformity with the regulations of the district in which it is located.

Nothing in this Chapter shall be deemed to prevent the strengthening or restoring to a safe condition of any building or part thereof declared to be unsafe by any official charged with protecting the public safety, upon order of such official.

G. Changing Non-conforming Uses

1. Any non-conforming use may be changed to a conforming use and once such change is made, the use shall not thereafter be changed back to a non-conforming use.
2. The Zoning Board of Adjustment may grant a change of use from one non-conforming use to another non-conforming use provided such change is to a use permitted in a zoning district where the original non-conforming use would be permitted or such change is to a use permitted in a more restrictive classification. However, such change of use and occupancy shall not tend to prolong the life of a non-conforming use. Upon review of the facts in accordance with the procedures for the Zoning Board of Adjustment, contained in *Chapter 1 – General Provisions* of this Land Development Code, the Zoning Board of Adjustment may establish a specific period of time for the return of the occupancy to a conforming use.
3. The Zoning Board of Adjustment may approve the remodeling or enlargement of a non-conforming use when such an enlargement would not tend to prolong the life of the non-conforming use. Upon review of the facts, the Zoning Board of Adjustment may establish a specific period of time for the return of the occupancy to a conforming use in accordance with the procedures of the Zoning Board of Adjustment contained in *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.8 AG – Agricultural District

- A. Agricultural District – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this Section, are the regulations of the AG - Agricultural District.
- B. Purpose and Intent – The purpose of the AG - Agricultural District is to provide for compatible land, building and structure uses primarily oriented to agricultural farming and ranching, and extremely low density residential purposes. The district's locational characteristics are usually confined to the outer fringe of developed urbanized areas and/or along, unprotected flood-prone areas. The district also serves as: 1) a transitional land use element pending future, more intensive urbanization; 2) open space for the protection and enhancement of scenic areas, vistas, and recreational uses, and 3) where unusual or problematic soils, topographic conditions, or sensitive ecological features are present that would normally not be conducive or appropriate to more intensive forms and patterns of urbanization

The primary intent of this district is a land use designated to aid in the protection of certain lands suitable for producing and supplying food and related agricultural farm and ranch products from more intense urbanization until such time as warranted by demand and supportive community facilities and services.

- C. Use Regulations – Land, buildings and structures may be used only for the purposes allowed in this Chapter.
- D. Permitted Principal Uses – The permitted principal uses allowed in this district as are designated in *Section 3.24.C - Schedule of Permitted Principal Uses*.
- E. Permitted Accessory Uses – Subject to the provisions of *Section 3.28 - Supplementary District Regulations*, accessory buildings, structures and uses customarily incidental to the "Permitted Principal Uses" are allowed, including but not limited to the following:
1. Buildings, structures and uses accessory to permitted farming and ranching operations;
 2. Private residential garages, carports and related storage buildings and greenhouses accessory to

permitted residential uses.

3. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All "at grade" swimming pools with a depth greater than twenty-four (24") inches and "above grade" swimming pools having a water depth twenty-four (24") inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than (4') feet nor more than eight (8') feet in height, and of such material and design to discourage unauthorized entry to the facility. Such pool(s) may be located in a required side or rear yard, but not within a required front yard not forward of the primary dwelling, and shall not be located closer than five (5') feet to any side or rear property line.~~
4. ~~Servants quarters for domestic servants employed on the premises or family members~~ Accessory dwellings provided the gross habitable square feet of floor area shall not exceed six hundred (600) square feet complies with regulations found in Section 3.27 of this chapter. Such quarters may be housed within the principal residential dwelling, above a residential garage, or be part of an accessory building on the same premises, and shall comply with minimum standards for light, health, safety, and occupancy in conformance with other applicable City codes and ordinances.
5. Lanais, gazebos, garden and patio shelters, and children's play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
6. Non-commercial radio and television receiving antennae and non-commercial radio transmitting antennae limited in height to sixty (60) feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
7. Required off-street parking and loading spaces.
8. Home occupation uses as defined in *Chapter 2 – Definitions* of this Land Development Code.
9. Parking and storage of private boats(s), camper trailer(s), or other recreational vehicle(s), in conformance with the regulations for "Parking, Storage or Use of Major Recreational Equipment and Vehicles."
10. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code and other applicable City codes and ordinances.
11. Supplemental single-family dwelling for a farm employee and family when located on the same premises as the principal agricultural use, provided:
 - a. Such dwelling shall be used exclusively for the housing of a single-family employed full time on the premises in the conduct of operation or management of the principal agricultural use;
 - b. Such dwelling is under the same ownership as that of the agricultural use and is on the same land as the owner's principal place of residency;
 - c. The land area devoted to such dwelling conforms with the minimum requirements established in *Section 3.24 - Schedule of District Regulations* for single-family dwellings in an "RE" District, as if it were on a separate recorded lot; and
 - d. The total land area under common ownership comprising the agriculture use and related owner's and employee's residence is not less than twenty (20) acres.

~~F. Special Exception Uses – In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the "Zoning Board of Adjustment"~~

Commented [EW2]: Recommendation that the pool not extend past the front of the house

Commented [EW3]: Pool barrier requirements are codified in the adopted building codes

Commented [BB4]: New standards for Accessory Dwellings

Commented [BB5]: Deleted per Council direction

~~may, after public hearing thereon, authorize and grant the issuance of a "Special Exception" for such special exception uses as allowed in Section 3.24 - "Schedule of Permitted Principal Uses." The issuance of such "exception" by the "Board" shall be contingent upon reasonable and appropriate conditions and safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use, or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

GE. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions for ~~—~~ "Classification of New and Unlisted Uses."

HG. Density, Area, Yard, Height, and Lot Coverage Requirement – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes, (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of *Section 3.24 - Schedule of District Regulations* and other applicable provisions of *Section 3.28 - Supplementary District Regulations*.

H. Off Street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform ~~with~~to the "Off-Street Parking Requirements" and "Off-Street Loading Requirements" contained elsewhere in this Land Development Code.

J. Land Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the official zoning map affecting this district shall be accompanied by a land plan and supporting document therefor, in conformance with the provisions of *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.9 RE – Single Family "Estate" Residential District

A. **RE-Single Family Estate Residential District** – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this section, are the regulations of the RE - Single-Family Residential Estate District.

B. **Purpose and Intent** – The purpose and intent of the RE - Single-Family Estate Residential District is to provide for compatible land, building, and structural uses primarily oriented to low density residential estate purposes, select agricultural uses, open space uses, and selected community facility uses. The locational characteristic of this district is generally confined to the outer fringe of the more intensely urbanized and developed areas and/or along unprotected flood prone areas. The district further serves as a transitional element between limited residential development and intense agricultural activities and of higher density urbanized areas of the city. Low density detached single-family residential dwellings and estate development, along with the aforescribed uses, comprise the principal elements of the district.

C. **Use Regulations** – Land, buildings and structures may be used only for the purposes allowed in this Section.

D. **Permitted Principal Uses** – The permitted principal uses allowed in this district are as designated in *Section 3.24 - Schedule of Permitted Principal Uses*.

E. **Permitted Accessory Uses** – Subject to the provisions of *Section 3.28 - Supplementary District Regulations*, accessory buildings, structures, and uses customarily incidental to the "Permitted Principal Uses" are allowed, including but not limited to the following:

1. Buildings, structures, and uses accessory to permitted farming and ranching operations;
2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All "at grade" swimming pools with a water depth greater than twenty-four (24") inches and "above grade" swimming pools having a~~

~~water depth twenty-four (24") inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than four (4') feet nor more than eight (8') feet in height, and of such material and design to discourage unauthorized entry to the facility. Such pool(s) may be located in a required side or rear yard, but not within a required front yard forward of the primary dwelling on the lot, and shall not be located closer than five (5') feet to any side or rear property line.~~

Commented [EW6]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW7]: Recommend that the pool does not extend past the front of the dwelling

3. Private residential garages, carports, and related storage buildings and greenhouses accessory to permitted residential uses.
4. ~~Servants quarters for domestic servants employed on the premises or family members. Accessory dwellings provided the gross habitable square feet of floor area shall not exceed six hundred (600) square feet complies with regulations found in Section 3.27 of this chapter. Servants quarters for domestic servants employed on the premises or family members provided the gross habitable square feet of floor area shall not exceed six hundred (600) square feet.~~ Such quarters may be housed within the principal residential dwelling, above a residential garage, or be part of an accessory building on the same premises, and shall comply with minimum standards for light, health, safety, and occupancy in conformance with other applicable City codes and ordinances.
5. Lanais, gazebos, garden and patio shelters, and children's play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
6. Non-commercial radio and television receiving antennae and non-commercial radio transmitting antennae limited in height to sixty (60) feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
7. Required off-street parking and loading spaces.
8. Home occupation uses as defined in *Chapter 2 – Definitions* of this Land Development Code
9. Parking and storage of private boat(s), camper trailer(s) or other recreational vehicle(s), in conformance with the regulations for "Parking, Storage or Use of Major Recreational Equipment and Vehicles."
10. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code.
11. Private domestic greenhouses.
12. Private stables for the keeping of grazing animals, provided:
 - a. Significant ground accumulations of manure shall be collected and properly disposed of so as not to create offensive odors, fly breeding, or in any way become a health hazard or nuisance to humans or animals;
 - b. Fences for pens, corrals or similar enclosures shall be of sufficient height and strength to properly retain the grazing animal(s) on the premises; and
 - c. The minimum space area of the lot upon which such grazing animal(s) may be kept, including pens, corrals, and stables, shall not be less than 15,000 square feet per each grazing animal over five hundred (500) pounds and not less than five thousand (5,000) square feet for any other grazing animal.

Commented [BB8]: New standards for Accessory Dwellings

~~F. **Special Exception Uses** — In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the "Zoning Board of Adjustment" may, after public hearing thereon, authorize and grant the issuance of a "Special Exception" for such special exception uses as allowed in Section 3.24 – Schedule of Permitted Principal Uses. The issuance of such "exception" by the "Board" shall be contingent upon reasonable and appropriate conditions and~~

~~safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

GF. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions for the “Classification of New and Unlisted Uses.”

HG. Density, Area, Yard, Height, and Lot Coverage Requirements – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of *Section 3.24 - Schedule of District Regulations* and other applicable provisions of *Section 3.28 - Supplementary District Regulations*.

HI. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform ~~with~~to the provisions of the “Off-Street Parking Requirements,” and the “Off-Street Loading Requirements.”

JI. Land Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the Official Zoning Map affecting this district shall be accompanied by a land plan and supporting document therefore, in conformance with the provisions of *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.10 ~~R-40~~ – Single Family Residential District

A. **~~R-40 – Single Family Residential District~~** – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this section, are the regulations of the ~~R-40 – Single Family Residential District~~.

B. **Purpose and Intent** – The purpose and intent of the ~~R-40 – Single Family Residential District~~ is to provide for compatible land, building and structure uses primarily oriented to low density residential purposes, open space uses, and select community facility uses. The locational characteristics of this district are not confined to any specific or general area; however, they are most appropriate on the outer fringe of the more intensively urbanized parts of the community, and/or along protected flood prone areas. Land uses in this district are normally connected to an approved public or private sewage collection and treatment system, rather than individual septic tanks and subsurface drainage fields. Low density detached single family residential dwellings and development, along with the aforescribed uses, comprise the principal elements of the district.

C. **Use Regulation** – Land, buildings and structures may be used only for the purposes allowed in this Section.

D. **Permitted Principal Uses** – The permitted principal uses allowed in this district are as designated in *Section 3.24 - Schedule of Permitted Principal Uses*.

E. **Permitted Accessory Uses** – Subject to the provisions of *Section 3.28 - Supplementary District Regulations*, accessory buildings, structures, and uses customarily incidental to the “Permitted Principal Uses” are allowed, including but not limited to the following:

1. Private residential garages, carports and related storage buildings and greenhouses accessory to permitted residential uses.
2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. All “at grade” swimming pools with a water depth greater than twenty-four (24”) inches and “above grade” swimming pools having a water depth twenty-four (24”) inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than four (4’) feet nor more than six (6’) feet in height, and of

~~such material and design to discourage unauthorized entry to the facility. Such pool(s) may be located in a required side or rear yard, but not within a required front yard -but not forward of the primary dwelling on the lot, -and shall not be located closer than five (5') feet to any side' or rear property line.~~

Commented [EW9]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW10]: Recommend that the pool cannot extend beyond the front of the existing dwelling

3. Lanais, gazebos, garden and patio shelters, and children's play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
4. Noncommercial radio and television receiving antennae and noncommercial radio transmitting antennae limited in height to sixty (60') feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
5. Required off-street parking and loading spaces.
6. Home occupation uses as defined in *Chapter 2 – Definitions* of this Land Development Code.
7. Parking and storage of private boat(s), camper trailer(s), or other recreational vehicle(s), in conformance with the regulations for the "Parking, Storage or Use of Major Recreational Equipment and Vehicles."
8. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code
9. Private domestic greenhouses.
10. Private stables for the keeping of grazing animals, provided:
 - a. Significant ground accumulations of manure shall be collected and properly disposed of so as not to create offensive odors, fly breeding, or in any way become a health hazard or nuisance to humans or animals;
 - b. Fences for pens, corrals or similar enclosures shall be of sufficient height and strength to properly retain the grazing animal(s) on the premises; and
 - c. The minimum space area of the lot upon which such grazing animal(s) may be kept, including pens, corrals, and stables, shall not be less than 15,000 square feet per each grazing animal over five hundred (500) pounds and not less than five thousand (5,000) square feet for any other grazing animal.

~~F. Special Exception Uses – In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the "Zoning Board of Adjustment" may, after public hearing thereon, authorize and grant the issuance of a "Special Exception" for such special exception uses as allowed in Section 3.24 - "Schedule of Permitted Principal Uses." The issuance of such "exception" by the "Board" shall be contingent upon reasonable and appropriate conditions and safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

~~G.F. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions of the regulation for the "Classification of New and Unlisted Uses."~~

~~H.G. Density; Area; Yard; Height; and Lot Coverage Requirements – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of Section 3.24 - *Schedule of District Regulations* and other applicable provisions of Section 3.28 - *Supplementary District Regulations*.~~

H. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform ~~with~~to the provisions for "Off-Street Parking Requirements," and "Off-Street Loading Requirements."

J. Land Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the Official Zoning Map affecting this district shall be accompanied by a land plan and supporting document therefore, in conformance with the provisions of *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.11 ~~R-30~~ Single Family Residential District

A. **~~R-30~~ Single Family Residential District** – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this Section, are the regulations of the ~~R-30~~ Single-Family Residential District.

B. **Purpose and Intent** – The purpose and intent of the ~~R-30~~ Single-Family Residential District is to provide for compatible land, building, and structural uses primarily oriented to low density residential purposes, open space uses, and selected community facility uses. The locational characteristics of this district are generally found in the inner urbanized developed areas of the City. Land uses in this district are normally connected to an approved public or private sewage collection and treatment system, rather than individual septic tanks and subsurface drainage fields. Moderately low density detached single-family residential dwellings and development, along with the aforescribed uses, comprise the principal elements of the district.

C. **Use Regulation** – Land, buildings and structures may be used only for the purposes allowed in this Section.

D. **Permitted Principal Uses** – The permitted principal uses allowed in this district are as designated in *Section 3.24 - Schedule of Permitted Principal Uses*.

E. **Permitted Accessory Uses** – Subject to the provisions of *Section 3.28 - Supplementary District Regulations*, accessory buildings, structures, and uses customarily incidental to the "Permitted Principal Uses" are allowed, including but not limited to the following:

1. Private residential garages, carports and related storage buildings and greenhouses accessory to permitted residential uses.
2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All "at-grade" swimming pools with a water depth greater than (24") inches and "above grade" swimming pools having a water depth (24") inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than (4') feet nor more than (8') feet in height, and of such material and design to discourage unauthorized entry to the facility.~~ Such pool(s) may be located in a required side or rear yard, but not ~~within a required front yard~~ forward of the primary dwelling on the lot, and shall not be located closer than (5') feet to any side or rear property line.
3. Lanais, gazebos, garden and patio shelters, and children's play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
4. Noncommercial radio and television receiving antennae and noncommercial radio transmitting antennae limited in height to sixty (60') feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
5. Required off-street parking and loading spaces.

Commented [EW11]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW12]: Recommend that the pool cannot extend beyond the front of the existing dwelling on the lot

6. Home occupation uses as defined in *Chapter 2 – Definitions* of this Land Development Code.
7. Parking and storage of private boats(s), camper trailer(s), or other recreational vehicle(s), in conformance with the regulations for the "Parking, Storage or Use of Major Recreational Equipment and Vehicles."
8. Signs, in conformance with these regulations and other applicable City codes and ordinances.
9. Private domestic greenhouses.

~~F. Special Exception Uses – In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the "Zoning Board of Adjustment" may, after public hearing thereon, authorize and grant the issuance of a "Special Exception" for such as allowed in Section 2.24 – "Schedule of Permitted Principal Uses." The issuance of such "special exception uses" by the "Board" shall be contingent upon reasonable and appropriate conditions and safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use, or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

~~GE. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions for the "Classification of New and Unlisted Uses."~~

~~HG. Density, Area, Yard, Height, and Lot Coverage Requirement – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes, (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of Section 3.24 - "Schedule of District Regulations" and other applicable provisions of Section 3.28 - "Supplementary District Regulations."~~

~~JH. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform with the provisions of the "Off-Street Parking Requirements" and "Off-Street Loading Requirements."~~

~~JL. Land Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the "Official Zoning Map" affecting this district shall be accompanied by a land plan and supporting document therefore, in conformance with the provisions of Chapter 1 – ~~General~~ General Provisions of this Land Development Code regarding "Petition for Zoning District Change: Land Plan and Supporting Documents Required."~~

Section 3.12 ~~R-20~~ Single Family Residential District

- A. R-20 – Single Family Residential District – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this Section, are the regulations of the ~~R-20~~ Single-Family Residential District.
- B. Purpose and Intent – The purpose and intent of the ~~R-20~~ Single-Family Residential District is to provide for compatible land, building, and structural uses primarily oriented to medium-low density residential purposes, open space uses, and selected community facility uses. The locational characteristics of this district are generally found in the inner urbanized developed areas of the city, adjacent to shopping facilities. Land uses in this district are normally connected to an approved public or private sewage collection and treatment system, rather than individual septic tanks and sub-surface drainage fields. Moderately low density detached single-family residential dwellings as exist in the inner area of the city comprise the principal elements of the district. It is further the intent to use this district and its regulations to accommodate and recognize the existence of small lot conventional single-family development, which presently exists in the city.

- C. Use Regulations – Land, buildings and structures may be used only for the purposes allowed in this Section.
- D. Permitted Principal Uses – The permitted principal uses allowed in this district are as designated in *Section 3.24 - Schedule of Permitted Principal Uses*.
- E. Permitted Accessory Uses – Subject to the provisions of *Section 3.28 - Supplementary District Regulations*, accessory buildings, structures, and uses customarily incidental to the “permitted principal uses” are allowed, including but not limited to the following:
1. Private residential garages, carports and related storage buildings and greenhouses accessory to permitted residential uses.
 2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All “at-grade” swimming pools with a water depth greater than twenty-four (24”) inches and “above-grade” swimming pools having a water depth twenty-four (24”) inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than four (4’) feet nor more than eight (8’) feet in height, and of such material and design to discourage unauthorized entry to the facility. Such pool(s) may be located in a required side or rear yard, but not within a required front yard forward of the primary dwelling on the lot, and shall not be located closer than five (5’) feet to any side or rear property line.~~
 3. Lanais, gazebos, garden and patio shelters, and children’s play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
 4. Noncommercial radio and television receiving antennae and noncommercial radio transmitting antennae limited in height to sixty (60) feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses.
 5. Required off-street parking and loading spaces.
 6. Home occupation uses as defined in *Chapter 2 – Definitions* of this Land Development Code.
 7. Parking and storage of private boat(s), camper trailer(s), or other recreational vehicle(s), in conformance with the regulations for “Parking, Storage or Use of Major Recreational Equipment and Vehicles.”
 8. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code.
 9. Private domestic greenhouses.

~~F. Special Exception Uses – In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the “Zoning Board of Adjustment” may, after public hearing thereon, authorize and grant the issuance of a “Special Exception” for such special exception uses as allowed in *Section 3.24 – “Schedule of Permitted Principal Uses.”* The issuance of such “exception” by the “Board” shall be contingent upon reasonable and appropriate conditions and safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

F. R-10 Single-Family Residential District Historic Designation: All lots within the City of Colleyville with the R-10 designation shall conform to the standards of the R-20 zoning district.

Commented [EW13]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW14]: Recommend that the pool cannot extend beyond the front of the existing dwelling on the lot

Commented [BB15]: This will address the existing R-10 properties

- G. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions for the “Classification of New and Unlisted Uses.”
- H. Density; Area; Yard; Height; and Lot Coverage Requirements – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of *Section 3.24 - “Schedule of District Regulations”* and other applicable provisions of *Section 3.28 - “Supplementary District Regulations.”*
- I. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform ~~with~~ the provisions for “Off-Street Parking Requirements,” and “Off-Street Loading Requirements.”
- J. Land Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the Official Zoning Map affecting this district shall be accompanied by a land plan and supporting document therefore, in conformance with the provisions contained in *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.13 ~~R-15~~ – Single Family Residential District

- A. R-15 – Single Family Residential District – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this Section, are the regulations of the ~~R-15~~ – Single-Family Residential District.
- B. Purpose and Intent – The purpose and intent of the ~~R-15~~ – Single-Family Residential District is to provide for compatible land, building, and structural uses primarily oriented to medium-low density residential purposes, open space uses, and selected community facility uses. The locational characteristics of this district are generally found in the inner urbanized developed core of the city and/or adjacent to shopping facilities. Land uses in this district are normally connected to an approved public or private sewage collection and treatment system, rather than individual septic tanks and sub-surface drainage fields. Medium low density detached single-family residential buildings as exist in the inner core area of the city on typically small lots, along with the aforescribed uses, comprise the principal elements of the district. It is further the intent to use this district and its regulations to accommodate and recognize the existence of small lot conventional single-family development, which presently exists in the city, but not to create new-zoned areas for such conventional small lots.
- C. Use Regulations – Land, buildings and structures may be used only for the purposes allowed in this Section.
- D. Permitted Principal Uses – The permitted principal uses allowed in this district are as designated in *Section 3.24 - Schedule of Permitted Principal Uses*.
- E. Permitted Accessory Uses – Subject to the provisions of *Section 2.28 - Supplementary District Regulations*, accessory buildings, structures, and uses customarily incidental to the “permitted principal uses” are allowed, including but not limited to the following:
 - 1. Private residential garages, carports and related storage buildings and greenhouses accessory to permitted residential uses.
 - 2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All “at-grade” swimming pools with a water depth greater than twenty-four (24”) inches and “above grade” swimming pools having a water depth twenty-four (24”) inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than four (4’) feet nor more than eight (8’) feet in height, and of~~

~~such material and design to discourage unauthorized entry to the facility.~~ Such pool (s) may be located in a required side or rear yard, but not within a required front yard forward of the primary dwelling on the lot, and shall not be located closer than five (5') feet to any side or rear property line.

Commented [EW16]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW17]: Recommend that the pool cannot extend beyond the front of the existing dwelling on the lot

3. Lanais, gazebos, garden and patio shelters, and children's play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
4. Noncommercial radio and television receiving antennae and noncommercial radio transmitting antennae limited in height to sixty (60') feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
5. Required off-street parking and loading spaces.
6. Home occupation uses, as defined in *Chapter 2 – Definitions* of this Land Development Code.
7. Parking and storage of private boat(s), camper trailer(s), or other recreational vehicle(s), in conformance with the regulations for the "Parking, Storage or Use of Major Recreational Equipment and Vehicles."
8. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code.
9. Private domestic greenhouses.

~~F. R-10 Single-Family Residential District Historic Designation: All lots within the City of Colleyville with the R-10 designation shall conform to the standards of the R-15 zoning district.~~

Commented [BB18]: This will address the existing R-10 properties. {At the worksession this was moved to the R-20 district}

~~G. Special-Exception Uses – In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the "Zoning Board of Adjustment" may, after public hearing thereon, authorize and grant the issuance of a "Special-Exception" for such special-exception uses as allowed in Section 3.24 – "Schedule of Permitted Principal Uses." The issuance of such "exception" by the "Board" shall be contingent upon reasonable and appropriate conditions and safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

- G. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the regulations for the "Classification of New and Unlisted Uses."
- H. Density; Area; Yard; Height; and Lot Coverage Requirements – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of *Section 3.24 "Schedule of District Regulations"* and other applicable provisions of *Section 3.28 - "Supplementary District Regulations."*
- I. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform with the provisions for "Off-Street Parking Requirements," and "Off-Street Loading Requirements."
- J. Land Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the Official Zoning Map affecting this district shall be accompanied by a land plan and supporting document therefore, in conformance with the provisions of *Chapter 1 – General Provisions* of this Land Development Code.

Section 3.14 RD – Two-Family Residential District

- A. ~~RD — Two-Family Residential District~~ – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this Section, are the regulations of the RD — Two-Family Residential District.
- B. Purpose and Intent – The purpose and intent of the RD — Two-Family Residential District is to provide for compatible land, building, and structure uses primarily oriented to medium-low density two-family residential purposes, open space usage, and selected community facility uses. The locational characteristics of this district are generally, but not always, found in the inner urbanized developed core of the city around shopping centers and neighborhood service facilities, plus as a transitional element between low density, single family districts and higher density multiple family districts. Land uses in this district are normally connected to an approved public or private sewage collection and treatment system, rather than individual septic tanks and sub-surface drainage fields. Dwellings containing two-family dwelling units, plus the aforescribed uses, comprise the principal elements of the district. ~~The intent of this district is not to allow single-family detached dwellings.~~
- C. Use Regulations – Land, buildings and structures may be used only for the purposes allowed in this Section.
- D. Permitted Principal Uses – The permitted principal uses allowed in this district are as designated in Section 3.24 - *Schedule of Permitted Principal Uses*.
- E. Permitted Accessory Uses – Subject to the provisions of Section 3.28 - *Supplementary District Regulations*, accessory buildings, structures, and uses customarily incidental to the “permitted principal uses” are allowed, including but not limited to the following:
1. Private residential garages, carports and related storage buildings and greenhouses accessory to permitted residential uses.
 2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All “at-grade” swimming pools with a water depth greater than twenty-four (24”) inches and “above-grade” swimming pools having a water depth twenty-four (24”) inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than four (4’) feet nor more than eight (8’) feet in height, and of such material and design to discourage unauthorized entry to the facility. Such pool (s) may be located in a required side or rear yard, but not within a required front yard.~~ forward of the primary dwelling on the lot. and shall not be located closer than five (5’) feet to any side or rear property line.
 3. Lanais, gazebos, garden and patio shelters, and children’s play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
 4. Noncommercial radio and television receiving antennae and noncommercial radio transmitting antennae limited in height to sixty (60’) feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
 5. Required off-street parking and loading spaces.
 6. Home occupation uses, as defined in Chapter 2 – *Definitions* of this Land Development Code.
 7. Parking and storage of private boat(s), camper trailer(s), or other recreational vehicle(s), in conformance with the requirements for “Parking, Storage or Use of Major Recreational Equipment and Vehicles.”
 8. Signs, in conformance with Chapter 7 – *Sign Regulations* of this Land Development Code.
 9. Private domestic greenhouses.

Commented [BB19]: The vast majority of properties zoned RD are developed with single-family residences

Commented [EW20]:

Commented [EW21R20]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW22]: Recommend that the pool cannot extend beyond the front of the existing dwelling on the lot

~~F. Special Exception Uses – In order to allow for certain uses which, because of the unique or unusual character thereof, can not be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the “Zoning Board of Adjustment” may, after public hearing thereon, authorize and grant the issuance of a “Special Exception” for such special exception uses as allowed in Section 2.24 – “Schedule of Permitted Principal Uses.” The issuance of such “exception” by the “Board” shall be contingent upon reasonable and appropriate conditions and safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

F. Single-Family Residential Uses – When a property with RD zoning is developed with a single-family residential use, the property shall conform to the standards of the R-20 Single Family Residential zoning district.

Commented [BB23]: Added per Council direction to address single-family residential development

G. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions for the “Classification of New and Unlisted Uses.”

H. Density, Area, Yard, Height, and Lot Coverage Requirements – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of Section 3.24 - “Schedule of District Regulations” and other applicable provisions of Section 3.28 - “Supplementary District Regulations.”

I. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform with the provisions for the “Off-Street Parking Requirements,” and “Off-Street Loading Requirements.”

J. Land Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the Official Zoning Map affecting this district shall be accompanied by a land plan and supporting document therefore, in conformance with the provisions of Chapter 1 – General Provisions of this Land Development Code.

Section 3.15 RMF – ~~Multi-family~~ Family Residential District

A. RMF – ~~Multi-family~~ Family Residential District – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this Section, are the regulations of the RMF – ~~Multi-family~~ Family Residential District.

B. Purpose and Intent – The purpose and intent of the RMF – ~~Multi-family~~ Family Residential District is to provide for compatible land, building, and structure uses primarily oriented to medium density multi-family residential purposes, open space uses, select community facility uses, and under special conditions, single-family uses. The locational characteristics of this district are generally, but not always, found in the inner urbanized developed core of the city around shopping centers and neighborhood service facilities, near employment centers, at the intersections of major and secondary thoroughfare streets, and as a transitional element between lower density and more intense nonresidential land uses. Land uses in this district are normally connected to an approved public or private sewage collection and treatment system, rather than individual septic tanks and sub-surface drainage fields. Garden apartment buildings and condominiums, and low-density townhouses, plus the aforescribed uses, comprise the principal elements of the district.

C. Use Regulations – Land, buildings and structures may be used only for the purposes allowed in this Section.

D. Permitted Principal Uses – The permitted principal uses allowed in this district are as designated in Section 3.24 - Schedule of Permitted Principal Uses.

E. Permitted Accessory Uses – Subject to the provisions of Section 3.28 - Supplementary District

Regulations, accessory buildings, structures, and uses customarily incidental to the "permitted principal uses" are allowed, including but not limited to the following:

1. Private residential garages, carports and related storage buildings and greenhouses accessory to permitted residential uses.
2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All "at-grade" swimming pools with a water depth greater than twenty-four (24") inches and "above-grade" swimming pools having a water depth twenty-four (24") inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than four (4') feet nor more than eight (8') feet in height, and of such material and design to discourage unauthorized entry to the facility. Such pool-(s) may be located in a required side or rear yard, but not within a required front yard forward of the primary dwelling on the lot,~~ and shall not be located closer than five (5') feet to any side or rear property line.
3. Lanais, gazebos, garden and patio shelters, and children's play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
4. Noncommercial radio and television receiving antennae and noncommercial radio transmitting antennae limited in height to (60) feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
5. Required off-street parking and loading spaces.
6. Parking and storage of private boat(s), camper trailer(s), or other recreational vehicle(s), in conformance with the regulations for "Parking, Storage or Use of Major Recreational Equipment and Vehicles."
7. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code.
8. Private domestic greenhouses.
9. Outdoor storage areas or storage buildings for boats, trailers, and other recreational equipment, automobiles, or household effects - for the exclusive use of the site occupants, provided these accessory uses are screened in general conformity with the requirements for "Fences, Free Standing Walls, and Screening Materials."
10. An office area not containing more than (2) percent of the gross floor area of the main building in a multifamily development used exclusively for administration purposes for said development only.
11. Coin-operated vending machines in a principal or accessory building for newspapers, candy, tobacco, soft drinks, ice and similar services for use by the site occupants and guests of permitted uses in this district.
12. Social and recreation buildings for use by the site occupants and guests of permitted uses in this district.
13. Group dining quarters within a principal building.

~~F. Special Exception Uses — In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the "Zoning Board of Adjustment" may, after public hearing thereon, authorize and grant the issuance of a "Special Exception" for such special exception uses as allowed in Section 3.24 – "Schedule of Permitted Principal Uses." The issuance of such "exception" by the "Board" shall be contingent upon reasonable and appropriate conditions and~~

Commented [EW24]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW25]: Recommend that the pool cannot extend beyond the front of the existing dwelling on the lot

~~safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

F. Single-Family Residential Uses – When a property with MF zoning is developed with a single-family residential use, the property shall conform with the standards of the R-20 Single Family Residential zoning district.

Commented [BB26]: Added per Council direction to address single-family residential development

G. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions for the - "Classification of New and Unlisted Uses."

H. Density, Area, Yard, Height, and Lot Coverage Requirements – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of Section 3.24 - "Schedule of District Regulations" and other applicable provisions of Section 3.28 - "Supplementary District Regulations."

I. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform with the provisions of the "Off-Street Parking Requirements," and ~~and~~ "Off-Street Loading Requirements."

J. Site Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the Official Zoning Map affecting this district, or for a "Special Use Permit" to be issued in this district, shall be accompanied by a site plan and supporting document therefore, unless otherwise waived by the City Planning and Zoning Commission or Zoning Board of Adjustment, in conformance with the provisions of Chapter 1 – General Provisions of this Land Development Code.

K. Open Space Required – Unless waived by the Planning and Zoning Commission, the RMF ~~Multi-family~~ Family Residential District shall conform to the Open Space Requirements as set forth in the provision for "Open Space Requirements," "Maximum Residential Density Permitted; and Density Increase Bonuses," and "Guarantee of Common Open Space."

L. Planned Single-Family Use in RMF Zoning Districts by Special Use Permit

Commented [BB27]: Not needed; single-family residential development to be allowed by right

~~1. Purpose and Intent – the purpose and intent of the grant of a special use permit for single family use in a R-MF Zoning District is to provide for the use in said zoning district of land, buildings and structures, for an appropriate combination of residential uses, accessory uses and special uses and to accommodate uses of land in multifamily zoning districts for single family purposes when said use is pursuant to a plan designed to encourage the most appropriate and aesthetic uses of land having due regard for the special arrangement of buildings, land uses, open spaces, circulation transportation patterns and consideration of special site and topographical features, which are controlled and the actual development becomes incorporated into the grant of the special use permit.~~

~~2. Allowable Uses – land, buildings or structures within an area zoned R-MF on which a special use has been granted may be used for any appropriate combination of principal uses, accessory uses, and special uses as permitted in residential zoning districts. However, the Planning and Zoning Commission and the City Council reserve the right to prohibit and exclude certain uses within any planned district, when, in their opinion, the inclusion of certain uses would or could cause or create an adverse impact within or to an adjacent development, or be an otherwise inappropriate use within the development or detrimental to persons or property within the adjacent districts thereto.~~

~~3. Permitted Uses – the land, buildings and structures within an RMF Zoning District upon which a special use permit has been granted may be used in any single purpose or mixed type of residential dwellings, including but not limited to the attached single family dwelling on conventional subdivision type lots, attached dwellings such as duplexes and townhouses, "cluster housing", patio homes, atrium homes, zero-lot line homes, (with a maximum of one side wall of the dwelling in common with a side property line). Additionally, accessory uses customary and incidental and secondary to any allowed foregoing use are allowed in the district.~~

- ~~4. Prohibited Uses – uses not expressly permitted in residential zoning districts of this Chapter are expressly prohibited in any R-MF District with special use permit unless otherwise authorized and approved by the City Planning and Zoning Commission and the City Council.~~
- ~~5. Minimum Lot Size Requirements; Minimum Yard Requirements; Maximum Building Heights; and Maximum Lot Coverage – the maximum height, lot width, lot depth, floor area ratio and lot area, and the minimum off street parking and loading requirements for a special use permit in RMF Zoning District shall comply with or be more restrictive than the standard established in RMF Zoning Districts. The Planning and Zoning Commission and City Council may alter such requirements when in their opinion the proposed development densities and land use arrangements shown on the site plan would result in the more innovative siting of buildings and facilities which would improve the usefulness of yard areas and the relationship to traffic circulation, admittance of light and air to buildings, fire protection and useable open space.~~
- ~~6. Off-Street Parking and Loading Requirements – off street parking and loading requirements pertaining to uses allowed in this district shall conform with the provisions of the “Off-Street Parking Requirements,” and “Off-Street Loading Requirements.”~~
- ~~7. Site Plan and Supporting Documents Required – any application for a change in zoning district boundaries on the “official zoning map” to establish a special use permit in an RMF Zoning District shall be accompanied by a site plan and supporting documents therefore, in conformance with the provisions of Chapter 1 – General Provisions of this Land Development Code.~~
- ~~8. Nature of Amending Ordinance Approving a Special Use Permit in RMF Zoning Districts – in approving any request for a special use permit in RMF Zoning Districts, the City Council shall, on the recommendation of the Planning and Zoning Commission, incorporate in the amending ordinance reference to the approved site plan, supporting documents and other conditions or restrictions imposed on the project by the commission including those of Council, and said information, conditions and restrictions shall constitute controls and limitations upon the development and use of the property. The approval and adoption of the amending ordinance by the Council shall result in the appropriate change to the “Official Zoning Map.” However, the zoning change does not constitute recording of a “final plat”, nor authorize the issuance of building permits and “certificates of occupancy,” until such time as a “final plat,” and supporting legal and construction documents have been prepared and submitted for City Council approval on all or part of the proposed development, in conformance with the requirements and procedures of the City Subdivision Regulation Ordinance and the requested zoning change.~~
- ~~9. Requirements for “Final Plat,” Submission Following Grant of Special Use Permit – within a maximum of six (6) consecutive months, following the approval of the special use permit in the RMF Zoning District by the City Council, the applicant shall file with the City Planning and Zoning Commission a “final plat” and necessary supporting documents of all or a part of the site in conformance with the City’s Subdivision Regulations Ordinance. In its discretion and for good cause, the Planning Commission may extend for six (6) months the period of filing for the “final plat,” upon written request by the applicant. Should the applicant fail to submit a “final plat” within the six-month period following the City Council approval of the Special Use Permit, or by the termination date of the filing of the extension granted by the Planning and Zoning Commission, the Commission may initiate proceedings to amend the official zoning map by removing all or part of the Special Use Permit in the RMF Zoning District from the official zoning map. The City Council may uphold the Commission’s recommendation and proceed to advertise and hold public hearings thereon, or may elect to continue the special use permit in the R-MF Zoning District.~~
- ~~10. Compliance with Development Schedule – an application for a planned unit development district shall be accompanied by a development schedule indicating the appropriate date on which construction is expected to begin and the rate of anticipated development to completion. The development schedule, if adopted and approved by the City Council, shall become a part of the development plan and shall be adhered to by the owner, developer and his successors in interest. The development schedule shall be reviewed annually by the City Manager or his designee and he shall report to the Planning and Zoning Commission the actual development accomplished as compared with the~~

~~development schedule. The Planning and Zoning Commission may, if in its opinion the owner or owners of property are failing or have failed to meet the approved schedule, initiate proceedings to amend the official Zoning Map by removing all or part of the special use permit in the RMF Zoning District from the official zoning map. Upon the recommendation of the Planning and Zoning Commission and for good cause shown by the owner and developer, the City Council may also extend the development schedule or adopt such new development schedule as may be indicated by the facts and conditions of the case.~~

Section 3.16 MH – Mobile Home Residential District

- A. MH – Mobile Home Residential District – The regulations set forth in this Section, or as set forth elsewhere in this Chapter when referred to in this Section, are the regulations of the MH – Mobile Home Residential District.
- B. Purpose and Intent – The purpose and intent of the MH – Mobile Home Residential District is to provide for the orderly, safe, and healthful development of mobile home parks and mobile home subdivisions. Since mobile homes are recognized as a special form of housing, the intent of this district is to provide appropriate standards as to compatible land uses, density, minimum mobile home park or subdivision size, and other relevant requirements pertaining to the design, construction, alterations, and extensions of mobile home parks and mobile home subdivisions. Land uses in this district are normally connected to an approved public or private sewage collection and treatment system, rather than individual septic tanks and sub-surface drainage fields.
- C. Use Regulation – Every mobile home park or mobile home subdivision hereafter constructed, enlarged, altered, extended, or created shall comply with all regulations set forth under this Section.
- D. Permitted Principal Uses – The permitted principal uses allowed in this district are as designated in *Section 3.24 - Schedule of Permitted Principal Uses*.
- E. Permitted Accessory Uses – Subject to the provisions of *Section 3.28 - Supplementary District Regulations*, accessory buildings, structures, and uses customarily incidental to the "permitted principal uses" are allowed, including but not limited to the following:
1. Private residential garages, carports and related storage buildings and greenhouses accessory to permitted residential uses.
 2. Private swimming pools, wading pools, and game courts (lighted or unlighted), provided that: if lighted, the lighting shall be so directed and shielded so as not to shine directly on any adjacent residential property; and further provided that any such pool or game court is for the private use of the site occupants and their guests, and not operated as a business. ~~All "at-grade" swimming pools with a water depth greater than twenty-four (24") inches and "above-grade" swimming pools having a water depth twenty-four (24") inches or more, except for inflatable portable tot pools, shall be enclosed by a fence and gate not less than four (4') feet nor more than eight (8') feet in height, and of such material and design to discourage unauthorized entry to the facility. Such pool (s) may be located in a required side or rear yard, but not within a required front yard~~ **forward of the primary dwelling on the lot**, and shall not be located closer than five (5') feet to any side or rear property line.
 3. Lanais, gazebos, garden and patio shelters, and children's play-houses, provided the privacy enjoyed by adjacent residential dwellings is not impaired.
 4. Non-commercial radio and television receiving antennae and non-commercial radio transmitting antennae limited in height to sixty (60') feet (measured from the ground line in front of the dwelling or use facing a public street), and further provided no electrical, radio or television signal interference is created which would adversely affect such audio or visual signals to nearby dwellings and other permitted uses;
 5. Required off-street parking and loading spaces.
 6. Home occupation uses, as defined by *Chapter 2 – Definitions* of this Land Development Code.

Commented [EW28]: Pool barrier requirements are already codified in the adopted building codes

Commented [EW29]: Recommend that the pool cannot extend beyond the front of the existing dwelling on the lot

7. Parking and storage of private boat(s), camper trailer(s), or other recreational vehicle(s), in conformance with the requirements for the "Parking, Storage or Use of Major Recreational Equipment and Vehicles."
8. Signs, in conformance with *Chapter 7 – Sign Regulations* of this Land Development Code.
9. Private domestic greenhouses.
10. Pool cabanas, laundry buildings, restroom/shower buildings, park office building, and other similar uses accessory to a Mobile Home Park or Mobile Home Subdivision.

~~F. Special Exception Uses – In order to allow for certain uses which, because of the unique or unusual character thereof, cannot be unconditionally permitted in this district, yet would or could be an appropriate or compatible use under certain controlled circumstances and locations, the "Zoning Board of Adjustment" may, after public hearing thereon, authorize and grant the issuance of a "Special Exception" for such special exception uses as allowed in Section 3.24 - "Schedule of Permitted Principal Uses." The issuance of such "exception" by the "Board" shall be contingent upon reasonable and appropriate conditions and safeguards, including the length of time thereof, when appropriate, so as to properly protect any adjacent property, use or neighborhood character, as well as insure the appropriate conduct of the special exception use of the land or buildings granted.~~

~~GE. Prohibited Uses – Any use not expressly authorized and permitted herein is expressly prohibited in this district, unless otherwise allowed in conformance with the provisions for the "Classification of New and Unlisted Uses."~~

~~HG. Density, Area, Yard, Height, and Lot Coverage Requirements – The requirements regulating the maximum permissible residential density, minimum lot size, minimum yard sizes (front, side and rear), maximum building height (stories and feet), and maximum percent of lot coverage by buildings, as pertains to this district, shall conform with the provisions of Section 3.24 - "Schedule of District Regulations" and other applicable provisions of Section 3.28 - "Supplementary District Regulations."~~

~~I. Off-street Parking and Loading Requirements – Off-street parking and loading requirements pertaining to uses allowed in this district shall conform with the provisions for the "Off-Street Parking Requirements" and "Off-Street Loading Requirements."~~

~~J. Site Plan and Supporting Documents Required – Any application for a change in zoning district boundaries on the Official Zoning Map affecting this district, or for a "Special Use Permit" to be issued in this district, shall be accompanied by a site plan and supporting document therefor, unless otherwise waived by the Planning and Zoning Commission or Zoning Board of Adjustment, in conformance with the provisions of Chapter 1 – General Provisions of this Land Development Code.~~

Section 3.17 CPO - Professional Office Commercial District

- A. Purpose – This district is designed to be compatible adjacent to or near residential areas and so as to provide office services needed by homeowners on a usual basis. The lot size maximum is small to encourage small-scale developments, and hours of operation do not permit businesses to be open at night.
- B. Permitted Uses
 1. See Table 3.24.B - Schedule of Permitted Principle Uses
- C. Special Uses
 1. See Table 3.24.B - Schedule of Permitted Principle Uses
- D. Site Requirements

Colleyville, Texas, Land Development Code

Minimum lot size: — 7, 200 s.f.	Minimum setbacks:	Max. Building height in stories: — 2 st.
Maximum lot size: 1 acre	front: 40 ft.	Max. building height in feet: — 35 ft.
Minimum lot width at front setback line: -100 ft.	side abutting residential: 25 ft. side abutting non-residential: 15 ft.	Max. building height adj. to residential district: see Sec. 24
Minimum lot depth: 120 ft.	rear abutting residential: 25 ft.	
Maximum lot coverage: 40%	rear abutting non-residential: 10 ft.	

E. Supplementary Requirements

General:	Landscaping Plans:	Off-Street Parking:
- outdoor storage is not permitted	- required as per Chapter 4	- as required by Sec. 3.29
- uses adjacent to single family uses must be screened as per Sec. 3.26	Commercial Bldg. Design Stds.	Site Plans:
- may be operated in daytime only	- each site must have a minimum of 25 points as per Chapter 56	- plans must be submitted in accordance with Sec. 3.31

Section 3.18 CN - Neighborhood Commercial District

A. Purpose – This district is designed to be compatible adjacent to or near residential areas and to provide goods needed by homeowners on a usual basis. The lot size maximum is small to encourage small-scale developments, and hours of operation do not permit businesses to be open at night.

B. Permitted Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

C. Special Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

D. Site Requirements

General Requirements:	PRIMARY USE & STRUCTURE:	Accessory Use & Structure:
Minimum lot size: 10,000 s.f.	Minimum setbacks:	Permitted per Sec. 3.24 & 3.2827
Maximum lot size: 1 acre	front: 40 ft.	
Minimum lot width at front setback line: 100 ft.	side abutting residential: 25 ft.	
Minimum lot depth: 120 ft.	side abutting non-residential: 15 ft.	
Maximum lot coverage: 40%	rear abutting residential: 25 ft.	
	rear abutting non-residential: 10 ft.	
	Max. Building height in stories: 2 st.	
	Max. building height in feet: 35 ft.	
	Max. building height adj. To residential district: see Sec. 24	

E. Supplementary Requirements

General:	Landscaping Plans:	Off-Street Parking:
- outdoor storage is not permitted	- required per Chapter 4	- as required by Sec. 3.29
- uses adjacent to single family uses must be screened as per Sec. 24	Commercial Bldg. Design Stds.	Site Plans:
- may be operated in daytime only	- each site must have a minimum of 25 points per Chapter 65	- plans must be submitted in accordance with Sec. 3.31

Section 3.19 CC1 - Village Retail District

A. Purpose – This district is oriented to general commercial retail goods and services as well as some office, entertainment and community facility uses. While the district is designed to encourage “clustering” stores, the site requirements allow for a smaller scale than a shopping center type development. It is likely that Village Retail centers will be built without a major anchor store and be located near but not at major street intersections.

B. Permitted Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

C. Special Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

D. Site Requirements

General Requirements:	PRIMARY USE & STRUCTURE:	Accessory Use & Structure:
Minimum lot size: 15,000 s.f.	Minimum setbacks:	Permitted per Sec. 3.24 & 3.2827
Maximum lot size: 5 acres	front: 40 ft.	
Minimum lot width at front setback line: 150 ft.	side abutting residential: 25 ft.	
Minimum lot depth: 120 ft.	side abutting non-residential: 15 ft.	
Maximum lot coverage: 50%	rear abutting residential: 25 ft.	
	rear abutting non-residential: 10 ft.	
	Max. Building height in stories: 2 st.	
	Max. building height in feet: 35 ft.	
	Max. building height adj. To residential district: see Sec. 3.24 (A&B)	

E. Supplementary Requirements

General:	Landscaping Plans:	Off-Street Parking:
- outdoor storage is not permitted	- required as per Chapter 4	- as required by Sec. 3.29
- uses adjacent to single family uses must be screened as per Sec. 24	Commercial Bldg. Design Stds.	Site Plans:
- may be operated 24 hours/day	- each site must have a minimum of 30 points as defined by Chapter 56	- plans must be submitted in accordance with Sec. 3.31

Section 3.20 CC2 - Shopping Center District

A. Purpose – This district is oriented to general commercial goods and services as well as office, entertainment and community facility uses. By nature, shopping center tracts are large-scale usually accommodating a large anchor store and several smaller stores. These tracts are generally located at major street intersections.

B. Permitted Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

C. Special Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

D. Site Requirements

General Requirements:		<u>PRIMARY USE & STRUCTURE</u>	<u>Accessory Use & Structure</u>
Minimum lot size:	20,000 s.f.	Minimum setbacks:	Permitted per Sec. 3.24 & 3.2827
Maximum lot size:	none	front: 40 ft.*	
Minimum lot width at front setback line:	150 ft.	*see Sec. 23 (D) for special "urban Village" front yard setback.	
Minimum lot depth	120 ft.	side abutting residential: 25 ft.	
Maximum lot coverage	60%	side abutting non-residential: 15 ft.	
		rear abutting residential: 25 ft.	
		rear abutting non-residential: 10 ft.	
		Max. Building height in stories: 2 st.	
		Max. building height in feet: 35 ft.	
		Max. building height in PUD: 4 st.	
		Max. building height adj. To residential district: see Sec. 3.24 (A&B)	

E. Supplementary Requirements

General: - outdoor storage is not permitted - uses adjacent to single family uses must be screened as per Sec. 3.24 - may be operated 24 hours/day	Landscaping Plans: - required as per Chapter 4 Commercial Bldg. Design Stds. - each site must have a minimum of 25 points as defined by Chapter 56	Off-Street Parking: - as required by Sec. 3.29 Site Plans: - plans must be submitted in accordance with Sec. 3.31
--	---	--

Section 3.21 CC3 - Highway Commercial District

A. Purpose – This district would permit uses that do not fit within the retail or manufacturing categories. Service and retail uses associated with outdoor storage, noise, especially auto repair and service and others would be permitted. The minimum lot size is less than the Shopping Center District to allow for more flexibility of uses. It is anticipated that most of these districts would not be located near residential districts.

B. Permitted Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

C. Special Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

D. Site Requirements

General Requirements:		<u>PRIMARY USE & STRUCTURE:</u>	<u>Accessory Use & Structure:</u>
Minimum lot size:	10,000 s.f.	Minimum setbacks:	Permitted as per Sec. 3.24 & 3.2827
Maximum lot size:	none	front: 40 ft.	
Minimum lot width at front setback line:	150 ft.	side abutting residential: 25 ft.	
Minimum lot depth	120 ft.	side abutting non-residential: 15 ft.	
Maximum lot coverage	70%	rear abutting residential: 25 ft.	
		rear abutting non-residential: 10 ft.	
		Max. Building height in stories: 2 st.	
		Max. building height in feet: 35 ft.	
		Max. building height adj. to residential district: see Sec. 3.24 (A&B)	

E. Supplementary Requirements

General: - outdoor storage is permitted - uses adjacent to single family uses must be screened as per Sec. 3.24 - may be operated 24 hours/day.	Landscaping Plans: - required as per Chapter 4 Commercial Bldg. Design Stds: - each site must have a minimum of 20 points as defined by Chapter 56	Off-Street Parking: - as required by Sec. 3.29 Site Plans: - plans must be submitted in accordance with Sec. 3.31
---	---	--

Section 3.22 ML - Light Manufacturing District

A. Purpose – This district would permit uses that involve the fabrication of products or have outdoor storage, noise, odors or other objectionable aspects that would not be compatible in retail or service areas. This district is limited to those uses that are not retail in nature or in some cases those that need outdoor space.

B. Permitted Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

C. Special Uses

1. See Table 3.24.B - Schedule of Permitted Principle Uses

D. Site Requirements

General Requirements: Minimum lot size: 10,000 s.f. Maximum lot size: none Minimum lot width at front Setback line: 100 ft. Minimum lot depth 120 ft. Maximum lot coverage 60%	PRIMARY USE & STRUCTURE: Minimum setbacks: front: 40 ft. side abutting residential: 25 ft. side abutting non-residential: 15 ft. rear abutting residential: 25 ft. rear abutting non-residential 10 ft. Max. Building height in stories: 2 st. Max. building height in feet: 35 ft. Max. building height adj. To residential district: see Sec. 3.24 (A&B)	Accessory Use & Structure: Permitted per Sec. 3.24 & 3.2927
---	--	---

E. Supplementary Requirements

General: - outdoor storage is permitted - uses adjacent to single family uses Must be screened as per Sec. 3.24 - may be operated 24 hours/day.	Landscaping Plans: - required as per Chapter 4 Commercial Bldg. Design Stds: - each site must have a minimum of 30 points as defined by Chapter 56	Off-Street Parking: - as required by Sec. 3.29 Site Plans: - plans must be submitted in accordance with Sec. 3.31
--	---	--

Section 3.23 PUD – Planned Unit Developments

(Ord. O-05-1529 / 06/21/05)

A. Purpose - The purpose of a Planned Unit Development (PUD) is to provide for greater flexibility and discretion in the approval of residential, non-residential and mixed use developments by encouraging creative, efficient and aesthetically desirable residential and commercial projects that are superior to what could be accomplished in other zoning districts through the use of increased open spaces, greenbelts, or by providing enhanced amenities or features within the development that will be of special benefit to the property owners or to the community.

B. Ordinance Required and Effect on Official Zoning Map – Every Planned Unit Development approved

under the provisions of this section shall be considered an amendment to the Land Development Code and Official Zoning Map of the City of Colleyville, Texas. In approving any request for a Planned Unit Development district, the City Council shall, upon recommendation of the Planning and Zoning Commission, incorporate in the approving ordinance reference the approved site plan, supporting documents and include other conditions or restrictions imposed on the project by the Commission, including those of the Council. The approval and adoption of the amending ordinance by the City Council shall result in the appropriate change to the "Official Zoning Map."

- C. General Development Standards – The standards and requirements set forth in the Land Development Code shall be applicable to every Planned Unit Development, except where a new or different standard or requirement has been set forth in the ordinance establishing the PUD district. Such standards or requirements may be in addition to or in lieu of a development standard contained in the Land Development Code. The ordinance creating the Planned Unit Development may establish these requirements specifically in the ordinance or by reference to another zoning district.
- D. Classification of Planned Unit Developments – The approving ordinance establishing a Planned Unit Development shall include one of the following classifications, which shall also be shown on the Official Zoning Map using the applicable letter symbol.

Planned Unit Development Classifications		
PUD Classification	Planned Unit Development- Residential	Planned Unit Development - Commercial
Map Symbol	PUD-R	PUD-C
Classifications Defined	Planned developments containing primarily residential dwelling units, which may be grouped into clusters and may have a higher density than a conventional single family project of the same acreage, shall be classified as Planned Unit Development – Residential. A PUD-R may also contain a portion of non-residential uses.	Planned developments containing primarily non-residential uses, such as commercial, office, professional services, retail, institutional and industrial uses, or combinations thereof, shall be classified as Planned Unit Development – Commercial. A PUD-C may also contain a portion of residential uses.

- E. Permitted Uses – The uses permitted in a Planned Unit Development shall be enumerated in the approving ordinance with land use descriptions consistent with the Table of Permitted Uses, contained elsewhere in this Land Development Code. A Planned Unit Development may allow a combination of land uses, a specific use, or a class of generic uses, such as single family residential, office, retail, commercial or educational facilities, or a reference to another zoning district.
- F. Prohibited Uses – Uses not expressly permitted in the ordinance approving the Planned Unit Development shall be prohibited.
- G. Maximum Residential Density – The maximum residential density permitted in a PUD-R district, or in a PUD-C district where residential uses are proposed, shall not exceed 1.8 dwelling units per gross net acre. For the purpose of this regulation, the density calculation shall include all residential areas of the project and one-half of any abutting street situated adjacent to the project. This calculation shall exclude all proposed non-residential acreage and street rights-of-way from the gross-net acreage.

~~H. Density Bonus – A proposal for a PUD-R or a PUD-C containing a residential density exceeding 1.8 dwelling units per acre may be considered where the amount of open space area provided exceeds the minimum open space requirement or where additional amenities are provided within the open space area. A PUD proposal which contains a density exceeding 1.8 dwelling units per acre shall only be acceptable in an area consistent with sound land use planning, such as a transitional area situated between a non-residential area and less dense residential developments, or near a major street intersection, or for smaller parcels with unique topographical features that make less dense development economically difficult.~~

Commented [BB30]: No density bonus desired

- I. ~~Minimum Residential Lot Size – Notwithstanding Paragraph C above regarding maximum density, the minimum lot size in a PUD-R district shall be 13,000 square feet, with an average lot size of 16,000 square feet. No lot shall have less than 100 feet of width at the building line. The minimum lot size in a Planned Unit Development district shall be stated in the approving ordinance.~~
- J. **Open Space Requirements** – All requests for approval of a Planned Unit Development shall include provisions for open space areas in conformance with the following:
1. **Residential Areas** – For all residential uses, common open space land, comprising not less than twenty percent (20%) of the gross residential project area, shall be provided for the primary use of the occupants of the residential units.
 2. **Non-Residential Areas** – For all non-residential uses, open space land, comprising not less than twenty percent (20%) of the non-residential area, shall be provided. Said open space area may be the same area as the landscaped area required elsewhere in this Land Development Code.
 3. **Definition of Common Open Space.** For the purpose of this section, common open space is defined as follows:
 - a. Common Open Space may include:
 - i. land area of the development used for aesthetic, leisure and recreational purposes, that is accessible to and permanently reserved for the common use and enjoyment of the occupants of the development,
 - ii. golf courses, parks, and public open space areas adjacent to the development, which are readily accessible,
 - iii. low-impact passive uses include conservation of open land in its natural state (for example, woodland, fallow field, or meadow), neighborhood squares, common areas, picnic areas, community gardens, walking trails, bikeways, other kinds of pathways, and similar low-impact passive recreational uses, or
 - iv. active recreation uses including recreational playing fields, playgrounds, tennis courts, neighborhood pools, and clubhouse structures.
 - b. Common Open Space shall not include:
 - i. land areas reserved for the exclusive use and benefit of an individual owner or tenant,
 - ii. public or private street right-of-way, parkways, alleys, driveways, parking or loading areas,
 - iii. religious institutions or private school sites, or
 - iv. street medians or islands.
2. **Open Space Design Requirements.**
- a. An application for a Planned Unit Development that includes a common open space area shall include a written description or a plan of amenities, such as landscaped areas, trees and shrubs, sidewalks and trails, benches, pavilions, and play areas, to be included in the open space areas.
 - b. The maximum amount of common open space used for storm water detention or retention purposes shall not exceed twenty-five (25%) of the common open space area. If the open space area contains a retention pond, the pond shall include at least one (1) aeration device, such as a fountain, waterfall or underwater device.
 - c. Common open space areas adjacent to street rights-of-way shall be a minimum depth of twenty-five (25) feet and shall be landscaped to include the retention or planting of one (1) three (3") inch caliper tree per each fifty (50) feet of street frontage, which may be clustered or distributed within the open space area.
3. **Guarantee of Common Open Space.** In order to guarantee the preservation and maintenance of the common open space, one of the following methods shall be required:
- a. **Public Open Space** – Common open space may be conveyed to the City or other public agency,

Commented [BB31]: The PUD ordinance will determine minimum lot standards for area dimension (size, width & depth)

Commented [BB32]: Should the 20% standard be a recommendation? Should Council be able to reduce this standard as part of the PUD approval?

provided the public agency accepts the conveyance and agrees to maintain the common open space and any buildings, structures or other improvements.

- b. Private Open Space – Common open space may be conveyed to a homeowner's association or property owner's association, provided the declaration of covenants and restrictions that govern the association include, but is not limited to, the following:
 - i. the establishment of the association is made before any lot in the development is sold or any building occupied,
 - ii. membership in the association is mandatory for each building or property owner and any successive owner and give the association the power to compel contributions from residents of the development to cover their proportionate shares of the costs associated with the maintenance and upkeep of the common open space areas,
 - iii. ownership and maintenance of the common open space is guaranteed by a restrictive covenant, which is permanent, running with the land for the benefit of the occupants of the development and state that the association is totally responsible for the maintenance of the common open space and any improvements,
 - iv. submittal of a draft copy of the proposed covenants at the time of preliminary platting, which will ensure the guarantees stated in this section and provides for restricting the use of common spaces for the designated purposes, and
 - v. the plat contains a note stating that the common open space shall be maintained by the home owners association

K. Special Submittal and Exhibit Requirements – To facilitate the review and public hearing process, all applications for a Planned Unit Development shall include the following documents and exhibits:

- 1. *Application* – These forms are furnished by the Administrative Official.
- 2. *Application Fee* – No application shall be processed or scheduled for public hearing until the application fee has been paid.
- 3. *Statement of Planning Objectives* – The developer shall provide a written statement of planning objectives which describes the nature and character of the proposed development, any proposed development standards, and the rationale behind the assumptions and choices made by the applicant, including use and ownership of any open spaces, etc.
- 4. *Legal Description* – A written metes and bounds description of the total site area proposed for the Planned Unit Development.
- 5. *Development Schedule* – A development schedule indicating the target dates for the start and completion of the project, including any key dates of phasing of the project. The development schedule, if adopted and approved by the City Council, shall be incorporated into the approving ordinance, which shall be adhered to by the owner, developer and his successors in interest.

If upon review by the Administrative Official, the owner or owners of property fail to meet the approved schedule, the Planning and Zoning Commission or City Council may initiate proceedings under Chapter 1 – General Provisions of this Land Development Code regarding "Amendments, Frequency of Petition and Site Plan Requirements: Zoning and Special Use Permits," to amend the Planned Development District by removing all or part of the Planned Development District from the Official Zoning Map and placing the area involved in another appropriate zoning district. Upon the recommendation of the Planning and Zoning Commission and for good cause shown by the owner and developer, the City Council may also extend the development schedule or adopt such new development schedule as may be indicated by the facts and conditions of the case.

- 6. *Site Plan* – The Site Plan, which may be conceptual and general in nature, but in sufficient detail appropriate for the type of development being proposed and shall at a minimum include the following items, where applicable:
 - a. Proposed layout, indicating the approximate size and dimensions of all residential and non-residential lots
 - b. Proposed land uses and building locations
 - c. General elevation drawings of all non-residential structures indicating building height
 - d. Landscaping, lighting, fencing and screening of common areas
 - e. General locations of existing tree clusters
 - f. Location and construction type of perimeter fencing

- h. Design of ingress and egress with description of any special pavement treatments
- i. Calculations and location of off-street parking and loading facilities
- j. Location and type of all commercial signage and lighting, including pole heights, for parking lots and common areas
- k. Location and description of subdivision signs and landscaping at entrance areas
- l. Street names on all proposed streets

Exception: A Planned Unit Development application may be submitted and approved without a Site Plan, if the approving ordinance contains sufficient written detail to establish all site criteria.

- 7. *Drainage Analysis* – The applicant shall submit a Preliminary Drainage Analysis to determine the need for drainage facilities. The Preliminary Drainage Analysis shall be prepared in accordance with drainage analysis requirements contained in *Chapter 14 – Engineering Design Standards* of the Land Development Code.

- L. Optional Preliminary Plat Submittal – To expedite a development proposal, a developer may submit a separate application for a Preliminary Plat, which meets all of the requirements specified in Chapter 8 of this Land Development Code for a Preliminary Plat submittal, and which may be processed and reviewed concurrently with a PUD application, provided that no Preliminary Plat application shall be approved prior to the approval of the PUD application. The developer shall request a waiver of the 30 day time limit for Preliminary Plat approval where such applications run concurrently with a PUD application.

M. Approval Process

- a. *Application* – An application for a Planned Unit Development shall be submitted and processed using the same requirements used for submittal of a rezoning request, which shall be reviewed and considered in accordance with the procedures specified in Chapter One of this Land Development Code.
- b. *Conditions Related to Approval* – In establishing a Planned Unit Development, each application shall be evaluated by the Planning and Zoning Commission and City Council as to its probable effect on the adjacent property and the community. The Planned Unit Development may be approved or denied as the findings indicate appropriate. The Planning and Zoning Commission may recommend and the City Council may approve safeguards or conditions of approval to reduce the effect on adjacent or surrounding properties, which may include any or all of the following site conditions:

- | | |
|-------------------------------------|---|
| i. Accessory buildings | xi. Lot sizes and dimensions |
| ii. Building and structure heights | xii. Outside storage and display |
| iii. Drainage | xiii. Pedestrian circulation |
| iv. Exterior construction materials | xiv. Public street access |
| v. Exterior lighting | xv. Refuse and waste storage |
| vi. Fire protection measures | xvi. Screening or buffer areas |
| vii. Hours of operation | xvii. Signs |
| viii. Land uses | xviii. Vehicle traffic, circulation, and parking lots |
| ix. Landscaping and open space | xix. Other conditions deemed appropriate |
| x. Lot coverage, density & setbacks | xx. Project phasing and development schedule |

- c. *Modification of a PUD requirement* – The Planning and Zoning Commission may recommend and the City Council may approve a proposal for a Planned Unit Development that includes a provision which modifies any requirement contained in these Planned Unit Development regulations.
- d. *Amending a Planned Unit Development* – Changes to a Planned Unit Development or to its approved Site Plan shall be processed in the same manner as the original request. However, the administrator of this Code may approve minor modifications in an approved Concept Plan, provided the modifications:
 - i. Do not alter the basic physical relationship of the property to adjacent property;
 - ii. Do not change the permitted land uses;
 - iii. Do not increase the maximum density, floor area, height; or,
 - iv. Do not reduce the minimum yards or setbacks.

- N. Effect of this Section on Existing Planned Unit Developments – Previously approved PUD amending

ordinances to the City's preceding zoning ordinance and Land Development Code, including accompanying plans and supporting documents, shall remain in full force and effect with respect to this Chapter and shall not be made to comply with the provisions of this Chapter. Where a prior ordinance fails to provide specific information regarding minimum lot sizes, lot width, lot depth, set backs, building heights and maximum lot coverage, the requirements contained in Section 3.24.G shall prevail.

Section 3.24 Schedule of Permitted Uses

- A. General Requirement and Symbols Used – Land and buildings may be used in accordance with Table 3.24.C, *Schedule of Permitted Principal Uses* and the additional requirements of this section. The following symbols are used in Table 3.24.C, *Schedule of Permitted Principal Uses*:
1. *Permitted Uses* – A "P" in a cell indicates that the use is allowed by right as the principal use in the applicable zoning district in accordance with Table 3.24.C, *Schedule of Permitted Principal Uses*.
 2. *Specific Uses* – An "S" in a cell indicates that the use may be allowed with the approval by the City Council of a Special Use Permit following the applicable review and approval procedures.
 3. *Prohibited Uses* – An empty cell indicates that the land use is prohibited in the applicable zoning district, unless otherwise allowed with the approval by the City Council of an ordinance establishing a Planned Unit Development District, or authorized by a Special Use Permit, or in conformance with the provisions contained in Section 3.6.B-*Classification of New and Unlisted Uses*.

Table 3.24.B- - Schedule of Permitted Principal Uses

Table 3.24.B- - Schedule of Permitted Principal Uses																		
Land Use Classification	Residential District									Non-Residential Districts						Special Land Use Standards or Section Ref.	Parking Group	
	AG	RE	R40	R30	R20	R15	RD	RMF	MH	CPO	CN	CC1	CC2	CC3	ML			
A. RESIDENTIAL ACCOMODATION USES																		
Single Family Detached Dwelling	P	P	P	P	P	P	P	S	S	P							8	3
Duplex – Attached Dwelling							P	S									8	2
Townhome – Attached Dwellings								P									8	4
Multi-family – Attached Dwellings								P									8	4
HUD Code Manufactured Housing									P								8	2
Assisted Living Facilities	PUD only															2	17	
Bed and Breakfast Lodging	S	S	S	S	S	S	S	S									1,8	18
Private (HOA) Recreational Facilities		P	P	P	P	P	P	P	P								9	5
B. ACCESSORY USES																		
Accessory Building	P	P	P	P	P	P	P	P	P								Sec. 3.27	n.a.
Carport	S	S	S	S	S	S	S	S	S								Sec. 3.27.C	n.a.
Home Occupations Uses	P	P	P	P	P	P	P	P	P								8	n.a.
Servants or Caretakers Quarters <u>Accessory Dwelling</u>	P	P	S	S	S										S		16	1
C. AGRICULTURAL USES																		
Commercial equestrian boarding stable and school	P	S															17	25
Crop Farming	P	P																n.a.
Livestock raising and breeding	P	P															12	n.a.
Private horse stables for domestic use	P	P	P	S	S													n.a.
Roadside produce stands (year round)	S	S	S	S	S	S	S	S	S									n.a.
D. UTILITY USES																		
Electrical Substations	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S			21

Commented [BB33]: Only applies to AG & RE districts

Public Utility Supply and Storage Yards	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		24	
Table 3.24.B- - Schedule of Permitted Principal Uses																		
Land Use Classification	Residential District										Non-Residential Districts						Special Land Use Standards	Parking Group
	AG	RE	R40	R30	R20	R15	RD	RMF	MH	CPO	CN	CC1	CC2	CC3	ML			
Solid Waste Disposal Sites															S		24	
Telecommunications Towers	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	3	21	
Water Pumping Stations	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		24	
Wind Driven Generators	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		n.a.	
E. PUBLIC AND INSTITUTIONAL USES																		
Colleges or Universities	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		12	
Community Centers or Recreation Centers	S	S	S	S	S	S	S	S	S	P	P	P	P	P	P		5	
Government Buildings, Offices and Facilities	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		8	
Fire Stations / Police Stations	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		16	
Golf Courses – Public Owned	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		22	
Government Maintenance Facilities	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		25	
Libraries										P	P	P	P	P	P		9	
Museums										P	P	P	P	P	P		8	
Post Office	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		10	
Parks and Open Space Areas	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		25	
Public Maintenance and Storage Buildings	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		25	
Private Schools – Elementary and Secondary	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		13	
Private Schools – High School	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		14	
Public Schools – Elementary and Secondary	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		13	
Public Schools – High School	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		14	
Religious Institutions	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P		18	
F. OFFICE USES																		

Commented [BB34]: Not a desired use

Commented [BB35]: Not appropriate in residential districts

Accountant's Offices											P	P	P	P	P	P	8
Table 3.24.B- - Schedule of Permitted Principal Uses																	
Land Use Classification	Residential District									Non-Residential Districts						Special Land Use Standards	Parking Group
	AG	RE	R40	R30	R20	R15	RD	RMF	MH	CPO	CN	CC1	CC2	CC3	ML		
Advertising Agencies										P	P	P	P	P	IS		8
Attorney Offices										P	P	P	P	P	IS		8
Chiropractic Clinics										P	P	P	P	P	IS		8
Emergency Clinic (24 hrs.)												S	P	P	IS	10	6
Engineering, Architect's, and Surveyor's Offices										P	P	P	P	P	IS		8
General Business Offices not elsewhere listed										P	P	P	P	P	IS		8
Insurance Agencies										P	P	P	P	P	IS		8
Management and Public Relations Services Offices										P	P	P	P	P	IS		8
Optometrist Office										P	P	P	P	P	IS		8
Psychologist Offices										P	P	P	P	P	IS		8
Physician's or Dentist's Offices										P	P	P	P	P	IS	5	7
Real Estate Agency Offices										P	P	P	P	P	IS		8
Security Broker Offices										P	P	P	P	P	IS		8
Telemarketing Offices												P	P	P	IS		5
Title Abstract Offices										P	P	P	P	P	IS		8
Trade or Business Schools												S	S	S	P		15
Travel Agency / Airline Ticket Offices										P	P	P	P	P	IS		8
G. RETAIL AND SERVICE USES																	
Alcoholic Beverage Sales – (Beer and Wine Only) – Off-Premises Consumption												S	S	S		13	n.a.
Alcoholic Beverage Sales – On-premises Consumption												S	S	S		13	n.a.
Package Store Sales – Off-premises Consumption												S	S	S		13	n.a.
Alcohol or Drug Treatment Center										S	S	S	S	S	S		24

Commented [BB36]: Permitted in restaurant that meets 60/40 alcohol food ratio (no more than 60% of total receipts for alcohol)

Antique Stores																P	P	<u>P</u>			7
Table 3.24.B- - Schedule of Permitted Principal Uses																					
Land Use Classification	Residential District										Non-Residential Districts						Special Land Use Standards	Parking Group			
	AG	RE	R40	R30	R20	R15	RD	RMF	MH	CPO	CN	CC1	CC2	CC3	ML						
Apparel and Accessory Stores												P	P	<u>P</u>						7	
Arts and Crafts Stores and Hobby Shops												P	P	<u>P</u>						7	
Bakery Stores												P	P	<u>P</u>						7	
Banks, Credit Unions and Financial Institutions											P	P	P	<u>P</u>						8	
Barber Shops, Beauty Shops and Day Spas											P	P	P	<u>P</u>		10				7	
Bicycle Shops												P	P	<u>P</u>						7	
Book, Stationary or Greeting Card Shops												P	P	P						7	
Camera or Music Stores												P	P	<u>P</u>						7	
Carnivals and Circuses												S	S							24	
Cemeteries or Mausoleums										S	S	S	S	S	S					24	
Charitable Donation Station												S	S	S						24	
Civic, Social or Fraternal Organizations										S	S	P	P							7	
Convenience Stores with gasoline sales												S	S	S	S					7	
Copy Centers/Print Shops										S	S	P	P	P	P					7	
Dance Studios, and Martial Arts Studios, and Cheerleading & Gymnastics Facilities										S	S	P	P	<u>P</u>	<u>P</u>					7	
Day Care Centers										S	S	S	S	S		17				11	
Department Stores												P	P	<u>P</u>						7	
<u>Dog Boarding with indoor kennels</u>													<u>P</u>	<u>P</u>	<u>P</u>	<u>4</u>				<u>8</u>	
<u>Dog Boarding with outdoor kennels</u>													<u>S</u>	<u>S</u>	<u>S</u>					<u>8</u>	
<u>Dog Grooming</u>													<u>P</u>	<u>P</u>	<u>P</u>					<u>8</u>	
Dry Cleaner Pick-up Stations											S	P	P	<u>P</u>						7	
Dry Cleaners (up to 5,000 s. f. w/on-site laundry)												P	P	<u>P</u>						7	

Equipment Rental and Leasing Stores																		S	P		7
Florist Shops											P	P	P	<u>P</u>							7
Food Catering													<u>P</u>	<u>S</u>	<u>P</u>	<u>P</u>					8
Funeral Homes												S	S	S							24
Furniture and Appliance Stores												P	P	P							9
<u>General Retail Store (not listed elsewhere)</u>												<u>S</u>	<u>S</u>	<u>S</u>							<u>7</u>

Table 3.24.B- - Schedule of Permitted Principal Uses

Land Use Classification	Residential District									Non-Residential Districts						Special Land Use Standards	Parking Group
	AG	RE	R40	R30	R20	R15	RD	RMF	MH	CPO	CN	CC1	CC2	CC3	ML		
Grocery Stores												P	P	<u>P</u>		18	7
Hardware, electrical & plumbing w/o outside display											P	P	P	P			
Hardware , electrical & plumbing with outside display													S	P	P		
Hospitals												S	S	S			24
Hotels and Motels												<u>S</u>	P	P			19
<u>Interior-Home</u> Decoration Stores										P	P	P	P	<u>P</u>			7
Jewelry Stores											P	P	P	<u>P</u>			7
Locksmiths											S	S	<u>S</u>	<u>S</u>	<u>P</u>		8
Mailing and Shipping Stores											P	P	P	P	<u>P</u>		7
Meat or Fish Market												P	P	P			7
Nurseries and Greenhouses with outside display													S	P	P		16
Pawn Shops															<u>P</u> <u>S</u>		7
Pet Stores												P	P	<u>P</u>			7
Pharmacy											S	P	P	P			7
Photography Studios										P	P	P	P	P	P		8

Commented [BB37]: Catch-All Category

Commented [BB39]: New use

Commented [BB39]: New use

Commented [BB39]: New use

Billiard Parlors														S	S	<u>S</u>		17	23
Commercial Recreation (outdoor)	S												S	S	S	S	S		24
Fitness Centers													<u>S</u>	P	P	P	<u>P</u>		7
Golf Courses – Privately Owned	<u>S</u>	<u>S</u>	<u>S</u>	<u>S</u>	<u>S</u>	<u>S</u>	<u>S</u>	<u>S</u>	<u>S</u>	<u>S</u>	P	P	P	P	P	P	P		22
Golf Driving Ranges													<u>S</u>	P	P	<u>S</u>	<u>S</u>		22
Miniature Golf Courses														P	P				20
Roller or Ice Skating Rinks													<u>S</u>	S	S				24
Theaters														P	P	<u>P</u>	<u>S</u>	7	18
I. AUTOMOTIVE AND TRANSPORTATION USES														<u>S</u>	<u>S</u>			<u>17</u>	<u>23</u>
Airports and Heliports	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		24
Auto Alarm / Stereo / Window Tinting Stores															P	P	P	13	7
Auto Lube Shops															S	P	P	13	9
Automotive and Motor Vehicle Sales															S	S	S	13	8

Table 3.24.B- - Schedule of Permitted Principal Uses

Land Use Classification	Residential District										Non-Residential Districts						Special Land Use Standards	Parking Group
	AG	RE	R40	R30	R20	R15	RD	RMF	MH	CPO	CN	CC1	CC2	CC3	ML			
Auto Parts and Accessory Stores												P	P	P	P	13	7	
Auto, Truck or Trailer Rental													S	S	S	13	8	
Auto Upholstery Shops														P	P	13	9	
Auto Parking Lots and Garages (free standing)										S	S	S	S	S	S		n.a.	
Auto Repair Shop													S	S	S	13	9	
Boat and Water-craft Sales and Service													S	S	S	13	8	
Bus or Passenger Train Stations												S	S	S	S		24	

Car Wash (self service and automatic)																		S	P		9
Commuter Transit Stations														S	S			S	S		24
Gasoline Service Stations																		S	S	13	7
LPG / CNG Dispensing Stations																		S	S		24
Motorcycle Sales and Service																		S	S	13	8
Paint and Body Shops																		S	S	13	9
Park and Ride Facilities														S	S			S	S		24
Railroad or Motor Freight Terminals																		S	S		24
Recreational Vehicle Sales and Service																		S	S	13	8
Tire and Battery Stores																		S	S	13	7
Truck and Heavy Equipment Sales and Service																		S	S	13	8
Vehicle Storage Yards or Facilities														S	S			S	S		24

J. HEAVY COMMERCIAL, INDUSTRIAL & MANUFACTURING USES

Appliance Repair Shops																		S	S		8
Building Material Sales with outside storage																		S	P		7

Table 3.24.B- - Schedule of Permitted Principal Uses

Land Use Classification	Residential District										Non-Residential Districts							Special Land Use Standards	Parking Group
	AG	RE	R40	R30	R20	R15	RD	RMF	MH	CPO	CN	CC1	CC2	CC3	ML				
Commercial Laundry															S	S			24
Contractor Office with storage yard															S	S			24
Contractor Office without storage yard															P	P			8
Electronic Assembly or Manufacturing																P			25
Exterminator Shop															S	S			24

Colleyville, Texas, Land Development Code

Food Packaging and Manufacturing																	S		24
Furniture and Cabinet Manufacturing																	P		25
Office Showroom																	P		25
Oil and Gas Extraction	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	See Ch. 3.1		24
Plumbing, HVAC and Electrical Trades Shops																	P	P	8
Printing and Publishing - Commercial																	P		8
Plumbing, HVAC and Electrical Trades Shops																	P	P	8
Printing and Publishing - Commercial																	P		8
Research and Development Labs																	P		8
Scientific Instrument Assembly and Manufacturing																	P		8
Self Storage Facilities (mini-warehouse)																	S		24
Upholstery and Furniture Repair Shops																	P	P	8
Warehouse and Distribution Facilities																	S		24
Wood, Paper or Leather Products																	P		25
Manufacturing not elsewhere listed																	S		24
Welding or Machine Shop																	P		25
<u>Wholesale Store/Supply</u>																	<u>P</u>		<u>25</u>
<u>Wholesale Store/Supply with outdoor storage</u>																	<u>S</u>		<u>24</u>

Commented [BB40]: Duplicate listings

Commented [BB41]: New Uses

C. Special Land Use Standards – The following Special Land Use: Standards, which are referenced in the Special Land Use Standards column of Table 3.24.B, Schedule of Permitted Principal Uses, refer to additional standards and requirements that are applicable to the listed land use.

1. Bed and Breakfast – a Certificate of Occupancy (C.O.) is required prior to occupancy of the premises as a bed & breakfast. The C.O. shall be obtained after an inspection has determined that the structure is in compliance with all applicable current codes and ordinances of the City of Colleyville and the following additional conditions:
 - a. The structure is structurally sound.
 - b. There are no clear and present dangers as to fire and fire safety.
 - c. The plumbing is in compliance with the currently adopted code requirements for the zoning district in which it is located.
 - d. The electrical system is in compliance with the currently adopted Electrical Code for the zoning district in which it is located.
 - e. Smoke detectors shall be placed in each individual bedroom which is offered for public use and smoke detectors shall also be placed in any hallway adjacent thereto.
 - f. Signs, not exceeding one and one-half (1-1/2) square feet, shall indicate only the address and the establishment name.
 - g. Off-street parking shall be located behind the front building line of the structure and shall be screened from public view, and shall be provided in the following manner: one space per bedroom offered for temporary rental in addition to that required for the zoning district in which it is located.
 - h. The total rental bedroom area of the structure shall not exceed twenty-five (25) percent of the total floor area of the dwelling.

Also, in order to continue operation:

- i. Annual inspections shall be required for each bed and breakfast facility to ensure ongoing compliance with the requirements of this Section.
 - ii. Food service shall comply with all provisions of the City Code.
 - iii. The structure shall comply with all current City Codes, including, but not limited to Building Codes, Plumbing Codes, Electrical Codes, Fire and Safety Codes, and others as may from time to time be adopted.
 - ix. The length of stay for any guest is limited to fifteen (15) consecutive days.
2. Assisted Living Facilities – A facility operated under a certificate of compliance document issued by the Texas Department of Aging and Disability Services, in which food, shelter, and person assistance or supervision are provided for a period of at least 14 days for four or more aged adults who do not require hospitalization or skilled or intermediate nursing care.
3. Telecommunication Towers – Construction shall be of monopole design only; and
 - a. the distance between the base of the tower and any Agricultural (Ag) or residential district or use shall be not less than two (2) times the height of the tower; and
 - b. the site plan shall meet all other commercial development requirements of the City such as site plan review, landscaping, setbacks; and
 - c. a minimum of one paved parking space shall be provided at the site of the structure.
4. Veterinarian Clinic with indoor kennels – A facility containing indoor kennels shall be subject to the following conditions.
 - a. The entire business must be conducted within a soundproofed building. Noise and odors created by activities within the building shall not be discernible beyond the property line.
 - b. No animals shall be kept outside the building.
5. Medical and veterinary clinics – Outpatient services only.
6. Archery & firearm ranges – An SUP required in every zoning district, except CN & CC, for sales activity over 9 mo. per year.

Commented [BB42]: Move to Ch. 2 - Definitions

7. Movie Theater Uses: A movie theater shall not contain more than six primary projection screens and two secondary executive viewing rooms and shall not exceed 28,500 square feet in total building size. For purpose of this regulation, a secondary executive viewing room shall not exceed a maximum of fifty (50) seats. (O-04-1454 / 4-16-04) (O-05-1538 / 09/06/05)
8. Home Occupation Uses:
- No person other than members of the family residing on the premises shall be engaged in such occupation;
 - The use of the dwelling unit or accessory building for the home occupation shall be clearly incidental and subordinate to its use for residential purposes by its occupants, and not more than twenty-five (25) percent of the floor area of the dwelling unit shall be used in the conduct of the home occupation;
 - There shall be no change in the outside appearance of the building or premises, or other visible evidence of the conduct of such home occupation other than one sign, not exceeding one (1) square foot in area, non-illuminated, and mounted flat against the wall of the principal building.
 - No traffic shall be generated by such home occupation in greater volumes than would normally be expected in a residential neighborhood, and any need for parking generated by the conduct of such home occupation shall be met off the street on a driveway or other hard surface all weather area;
 - No equipment or process shall be used in such home occupation which creates noise, vibration, glare, fumes, odors, or electrical interference detectable to the normal senses of any adjacent or nearby site occupant. In the case of electrical interference, no equipment or process shall be used which creates visual or audible interference in any radio or television receivers off the premises, or causes fluctuations in line voltage off the premises.
 - Home occupation uses and activities shall be limited to the following: seamstress; accounting; bookkeeping and tax services; notary public; insurance and real estate; small-scale production of cosmetics and household sundries; private educational, music and dance tutoring; arts, crafts and home hobby shops; garage, yard and patio sales of short temporary duration; mail order brokerage; and other similar activities --- but excluding medical and law offices, auto repair, beauty shops, pet grooming services, kennels and other such activities.
 - If a home occupation is deemed to become a nuisance, the Administrative Official may halt the use of the home occupation.
9. Private (HOA) Recreational Facilities – Buildings or structures in which members of a neighborhood association may gather for social, educational or cultural activities that are intended to serve the site occupants and guests thereof.
10. Emergency Clinics – Outpatient services only.
11. Livestock Raising and Breeding – A Special Use Permit is required for swine farming.
12. Alcoholic Beverage and Package Store Sales – A Special Use Permit is required for the sale of alcoholic beverages. A package store shall require the approval of a separate Special Use Permit. Any existing Special Use Permit for the sale of alcoholic beverages for off-premise consumption shall only be for beer and/or wine as specified in the approving ordinance and shall not be considered as approval for a package store as defined in Chapter Two. Also refer to Chapter 6 of the Code of Ordinances for additional regulations regarding alcoholic beverage sales.
13. Vehicle Repair – Vehicle repair, including the repair of other motorized vehicles, are permitted in accordance with the Schedule of Permitted Uses, subject to the following conditions.
- All repairs and servicing shall be conducted within an enclosed building.
 - A business that conducts vehicle repair and is located on property adjacent to a residential use shall provide an sixeight-foot tall solid screen along the property line adjacent to the residential use.

Commented [BB43]: Regulations deemed not needed

Commented [BB44]: Clarification of uses, permitted & non-permitted

Commented [EW45]: Recommended language for clarity of activities allowed

Commented [BB46]: New proposed regulation

Commented [BB47]: Move to Ch. 2 - Definitions

Commented [BB48]: A review of Ch. 6 needed to modify the alcohol to food ratio for total receipts

- c. Except for wrecked vehicles, no more than two vehicles per bay or repair/inspection station that have been accepted for repair or servicing shall be parked/stored outside after regular business hours.
 - d. Wrecked or dismantled vehicles waiting for repair shall not be visible from the street or other residential property and shall be stored in an enclosed building or within a completely enclosed area behind a six~~eight~~-foot tall solid masonry screening fence.
14. ~~Servants or Caretaker Family or Servants Quarters~~ Accessory Dwelling – ~~A secondary dwelling for use by family members or domestic servants employed on the premises of family members provided the gross habitable square feet of floor area shall not exceed six hundred (600) square feet complies with regulations found in Section 3.27 of this chapter~~ 5% of the lot area. Such quarters may be housed within the principal residential dwelling, above a residential garage, or be part of an accessory building on the same premises, and shall comply with minimum standards for light, health, safety, and occupancy in conformance with other applicable City codes and ordinances.
15. Day Care Centers – A facility operated with a state license for the purpose of providing care, protection and guidance to more than twelve children under the age of fourteen years of age for less than a 24-hour period. This term does not include kindergartens and public and private educational facilities or any facility offering care to individuals for a full 24-hour period.
16. Grocery Stores – A special use permit is required for the use of gasoline pumps in conjunction with a grocery store.
17. Billiard Parlor – Compliance with Chapter 10 of the Code of Ordinances is required for a Billiard Parlor.
18. Wind Driven Generators – No wind driven generator shall be constructed without approval of a special use permit per Section 3.24 of the Land Development Code.
- a. All wind driven generator towers shall be of a monopole design. All wiring shall be buried underground by means of a conduit system.
 - b. A wind driven generator may be considered on lots measuring a minimum of 1.5 acres.
 - c. The maximum height of a wind driven generator shall be no greater than 50 feet, measured from the existing ground level to the highest point of the blades.
 - d. All wind energy structures, including tower and rotor, shall stand independent of any building or structure and shall have a minimum setback from any property line, right-of-way, power line, or other improvement of 1.5 times the height of the wind energy structure. It shall also be located entirely in the rear yard and shall not be located in any required setback.
 - e. The maximum noise level shall not exceed 50 dB(a), measured from the property line, adjacent to any residentially zoned property, and 60 dB(a) adjacent to all other zoning districts.
 - f. A wind tower and generator shall not be artificially lighted unless such lighting is required by the Federal Aviation Administration.
 - g. The wind tower must either (a) have a locked anti-climb device installed on the tower; or (b) be completely enclosed by a locked, protective fence at least 6 feet in height.
 - h. No signage or advertisements shall be allowed on the wind tower.
 - i. A maximum of one wind energy system, including the tower, shall be permitted per lot.
 - j. A wind driven generator, found to be non-productive or unused, for a period exceeding 180 days, shall be immediately removed from the premise and the site returned to its prior condition, at the expense of the property owner.
19. Portable Storage Structures – A portable storage structure is any container, storage unit, shed-like container or other portable structure, other than an accessory building as defined in Chapter Two of the Land Development Code, complying with all building codes and Land Development Code requirements, that can or is used for the storage of personal property of any kind and which is located for such purposes outside an enclosed building.

The use of portable storage structures are allowed under the following conditions:

- a. Seven Day Provision: Portable storage structures placed on private property for a period of not more than seven (7) days are hereby exempt from these regulations provided the view of any

Commented [EW49]: Recommended provisions

Commented [EW50]: Recommend change in heading for this section

Commented [EW51]: Same language but relocated to beginning of paragraph

Commented [BB52]: New standards for Accessory Dwellings

Commented [BB53]: Move to Ch. 2 - Definitions

vehicular traffic is not impeded in any way. A permit shall be required per the provisions of sub-section "b". However, there shall be no fee required for structures that are placed for seven (7) or fewer days.

- b. A temporary use permit for a portable storage structure shall be obtained from the Community Development Department prior to placement for any portable storage structure.
- c. There shall be no more than one (1) portable storage structure per property.
- d. The portable storage structure shall be no larger than ten (10) feet wide, twenty (20) feet long and ten (10) feet high.
- e. Notwithstanding the requirements of sub-sections "k" and "l" below, a portable storage structure shall not remain at a property in any zoning district in excess of thirty (30) consecutive days, and shall not be placed at any one property in a zoning district in excess of thirty (30) days in any calendar year.
- f. The portable storage structure shall be set back a minimum of five (5) feet from all property lines.
- g. The portable storage structure shall be set back a minimum of five (5) feet from the nearest wall of a building.
- h. Where a side facing garage or a garage that is located behind the principal structure exists, the portable storage structure shall be located behind the front line of the principal structure.
- i. The portable storage structure shall be placed on an asphalt or concrete surface. A gravel surface is permitted if the portable storage structure is located behind the principal structure.
- j. The portable storage structure shall not be placed upon any street or within any rights-of-way. Exception: Portable storage structures located in mixed-use, townhome, multifamily, or similar residential developments may locate within existing, striped on-street parking spaces provided there are no public safety or vehicular traffic issues caused by the location of the structure.
- k. Portable storage structures associated with construction of a new principal building at a site where a new building permit has been issued are permitted for the duration of construction and shall be removed from the site within fourteen (14) days of the end of construction. Portable storage structures associated with new construction are exempt from the aforementioned conditions.
- l. Portable storage structures associated with any construction that is not part of the construction of a new principal building, and only in conjunction with the issuance of a building permit, may be placed for a maximum period of 180 days or upon completion of construction, whichever occurs first. The fee assessment for a portable storage structure associated with this sub-section shall be as follows:

0 to 30 days:	standard fee
30 to 60 days:	double the standard fee
60 to 90 days:	three times the standard fee
90 to 120 days:	four times the standard fee
120 to 180 days:	six times the standard fee

- m. Any waivers to the conditions of this section shall be considered by the Zoning Board of Adjustment **Special Use Permit (SUP)** in accordance with Chapter One **Section 3.25 Special Use Permit** of the Land Development Code.

Commented [BB54]: Revised for SUP approval

D. Temporary Buildings and Uses (O-04-1497 / 12/21/04)

- 1. Temporary Use Permit – The Building Official may approve a permit for a temporary use specified in this Section for limited periods of time, provided evidence is furnished by the applicant that adequate measures are taken to satisfy public safety concerns and related site criteria concerns. All temporary

uses shall be subject to the regulations contained in this Section. The building official may recommend a temporary use permit application be considered by the City Council where it has been determined by the building official that the proposed temporary use may have significant public interests. A temporary use permit, as herein prescribed, shall not be required for neighborhood block parties held in conjunction with the annual National Night Out neighborhood celebration or for events approved by a municipal department where said event is conducted on municipally owned property.

- a. Revocation: The Building Official may revoke a temporary use permit if determined that:
 - i. The applicant has misrepresented any material fact on the application, or supporting materials.
 - ii. The temporary use fails or ceases to comply with applicable standards or criteria for issuance of a permit.
 - iii. The operation of the temporary use violates any statute, law, ordinance or regulation.
 - iv. The operation of the temporary use constitutes a nuisance or poses a real or potential threat to the health, safety or general welfare of the public.
2. Permit Conditions – The Building Official is hereby authorized to prescribe reasonable conditions upon a temporary use permit to protect the public health, safety, and general welfare of the community, with particular attention to areas adjacent to or in the vicinity of the permitted temporary use. Such conditions may include specific performance standards, noise mitigation measures, lighting restrictions, limitation on hours of operation, odor control measures, off-street parking requirements, traffic restrictions, or other standards designed to minimize adverse impacts on surrounding properties. In the event that a sponsor is dissatisfied with the Building Official's decision, the sponsor may appeal the decision to the City Council.
3. Construction Offices and Sales Offices – The Building Official may approve a permit for a temporary building for use as a construction office or a sales office for new home or lot sales in any zoning district during the construction phase of a permanent building or new subdivision, provided such temporary buildings comply with the following requirements:
 - a. No temporary used as a construction office or a sales office shall encroach within five (5) feet of a property line or encroach within the visibility triangle required in Section 3.26 of this Land Development Code.
 - b. A temporary building used as a construction office during the construction of a permanent building shall be removed within ten (10) days after the issuance of the certificate of occupancy of the permanent building, weather permitting, ~~weather permitting~~.
 - c. A temporary building used as a real estate sales office shall be removed within ten (10) days after ninety (90%) percent of the lots within the subdivision have been sold.
 - d. A temporary construction office or real estate sales office shall sit on a blocked foundation acceptable to the Building Official. No temporary construction office or real estate sales office shall be used that rests only on the wheels.
 - e. A model home may be used as a temporary real estate sales office and shall be exempt from paragraphs a, b, c, and d above.
4. Community Special Events – Outdoor events of public interest which are anticipated to attract less than 500 persons in attendance at any one time for a period of eight consecutive hours or more, such as business activities, carnivals, circuses, and similar temporary events or special fund-raising events, ~~sponsored by a public entity, civic or non-profit organization located within the City.~~ Events sponsored by the City shall be exempt from the requirements of this section. Special Events shall comply with the following:
 - a. Application and site plan for a Special Event shall be submitted at least ten (10) business days in advance of the proposed event
 - b. Events located in parking lots which cause the loss of existing parking spaces shall require the submittal of written approval from the owner

c. A Special Event shall not extend greater than any time period over ~~two~~three (23) consecutive days.

Commented [BB55]: Revised per Council direction

d. ~~There shall be at least one hundred eighty (180) calendar days between events before another permit can be obtained by the business or organization. Any entity that is directly or indirectly affiliated with the previous permit holder shall require the minimum separation between permits. There shall be no more than four (4) special events allowed per location per calendar year. There shall be at least thirty (30) calendar days between events before another permit can be obtained for the location.~~

Commented [BB56]: Revised per Council direction

5. Tents – A temporary use or special event which includes the use of a tent shall require a separate permit in accordance with the standards contained in the Colleyville Fire Code.
6. Temporary Asphalt or Concrete Batch Plant – The Building Official shall approve a permit for a temporary asphalt or concrete batch plant to provide construction materials for the site on which the temporary batch plant is located during the construction phase of a permanent building, new residential subdivision or other project as authorized by the city manager, provided such temporary use comply with the following requirements:
 - a. The temporary batch plant shall receive an approved air quality permit from the State of Texas, and evidence must be presented at the time of application for the temporary use permit.
 - b. The temporary batch plant shall follow all State of Texas storm water run-off requirements. A copy of any required State documents must be on the site of the temporary batch plant at all times.
 - c. A location map, drawn to scale, shall be provided and indicate the following: the location of the batch plant on the subject property along with a defined plant boundary, the location of all related equipment including but not limited to batching equipment and containers, storage areas, hazardous materials storage if applicable. Another drawing, drawn to scale, shall be provided showing the closest habitable residences, schools and religious institutions. The minimum distances shall be 300 feet measured in a direct line from the boundary of the temporary batch plant, as indicated on the application, to the property boundary of the protected use.
 - d. The material delivery route shall be provided indicating routes for raw material delivery with details on the type and numbers of trucks per day. Said route shall require final approval by the City Manager or his/her designee.
 - e. The hours of operation shall follow the construction hours of operation as required in the Colleyville Code of Ordinances.
 - f. A letter of permission shall be provided by the property owner stating that the temporary batch plant will be used to provide concrete/asphalt for the same site where it is located and no other project(s). The letter must also state that the site will be left in good or better condition.
 - g. The application must state the amount of time that the temporary batch plant will be in operation. The permit duration shall not exceed 30 days from the date of issuance. The Administrative Official may extend the permit for an additional 30 days with good cause. Only one permit may be issued for a given parcel of property within a 12 month period.
 - i. The Public Works Director shall determine if additional materials testing is required and may determine the testing personnel required. Any cost of testing shall be paid by the applicant.
 - j. The batch plant shall not be used as a batching facility for any other site other than the site on which it is located and no concrete, asphalt and or any raw materials may be sold from said plant.

- k. Any appeal or waiver from the requirements of this section shall require final approval by the City Council.

E. Outdoor Storage; Screening and Hours of Operations

Zoning Districts		Outdoor Storage Allowed	Screening Requirements Adjacent to Single Family	Hours of Operation	Commercial Building Design Standards
CPO	Professional Office Commercial	No	8'	Daytime only	30-25 pts.
CN	Neighborhood Commercial	No	8'	Daytime only	30-25 pts.
CC1	Village Retail	No	8'	24 hours	30 pts.
CC2	Shopping Center	No	8'	24 hours	30-25 pts.
CC3	Highway Commercial	Yes	8'	24 hours	30-20 pts.
ML	Light Manufacturing - Industrial	Yes	8'	24 hours	30 pts.

Commented [BB57]: Revised to match each district

F. District Regulation Notes ~~{renumber as needed}~~

- ~~A. Where abutting a lot zoned or used for residential purposes (RE through MH) maximum building height shall not exceed requirements shown in Figure 1 "Height Zones for Commercial Districts Adjoining Residential Districts". The roofline within that 50 feet shall have a maximum height of 16' at the eave and the roof design shall be of a residential style.~~
- ~~B. No structure shall be erected in any zoning district in excess of the specified maximum building height either in the number of stories or feet, whichever is less, unless an exception to said maximum building height is contained in this Chapter, except as noted in note "C" below.~~
- ~~C. Heights of four (4) stories may be permitted in CC2 (Shopping Center) district if combined with a Planned Unit Development (PUD).~~
- D. To achieve the "urban village" design, front yards may be varied to as little as 10' from the front property line if required parking is setback not less than forty feet (40') from the front property line.
- E. Where abutting a lot zoned or used for residential purposes (RE through MH) there shall be a twenty-five (25') foot side yard.
- F. Side or rear yards not required where no windows or other openings for light or entry face the yard, and not adjacent to single family.
- ~~G. There shall be a ten foot (10') side yard set-back, unless an ordinance approving a planned unit development for the property in question specifies a different side yard set-back; however, where abutting a lot zoned for commercial or industrial use, no side yard shall be required, provided there are no window or other openings for light or entry in the encroaching walls facing the side yard.~~
- ~~H. There shall be a ten (10') foot side yard set-back, unless an ordinance approving a planned unit development for the property in question specifies a different side yard set-back.~~
- I. Where abutting a lot zoned or used for residential purposes (RE through MH) there shall be a twenty-five (25') foot rear yard.
- ~~J. There shall be a minimum twenty-five (25) foot rear yard set-back, unless an ordinance approving a planned unit development for the property in question specifies a different rear yard set-back; however, the rear yard set-back may be reduced to ten feet (10'), provided there are no window or other openings for light or entry in the encroaching walls facing the rear yard.~~
- ~~K. Where abutting a lot zoned or used for residential purposes there shall be a minimum twenty-five (25') foot rear yard set-back, unless an ordinance approving a planned unit development for the property in question specifies a different rear yard set-back, however, the rear yard set-back may be reduced to ten feet (10') where abutting a lot zoned or used for non-residential purposes.~~
- L. All regulations may vary when above districts are used as a base district for a PUD.

Commented [BB58]: These notes not needed, not included on the chart

Commented [BB59]: Not needed with removal of PUD lined from chart

Commented [BB60]: Not needed with removal of PUD lined from chart

Commented [BB61]: Not needed with removal of PUD lined from chart

Commented [BB62]: Move to footnotes section of the chart

SECTION 3.24.G - SCHEDULE OF DISTRICT REGULATIONS

MAXIMUM RESIDENTIAL DENSITY; MINIMUM LOT SIZE REQUIREMENTS; MINIMUM YARD REQUIREMENTS;
MAXIMUM BUILDING HEIGHT; MAXIMUM LOT COVERAGE; OUTDOOR STORAGE; SCREENING
AND HOURS OF OPERATION

(See District Regulations Notes following Section 3.24.F for explanation of letters in charts)

Zoning Districts		Max. [*] Res. Density	Minimum Lot Size Requirements					Minimum Yard Requirements				Max. Building Height		Max. Lot Coverage
Classification	DU/AC		Area (sq. ft.)		Min. Width in feet	Min. Depth in feet	Max. Lot Size	Front (feet)	Each Side (feet)	Rear (feet)	Stories	Feet	Percent	
			Per Family	Total										
AG	Agricultural	0.3	130,680	130,680	200'	300'	n.a.	40'	25'	40'	2.5	35'	20%	
RE	S. F. "Estate" Residential	0.5	80,000	80,000	200'	300'	n.a.	40'	25'	40'	2.5	35'	20%	
R-40	Single Family Residential	1.25	40,000	40,000	150'	150'	n.a.	40'	15'	25'	2.5	35'	20%	
R-30	Single Family Residential	1.5	30,000	30,000	125'	125'	n.a.	35'	10'	25'	2.5	35'	25%	
R-20	Single Family Residential	2.1	20,000	20,000	100'	125'	n.a.	30'	10'	25'	2.5	35'	30%	
R-15	Single Family Residential	3	15,000	15,000	100'	125'	n.a.	30'	10'	25'	2.5	35'	30%	
R-D	Two Family Residential	8	4,000	8,000	70'	115'	n.a.	25'	10'	25'	2.5	30'	50%	
R-MF	Multi-Family Residential (zoned after June 16, 1981)	8	2,700	18,000	70'	115'	n.a.	25'	10'	25'	2.0	30'	50%	
R-MF	Multi-Family Residential (zoned before June 16, 1981)	18	1,500	10,000	70'	115'	n.a.	25'	10'	25'	3.0	30'	75%	
MH	Mobile Home (Minimum size of mobile home park - 40 spaces)	2.1	20,000	20,000	100'	125'	n.a.	30'	10'	25'	2.5	30'	30%	
C-PO	Professional Office Commercial	n.a.	n.a.	7,200	100'	120'	1 acre	40'	15' (E / F)	10' (F / I)	2.0	35'	40%	
CN	Neighborhood Commercial	n.a.	n.a.	10,000	100'	120'	1 acre	40'	15' (E / F)	10' (F / I)	2.0	35'	40%	
CC1	Village Retail	n.a.	n.a.	15,000	150'	120'	5 acres	40' (D)	15' (E / F)	10' (F / I)	2.0	35'	50%	
CC2	Shopping Center	n.a.	n.a.	20,000	150'	120'	none	40' (D)	15' (E / F)	10' (F / I)	2.0	35'	60%	
CC3	Highway Commercial	n.a.	n.a.	10,000	150'	120'	none	40'	15' (E / F)	10' (F / I)	2.0	35'	70%	
ML	Light Manufacturing	n.a.	n.a.	10,000	100'	120'	none	40'	15' (E / F)	10' (F / I)	2.0	35'	60%	
POD-R	Planned Unit Dev. - Residential	n.a.	n.a.	10,000	100'	120'	n.a.	30'	10' (H)	25' (J)	3.0	30'	30%	
POD-C	Planned Unit Dev. - Commercial	n.a.	n.a.	7,200	70'	115'	n.a.	40'	10' (S)	10'	3.0 (S)	35'	50%	
POD-I	Planned Unit Dev. - Industrial	n.a.	n.a.	10,000	70'	115'	n.a.	40'	10' (S)	10'	3.0	30'	30%	

* Maximum residential density is the number of dwelling units per acre, not including streets, alleys, or public space. R-MF zoned after June 16, 1981 - four units per building maximum.

** 16,000 s.f. average

*All regulations may vary when above districts are used as a base district for a PUD

Section 3.25 Special Use Permit

(O-02-1331 / 02-19-2002)

The purpose of a Special Use Permit is to allow a use not normally allowed in a zoning district, which could be of benefit in a particular case to the general welfare, provided adequate development standards, and special requirements are imposed to protect surrounding uses or to preserve the character of the neighborhood. Upon proper application and payment of the applicable fee, the City Council, after public hearing and proper notice to all parties affected and after recommendation from the Planning and Zoning Commission, may authorize a Special Use Permit for a use not allowed by right in *Section 3.24 "Schedule of Permitted Principal Uses"* in accordance with the following criteria.

1. Procedures – Every Special Use Permit application shall be reviewed and considered using the same procedures for reviewing and considering a rezoning application as specified in *Chapter 1 – General Provisions* of this Land Development Code.
2. Site Plan – The applicant must submit a site plan in the form and manner specified by the Administrative Official, showing the details of the proposed use and its relationship to surrounding properties.
3. Additional Information – The City Council and the Planning and Zoning Commission, in considering and determining its recommendation to the City Council on any request for a Special Use Permit, may require from the applicant, plans, information, operating data and expert evaluation concerning the location and function and characteristics of any building, structure or use proposed.
4. Conditions of Approval – The City Council may impose such safeguards, requirements and conditions as it deems are necessary to properly protect any surrounding property, surrounding use, or neighborhood character and to insure the appropriate conduct of the special permitted use, including, without limitation, imposing development standards, requiring public facility improvements and means of ingress and egress of public streets, establishing conditions of operation, establishing time limits, establishing location, arrangement and construction of any uses or structures, adopting regulations to protect the general welfare and adjacent property from excessive noise, vibration, dust, dirt, smoke, fumes, gas, odor, explosion, glare, offensive view of other undesirable or hazardous conditions. All conditions imposed by the City Council shall be complied with prior to the issuance of a Certificate of Occupancy.
5. Revocation Upon Failure to Develop – A special use permit approved by the Council shall become null and void one year from the date of approval by the City Council unless a building permit or certificate of occupancy, whichever is applicable, has been obtained on the property within said one year period. The City Council may in its adopting ordinance, shorten or lengthen the time in which a building permit or certificate of occupancy must be issued in order to preserve the special use permit. Any Special Use Permit in existence upon the passage of this ordinance shall become null and void one year after the passage of this ordinance, unless a building permit or certificate of occupancy, whichever is applicable, has been issued within said year.

Exception: The ordinance authorizing a Special Use Permit may provide for an alternate expiration period.

6. Termination and Abandonment of Use – In the event the building, premises or land uses authorized by a Special Use Permit are terminated or abandoned for a period of six (6) months or longer, the use of the same shall thereafter conform to the regulations applicable to the zoning district, unless a new and separate Special Use Permit is approved for continuation of the use.
7. Modification – No building or premises authorized by a Special Use Permit may be enlarged, modified, structurally altered, or otherwise significantly changed unless an amendment to the Special Use Permit is approved by the City Council using the procedures specified in *Chapter 1 – General Provisions* of this Land Development Code.
8. Violation – It shall be unlawful for property owner or tenant to violate any terms or conditions of the ordinance approving the Special Use Permit.

Section 3.25.1 Large-Commercial Buildings

(O-00-1249 / 11/08/00)

Commented [BB63]: Section to be moved to Chapter 6: Commercial Design Standards

- A. Applicability – The criteria in this Section shall be applicable to the construction of any new large commercial building proposed for construction on or after November 8, 2000. These criteria shall not be applicable to the following:
1. ~~The~~ use, re-use, modification or consolidation of existing commercial buildings developed prior to November 8, 2000, or to the expansion of commercial buildings existing as of November 8, 2000, provided expansion does not exceed ten percent (10%) of the existing building footprint, including the cumulative amount of all prior expansions, or
 2. ~~B~~ buildings constructed within the limits of the PUD-C established by ordinance O-99-1141.
- B. General Provision – No new large commercial building shall be permitted for construction within the city of Colleyville, except where allowed as follows:
1. Large Commercial Building shall be allowed by right in the ML – Light Manufacturing District.
 2. Large Commercial Building shall be allowed with approval of a Planned Unit Development – Commercial.
 3. No large commercial building shall be permitted within a previously approved Planned Unit Development – Commercial, unless the approving ordinance contains a specific provision for a large commercial building as provided in this Section. The requirements and procedures for a Planned Unit Development – Commercial contained elsewhere in the Colleyville Land Development Code and the additional requirements set forth in this Section shall be used in the review of an application for a large commercial building. The City Council may establish such terms and conditions as are necessary to protect life, health, property, public peace and the general welfare of the public and the adjacent properties. For purpose of this regulation, a commercial building which contains a building footprint of forty thousand (40,000) square feet, or more, shall be declared a large commercial building and be subject to these criteria.
- C. Application and Development Requirements – Every large commercial building must comply with the requirements of this Section. All site plan reviews required by the Colleyville Land Development Code or applications for a rezoning request for a Planned Unit Development – Commercial for a large commercial building shall include all the information outlined as follows.
1. Site Plan – A site plan, drawn to scale, showing the property boundary, all proposed buildings, water features, creek channels, the 100-year flood plain, outdoor display areas, proposed driveways, parking lots, landscaped areas, loading and delivery docks, refuse and recycling facilities and other physical features which may influence the development of the site.
 2. Elevation Drawings – Building elevation drawings, drawn to scale, indicating the type and percentage of each exterior building wall material.
- D. Development Requirements
1. Building Height, Set Back Requirements and Maximum Lot Coverage – The minimum front, side and rear building set back lines, maximum building height, and maximum lot coverage for a 40,000 square foot building footprint shall be in accordance with the following schedule:

Minimum Building Line Set Backs, Maximum Height and Maximum Lot Coverage for a 40,000 s.f. Large Commercial Building			
Minimum Building Set Back	Front:	40 ft.	(1) (2)
	Side:	40 ft.	(1) (2)
	Rear:	40 ft.	(1) (2)
Maximum Building Height		35 ft.	
Maximum Lot Coverage		40%	

Notes:

- (1) The minimum building set back line adjacent to a public street shall be increased one foot for each additional increment of 2,000 s.f. of building footprint over 40,000 square feet of building footprint.
 - (2) The minimum building set back line adjacent to a residential zoned property shall be a minimum of 50 feet and shall be increased one foot for each additional increment of 1,000 s.f. of building footprint over 50,000 square feet of building footprint with a maximum building setback of 250 feet. If a public road stands between the residential zoned property and the commercial establishment, the road width may be included in the setback calculation if the setback exceeds 100 feet.
 - (3) The setback requirements between two commercial zoned properties shall conform with the CC2 zoning requirements as outlined in the Land Development Code.
2. *Façade Articulation* – All large commercial buildings shall have facades which comply with the following requirements:
- a. *Horizontal Articulation* – No building façade which faces a public street shall extend horizontally greater than three (3) times the height of the wall without having an off-set of not less than fifteen (15%) percent of the wall's height as shown on the attached Exhibit "A", and such off-set shall continue for a minimum distance equal to at least twenty-five (25%) percent of the length of the longest adjacent plane.
 - b. *Vertical Articulation* – No building façade which faces a public street shall extend horizontally for a distance greater than three (3) times the height of the wall unless the wall contains at least one of the following features and every front building façade shall have no less than two of the following features:
 - (1) Parapets which change the roof line. The parapet height shall be a minimum of fifteen (15%) percent of the wall's height, and such height change shall continue for a minimum distance equal to at least twenty-five (25%) percent of the length of the longest adjacent plane.
 - (2) Overhanging eaves, extending no less than three (3) feet past the supporting walls.
 - (3) Sloping roofs that do not exceed the average height of the supporting walls, with an average slope greater than or equal to one (1) foot of vertical rise for every three (3) feet of horizontal run and less than or equal to one (1) foot of vertical rise for every one (1) foot of horizontal run.
 - (4) Three or more roof slope planes.
 - (5) A covered walkway along a minimum of fifty (50%) percent of the front façade length.
3. *Side and Rear Facade Features* – Side and rear building facades, which do not face a public street, shall include a minimum of three architectural changes, such as (1) a changing plane not less than five (5) feet in width and eighteen (18) inches in depth, (2) a surface material change of not more than thirty (30) feet in length, as measured horizontally, or (3) a combination of these elements.
4. *Building Design* – In addition to the building façade requirements contained herein, the site plan and building elevation plans shall comply with the requirements of *Chapter 6 – Building Design* of the Colleyville Land Development Code, except where modified by the requirements in this Section. The minimum building design score shall be 30 points.
5. *Exposed Columns* – Exposed structural support columns shall be constructed of, or clad in, the same masonry material as the principal structure. Architecturally significant columns (e.g. fluted, etc.) may be permitted.
6. *Exterior Surface Materials* – A minimum of ninety (90%) percent of each exterior wall surfaces, excluding door and window openings, shall be constructed of clay-fired brick, native stone, cast stone, or a combination of these materials. Tilt - up concrete construction is permitted, provided the

exterior surface is covered with clay-fired brick, native stone, cast stone, or a combination of these materials. Stucco and EIFS (Exterior Installation Finished System) are permitted for not more than ten (10%) percent of the exterior surface. Concrete block, split-faced block or cinder-block shall not be acceptable, except where a wall surface faces an adjacent non-residential building. Proposals for surface materials with similar durability and appearance of clay-fired brick, native stone, or cast stone may be considered.

7. *Exterior Surface Colors* – The exterior surfaces shall be of a natural finish, provided the colors are, subtle, or neutral colors. Trim and accent areas may be painted and feature brighter colors, including primary colors, but not more than ten (10%) percent of the wall surface area. High intensity or fluorescent colors are prohibited.
8. *General Landscaping Requirement* – The landscaping of the development shall comply with the requirements of Chapter 4 – Landscaping and Buffering of the Land Development Code, except where modified by the requirements of this Section. All ground surfaces not used for buildings, sidewalks, roadways or other impermeable surfaces shall be covered with live grass, turf, shrubbery, trees, ground cover, flowering plants or appropriate mulching. In order to insure for a variety of plant materials the following minimum requirements for grass, shrubs, and trees shall be provided:
 - a. *Minimum Landscaping Coverage*: Not less than twenty percent (20%) of the total land area of the development shall be, landscaped. At least fifty percent (50%) of the total landscaped area shall be located in the street yard(s). The overall minimum percentage of required landscaping may not be reduced by the application of landscaping enhancement credits.
 - b. *Trees*: Landscaping shall include the retention or planting of one (1) three-inch (3") caliper overstory shade tree per each forty (40) feet of street frontage. These trees to be planted within the landscaped buffer adjacent to each street frontage.
9. *Landscape Buffer and Screening Wall Adjacent to Residential Property* – Along the entire length of the common property line adjacent to residential property there shall be a landscape buffer, a minimum of forty (40) feet in width, and a solid screening wall constructed of clay-fired brick, native stone, cast stone, or a combination of these materials, not less than eight (8) feet in height nor more than ten (10) feet in height. The landscape buffer and the solid screening wall shall be provided along the entire length of any property line adjacent to any residential property. The landscaped buffer shall contain lawn grass or ground cover and be maintained as a permanent landscaped area. There shall be no buildings, parking areas, driveways, sidewalks or structures contained within the required buffer. The landscaping buffer shall include the retention or planting of one (1) three-inch (3") caliper overstory shade tree per each forty (40) feet of common property line with an adjacent residential property. Said screening wall shall be constructed generally along the common property line with the residential property, but its terminus shall not encroach nearer than twenty-five (25') to a street right-of-way.
10. *Landscape Buffer and Screening Adjacent to Public Streets* – There shall be a minimum forty (40) foot wide landscape buffer adjacent to all street rights-of-way. There shall be no buildings, parking areas, driveways, sidewalks or structures, except permanent signs, contained within the required landscape buffer. A driveway or sidewalk may cross the buffer to provide access to the site. Within the landscaped buffer, there shall be either one or a combination of the following landscaping features:
 - a. *Earthen Berms*: A minimum of thirty (30) inches in height with a maximum side slope of three feet to one foot of rise as shown on the attached Exhibit "B". The berm shall not extend parallel to the street right-of-way, but shall meander in a serpentine fashion and shall be entirely vegetated with lawn grass or groundcover.
 - b. *Shrubs*: A row of shrubs consisting of individual shrubs planted not more than thirty-six (36) inches on center which will form a solid continuous visual screen of not less than thirty (30) inches in height within a two year period after planting as shown on the attached Exhibit "C". Shrubs shall be maintained so as to not exceed six (6) feet in height. The shrub row shall be located along the portion of the landscaped buffer that is the furthest from the street right-of-way.

- c. *Low Solid Wall:* A solid wall constructed of clay-fired brick, native stone, cast stone, or a combination of these materials, not less than thirty (30) inches in height as shown on the attached Exhibit "D". Said wall shall be constructed generally parallel to and twenty (20) feet from the street right-of-way. The solid wall shall not constitute more than thirty (30) percent of the length of the abutting street frontage.
11. *Parking Lot Landscaping* – Parking areas shall contain a minimum of one (1) ~~landscaped~~ landscaped island per sixteen (16) parking spaces. No landscaped island shall be less than three-hundred (300) square feet. Every landscaped island shall include one (1) three-inch (3") caliper shade tree with the remaining area covered with grass, shrubs or ground cover. Landscaped planting areas shall be located so that no parking space shall be more than seventy-five (75) feet from the trunk of a shade tree. Where a landscaped island is adjacent to a landscaped buffer, the parking spaces adjacent to the landscaped island shall be paved with a pervious material pave-stone. The parking lot landscaping requirements contained in the paragraph shall not be applicable to the interior parking spaces of a parking garage.
12. *Parking Lot Walkways* – There shall be a pedestrian walkway a minimum of eight (8) feet in width for every four rows of parking within the parking area. Said walkway shall be constructed parallel to the parking rows as shown on the attached Exhibit "B". The walkway shall be paved with a hard surface.
13. *Curbing of Landscaped Areas* – All landscaped islands and landscaped areas shall be protected from vehicular encroachment by concrete curbs a minimum of six (6) inches in height.
14. *Permanent Ground Signs* – The development shall comply with the provisions of Chapter 7 – Sign Regulations of the Colleyville Land Development Code, except that only one monument sign per street frontage shall be allowed. The maximum height of the monument sign structure shall be eight (8) feet. The maximum area of the monument sign structure shall be one-hundred (100) square feet. Only external illumination shall be allowed. Each side of the monument sign structure shall contain an architectural feature of clay-fired brick, native stone, cast stone or a combination of these materials. The architectural feature shall be equivalent to fifteen (15%) percent of the total area of the sign structure.
15. *Attached Building Signs* – The development shall comply with the provisions of Chapter 7 – Sign Regulations of the Colleyville Land Development Code, except that the total square footage of all wall signs shall not exceed ten (10%) percent of the wall face.
16. *Tree Preservation* – The development shall comply with the provisions of Chapter 5 – Tree Preservation of the Colleyville Land Development Code.
17. *Off-Street Parking and Loading Requirements* – The development shall comply with the requirements of Section 3.29 – Off-Street Parking Requirements of the Colleyville Land Development Code. The maximum number of parking spaces shall be one (1) space per two-hundred (200) square feet of gross floor area.
18. *Delivery / Loading Spaces* – No delivery or loading space shall be located within one-hundred (100) feet of a residential property. All delivery and loading spaces shall be screened from public view from a street right-of-way or an adjacent residential property by an eight (8) foot to ten (10) foot tall solid screening wall constructed of like material to the building. Additional planting materials shall be provided so that no more than two-thirds of the surface area of the solid screening wall is visible from the street or residential property. The live plant screening shall consist of shrubs, a minimum of three (3) feet in height when planted, and which can be expected to reach six (6) feet or greater in height within three (3) years of planting. Shrubs shall be spaced so that there shall be no gap greater than four (4) feet between mature plant materials. No delivery or loading area shall be operated between the hours of 11:00 p.m. and 6:00 a.m. Parking of delivery vehicles shall not exceed 48 hours duration.
19. *Outdoor Display Areas* - Outside display of merchandise shall be allowed, provided that it shall be limited to an area within eight (8) feet of the front wall of the primary building and further provided that emergency pedestrian access to the building is not blocked. No merchandise shall be displayed between the hours of 11:00 p. m. and 6:00 a. m.

For purpose of this regulation, the front wall shall be the front containment wall of the structure and not the front of an overhanging walkway cover.

20. *Outside Storage and Sales Areas* –There shall be no outside storage or outside sales areas of landscaping materials, plants or general merchandise, except for an outside display area, as provided in the above paragraph. For purpose of this regulation, nothing shall prohibit the sale or display of landscaping materials, plants or general merchandise located behind an enclosed solid screening wall constructed of like material to the building, provided merchandise is not visible above the top of the screening wall.
21. *Refuse Collection* – No refuse collection shall occur within 100 feet of residential property. All refuse containers, including recycling containers, and trash compactors shall be screened from view from a public street and from adjacent residential properties by an enclosure constructed on three sides with an eight (8) foot high solid masonry screening wall constructed of like material to the building. Said screening enclosure shall include solid metal doors. When a refuse container, trash compactor or recycling container is situated adjacent to a residential property, the screening wall enclosure shall comply with the building setback lines established for the zoning district.
22. *Screening of Mechanical Equipment* - Roof or ground-mounted mechanical equipment shall be screened to mitigate noise and views in all directions from adjacent property. If roof mounted, the screening material shall be designed to conform architecturally with the design of the building. Ground-mounted mechanical equipment shall be screened by a solid masonry screening wall constructed of like material to the building and be of sufficient height to block the view and noise of the equipment from adjacent property.
23. *Cart Storage* – All shopping cart storage areas shall be contained within the primary building. Temporary shopping cart parking within parking areas shall be allowed, provided carts are removed to within the primary building on a frequent basis.
24. *Outdoor Lighting* – ~~Light poles situated within 300 feet of residential property shall not exceed twenty (20) feet in height. Exterior lighting must be High Intensity Discharge (HID) lights shielded and directed away from adjacent properties and shall produce light no greater than one foot candle at the property line, except at driveway entrances which shall be lighted adequately to provide for safe access to the property. The parking lot lighting system shall be designed to dim between the hours of 11:00 p.m. and 6:00 a.m. Wooden light poles shall be prohibited as an illumination standard. Security lighting at the rear and sides of the building shall be designed to reduce light pollution and to prevent objectionable glare onto any residential property.~~ [Exterior lighting shall comply with Chapter 6 \(Building Design Standards\) of the Land Development Code.](#)

Commented [EW64]: New Section 6.6 in Chapter 6 addresses exterior lighting in all commercial districts





Exhibit "A"


Façade Articulation

Berm




**Landscape Berm
Exhibit "B"**

Hedge




**Landscape Shrubs
Exhibit "C"**

**Masonry
wall**



**Solid Wall
Exhibit "D"**



Parking Lot Walkway
Exhibit "E"

Section 3.26 Fences, Free Standing Walls, and Screening Materials

A. Scope

1. This section is to regulate fences, free standing walls and other screening material in a manner so as to promote safety, preserve property values, promote the general welfare of the City of Colleyville, and to enhance the aesthetic quality of the community.
2. No fence, screen, freestanding wall or other visual barrier shall be constructed or placed in such a manner as would endanger the health or safety of the general public.
3. For administrative purposes, all references to fences or walls shall be interpreted to apply to free standing structures.

B. Definitions - Fence or Wall Placement

Perimeter Subdivision Fencing. A subdivision perimeter fence shall be construed to be any decorative or security fence along a substantial portion of the boundary or property line of any plat, replat or phase of a plat or replat or filing of a plat or replat as those terms are defined in *Chapter 2 - Definitions* of this Land Development Code, of any property (1) zoned other than CPO, CN, CC1, CC2, CC3, or ML and shown on an approved plat thereof, or (2) property that is zoned AG, RE, R40, R30, R20, R15, RD, RMF. The actual location of a fence or wall on a site is assumed to be to on the property or common property line and encroachments onto adjacent property are not expressly authorized by the Administrative Official or their representatives.

C. Maintenance

1. All fences erected as provided for in this section shall be maintained in good condition.
2. A fence shall not lean more than one inch out of vertical for each foot of height as measured from the top of the fence.
3. The owner shall replace broken, damaged, removed or missing parts of a fence within ten (10) days of the day the owner received notice from the Administrative Official; with the same material, or material with comparable composition, color, size, shape and quality of the original fence to which the repair is being made. No permit is required for repairs as defined in this ordinance. The Administrative Official may, upon written notice from the owner that unusual circumstances prevent the timely repair of a fence, extend the replacement time as required. The Administrative Official shall not extend the replacement time longer than reasonably necessary. The owner requesting a replacement time

Commented [EW65]: A sub-section for "Definitions" that contains only one definition is not necessary and should be located in Section 2 of LDC. Retitled this section as "Fence or Wall Placement".

Commented [BB66]: Move to Ch. 2 - Definitions

Commented [EW67]: Added disclaimer for when property owners dispute the fence is crossing property lines.

extension shall provide the Administrative Official a written scope and schedule detailing materials and estimated time period of the completed replacement for approval.

4. A fence shall be maintained in sound structural condition as a whole or completely removed, including post(s).
5. Property owners shall maintain fences, including those existing prior to the adoption of this Ordinance, at all times in a state of good repair, safe and secure condition, with all braces, bolts, nails, supporting frame and fastenings free from deterioration, termite infestation, rot, rust or loosening, and able to withstand at all times the wind pressure for which they were designed.
6. Property owners shall regularly paint fence supports, gates, structural members and exterior surfaces that are covered with paint to prevent rusting, peeling or blistering surfaces.
7. Existing fences that were constructed prior to the adoption of this Ordinance that were constructed with materials not currently permitted by this Ordinance may be maintained as long as no part of the fence is or becomes unsafe, dilapidated, or a public nuisance. If the Administrative Official determines the fence is unsafe, dilapidated, or a public nuisance the fence must be repaired with materials approved by this Ordinance or be removed.

9.8. The construction of a fence or wall on the property line shall not preclude the property owner's responsibility to maintain and keep the area between the fence and an adjacent fence on a neighboring property, the property line to the back of curb or edge of the pavement or center of alley, free and clear of debris and high weeds.

D. General Requirements/Prohibitions for all Fences and Free-standing Walls

1. *Screening Required in Residential Districts:*

- a. Nonresidential uses in a residential district shall be suitably screened from view of any adjacent residential lot or dwelling use along the side and rear property lines of such nonresidential use with a decorative masonry wall of not less than eight (8) feet in height. ~~Said screening requirements shall not be mandatory for public schools, parks or churches, except where active outdoor intensive use area (such as a playground) is adjacent to a residential lot or dwelling.~~ Off-street loading areas of any non-residential use shall be adequately screened from view of any residential dwelling or lot or of any other adjacent public or semi-public land use with a decorative masonry wall of not less than (8) feet in height or a landscaped berm.
- b. Where a multifamily or mobile home use abuts a one or two family district, or where a mobile home use abuts a one, two or multifamily use or district, the side and rear property lines of said multifamily or mobile home use or district shall be suitably screened from view of any adjacent dissimilar residential dwelling or lot with a decorative masonry wall of not less than eight (8) feet in height or a landscaped berm.
- c. Nothing in this section shall restrict the fencing of tennis courts with traditional fencing material to a maximum of twelve (12) feet.

2. *Screening Required in Non-Residential Districts:*

- a. Where a nonresidential use abuts a residential lot, use or district, the side and rear property lines abutting said residential lot, use or district shall be suitably screened, with a decorative masonry wall, by the nonresidential use so as to obscure the view from the residential lot, use or district to the nonresidential use to a height not less than eight (8) feet.
- b. Where a district boundary separating a residential district from a nonresidential district is along a street, and an automobile parking lot or parking area is located in the front yard of the nonresidential use, then said parking lot or parking area facing the residential lot, use or district shall be suitably screened to a height of not less than three and one-half (3-1/2) feet.

Commented [BB68]: Churches and schools should be expected to provide screening when adjacent to residential uses

- c. In all districts where open storage is permitted and the screening thereof is required, then such screening shall be provided around the exposed perimeter thereof of not less than six (6) feet in height and shall be composed of decorative masonry material
 - d. Off-street loading areas shall be adequately screened from view of any residential dwelling lot or of any other adjacent residential land use with a decorative masonry wall of not less than eight feet in height or a landscaped berm.
 - e. All roof mounted mechanical equipment and parapet wall structural supports shall be screened from view.
 - f. All required screening between residential and commercial, institutional, multifamily and mobile home uses shall be maintained in good condition by the property owner of the commercial, institutional, multifamily and mobile home use.
3. *Screening Requirements for Waste, Garbage, Compacting and Recycling Containers:* The following regulations shall apply to all multifamily, mixed-use, institutional and commercial uses where large containers are utilized for the storage or compacting of waste, garbage or recycling materials for any properties where the building permit for the primary structure was issued on or after April 17, 2013:
- a. All containers shall be fully enclosed by a decorative masonry wall.
 - b. Masonry materials shall match the masonry materials of the exterior wall of the primary structure on the property where the container is located.
 - c. The height of the screening wall shall be a minimum of six feet, or one foot above the height of the container/compactor, whichever is greater, and shall not exceed 10 feet in height.
 - d. The gate shall be composed of solid metal and shall be of a color that matches or complements the masonry wall.
 - e. The gate shall remain closed at all times. Exception: gates for recycling bins that are accessible to the public may remain open provided all recycling material is completely stored within the container.
 - f. Where possible, gates shall be oriented away from the view of any roadway traffic.
 - g. All enclosures and containers shall be located behind all required building setbacks.
 - ~~h. and All enclosures and containers shall be located a minimum of 25 feet from any properties zoned or used for non-multifamily residential purposes.~~
 - hi. Unless subject to a different requirement as part of an SUP or PUD ordinance, for properties where the building permit for the primary structure was issued before April 17, 2013, the required enclosure and gate may be composed of wood or masonry materials to a minimum height of six feet and the gate must remain closed at all times. Otherwise, said properties shall be exempt from the other provisions of this section. However, loss of any legal-nonconforming status for any property and/or building as described in Section 3.7 in the Land Development Code shall require full compliance with this section.
 - ij. The City shall have the right to remove any container in an enclosure that has been non-compliant with this sub-section for more than 30 days.
4. *Obstruction Prohibited:* No fence, screen, free standing wall or other visual barrier shall be so located or placed that it obstructs the vision of a motor vehicle driver approaching any street, alley or drive intersection. A visual barrier shall be deemed to be any fence, wall, hedge, shrubbery, etc., higher than thirty (30) inches above ground level at the property line, except single trees having single trunks, which are pruned to a height of seven (7) feet above ground level. See Exhibit "3-1".

Commented [BB69]: Separated into 2 regulations




Exhibit "3-1"
Obstructions Prohibited

5. *Twenty-Five (25) Foot Visibility Triangle Required:* No fence, screen, wall or visual barrier shall be located or placed where it obstructs the vision of motor vehicle drivers approaching any street intersection. At all street intersections, clear vision shall be maintained across the lot for a distance of twenty-five (25) feet back from the property corner along both streets. See Exhibit "3-2".




Exhibit "3-2"
Visibility Triangle

6. *Barbed Wire Prohibited:* Fences constructed of barbed wire and walls topped with broken glass or surfaced with any like material shall be prohibited except as provided below.

Barbed wire fences used in conjunction with permitted agricultural, livestock, and related activities, or in industrial districts are permitted without restrictions.

Barbed wire strands may be placed on the top of security fences in non-residential districts for the purpose of security from theft, entry and hazard such as around public utility substations and uses of a similar nature, provided the top strand is not higher than eight (8) feet nor the bottom strand lower than six (6) feet from the adjacent grade line.

7. *Electrical Fences:* Electrical fences and fence charging devices (Underwriters Laboratory approved) shall be plainly marked at a minimum of twenty-five (25) foot intervals as to the nature thereof.
8. *Eight (8) Foot Maximum Height:* No fence in a residential district shall exceed eight (8) feet in height above ground level at the fence line.
9. *Property Owners' Responsibility:* The construction of a fence or wall on the property line shall not preclude the property owner's responsibility to maintain and keep the area defined between the extension of the property lines to the back of curb or edge of pavement free and clear of debris and high weeds. See Exhibit "3-3".




Exhibit "3-3"
Property Owner's Responsibility

10. *Public Property:* No fence, guy wire, brace or any post of such fence shall be constructed upon or cause to protrude over property that the City or the general public has dominion and control over, owns or has an easement over, under, around or through, except upon drainage and utility easements which are permitted to be fenced.
11. *Floodway Permit Required:* The construction of a fence or wall in a floodway as shown on the most recent revision of the "Floodway - Flood Boundary and Floodway Map" prepared by the Federal Emergency Management Agency (FEMA) shall require a development permit as currently required in the City's drainage policies.
12. *Swimming Pools:* All swimming pools shall be fenced. A solid or chain link type fence or a barrier at least four (4) feet in height shall completely enclose every swimming pool to be constructed. There shall be no openings, holes, or gaps bigger than four (4) inch spaces and no openings whatsoever on horizontal picket type fences. All gates allowing access to the pool area shall be self-closing with self-latching devices located in the upper quarter of the gate. All entrances to the swimming pool area must be able to be secured by a combination or key locking device. A dwelling house, accessory building, or apartment building may be used as part of such enclosure provided that all entrances to the swimming pool are equipped with gates as described herein. All fences should conform to local governmental codes and restrictions.
13. *Pre-Formed Concrete:* Pre-formed concrete is a permitted masonry material provided the texture adequately mimics the intended style match, be it wood, brick, stone, etc. Pre-formed concrete fences shall be maintained in good condition including any painted fences. The building official shall approve the final finished surface and reserves the right to deny a fence permit application if the surface does not adhere to these regulations.
14. *General Construction Requirements for Wood Fences*
 - a. For commercial properties, all vertical posts on fences over four (4) feet in height shall be galvanized steel with a minimum two (2) and three-eighths (3/8") inch diameter, a minimum fifteen (15) gauge thickness, and set in a concrete footing. Picket fences, split rail fences, ranch style or agricultural fences, or other types of decorative fences approved by the Building Official or his/her designee shall be permitted to use wood posts.
 - b. Concrete footings shall be a minimum of eight (8) inches in diameter.
 - c. For fences less than seven (7) feet in height, posts shall be spaced at a maximum of eight (8) feet on center, set in a concrete footing of no less than twenty-four (24") inches deep.
 - d. For fences that are seven (7) feet or greater in height, posts shall be spaced at a maximum of six (6) feet on center, set in a concrete footing of no less than thirty-six (36") inches deep.
 - e. Fence posts attached to or supported by other structures, including retaining walls, shall be provided with foundation and anchorage to prevent movement of structure or retaining wall.

- f. All materials shall be securely fastened, vertical boards to horizontal stringers, stringers to vertical posts, top rail, to ensure an ongoing attractive appearance and safe condition, free from rot, rust, vandalism and other sources of decay.
- g. The bottom of the fence shall be designed to prevent ground to wood contact. This can be achieved through the use of a concrete strip poured between the fence supports or by raising the pickets to provide a minimum of two inches between the bottom of the pickets and the ground. Fences located within drainage easements must be approved by the Public Works Director per the requirements of Section 8-170 of the Land Development Code and shall be built such that required drainage and storm water run-off is not impeded.
- h. All wood material shall be stained, pressure treated, painted, or adequately sealed to prevent decay.

Commented [EW70]: "storm water" is two separate words

15. Perimeter Subdivision Fences: A fence along the perimeter of a subdivision is allowed under the following conditions:

- a. No setback shall be required from any street right-of-way line.
- b. No perimeter subdivision fence shall encroach into the required twenty-five (25) foot visibility triangle as defined above.
- c. The perimeter subdivision fence shall have a maximum height of eight (8) feet, to include any element associated with the fence.
- d. Materials along Street Frontage: The perimeter subdivision fence shall be decorative in nature and constructed of stone, brick, wrought-iron, or a combination of these materials for any portion along a perimeter street. The use of wood and composite materials shall be prohibited along the street frontage.

Commented [BB71]: Codified standards for perimeter subdivision fences

Commented [BB72R71]: After review, staff recommends approval of these standards. Revision was made to material standards along street frontages.

16. Sealed Plans Required for Masonry Walls, Columns and Fences: For all masonry walls, columns and fences authorized by this Section, required plans and specifications shall be prepared and sealed by a State of Texas registered engineer and shall consider the site's soil characteristics, wind loadings, and other environmental considerations. All field inspections and verifications for a new masonry wall, fence, and column must be approved by the design professional mentioned above or the professional's representative. Said inspection approval must be submitted to the Building Official in writing prior to the City's final inspection.

E. Fence and Free Standing Wall Setback Requirements

- 1. **Front Yards:** No fence or free standing wall greater than thirty (30) inches in height and no greater than twenty-five (25) percent solid opaque construction shall extend into the required yard on which the primary structure faces.
 - a. The primary fencing material shall be of wrought iron, pre-formed concrete, poured in place concrete, concrete masonry unit (CMU), brick, approved wood rail construction, a combination thereof or other similar material approved by the City Building Official. All poured in place concrete and CMU shall contain an architectural finish.
 - b. On a corner lot, a house shall be deemed to face on that street on which it has its least dimension unless otherwise determined by the Building Official.
 - c. Vehicle Gate setback: Any vehicle gate shall be set back a sufficient distance from the property line to allow vehicle queuing space in order to maintain safety and to prevent backup along the street pavement. Sufficient distance shall be determined by the Building Official.
 - d. Exceptions to front yard requirement: Lots containing a minimum of 40,000 square feet, and subdivisions, shall be allowed to construct a perimeter fence within the front yard setback. Said

Commented [EW73]: Provides consistency for term used throughout Subsection E

Commented [EW74]: Specifies that the section applies to vehicle gates – not pedestrian gates

fencing shall be no greater than eight (8) feet in height and shall have no greater than twenty-five (25) percent solid opaque construction within the front yard. Allowed construction materials shall be the same as paragraph "1.a" above. **This exception shall not apply to properties zoned as a PUD district.**

Commented [EW75]: Provides consistency for term used throughout Subsection E

2. **Corner Side Yards:** Except where allowed elsewhere in this chapter, fences and walls within a required side yard adjacent to a street right-of-way shall meet the following setback standards:

A privacy fence or wall (which shall be defined as any fence or wall greater than thirty inches (30") in height ~~or that is~~ greater than 25 percent opaque construction) within a required street side yard shall be subject to whichever of the following provisions a) through d) shall yield the greatest setback:

Commented [BB76]: This would allow for a fence that is not opaque (i.e. wrought iron) to be located along the property/ROW line and within the setback.


Commented [BB77R76]: Per City Council, all fences must meet setback. Waiver requests require SUP approval.

- If the subject lot has a street side yard which faces a dwelling front or lot front across the side street, the side yard privacy fence or wall shall be located not less than fifteen feet (15') from the property line, except on any lot having either a required side yard less than fifteen (15') feet or an existing primary structure setback less than fifteen (15') feet, then the fence or wall may be constructed with the same setback as the primary structure; or
- If the subject lot backs to the rear of another residential lot, the side yard privacy fence or wall shall be located not less than fifteen feet (15') from the side property line; or
- If the subject lot backs to the side of another residential lot, the side yard privacy fence or wall shall be located not closer to the side property line than the required front setback of the adjoining lot; or
- If the subject lot backs to an alley, the side yard privacy fence or wall shall be located not closer than fifteen feet (15') from the side property line.

A decorative wall or fence (which is defined as any wall or fence not greater than thirty inches in height and not greater than twenty-five percent opaque construction) within a required street side yard shall not be placed less than three feet (3') from the side property line, and shall not be subject to the provisions of the preceding sections (a) through (d).

3. **Adjacent to Undeveloped Property:** Except for perimeter subdivision fencing meeting the requirements in paragraph "1.a" above, no fence or wall greater than thirty (30) inches in height and no greater than twenty-five (25) percent solid ~~masonry~~ opaque construction, shall be located less than fifteen (15) feet from the side property line adjacent to the street which leads into undeveloped property. See Exhibit "3-4".

Commented [EW78]: Provides consistency with term used throughout Subsection E



(1) Set-back established by district regulations

Exhibit "3-4"
Typical 15'-0" Fence Setbacks

4. **Rear Fence and Free Standing Wall Setbacks:** Fences and walls meeting all of the construction

requirements of paragraph "1.a" above and ~~the Uniform Building Code~~ other adopted standards may be erected on the rear property line except; however, lots whose rear property line abuts a public street on which one of the immediate adjacent lots maintains its required front yard, then no fence nor wall greater than thirty (30) inches in height shall be located within fifteen (15) feet of the subject lots rear property line. See Exhibit "3-4".

Commented [EW79]: Uniform codes are obsolete


5. Twenty-five Percent Opaque Construction: The intent of this provision in Subsection E is to discourage barriers that resemble a compound or fortress and the calculation shall be as follows: Every eight (8) linear feet of fencing shall be at least 75% open to view from the street or public way. The 25% opaque construction shall be calculated based on the area of each eight (8) foot linear segment of the barrier.

Commented [EW80]: This added provision attempts to specify how the calculation is applied to eliminate completely solid walls for longer runs and then installing wrought-iron on the ends

F. Security Gating Encroachments

~~A front yard fence or screening wall providing support for a security gate and not exceeding a maximum height of 6 feet, may encroach a maximum of 10 feet into the front yard setback of a residential lot when the fence or screening wall meets the following criteria and shown in Exhibit "A":~~

- ~~1. The fence or screening wall shall attach to a gated entry across the driveway;~~
- ~~2. The fence or screening wall shall attach to the dwelling unit not more than 10 feet from the driveway and extend toward the driveway;~~
- ~~3. The fence or screening wall shall extend to the nearest side property line;~~
- ~~4. The fence or screening wall shall not extend beyond 10 feet into the setback from the dwelling unit;~~
- ~~5. The fence or screening wall shall not enclose nor extend across the entire front yard;~~
- ~~6. The gate and columns may not extend beyond one foot in height above the fence;~~
- ~~7. A minimum setback distance of 20 feet from the fence, screening wall and gate to the front property line shall be maintained.~~



G. Administration

1. Fence Permit Required - It shall be unlawful for any individual, partnership, company or corporation to erect or have erected a fence or any part of a fence of permanent construction in the city limits without first obtaining a fence permit from the Community Development Department.
2. Application for Permit - Any individual, partnership, company or corporation making application for a fence permit must sign an application for same showing the following information:
 - a. Applicants name, address, and in addition, if the applicant represents a company or corporation, the name and address of the supervisor or foreman of said company or corporation and the name of its president.
 - b. Name and owner of the property.

- c. Local address where fence is proposed to be erected.
- d. Materials and type of fence construction.
- e. Height of fence.
- f. Applicant shall provide engineering plans and specifications for those types of fences where such engineering is deemed appropriate by the Building Official. The engineering plans shall be reviewed and approved by the Building Official prior to issuance of a fence permit.
- g. Survey showing lot on which the fence is proposed to be erected and the location of adjoining or adjacent lots showing existing structures and fences. The proposed fence shall be delineated by a dark heavy line. In AG zoning districts a scaled plot plan can be submitted in lieu of a survey.

H. Variances

1. Any variance to the provisions of this section shall be heard by the Zoning Board of Adjustment.

Commented [BB81]: Redundant language

Section 3.27 Accessory Buildings and Residential Carport Regulations

The following regulations shall govern the location, size and use of accessory buildings:

A. Accessory Buildings Located in Residential Zoning Districts (O-00-1223 / 07/18/00)

1. Permit Required:

- a. A building permit shall be required for any accessory building which exceeds one hundred and twenty (120) square feet. However, all accessory buildings containing 120 square feet or less shall comply with the height and setback requirements of this Section. An accessory building shall only be allowed as an incidental structure to a principle building unless the accessory building is located in the Agricultural District.
- b. For the purpose of this Section, the term accessory building shall include detached residential garages, and pool houses, but shall exclude a carport (see Section 3.27.C), ~~accessory dwellings, gazebos, cabanas, trellises, arbors, outdoor fireplaces/chimneys, or other shade structures.~~ Exception: structures for specific use as playground assemblies and/or playhouses shall be exempt provided that minimum five (5) feet setbacks from property lines are maintained.

Commented [EW82]: Recommended expansion of language and provisions for children's structures

2. Maximum Size and Number of Buildings:

- a. The maximum number of accessory buildings allowed per lot shall be three (3) buildings. In addition, the combined square footage of all accessory buildings shall not exceed the maximum square footage specified in the following table. ~~four percent (54%) of the aggregate area of the lot. Exemption: Lots containing a minimum of 80,000 square feet shall be exempt from the requirement for the maximum number of accessory buildings.~~

Commented [BB83]: Four percent (4%) is more in-line with current size allowances

Commented [EW84]: Allows for building sizes based on land area, not category

Commented [BB85]: Exemption added for large properties per Council direction

Maximum Square Footage of all Accessory Buildings				
Lot Size	Under .5 ac	.5 – .99 ac.	1 – 2.99 ac.	3+ ac.
Total s. f.	750 s. f.	1,000 s. f.	1,750 s. f.	2,500 s. f.

- b. Accessory dwellings allowed by the Land Development Code shall be limited in size to be no more than the most restrictive of the following:
 1. Fifty percent (50%) of the primary structure;

2. ~~The maximum allowed square footage for accessory buildings on the lot; or~~
3. ~~No more than twelve hundred (1,200) square feet~~

c. For the purpose of this Section, the size of an accessory building shall be the square footage of the building footprint ~~each floor, mezzanine, covered porch, or shade structure.~~

ed. ~~An application to exceed the total square footage shown in the above table~~ authorized above may be approved as a Special Use Permit (SUP).

de. ~~An existing accessory building may be remodeled or expanded provided the combined square footage of all accessory buildings does not exceed the maximum square footage allowed. However, an a legally-existing accessory building which exceeds the maximum square footage allowed may be remodeled or replaced with a new accessory building, but not expanded or increased in height.~~

ef. There shall be no physical connection between accessory buildings and a minimum separation of three (3) feet between accessory buildings.

3. *Setbacks:*

- a. No accessory building shall be erected in any required yard, as defined in *Chapter 2 – Definitions*, except as set forth herein.
- b. Attached accessory buildings – Accessory buildings erected ten (10) feet or closer to the principal building shall be considered attached, and shall comply with the setback lines established for the applicable zoning district. For the purpose of this regulation, the distance between buildings shall be measured between the nearest wall surfaces.
- c. Detached accessory buildings – A detached accessory building shall comply with the setback lines established for the applicable zoning district, unless the accessory building is located totally behind the rear of the principal building, then it shall not be placed closer than five (5) feet to any side or rear lot line.

4. *Maximum Height:* No accessory building shall penetrate a vertical height envelope defined as being a point five feet from a side or rear lot line and extending vertically 8 feet to a point, then extending at a 45° angle to the height of the primary building.

5. *Permitted Uses:* The use of an accessory building shall be consistent with the permitted uses of the applicable zoning district, except, no accessory building shall be used for dwelling purposes other than for ~~domestic family or servants quarters an accessory dwelling~~ employed for the premises, where permitted by the district regulations.

6. *Special Use Permit Provision:* Any request for a building permit for an accessory building which does not meet the criteria in this Section shall only be authorized after approval of a Special Use Permit by the City Council using the procedures contained elsewhere in this Land Development Code.

B. For Accessory Buildings Located in Non-residential Zoning Districts

1. No accessory building shall be erected in any required yard area except as set forth by this section.
2. No accessory building shall be erected within ten (10) feet of any other building unless such accessory building is used as a commercial kiosk, in which case such commercial kiosk cannot be located within fifty (50) feet of another building.
3. Commercial kiosks as accessory uses and/or buildings may be located within approved nonresidential districts subject to the following conditions:
 - a. Maximum size of two hundred-fifty (250) square feet.

Commented [BB86]: Size limitations for accessory dwellings

Commented [EW87]: Large accessory structures and extensions from accessory buildings should be accounted for.

Commented [EW88]: Non-compliance should be addressed in new Section 7 below - Variances

Commented [BB89R88]: Need to keep per City Council direction

Commented [EW90]: Provision that does not “grandfather” buildings that were constructed without permits or otherwise authorized

Commented [EW91]: Matches definitions

- b. No inside sales or service or drive in sales or service; walk-up and/or drive-up service permitted.
- c. Exterior walls shall be of at least seventy-five percent (75%) masonry, glass, or other equivalent material, provided metal material does not exceed twenty-five percent (25%) of the exterior walls.
- d. Located within required setbacks and in conformance with this section.
- e. Located in such a manner as to not impede, impair or endanger vehicular traffic on the property where the kiosk is located and for vehicular traffic ingressing from and egressing to public rights-of-way.
- f. Submission of an acceptable site plan shall be required for consideration of the issuance of a building permit unless a current valid Certificate of Occupancy exists.
- g. Limited to one (1) kiosk per platted plot.

4. Accessory buildings on sites involving residential adjacency shall require approval of a Special Use Permit by City Council unless previously identified on an approval Site Plan.

C. Residential Carport Regulations – Carports located in zoning districts which permit single family residential dwellings shall comply with the regulations contained in this section.

- 1. *Approval by Special Use Permit Only:* In accordance with the Special Use Permit procedures contained in this Chapter of these zoning regulations, no carport shall be built in the City of Colleyville without approval by the City Council for a Special Use Permit to construct a carport in a zoning district that permits single family residential dwellings.
- 2. *Carport Standards:* A carport shall comply with the following regulations, unless the City Council in approving a Special Use Permit for a carport has imposed other requirements necessary in the particular case to protect the public interests.
 - a. *Size:* A carport shall not exceed 480 square feet in area. The longest dimension on a carport shall not exceed 24 feet.
 - b. *Height:* A carport shall not exceed a maximum height of 15 feet. The height shall be measured from the finished grade to the highest point of the roof.
- c. *Setbacks:*
 - i. A carport located within ten (10) feet of the principal building shall comply with the front, side and rear yard setbacks of the zoning district. The distance shall be measured between the two closest points of the carport and principal building.
 - ii. A carport located 10 feet or more from a principal building may extend into a required side yard, provided all of the following conditions are satisfied:
 - (1) every part of such carport is unenclosed except for necessary structural supports;
 - (2) no part of the carport is less than five (5) feet from a side or rear lot line, and
 - (3) the carport is located completely within the rear yard area as defined in these zoning regulations.
- d. *Maximum Number Per Lot:* one
- e. *Paving and Street Access:*

The parking area of a carport shall be paved not less than nine feet (9') by eighteen feet (18') and provide access to a public street right-of-way. Said access shall be a minimum of nine feet (9') in width and paved. All paved surfaces shall be either concrete, asphalt or pave-stone.

f. *Design Criteria:*

Commented [EW92]: Recommended for protections of residentially zoned properties

Commented [BB93R92]: Needed?

- i. Roof - Carports shall have a pitched roof of at least 2:12. Flat roofs shall be prohibited.
 - ii. Posts - Posts shall be ~~constructed clad or finished~~ of brick, stone, cedar or decorative metal, such as metal lattice. For purpose of this requirement, decorative metal shall consist of twenty-five (25) percent opaque surfaces. The dimension of each post as viewed from each primary elevation shall not be less than ~~twelve-eight~~ inches (128") or more than forty-eight inches (48"). Any carport with two or more elevations that exceed the 48-inch criteria shall be considered an accessory building and be regulated as such. ~~Wooden Cedar~~ posts shall be ~~prohibited wrapped using masonry stone or brick from the base to at least 50% of the post height. The exposed portion of the cedar post shall be a minimum of 8 inches.~~
- g. *Adequacy of Plans and Specifications:*

The applicant requesting a Special Use Permit to construct a carport shall submit plans and specifications of the proposed carport for review. Said plans and specifications shall contain sufficient information to allow the City Council to determine that the proposed carport complies with these regulations and the City Council may require additional information when necessary to clarify the applicant's request. At a minimum, the drawings shall contain a plot plan, elevation views and a description of the construction materials.

Commented [EW94]: Recommend allowing cedar as an approved material

Section 3.28 Supplementary District Regulations

- A. Reserved (O-00-1241 / 10/03/00)
- B. Erection of More Than One Principal Building on a Lot – In any district other than Agricultural zoning, no more than one (1) building housing a permitted or permissible principal use may be erected on a single lot.
- C. Buildings Constructed Across Lot Lines – No building may be constructed across existing platted lot lines unless a replat is filed and approved in accordance with applicable regulations of the city.
- D. Exceptions to Height Regulations
1. Schools, public buildings, and institutions may be erected to a height not exceeding (85) feet ~~the~~ maximum height in any district in which they are permitted, provided front and rear yards are increased in depth and side yards increased in width one (1) foot for each foot of height that the building exceeds the height regulations of the district in which it is located.
 2. The height regulations prescribed elsewhere in this Chapter shall not apply (except as may be applicable to paragraph d. hereof) to grain elevators, television and radio towers, church spires, belfries, cupolas, antennas, water tanks, ventilators, chimneys, ornamental towers, monuments, conveyors, fuel storage tanks, asphalt and concrete batch plant equipment not intended for human occupancy.
 3. Limitations on number of stories shall not apply to buildings used exclusively for manufacturing or storage purposes provided such buildings do not exceed the height in feet permitted in the district in which they are located.
 4. The permitted height of any occupied building shall be further restricted to the capability of the local fire fighting equipment to adequately handle any such building height.
 5. In CC and ML zoning districts, the City Council may vary the maximum height of a building if the City Council finds that the location and/or configuration of the building is such that it will conform to the surrounding area and provide adequate light and air under the circumstances. For each foot of proposed height over the standard, there shall be a foot increase in the front and rear yards or as approved by the council. The request for a variance shall be accompanied by a site plan of the property and an architectural drawing of the proposed building.

Commented [EW95]: Ag zoning district allows for a secondary dwelling

Commented [BB96]: The size of the property will dictate the maximum height of the structure

E. Projections of Buildings, Structures and Appurtenances into Required Yards

1. Open or lattice enclosed fire escapes may project into a required yard not to exceed fifteen (15) feet. The ordinary projections of chimneys and pilasters shall be permitted by the City's Building Official when placed so as not to obstruct light and ventilation.
2. Terraces, balconies, decks, ~~uncovered porches~~ and ornamental features above the floor level of the ground (first) story may project into a required side yard, provided these projections be at least five (5) feet from any adjacent side lot line.
3. ~~An uncovered porch in the front yard may not be more than eighty (80) square feet or project into the front yard setback for distance of more than eight (8) feet.~~ Fountains and other decorative features may project into the required front yard but shall not include structures used for occupancy such as guard sheds, shade structures, etc.
4. A porte-cochere or canopy may project into a required side yard, provided every part of such porte-cochere or canopy is unenclosed except for necessary structural supports, and not less than five (5) feet from any side lot line.
5. Every part of a required yard shall be open to the sky, unobstructed by a building, except for the ordinary projections of sills, belt courses, cornices, and ornamental features not exceeding twelve (12) inches, or as otherwise excepted in paragraph a. through d. above. Roof eaves may project into required side yards provided the projections be at least five (5) feet from any adjacent side lot line.
6. Gasoline filling station pumps and pump islands may be located or project into a required yard provided they are not less than twenty-five (25) feet distant from any street, highway or alley right-of-way line, and not less than fifty (50) feet distant from any residential property line.

Commented [EW97]: Uncovered flatwork has no effect on the requirement provided lot drainage is not impacted

Commented [EW98]: Uncovered flatwork, regardless of size, has no effect on aesthetics at the front of a property

Commented [EW99]: Provides for decorative features in a front yard

F. Minimum Width of Enclosed or Partially Enclosed Open Space – Where an open space is more than fifty (50) percent surrounded by a building, the minimum width of the open space shall be at least twenty (20) feet for one-story and one and a half-story buildings, thirty (30) feet for two-story buildings, and forty (40) feet for three or more story buildings.

G. Buildings and Structures to Have Access – Every building or structure hereafter erected or moved shall be on a lot adjacent to a public street, or with access to an approved private street, and all structures shall be so located on lots as to provide safe and convenient access for servicing, fire protection, and required off-street parking.

H. Parking; Storage or Use of Major Recreational Equipment and Vehicles – No major recreational equipment shall be parked or stored on any lot in a residential district except in a carport or enclosed building, or in a required side or rear yard on an all-weather hard surface driveway; provided, however, that such equipment may be parked anywhere on residential premises not to exceed twenty-four (24) hours during loading or unloading. No such equipment shall be used for living, sleeping, or housekeeping purposes when parked or stored on a residential lot, except for the temporary housing of guests not to exceed two (2) consecutive weeks.

Commented [EW100]: Prohibits parking RV's on the grass

For purposes of these regulations, major recreational equipment is defined as including boats and boat trailers, travel trailers, pick-up campers or coaches (designed to be mounted on automotive vehicles), motorized dwellings, tent trailers, and the like, and cases or boxes used for transporting recreational equipment, whether occupied by such equipment or not.

I. Parking and Storage of Vehicles in General

1. One commercial vehicle of not more than one ton capacity, except pick-up trucks, when used in the employ by the site occupant of a dwelling may be permitted on a residentially zoned lot, provided said parking space shall be in an enclosed garage, carport, or on an all-weather hard surface driveway, or in a side or rear yard on an all-weather surfaced driveway. Nothing in this Chapter shall prohibit the occasional overnight storage or parking of a commercial vehicle on residential property.

2. Off-street vehicle parking spaces shall not be located within ten (10) feet of existing proposed major thoroughfare street right-of-way lines in any commercial or industrial district. Such off-street parking spaces shall consist of a paved surface, i.e., concrete, HMAC, brick or paving stone approved by the city building official. All ten (10) foot buffer areas shall be landscaped and maintained to enhance esthetic qualities.
3. To avoid the unsightly appearance of junked and abandoned vehicles in residential districts, no vehicles may be parked or stored on a residential premise where visible to any adjacent residential use, unless a current state vehicle inspection sticker is displayed thereon.

J. Front Yard Adjustments – Front yard requirements as established in *Section 3.24 - Schedule of District Regulations* may be adjusted in the following cases:

1. Where forty (40) percent or more of the frontage on the same side of a street between two intersecting streets is presently developed or may hereafter be developed with buildings that have (with a variation of ten (10) feet or less), a front yard greater or lesser in depth than herein required, new buildings shall not be erected closer to the street than the average front yard so established by the existing buildings.
2. Where forty (40) percent or more of the frontage on one side of a street between two intersecting streets is presently developed or may hereafter be developed with buildings that do not have a front yard as described above, then:
 - a. —Where a building is to be erected on a parcel of land that is within one hundred (100) feet of existing buildings on both sides, the minimum front yard shall be a line drawn between the two closest front corners of the adjacent building on each side, or
 - b. —Where a building is to be erected on a parcel of land that is within one hundred (100) feet of an existing building on one side only, such building may be erected as close to the street as the existing adjacent buildings.
3. Interior lots abutting on two streets shall provide the required front yard on both streets.
4. On corner lots, a front yard shall be provided on each street frontage except for lots of record as described in this Chapter.
5. Front yard requirements in all districts adjacent to an existing or proposed major thoroughfare or secondary thoroughfare street, as designated in the City's latest Comprehensive Plan, shall be measured from such existing or proposed major thoroughfare or secondary thoroughfare street right-of-way line.

K. Side Yard Adjustments – Side yard requirements as established in *Section 3.24 - Schedule of District Regulations* may be adjusted in the following cases:

1. Commercial buildings used in part for dwelling purposes, where permitted, shall provide side yards not less than five (5) feet in width unless every dwelling unit therein opens directly upon a front yard, rear yard or court yard.
2. Whenever a lot of record at the time of the effective date of this Chapter has a width of less than fifty (50) feet, the side yard on each side of a building may be reduced to a width not less than ten (10) percent of the width of the lot, but in no instance shall such width be less than four (4) feet.
3. On corner lots of record the yard adjacent to the side street shall not be less than fifteen (15) feet.
4. For commercial or industrial lots abutting a lot zoned CC1, CC2, CC3, CN, CPO or ML, subject to the approval of the city building official, a zero lot line is permitted on one side, provided a four hour fire wall is constructed at said zero lot line.

L. Rear Yard Adjustments – Rear yard requirements as established in *Section 3.24 - Schedule of District Regulations* may be adjusted in the following case:

1. Where a lot abuts an alley, one-half the alley width may be considered as part of the required rear yard.
- M. Lot Area Per Family Adjustments – Lot area per family (dwelling unit) requirements as established in *Section 3.24. - Schedule of District Regulations* shall be adjusted in the following cases:
 1. Where a lot of record or a lot in a subdivision which the Planning and Zoning Commission and City Council have officially approved and agreed to accept at the time of the effective date of this Chapter has less area or width than herein required, in the district in which it is located, said lot may nonetheless be used for a residential or nonresidential use, whichever is applicable, in the district in which it is located.

Section 3.29 – Parking Requirements

- A. Purpose – The purpose of this section is to require off-street parking and loading facilities proportional to the need created by each use. Where the minimum number of required parking spaces can not be calculated in accordance with the parking group schedule, the Building Official shall be authorized to determine the minimum number of required parking spaces using acceptable industry comparables.
- B. General Provision – In all zoning districts, there shall be provided in connection with the appropriate permitted use, off-street parking spaces in accordance with the provision of this section, unless a different parking standard has been set forth as a condition of a Special Use Permit or Planned Unit Development for a specific site. Existing facilities being used for off-street parking shall not be reduced in capacity to less than the minimum number of spaces prescribed, or altered in design or function to less than the minimum standards prescribed herein.
- C. Location of Parking – All required parking spaces shall be provided on the same lot or tract occupied by the use being served, except that where an increase in the number of spaces is required by a change or enlargement of a non-residential use, the additional required parking spaces may be located off-premises in accordance with the shared parking requirements contained in this section, unless a different parking standard has been set forth as a condition of a Special Use Permit or Planned Unit Development for a specific site. Required parking spaces for a residential use shall be provided on the lot or tract occupied by the use being served.
- D. Parking Space Locations Prohibited – No off-street parking space shall be located, either in whole or in part, within any fire lane, driveway, driving lane, or maneuvering area. Furthermore, no required off-street parking space shall be located, either in whole or in part, in a public street, sidewalk, parkway, alley or other public right of way.
- E. Parking Space Dimensions – No required off-street parking space shall be less than nine (9) feet in width by eighteen (18) feet in length.
- F. Mixed Use Parking – The parking requirements for a lot or building containing a mixture of uses shall be the sum of the requirements for each type of use. No parking space provided for one type of use or building shall be included in the calculation of the parking requirements for any other use or building. For multi-tenant developments containing greater than 30,000 square feet of floor area, the sum of the total number of required parking spaces may be reduced by ten percent (10%).
- G. Shared Parking – Where an increase in the number of off-street parking spaces is required by a change or enlargement of use, the additional required spaces may be located on another property that is located on or adjacent to the site as defined by contiguous lot lines of a use not normally open and used or operated during the same hours, provided, that the following conditions are satisfied:
 1. The parking spaces are located within three-hundred feet from an entrance to the building or use being served, measured along the shortest available pedestrian route with public access.
 2. A copy of the written agreement, executed by the parties concerned, is furnished to the Building Official, assuring their retention for such purposes.

Commented [EW101]: Allows for an adjacent property to be used for shared parking

H. Building Renovations – When an existing building or use is enlarged, structurally altered, or remodeled to the extent of increasing or changing the use by more than ten percent (10%), but less than fifty percent (50%), of the existing square footage, additional off-street parking shall be provided for the incremental increase in accordance with the off-street parking regulations set forth herein. When an existing building or use is enlarged, structurally altered, or remodeled to the extent of increasing or changing the use by fifty percent (50%) or more of the existing square footage, the off-street parking requirements for the entire building shall be comply with the parking regulations set forth herein.

I. Supplemental Parking Space Requirements

1. Parking regulations are based on the gross floor area (GFA) of the building.
2. In determining the required number of parking spaces, fractional spaces shall be rounded to the nearest whole space. Parking spaces located in buildings used for repair garages or car washes, and spaces in drive-through lanes shall not be counted as meeting the required minimum number of parking spaces.
3. Wooden poles shall not be used for parking lot or site lighting for a non-residential use.
4. Except for single-family dwelling units, parking spaces shall be arranged so that vehicles shall not be required to back out of the parking spaces directly into a street.

5. A reduction of up to twenty percent (20%) may be approved by the City Council when associated with new development or a significant change in use of an existing building or site. A parking analysis report justifying the reduction shall be provided as part of a request for parking reduction.

J. Parking Group Schedule – The minimum number of off-street parking spaces to be provided in connection with the permitted use listed in Table 3-310, *Schedule of Permitted Principal Uses*, shall be in accordance with the following Table 3.29 – *Parking Group Schedule*.

Commented [BB102]: The percentage is up for discussion; this allows for greater flexibility for unique and/or large developments

Table 3.29 Parking Group Schedule	
Parking Group	Minimum Number of Off-Street Parking Spaces
1	1 per unit
2	2 per unit
3	2 per unit, exclusive of "in-garage" parking
4	1 per unit plus 1 guest space per every 5 units
5	1 per 100 sq. ft. of gross floor area
6	1 per 150 sq. ft. of gross floor area
7	1 per 200 sq. ft. of gross floor area

8	1 per 300 sq. ft. of gross floor area
9	1 per 400 sq. ft. of gross floor area
10	1 per 500 sq. ft. of gross floor area
11	1 per 5 pupils plus drop-off and pick-up areas
12	1 per classroom plus 1 per each 2 students
13	1 per classroom plus 1 per 400 sq. ft. of office space
14	1 per 1.5 students and staff, based on capacity
15	1 per 3 students
16	1 per 200 sq. ft. of gross floor area plus 1 per 5,000 sq. ft. of exterior nursery area
17	1 per living unit
18	1 per 3 seats in primary seating area
19	1 per guest room plus 1 per 300 sq. ft. of office area – parking for restaurant additional
20	2 per hole
21	1 space
22	5 per hole (one per tee area for driving ranges)
23	5 per alley or table
24	As set by the SUP or PUD approved ordinance
25	Determined by the Building Official using acceptable industry comparables

Section 3.29.1 –Parking Space Construction Standards

- A. Dimensions – No parking space shall be less than nine (9) feet in width by eighteen (18) feet in length. The design and dimensions of off-street parking areas shall be in accordance with the following Table 3.29.1 – *Table of Parking Space Dimensions*.

Table 3.29.1 Table of Parking Space Dimensions					
Angles (Degrees)	0	30	45	60	90
Stall, Parallel to Aisle	23.0	18.0	12.7	11.4	9.0
Stall, Perpendicular to Aisle	9.0	16.5	19.0	20.0	18.0
Aisle Width, One-Way (1)	12.0	12.0	12.0	16.0	22.0
Aisle Width, Two-Way	24.0	24.0	24.0	24.0	24.0

(1) Aisle width shall comply with the requirements of the fire code when the aisle serves as a fire lane

- B. Surfacing (New Structures) – All parking spaces, aisles and maneuvering areas shall be constructed of an all-weather surface composed of concrete, asphalt, brick or paving stone. Such paving shall meet the minimum construction standards contained in the Colleyville Building Code. Such all-weather surface shall be provided for all parking spaces, whether enclosed or unenclosed, and shall be connected by an all-weather surface driveway to a street or alley. Rock, gravel and dirt parking surfaces are prohibited.
- C. Striping – For all non-residential uses and multi-tenant residential uses, parking spaces shall be striped or otherwise clearly designated on the parking facility surface, as determined by the Building Official.
- D. Curbs, Wheel Stops and Islands – Parking spaces abutting on adjoining property lines or street right-of-way lines shall be provided with wheel guards or bumper guards so located that no part of a normally parked vehicle will extend beyond the property line.

Section 3.30 Off-Street Loading Requirements

- A. Purpose and Intent – The purpose and intent of these regulations are to secure safety from fire, panic and other dangers; to lessen congestion in the streets and alleys; to facilitate the adequate provision of transportation and circulation; to conserve the value of building and land uses; and to encourage the most

appropriate use of land. To this end, in all zoned districts where applicable, there shall be provided at the time any use is established or expanded, or any building is erected or structurally altered (except as otherwise provided elsewhere in this section) minimum off-street loading in conformance with the requirements established herein.

- B. Location of Loading Spaces – Off-street loading spaces shall be provided and maintained for all retail, commercial and industrial uses and structures for receiving and loading merchandise, supplies, and materials within a building or on the lot or tract adjacent thereto. Such spaces shall be marked with painted outline and may be adjacent to a public alley or private service drive or may consist of a truck berth within a building or structure, however no portion of the off-street loading space shall be located within or extend into any public street, highway or alley right-of-way. (O-00-1261 / 12/19/00)
- C. Computation of Off-street Loading Space Sizes – At least one-half of the required number of off-street loading spaces or truck berths shall have a minimum dimension of ten (10) feet by fifty (50) feet each and the remaining required spaces or berths shall have a minimum dimension of ten (10) feet by twenty-five (25) feet each - exclusive of turnaround and maneuvering space.
- D. Type of Parking Surface Required for Loading Space – All surface areas upon which vehicles and trucks are parked during unloading operations shall consist of a paved surface, i.e., concrete, HMA, brick, paving stone, approved by the city building official.
- E. Rules for the Computation of Off-street Loading Spaces
1. No building, structure or part thereof used for nonresidential purposes on any "CN" or "CC" district shall hereafter be enlarged or extended unless off-street loading space is provided in accordance with the provisions of this section.
 2. No building, structure or part thereof used for nonresidential purposes in any "ML" district shall hereafter be enlarged or extended to provide a gross floor area of 25,000 square feet or more unless off-street parking is provided in accordance with the provisions of this section.
- F. Number of Off-street Spaces Required – The minimum number of off-street loading spaces required shall be in conformance with the following schedules:
1. Retail, Service (except personal service), Commercial and Industrial Uses

Sq. Ft. of Floor Area in Building or Structure	Minimum Number of Off-Street Loading Spaces or Berths Required
0 to 9,999	None
10,000 to 49,999	1
50,000 to 99,999	2
100,000 to 199,999	3
Each additional 100,000	1 additional

2. Office Buildings, Hotels/Motels, Restaurants and Similar Establishments

Sq. Ft. of Floor Area in Building or Structure	Minimum Number of Off-Street Loading Spaces or Berths Required
0 to 49,999	None
50,000 to 149,999	1
150,000 to 299,999	2
300,000 to 499,999	3
500,000 to 999,999	4
Each additional 500,000	1 additional

Section 3.31 Duties of Administrative Official

- A. Administration and Enforcement – An Administrative Official designated by the City Manager shall administer and enforce this Chapter. Said person may be provided with the assistance of such other persons as the City Manager may direct.

If the Administrative Official finds that any of the provisions of this Chapter are being violated, he ~~the~~ Administrative Official or their representative shall notify in writing the person responsible for such violations, indicating the nature of the violation and ordering the action necessary to correct it. He ~~The~~ Administrative Official or their representative shall order discontinuance of illegal use of land, buildings, or structures, removal of illegal buildings or structures or of illegal additions, alterations, or structural changes; discontinuance of any illegal work being done, or shall take any other action authorized by this Chapter to ensure compliance with or to prevent violation of its provisions.

Commented [EW103]: Revised language that was gender-specific

- B. Building Permits Required – No building or other structure shall be erected, moved, added to, or structurally altered without a permit therefore where applicable, and issued by the Administrative Official. No building permit shall be issued by the Administrative Official except in conformity with the provisions of this Chapter, unless he receives a written order from the Zoning Board of Adjustment in the form of an administrative review, special exception, or variance as provided by this Chapter. No building permit shall be issued unless the property has been platted of record, except that a building permit may be issued for unplatted property meeting all of the following five criteria:

1. The parcel is a "lot of record" as defined herein; and
2. Right-of-way and easements sufficient for Master Plan roads or drainage/utility facilities exist; and
3. The parcel adjoins an approved public street; and
4. The parcel contains a principal residential use in a residential structure; and
5. The requested construction permit(s) and all construction permits issued for the parcel within the past three years allow improvements whose combined value does not exceed 50% of the appraised value of the parcel as shown in the current parcel record of the Tarrant County Appraisal District.

- ~~C. Application for Building Permit – All applications for building permits shall be accompanied by plans in triplicate drawn to scale, showing the actual dimensions and shape of the lot to be built upon; the exact sizes and locations on the lot of buildings already existing, if any, and the location and dimensions of the proposed building or alteration. The application shall include such other information as lawfully may be required by the Administrative Official, including existing or proposed building or alteration; existing or proposed uses of the building and land; the number of families, housekeeping units, or rental units the building is designed to accommodate; conditions existing on the lot; and such other matters as may be necessary to determine conformance with, and provide for the enforcement of, this and other city ordinances.~~

~~One copy of the plans shall be returned to the applicant by the Administrative Official, after he shall have marked such copy either as approved or disapproved and attested to same by his signature on such copy. The original and one copy of the plans, similarly marked, shall be retained by the Administrative Official.~~

Commented [EW104]: The adopted building codes already codify the requirements for building permit applications

- D. Site Plan Approval Required – Where the property is zoned CPO, CN, CC, ML, SU, PUD-C, or PUD-I, a site plan shall be submitted for review and approval to the Administrative Official prior to the issuance of a building permit. The site plan referred to herein shall contain the following:

1. The boundary lines and dimensions of the property, existing subdivision lots, available utilities, easements, roadways, sidewalks, fire lanes, and public rights-of-way.
2. Topography of the property proposed for development in contours of not less than two (2) feet, together with any proposed grade elevations, if different from existing elevations. If the natural

contour of the land is to be altered or changed in any location on the property more than four (4) feet then the site plan must provide detailed information on the proposed grading plan. This information shall include the correlation of the proposed grading plan to the surrounding properties and the use of surrounding properties, and shall include information indicating the drainage and line of sight effect the proposed grading plan will have on the surrounding properties.

3. The 100 year flood plain, water courses, wetlands, drainage areas, and other significant features including, but not limited to, rock outcroppings and tree groupings.
4. The location and use of all existing and proposed buildings or structures, including all refuse storage areas, and the minimum distance between buildings. Where building complexes are proposed, a site plan showing the location of each building and the minimum distance between buildings, and between buildings and the property line, street or curb line and/or alley shall be submitted.
5. Total number of off -street parking and loading spaces in accordance with Section 29 "Off-Street Parking Requirements", and Section 30 "Off-Street Loading Requirements" of this Chapter.
6. All points of vehicular ingress and egress and circulation within the property. Any special traffic regulation facilities, proposed or required, to assure the safe function of the circulation plan shall also be shown.
7. Setbacks, lot coverage, and when relevant, the relationships of the setbacks provided and the height of any existing or proposed building or structure.
8. The location, size, and arrangement of all outdoor signs, exterior auditory speakers and lighting.
9. A landscape plan prepared in accordance with the requirements of *Chapter 4 – Landscaping & Buffering* of this Land Development Code.
10. The location and height of fences or, screen plantings and the type of building materials or plantings to be used for fencing or screening in accordance with the requirements of Section 26 "Fences, Free Standing Walls, and Screening Materials" of this Chapter.
11. Note a soil erosion control plan for the period during which construction will be taking place.
12. Where multiple types of land uses are proposed, a land use plan delineating the specific areas to be devoted to various uses shall be required.
13. Vicinity map, north point, scale, name of the development, name of the owner, name of the planner, total acreage of the project, street address or common description of the property.
14. Current land uses and zoning district of the property and current land uses and zoning districts of the contiguous properties and buildings on the exterior of the site and within twenty-five (25) feet of all property lines.
15. The location and size of existing and proposed surface and subsurface drainage facilities.
16. A description of the type of land use that is proposed for the site including its Standard Industrial Classification (SIC) Code if there are any chemicals or toxic materials involved.

The Administrative Official may allow all of the foregoing to be contained within a single drawing if in the opinion of the Administrative official the drawing can be properly evaluated.

~~E. Expiration of Building Permit – If the work described in any building permit has not begun within (6) calendar months from the date of issuance thereof, said permit shall expire. It shall be cancelled by the Administrative Official, and written notice thereof shall be given to the persons affected, together with notice that further work as described in the cancelled permit shall not proceed unless and until a new building permit has been obtained. Further, the Administrative Official shall make an inspection of the work each (6) months, and if the work has not progressed, said permit shall expire.~~

~~F. Certificate of Occupancy Required For New, Altered Changes in Use, or Non-conforming Uses – It shall~~
Chapter 3 - Land Use

Commented [EW105]: The adopted building codes already codify the requirements for expired permits

~~be unlawful to use or occupy or permit the use or occupancy of any building or premises, or both, or part thereof hereafter created, erected, changed, converted, or wholly or partly altered or enlarged in its use or structure until a certificate of occupancy shall have been issued therefor by the Administrative Official stating that the proposed use of the principal building or land conforms to the requirements of this Chapter.~~

- ~~a. No nonconforming building or use shall be maintained, renewed, changed, or extended until a certificate of occupancy shall have been issued by the Administrative Official. The certificate of occupancy shall state specifically wherein the nonconforming use differs from the provisions of the ordinance.~~
- ~~b. No permit for erection, alteration, moving or structural repair of any building shall be issued until an application has been made for a certificate of occupancy, and the certificate shall be issued in conformity with the provisions of this Chapter upon completion of the work.~~
- ~~c. A temporary certificate of occupancy may be issued by the Administrative Official for a period not exceeding (6) months during alterations or partial occupancy of a building pending its completion, provided that said temporary certificate may include such conditions and safeguards as will protect the safety of the occupants and the public.~~
- ~~d. The Administrative Official shall maintain a public record of all certificates of occupancy.~~
- ~~e. Failure to obtain a certificate of occupancy shall be a violation of this Chapter and punishable under Chapter 1 – General Provisions of this Land Development Code.~~

Commented [EW106]: The adopted building codes already codify the requirements for a Certificate of Occupancy

- f. Construction and Use to be Provided in Applications, Plans, Permits and Certificate of Occupancy – Building permits or certificates of occupancy issued on the basis of plans and applications approved by the Administrative Official authorize only the use, arrangement, and construction set forth in such approved plans and applications, and no other use, arrangement, or construction. Use, arrangement, or construction at variance with that authorized shall be deemed violation of this Chapter, and punishable as provided by Chapter 1 – General Provisions of this Land Development Code.

Section 3.32 Comprehensive Zoning Ordinance – Zoning Map

This Chapter when read together with the official Zoning Map of the City of Colleyville, Texas, shall constitute the comprehensive zoning ordinance for the City of Colleyville, Texas.

The Zoning Map, as submitted with Ordinance 0-70-15, revised and updated in 1976, a copy of which is on file in the City Secretary's office shall remain the official Zoning Map of the City of Colleyville, until a new map is established in accordance with the provisions contained in this Chapter.

Section 3.33 Amendments to This Chapter

Reserved for listing of amendments to this Chapter.

Ord. Number	Date	Subject
O-00-1223	07/18/00	Residential Accessory Buildings
O-00-1241	10/03/00	Temp. Construction Offices & Temp. Real Estate Offices
O-00-1249	11/08/00	Large Commercial Buildings
O-00-1261	12/19/00	Location of Loading Spaces / Non-conforming Uses, Lots and Buildings
O-02-1331	02/19/02	Established one year time limit on SUP performance
O-02-1330	02/26/02	Tents and other special events
O-04-1454	04/16/04	Maximum size and number of screens for movie theaters
O-04-1497	12/21/04	Temporary Buildings and Uses
O-05-1529	06/21/05	Amend PUD regulations

Colleyville, Texas, Land Development Code

O-05-1532	07/19/05	Amend PUD side and rear yard set-back regulations
O-05-1538	09/06/05	Amend movie theater regulations regarding viewing screens
O-07-1607	01/16/07	Update Land Use Table and Parking Schedule
O-07-1608	02/20/07	Security gating setback standards across driveways
O-07-1633	9/4/07	Amend Sections 3.17 to 3.22 and Section 3.24, Table of Permitted Uses
O-08-1656	02/05/08	Amend Section 3.24, Table of Permitted Uses
O-09-1708	02/17/09	Amend Sections 3.26 and 3.27
O-09-1709	02/17/09	Amend Section 3.24.C, Wind Driven Generators
O-10-1750	05/04/10	Addition of Package Store Use, Regulations and Provisions
O-12-1838	6/19/12	Amend Section 3.24, Table of Permitted Uses to include purchasing and/or resale of precious metals
O-13-1863	2/5/13	Amend Section 3.24, Table of Permitted Uses to include addition of medical office uses to CPO zoning district
O-13-1871	4/16/13	Addition of Portable Storage Structure standards to Section 3.24(C). Amendments to Section 3.26 regarding commercial screening and dumpster screening
O-14-1905	1/21/14	Addition of fence maintenance and construction standards
O-14-1914	4/15/14	Addition of Concrete/Asphalt batch plant standards